This is a digital copy of a book that was preserved for generations on library shelves before it was carefully scanned by Google as part of a project to make the world's books discoverable online.

It has survived long enough for the copyright to expire and the book to enter the public domain. A public domain book is one that was never subject to copyright or whose legal copyright term has expired. Whether a book is in the public domain may vary country to country. Public domain books are our gateways to the past, representing a wealth of history, culture and knowledge that's often difficult to discover.

Marks, notations and other marginalia present in the original volume will appear in this file - a reminder of this book's long journey from the publisher to a library and finally to you.

Usage guidelines

Google is proud to partner with libraries to digitize public domain materials and make them widely accessible. Public domain books belong to the public and we are merely their custodians. Nevertheless, this work is expensive, so in order to keep providing this resource, we have taken steps to prevent abuse by commercial parties, including placing technical restrictions on automated querying.

We also ask that you:

+ *Make non-commercial use of the files* We designed Google Book Search for use by individuals, and we request that you use these files for personal, non-commercial purposes.

+ *Refrain from automated querying* Do not send automated queries of any sort to Google's system: If you are conducting research on machine translation, optical character recognition or other areas where access to a large amount of text is helpful, please contact us. We encourage the use of public domain materials for these purposes and may be able to help.

+ *Maintain attribution* The Google "watermark" you see on each file is essential for informing people about this project and helping them find additional materials through Google Book Search. Please do not remove it.

+ *Keep it legal* Whatever your use, remember that you are responsible for ensuring that what you are doing is legal. Do not assume that just because we believe a book is in the public domain for users in the United States, that the work is also in the public domain for users in other countries. Whether a book is still in copyright varies from country to country, and we can't offer guidance on whether any specific use of any specific book is allowed. Please do not assume that a book's appearance in Google Book Search means it can be used in any manner anywhere in the world. Copyright infringement liability can be quite severe.

About Google Book Search

Google's mission is to organize the world's information and to make it universally accessible and useful. Google Book Search helps readers discover the world's books while helping authors and publishers reach new audiences. You can search through the full text of this book on the web at `http://books.google.com/`



A

COLLECTION

OF THE

YEARLY BILLS

OF

MORTALITY,

From 1657 to 1758 inclusive.

Together with several other Bills of an earlier Date.

To which are subjoined

I. Natural and Political Observations on the bills of mortality: by Capt. John Graunt, F. R. S. reprinted from the sixth edition, in 1676.

II. Another essay in political arithmetic, concerning the growth of the city of London; with the measures, periods, causes, and consequences thereof. By Sir William Petty, Kt. F. R. S. reprinted from the edition printed at London in 1683.

III. Observations on the past growth and present state of the city of London; reprinted from the edition printed at London in 1751; with a continuation of the tables to the end of the year 1757. By Corbyn Morris, Esq; F. R. S.

IV. A comparative view of the diseases and ages, and a table of the probabilities of life, for the last thirty years. By J. P. Esq; F. R. S.

LONDON:

Printed for A. MILLAR in the *Strand*.

MDCCLIX.

ASTOR LIBRARY NEW-YORK

Receipt No. 2/2/105

NEW YORK
PUBLIC
LIBRARY

PREFACE.

A Regiſter of the births, diſeaſes, and deaths among any conſiderable number of people will eaſily afford much uſeful information to philoſophers in general, as well as to the ſtateſmen and phyſicians of the particular country, in which it is kept. For their ſakes therefore, and by their means for the ſake of the public, ſome pains have been taken to make as perfect a collection, as was poſſible, of all the London bills of mortality, from their beginning to this preſent year 1758. It can only be from a long ſeries of ſuch regiſters, that we are enabled to make any near approaches to truth, in the calculations founded upon them; and the longer the ſeries is, the nearer will our approaches be. But as theſe bills are publiſhed in looſe leaves, and very little care has hitherto been taken to preſerve them, it is evident, that the keeping of this regiſter has loſt a great part of its uſe. For it is become a matter of great trouble to find any number of bills together, greater perhaps than many of thoſe would chuſe to take, who are able, and might be willing, to draw out ſeveral important concluſions from them, when thrown in their way, as by the preſent publication.

Notwithſtanding all the ſearch, which has been made, many of theſe bills have hitherto proved irrecoverable; and the reſt would probably have had the ſame fate, if this collection had been deferred. Perhaps this publication may be the means of bringing thoſe, which are wanted, to light, if they are any where extant; and of preſerving thoſe, which will be publiſhed hereafter.

As a ſpecimen of the uſe, which may be made of them, there are ſubjoined to this collection:

Capt. Graunt's *Natural and Political Obſervations on the Bills of Mortality:*

Sir William Petty's *Eſſay concerning the Growth of the City of London, with the Meaſures, Periods, Cauſes, and Conſequences thereof.*

The very judicious performance of Corbyn Morris, Eſq; intitled, *Obſervations on the paſt Growth and preſent State of the City of London:*

And laſtly, A comparative view of the diſeaſes and ages, for the laſt thirty years, drawn from the bills of mortality, with their proportions to a thouſand; and alſo a table of the probabilities of life, for the laſt thirty years, compared with that of Mr. Smart's, for the firſt ten of the ſaid thirty; for all which the public is obliged to an accurate and careful calculator.

Though the reader is here preſented with the beſt materials, which could be had, it is but fair to acquaint him, that theſe bills are very far from being ſo accurate, as they might have been; and therefore, that no greater authority may be allowed them, than they deſerve, it may be of uſe to point out the ſeveral cauſes of this imperfection.

Many obvious and apparent defects in the weekly and yearly bills of mortality occur to every one, who has looked into this ſubject: but others, not ſo generally known, can hardly eſcape thoſe, whoſe nearer ſituation gives them an opportunity of enquiring into this matter with more exactneſs.

Our bills muſt plainly be a very defective regiſter of births, as

1. They extend only to baptiſms, which are adminiſtered according to the rites and uſage of the church of England. Very few of the numerous body of diſſenters, and none of the Roman-catholicks, are included in this number.

2. They take no notice of thoſe, who die unbaptized; or of thoſe, perhaps no inconſiderable number among the loweſt claſs of the people, who never are brought to be baptized at all. This defect is probably not made up by ſuch of the diſſenters, who may occaſionally be baptized in the form of the eſtabliſhed church.

Suppoſing then the papiſts and proteſtant diſſenters to make up one ſixth part of the whole number of inhabitants; the baptiſms, as they now ſtand in the bills, muſt be encreaſed in this proportion, to give the true number of births within the bills of mortality.

Theſe bills muſt be alſo an imperfect regiſter of deaths, as intending only to comprehend perſons belonging to the church of England, and buried according to the form of its ſervice.

Some few indeed among the poorer ſort, both of papiſts and diſſenters, who live at a diſtance from their reſpective burial-grounds, and

cannot bear the expence of being carried thither, are buried according to the rites of the church of England, and by that means have a place in the weekly bills.

Some have been willing to think, that, though the bills are defective in the ſeveral articles of births and burials, yet they are defective in nearly the ſame degree; ſo that a proportion is ſtill in ſome meaſure kept up. But the laſt obſervation deſtroys this ſuppoſed proportion; as the burials of ſome few papiſts, and of more diſſenters, but the births of none in either perſuaſion, are regiſtered there.

Another defect in the bills, not ſo generally attended to, is, that the number of perſons, carried into the country to be buried, is not brought to account in them. Many are frequently removed from one pariſh to be buried in another, that are both within the bills; which makes no alteration upon the whole. But great numbers are carried from pariſhes in town to be buried in the country. This number has probably encreaſed, as the faſhion of having country-houſes has more prevailed. A few indeed, who die elſewhere, are brought to be buried in pariſhes within the bills: but the number of theſe is very diſproportionate to thoſe, who are carried out. A diſtinct account of this matter ought to be kept in the ſeveral pariſhes, but ſeldom is kept with any exactneſs.

In one of the largeſt and moſt populous pariſhes in Weſtminſter, in which as careful a regiſter is made as in any, the account is found to ſtand thus:

Buried here each year at an average, for the laſt ten years, ——		1074
Carried out to be buried every year, at an average, —— —		261
Brought in every year, at an average, —— ——	124	
Of theſe, at leaſt one fixth are children of the pariſh out at nurſe in the neighbourhood, and to be conſidered as perſons living and dying in the pariſh—	20	104
Difference between thoſe carried out and brought in —— ——		157
		1074
Total of perſons dying in the pariſh each year,		1231

This

This may be of ſome uſe in forming a judgment of the reſt; and yet this is far from being perfect. Thoſe, who are brought in to be buried, are carefully regiſtered; thoſe, who are carried out, are not ſo. Such are entered by themſelves in the burial-account, as come to the knowledge of thoſe, whoſe buſineſs it is to attend to theſe matters: but of theſe, many are heard of but by accident, and ſome not at all.

Suppoſing the number of perſons carried away, and not brought to account, to be one ſixth (which I think comes as near the truth, as any ſuppoſition we can make) this will make the whole number of deaths to be one fifth more than are regiſtered in the bills.

If the ſtate of deaths, which are not regiſtered in the bills, be the ſame, or nearly the ſame, in this pariſh as in others, the defect in this article may with ſome degree of probability be ſupplied. But there is another material defect, which affects both baptiſms and burials, and cannot be ſupplied ſo probably. This ariſes from the neglect of pariſh-clerks and their deputies, in not making exact returns to the common-hall. From ſome large pariſhes no account is ſent for ſeveral weeks together, and the account for ſeveral is ſometimes inſerted in one weekly bill. If this was done without any omiſſions, the account would come right at the end of the year: but omiſſions in many, there is good reaſon to believe, are never ſupplied or corrected. This is often to be aſcribed to negligence; but it is ſometimes owing to diſputes between the clerk in orders and the officiating clerk, that the bills of births and burials are neither ſo regularly kept, nor ſo exactly returned, as they ought to be. What allowance is to be made for theſe omiſſions, can be hardly ſettled; but it is judged, that they are not inconſiderable.

Mr. Maitland obſerves (*a*), that the bills of mortality are very defective, none being mentioned therein, but ſuch as are buried in parochial cemeteries; by which means no account is taken of thoſe, who are buried in many burial grounds belonging to the church of England; ſuch as St. Paul's cathedral, Weſtminſter abbey, the Temple church, St. Peter's ad Vincula, the Rolls, and Lincoln's-Inn chapels, the Charter-houſe, and divers others belonging to hoſpitals.

(*a*) Hiſtory of London, p. 537. Edition 1739.

And

And he farther ſays (*b*), that the number of perſons buried, in and from the city and ſuburbs of London in 1729, not taken notice of in the bills of mortality, amounted to 3038.

Every pariſh appoints a ſearcher, whoſe buſineſs it is to examine the corpſe, and to report the diſtemper. The low capacity of the perſon uſually choſen into this office has been made an objection to the truth and juſtneſs of the bills. But with regard to natural deaths, there ſeems no other capacity neceſſary in theſe ſearchers, than that of relating what they hear. For the wiſeſt perſon in the pariſh would be able to find out very few diſtempers from a bare inſpection of the dead body, and could only bring back ſuch an account, as the family and friends of the deceaſed would be pleaſed to give. And it ſhould indeed be always remembered from whom this account comes, that proper allowances may be made for miſtakes, or miſrepreſentations, in thoſe diſtempers, which they might not be very able to know, or not very willing to own.

Beſides the putting of the calculator on his guard, it may be hoped, that the expoſing of the preſent faulty manner, in which the London bills of mortality are kept, will excite thoſe, who have it in their power, to find out a remedy.

The antients probably never kept any regiſters of this ſort; and accordingly they appear to have had no juſt notion of the proportions of deaths in the ſeveral ages, if we may form any judgment about ſuch a ſerious matter from what occurs in ſo ludicrous a writer as Lucian. For in his Cataplus he tells us, that out of a thouſand perſons, who died, there were three hundred and ninety eight above ſixty years of age; which is, I ſuppoſe, double to the general proportion, and is ſo much out of nature, that we need not doubt his having ſaid it from a random gueſs, without any helps from obſervation.

The pariſh-regiſters in England began no earlier than in 1538, in conſequence of one of the ſeventeen *injunctions* ſet forth that year, in the name of king Henry VIII. by the lord Thomas Cromwell, his vice-regent in eccleſiaſtical matters; which injunction appointed, that the parſon, vicar, or curate of every pariſh, ſhould keep a true and exact regiſter of all weddings, chriſtenings, and burials. And the weekly bills of mortality,

(*a*) Hiſtory of London, p. 537.

containing

containing an account of chriſtenings as well as burials, taken by the company of pariſh-clerks in London, had their riſe on the 21ſt of December, 1592.

In the year 1594, the particular or weekly account, both of chriſtenings and burials, was firſt made public, as alſo the general or yearly account, untill the 18th of December, 1595, when it was diſcontinued upon the ceaſing of the plague.

It is proper to be remarked here, that the bill of mortality, now in its infancy, conſiſted of but one hundred and nine pariſhes, which pariſhes were then only alphabetically ſet down, without making any diſtinction of the out-pariſhes from thoſe within the walls; whereas afterwards, in 1665, when Mr. John Bell, clerk of the company of pariſh-clerks, publiſhed at London, in quarto, his *London's Remembrancer; or, a true account of every particular week's chriſtenings and mortality, in all the years of peſtilence, within the cognizance of the bills of mortality*; the ſaid bill comprehended one hundred and thirty pariſhes, and diſtinguiſhed the pariſhes by the four diviſions of the *ninety ſeven pariſhes within the walls, the ſixteen pariſhes without the walls, the twelve out-pariſhes in Middleſex and Surry, and the five pariſhes in the city and liberties of Weſtminſter.*

In the ninety ſeven pariſhes within the walls was wanting that of St. James Duke's place.

In the ſixteen pariſhes, being part within the liberties, and part without, were wanting; St. Bartholomew the Great, Bridewell precinct, and Trinity in the Minories. Which three pariſhes, together with that of St. James Duke's place, Mr. Bell conceived were not inſerted in the bill, on account of their being all precincts.

The twelve out-pariſhes in Middleſex and Surry, and the five in Weſtminſter, were then wholly exempt.

In the year 1603, on the 29th of December, the firſt of the continued weekly bills of mortality extant at the pariſh-clerks hall begins. Since which time a weekly account hath been kept there of chriſtenings and burials.

In 1604, were added to the hundred and nine pariſhes theſe undermentioned; to the then thirteen, the three pariſhes mentioned to be wanting of the ſixteen, viz. St. Bartholomew the Great, Bridewell precinct, and Trinity in the Minories; and theſe eight, viz.

St. Cle-

St. Clements Danes, St. Leonard Shoreditch,
St. Giles in the Fields, St. Mary in Whitechapel,
St. James at Clarkenwell, St. Martin in the Fields,
St. Catharine Tower, St. Mary Magdalen Bermondſey.

In 1606 was added to thoſe eight St. Mary at the Savoy.

In 1611, on the 19th of January, the pariſh-clerks, who had been incorporated by letters patent of the 17th of king Henry III. in the year 1233, by the name of the *Fraternity of St. Nicholas*, were reincorporated by charter of the 9th of king James I.

In 1625, the bills of mortality having now acquired a general reputation, the company of pariſh-clerks obtained a decree, or act, under the ſeal of the High-commiſſion-court or Star-chamber, for the keeping of a printing-preſs in their hall, in order to the printing of the weekly and general bills within the city of London and liberties thereof; for which purpoſe a printer is aſſigned by the archbiſhop of Canterbury. And on the 18th of July that year, a printing-preſs was accordingly ſet up, and an order then made, that from thenceforth the weekly reports of the burials, within the limits aforeſaid, ſhould be printed, with the number of burials againſt every pariſh; which till that time had not been done.

The year following, viz. 1626, the pariſh or precinct of St. James Duke's place was added to the then ninety ſix pariſhes within the walls: all which pariſhes, ever ſince their ſeveral additions, and the other ever ſince the year 1604, brought to the company of pariſh clerks, not only the number of all the chriſtenings and burials, but alſo an account of all the *diſeaſes and caſualties*, though no ſuch account was publiſhed till 1629.

In this year, 1626, the city of Weſtminſter was likewiſe added, which brought in only the number of the chriſtenings, burials, and plague, without taking notice of or ſpecifying any other diſeaſes or caſualties.

In 1629, was inſerted an account of *the diſeaſes and caſualties*, with the diſtinction of *males and females*.

In 1636, the pariſhes of Hackney, Iſlington, Lambeth, Newington, Rotherith, and Stepney, brought in their reports of the chriſtenings, burials, and plague, in like manner and form, as the city of Weſtminſter had before done.

In 1647, the pariſh of St. Paul, Covent-Garden, was added, making the number of out-pariſhes ten.

In 1660, the bills were new-modelled, and the account of all the diſeaſes and caſualties, in the whole 130 pariſhes, was brought in; and the twelve pariſhes in Middleſex and Surrey were made a diviſion by themſelves; and the five pariſhes within the city and liberties of Weſtminſter were made a diviſion in the bills by themſelves; whereas before they were intermixed with each other.

In 1665, the totals of the chriſtenings were diſtinctly ſet down in the bills, under each of the four diviſions of the ninety ſeven, ſixteen, twelve, and five pariſhes reſpectively.

In 1670, St. Paul's, Shadwell, heretofore part of Stepney and a chapel of eaſe to the ſame, was added to the twelve pariſhes in Middleſex and Surrey.

In 1671, Chriſt-church in Surrey, heretofore part of St. Saviour's, Southwark, was added to the out-pariſhes in Middleſex and Surrey, making the number of pariſhes one hundred and thirty two.

In 1685, July 14, St. James's Weſtminſter was added;
In 1686, April 6, St. Anne's Weſtminſter;
In 1694, April 17, St. John Wapping;
In 1726, June 28, St. Mary le Strand;
In 1729, October 7, St. Geoge Hanover Square; and
December 16, St. Peter *ad Vincula*, in the Tower of London, was added: but a conteſt ariſing between the inhabitants of the Tower-liberty without and within the Tower, whether this church of St. Peter *ad Vincula* was parochial or not, the queſtion was tried in the court of King's-bench at Weſtminſter, in 1730, when it was determined in the negative; which occaſioned this church to be left out of the bill of mortality ſoon after.

In the ſame year, 1729, were added likewiſe the pariſhes of
Chriſt Church Spittlefields,
St. George Radcliffe High-way,
St. George the Martyr, in Queen's-ſquare, and
In 1730, September 22, St. Anne Limehouſe;
In 1731, April 13, St. George Bloomſbury;
Auguſt 3, St. John Evangeliſt Weſtminſter;
In 1733, Auguſt 21, St. John in Southwark;
November 27, St. Luke in Old-ſtreet; and
In 1746, St. Matthew Bethnal-Green.

To

To what Capt. Graunt obſerves, in his fourth chapter on the plague, may be added the following remark. Before the plague begins, there ſometimes dies not one in a week of the ſpotted fever, and never at moſt above four (*a*). But in the firſt week of the plague there die twelve, and afterwards the number increaſes as the plague increaſes, ſo that there frequently die above a hundred, and one week one hundred and ninety. This fever decreaſes again with the plague. There is reaſon therefore to ſuſpect, that this fever was the ſame from the beginning, as the true plague: at leaſt, if we conſider what has juſt now been obſerved, we muſt ſuppoſe, that the true plague very often paſſed under the name of the ſpotted-fever. This might be done willfully by ſome, who were unwilling to own, that the plague was in their houſes; which is worth the attention of the magiſtrate. It probably ſometimes happened by a miſtake through ignorance; purples only appearing in ſeveral, who had the plague, without any buboes or carbuncles; which is worth the attention of phyſicians (*b*). But, however it happened, we muſt conclude, that great as the reputed number was of thoſe, who died of the plague, the real number was ſtill greater, by all or moſt of the one thouſand nine hundred and twenty nine, who are ſaid to have died of the ſpotted-fever; for this is a greater number, than is found to have died of it in twenty other years. The number of thoſe likewiſe, who die of the plain or common fever, may be obſerved to riſe every week with the plague, and to decreaſe with it; ſo that in one week, during the height of the plague, three hundred and eighty three are reputed to die of a fever, when at the beginning and end of the year not above one tenth of this number is found under this article; and in the whole year, the number of deaths by fevers is five times as great as that of ordinary years. So that from both theſe articles we may fairly take five thouſand, and add them to ſixty eight thouſand five hundred and ninety ſix, the reputed number of thoſe, who were deſtroyed by the plague: and even then we ſhall be far from having the whole number; for the bills of mortality did not take in thoſe, who died among the

(*a*) See the weekly bills for the plague year printed at London 1665, quarto, by E. Cotes, printer to the company of pariſh-clerks.

(*b*) "The practitioners in phyſic --- ſtand amazed to meet with ſo many various ſymptoms, which they find among their patients (who are ill of the plague). One week the general diſtempers are blotches and boils; the next week as clear-ſkined as may be. But death ſpares neither. One week full of ſpots and tokens, and perhaps the ſucceeding bill none at all". A letter from John Tilliſon, London, Sept. 14. 1665, to Dr. Sancroft, dean of St. Paul's, and afterwards archbiſhop of Canterbury, among the archbiſhop's papers, in the Britiſh Muſeum, vol. 3785.

diſſenters, or in Ludgate, Newgate, Chriſt-church hoſpital, and many other places (*c*).

On this head of the plague it is very obſervable, that London has now been free from it for near a century, though before the laſt plague there are but few yearly bills without it; and there hardly paſſed any twenty years together, in one of which it did not rage to ſuch a degree, that it could not be miſtaken, which might be ſuſpected, when only a few are ſaid to have died of it. This would almoſt tempt one to doubt the truth of the common opinion, that the plague was never bred in England, but has always been imported from other countries, where it is endemial. For if it always comes from abroad, and the danger of its being imported is in proportion to the imports made from other nations, we muſt have had much more of the infection brought to us during the laſt century, than in any preceding one, as the trade of the nation has been unqueſtionably greater. But perhaps it will be thought, that though we have no cauſes among us ſtrong enough to produce the plague, yet there may be ſuch, as will diſpoſe us to receive the infection at one time, and be too weak to admit it at another; juſt as experience has frequently taught us, that the ſame quantity of infection will ſometimes communicate the ſmall-pox, and ſometimes fail of doing it. Whether then we are become leſs apt to breed, or to receive this dreadful evil, one of the cauſes of this happy event ſeems to be the greater freſhneſs and purity of the air of London, ſince the rebuilding of it after the great fire; the ſtreets being made wider, and the inhabitants not crowded ſo cloſely together. As it is perhaps owing to its being more thinly peopled than the reſt of the world, that America has never yet been viſited with the plague, while the crowded and filthy cities of Cairo and Conſtantinople are ſeldom free from it. Another, and probably the moſt effectual preſervative has been the great quantity of water from the Thames and the New river, which, for the laſt century, has waſhed the houſes ſo plentifully, and afterwards running down into the kennels and common ſewers, conſtantly hinders, or weakens the tendency to putrefaction: and if more water could ſtill be derived into our houſes, ſtreets, and common ſewers, it might perhaps fully make amends for the imperfections of quarantines, ariſing from the thoughtleſſneſs, negligence, avarice, and obſtinacy of thoſe, who may have the direction of them, or of thoſe by whom they ſhould be performed.

(*c*) See the letter of J. Tilliſon. The writer mentions a report, which ſeems almoſt incredible, that the quakers buried a thouſand in a week for ſome weeks together.

The

The deaths imputed to the meaſles are very remarkably different in different years: and yet it is poſſible, that this diſeaſe is not in reality ſo very irregularly epidemical or fatal, as by the bills it appears to be. The ſcarlet fever and malignant ſore throat often occaſion ſuch appearances upon the ſkin, as may eaſily be miſtaken for the meaſles by better judges, than the mothers and nurſes; who thinking themſelves able to diſtinguiſh this diſtemper, and equal to the management of it, often call in no other aſſiſtance. This miſtake is well known to have been ſometimes made within theſe few years, during which the ſcarlet fever and malignant ſore throat have been ſo common. It may perhaps have happened in every year, in which an extraordinary number of deaths are charged to the meaſles; and conſequently thoſe two formidable diſtempers, (if they are two diſtinct diſtempers, and not one and the ſame) being diſguiſed under the name of the meaſles, may have been older, and more general than is uſually imagined.

The large article of deaths by convulſions belongs chiefly, if not ſolely, to children under two years of age; which will eaſily appear, if in any year we ſet aſide the number of thoſe, who die by diſeaſes, in which children are known to have no ſhare, allowing at the ſame time to the children any reaſonable proportion of thoſe diſeaſes, to which they are ſubject in common with grown perſons: for there will ſtill remain the deaths of ſo many children to be accounted for, as will fill up, beſides the diſeaſes peculiar to them, almoſt the whole number of deaths by convulſions.

The yearly ſum of the deaths ranged under the heads of apoplexies, ſuddenly, planet-ſtruck, lethargies, and palſies, fluctuates without any conſtant increaſe or decreaſe, till the beginning of the preſent century: from which time this ſum has been perpetually increaſing, ſo that the middle proportion of it for every ten years to the total of the burials conſtantly exceeds that of the preceding ten years. In the laſt ten years this increaſe has been the greateſt of all, nearly one fourth more having died of theſe diſtempers, than there did at a medium in any other ſucceſſive ten years; and a double proportion died of them in theſe ten years, to what there did at an average in the ſame ſpace of time before the beginning of this century. Is this difference only an apparent one, ariſing from the placing of ſome deaths under theſe in the later bills, which formerly came under other articles? There ſeems no reaſon for ſuch a ſuſpicion, and the

gradual increaſe of theſe ſums is an argument againſt it. If the increaſe be real, is it owing to any alteration in our manners, or diet? And what is that alteration? The practice of drinking ſpirituous liquors muſt, probably, anſwer for ſome part of this; and it might be of public uſe, if ſome attention were paid to the finding out of the other cauſes.

But there does not appear to be any increaſe in the diſtempers juſt mentioned, or in any other, which is not likely to be abundantly made amends for, by the decreaſe in the numbers deſtroyed by the ſmall-pox, which may be hoped for from the practice of inoculation. The good effects of which do not yet appear for want of its being more general: for while inoculation prevails only among a part of any number of people, who all have an intercourſe with one another, it may occaſion as many deaths by ſpreading the diſtemper in, as it is called, the natural way, as it prevents among thoſe, on whom it is practiſed.

The reader may find, that the ſum total, as ſet down in the bills, of all the deaths, does not correſpond in ſome years to the ſum of the particulars, which is owing to ſome miſtake in the original bills.

The number of the inhabitants of Rhode-Iſland, taken by order of the lords commiſſioners of trade, was in the year

	Whites	Blacks
1730	15,302	2,633
1748	29,755	4,373
Dec. 24, 1755	35,939	4,697

And it is believed, that within the time here mentioned there had been little or no acceſſion made to them by new-comers from other places. From this account it appears, that the inhabitants of that country were nearly doubled in eighteen years: and great as this increaſe is, there are probably even among them ſome cauſes ſubſiſting, which hinder their increaſe from being ſo great, as it naturally would be. What then are we to think of the inhabitants of Great Britain, who increaſe ſo ſlowly, if they do at all, that ſome intelligent perſons have been inclined to believe, that they even decreaſe? And as to the inhabitants within the bills of mortality, it is evident, that there is a great waſte, and conſtant leſſening of their number, which is annually filled up by ſupplies from all parts of the country. Pride, poverty, the abuſe of ſpirituous liquors, the crowded manner of living in our

our cities, the unhealthfulneſs of many occupations, and the falſe ridicule thrown upon marriage, particularly by thoſe great patrons of debauchery, who wrote for the ſtage towards the end of the laſt century and in the beginning of the preſent, ſeem to be ſome of the cauſes, which reſtrain the natural fertility of mankind in Great Britain. Whoever could find them all out, and provide a proper remedy for them, as far as they will admit of being remedied, would remove evils, which do more to diſpeople this nation, than has ever been done by famine, war, or peſtilence. But it is not to be expected in a country ſo populous as England, that the increaſe ſhould be as great, as in thoſe parts of the globe, which are thinly peopled. For the nearer any country approaches to the point, at which it would be ſtocked with as many inhabitants as it can maintain, the more extenſively will the difficulties be felt of providing for children; and theſe may reaſonably diſcourage many from marrying early, and not a few from marrying at all.

The Foundling-hoſpital muſt have made a difference in the proportion of the births to the burials, and of the burials of infants to thoſe of adults, ever ſince it was firſt opened March 25, 1741; and a very conſiderable one, ever ſince it has received all the children that are brought; which it began to do in June 1756.

For though many children are ſent thither from the country, yet the greateſt part received into the hoſpital are undoubtedly born in London, and are accounted for in the births; but the deaths of none of theſe children are ever inſerted in the London bills. Such of them as die in the country, are buried there; and ſuch as die in the hoſpital, are buried in Pancras pariſh, which is out of the bills of mortality. This ſhould be attended to in all calculations, in which it may be concerned; and in particular, this will account for ſome part of the increaſed proportion of apoplexies, &c. to the other deaths for the laſt ten years; for theſe are not the diſeaſes of children, and conſequently there is little or no deduction made from theſe diſtempers, while a conſiderable deduction is made from the ſum total of the burials.

The following form of a bill of mortality is ſubmitted to the judgment of the reader.

The

The Diſeaſes.				Caſualties.
Age — —	Convulſions — —	Pleuriſy — —		Broken limbs —
Ague or fever —	Diabetes — —	Pox — —		&c. &c. &c.
Apoplexy, lethargy, palſy, or ſuddenly	Dropſy — —	Quinſy — —		
Aſthma, or phthiſic	Evil — —	Rickets — —		
Bite of a mad dog —	Gout, or rheumatiſm	Rupture — —		
Bloody flux or loofeneſs —	Hooping-cough —	Small-pox — —		
Cancer — —	Jaundies — —	Stone, ſtrangury, or ſuppreſſion of urine		
Childbed — —	Loſs of blood — —	Teeth — —		
Colic — —	Meaſles — —	Ulcers, fiſtula, or mortification —		
Conſumption — —	Miſcarriage — —	Worms — —		

Whereof have died

Of one month old or under	Three to four — —	Twenty to thirty	Sixty to ſeventy —
From one to three months	Four to five ——	Thirty to forty	Seventy to eighty —
Three months to one year	Five to ten — —	Forty to forty-five	Eighty to ninety —
One year to two years	Ten to fifteen —	Forty-five to fifty	Ninety to one hundred
Two to three — —	Fifteen to twenty —	Fifty to Sixty —	Above a hundred —

*** If any of the original yearly bills, antecedent to the year 1657, ſhall be ſent to the bookſeller within a year after the publiſhing of this collection, they ſhall be printed in the ſame manner as the reſt, and given gratis to the purchaſers of the book.

A BILL of Mortality for the Year 1593,

Being a Plague Year. *

London.	Bur.	Pla.
St Albans Wood-ſtreet	68	30
Alhallows Barking	203	102
Alhallows Bread-ſtreet	45	19
Alhallows the Great	305	194
Alhallows Honey-lane	21	9
Alhallows the Leſs	108	64
Alhallows Lombard-ſtreet	96	47
Alhallows Staining	183	102
Alhallows the Wall	202	106
St Alphage	176	98
St Andrew Hubbard	97	67
St Andrew Underſhaft	197	88
St Andrew Wardrobe	147	59
St Anns Alderſgate	206	101
St Anns Black Friars	200	85
St Antholins Pariſh	207	69
St Auſtins Pariſh	146	106
St Bartholomew Exchange	194	125
St Bennet Finck	63	54
St Bennet Grace-church	140	78
St Bennets Pauls Wharf	51	23
St Bennet Sherehog	58	24
St Botolph Billinſgate	306	152
Chriſt Church	36	18
St Chriſtopher	186	117
St Clements Eaſtcheap	506	337
St Dionis Back-church	44	16
St Dunſtans Eaſt	107	67
St Edmunds Lombard-ſtreet	105	68
St Ethelborough	406	209
St Faiths	84	45
St Foſters	107	52
St Gabriel Fen-church	300	107
St George Botolph-lane	67	32
St Gregorys by Pauls	52	25
St Hellens	25	4
St James Dukes Place	314	215
St James Garlickhithe	207	41
St John Baptiſt	209	477
St John Evangeliſt	304	164
St John Zachary	3	1
St Katherine Coleman	444	222
St Katherine Cree-church	106	46
St Lawrence Jewry	307	85
St Lawrence Pountney	41	12
St Leonards Eaſtcheap	114	56
St Leonards Foſter-lane	106	46
St Magnus	184	87
St Margaret Lothbury	208	46
St Margaret Moſes	107	42
St Margaret New Fiſh-ſtreet	84	52
St Margaret Pattons	38	22
St Mary Abchurch	92	61
St Mary Aldermanbury	79	54
St Mary Aldermary	104	67
St Mary le Bow	194	97
St Mary Bothaw	104	47
St Mary Colechurch	38	18
St Mary Hill	39	15
St Mary Mounthaw	29	13
St Mary Somerſet	110	72
St Mary Stainings	62	39
St Mary Woolchurch	207	148
St Mary Woolnoth	42	28

* *Reflections on the Weekly Bills of Mortality for the Cities of London and Weſtminſter, and the Places adjacent; but more eſpecially ſo far as they relate to the Plague, and other mortal Diſeaſes, that we Engliſhmen are moſt ſubject unto, &c.* London, printed for Samuel Speed, at the Rainbow in Fleet-ſtreet, 1665, Quarto.

	Bur.	Pla.
St Martins Iremonger-lane	43	31
St Martins Ludgate	62	34
St Martins Orgars	25	18
St Martins Outwich	205	104
St Martins in the Vintrey	62	42
St Matthew Friday-ſtreet	40	20
St Maudlins Milk-ſtreet	229	116
St Maudlins Old Fiſh-ſtreet	19	9
St Michael Baſſiſhaw	141	46
St Michael Cornhill	204	96
St Michael Crooked-lane	129	139
St Michael Queenhithe	115	71
St Michael in the Quern	116	82
St Michael Royal	151	81
St Michael Wood-ſtreet	41	19
St Mildred Bread-ſtreet	96	41
St Mildred Poultry	109	47
St Nicholas Acons	47	37
St Nicholas Cole-abby	76	45
St Nicholas Olaves	27	15
St Olaves Hart-ſtreet	64	41
St Olaves Jewry	53	36
St Olaves Silver-ſtreet	197	83
St Pancras Soper-lane	38	17
St Peters Cheap	109	89
St Peters Cornhill	112	5
St Peters Pauls Wharf	57	26
St Peters Poor	221	109
St Stevens Coleman-ſtreet	90	60
St Stevens Walbrook	49	26
St Swithins London-ſtone	406	250
St Thomas Apoſtles	21	9
Trinity Pariſh	72	48

Buried in the ſixteen Out Pariſhes, and at the Peſt-houſe.

St Andrews Holborn	1561	936
St Bartholomew the Great	254	187
St Bartholomew the Leſs	99	66
St Brides Pariſh	897	607
Bridewell Precinct	1461	841
St Botolph Alderſgate	144	97
St Botolph Algate	1771	624
St Botolph Biſhopſgate	287	104
St Dunſtans Weſt	585	363
St George Southwark	1112	618
St Giles Cripplegate	2968	1989
St Olaves Southwark	1998	1064
St Saviours Southwark	1946	1242
St Sepulchres Pariſh	3440	2502
St Thomas in Southwark	304	194
Trinity Minories	109	78
At the Peſt-houſe	208	195

Buried in the nine Out Pariſhes.

St Giles in the Fields	894	569
Hackney Pariſh	999	669
St James Clerkenwel	740	479
St Katherines Tower	698	489
Lambeth Pariſh	1569	1308
St Leonards Shoreditch	1202	773
St Magdalens Bermondſey	2606	2095
St Mary Newington	964	702
St Mary Iſlington	206	150

1593.

BURIED of all Diſeaſes, within LONDON, and the Liberties thereof,

From March to December 1593. *

			Plague.
March	17.	230	3
	24.	251	31
	31.	219	29
April	7.	307	27
	14.	203	33
	21.	290	37
	28.	310	41
May	5.	250	29
	12.	339	38
	19.	300	42
	26.	450	58
June	2.	410	62
	9.	441	81
	16.	399	99
	23.	401	108
	30.	850	118
July	7.	1440	927
	14.	1510	893
	21.	1491	258
	28.	1507	852
Aug.	4.	1503	983
	11.	1550	797
	18.	1532	651
	25.	1508	449
Sept.	1.	1490	507
	8.	1210	563
	15.	621	455
	22.	629	349
	29.	450	330
Oct.	6.	408	327
	13.	422	323
	20.	330	308
	27.	320	302
Nov.	3.	310	301
	10.	309	209
	17.	301	107
	24.	321	93
Decem.	1.	349	94
	8.	331	86
	15.	329	71
	22.	386	39

The Total of all the Burials of the Time aboveſaid 25886
Whereof of the Plague —— —— —— 11503

* Extracted from a Paper, intitled, *The four great Plagues, viz.* 1593, 1603, 1625, *and* 1636, *compared with the Weekly Bills of Mortality printed every Thurſday in the ſaid Years; by which an Increaſe and Decreaſe is plainly diſcovered in all thoſe Years. Printed for Peter Cole, at the Printing Preſs in Cornhill in the Royal Exchange,* 1665. It is in the late Sir HANS SLOANE's Library now in the Britiſh Muſeum.

A brief

1593.

A brief Report of all the CHRISTENINGS and BURIALS within the City of LONDON and the Liberties thereof, for one whole Year paſt, viz.

From Thurſday at Noon the 21ſt of December, Anno 1592, unto the 20th Day of December, being Thurſday at Noon, Anno 1593. *

Buried	17844
Whereof have died of the Plague	10662
Chriſtened this whole Year	4021
Pariſhes clear of the Plague	0

1603.

The whole Number of BURIALS in LONDON and the Liberties,

From the 17th of December 1602, to the 14th of July 1603 †		—	4314
Whereof of the Plague			3210
From the 14th of July to the 21ſt of the ſame	867	In the Out Pariſhes —	319
Whereof of the Plague	646	Whereof of the Plague	271
Buried in all this Week 1186		Whereof of the Plague 917	
From the 21ſt of July to the 28th of the ſame	1312	In the Out Pariſhes —	398
Whereof of the Plague	1025	Whereof of the Plague	254
		Out of the Peſt-houſe —	18
Buried in all this Week 1728		Whereof of the Plague 1396	
From the 28th of July to the 4th of Auguſt —	1700	In the Out Pariſhes —	537
Whereof of the Plague	1439	Whereof of the Plague	464
		Peſt-houſe —	19
Buried in all this Week 2256		Whereof of the Plague 1922	
From the 4th of Auguſt to the 11th of the ſame	1655	In the Out Pariſhes —	410
Whereof of the Plague	1372	Whereof of the Plague	361
		Peſt-houſe —	12
Buried in all this Week 2077		Whereof of the Plague 1745	

* Preface to *London's Remembrancer; or a true Account of every particular Week's Chriſtenings and Mortality in all the Years of Peſtilence within the Cognizance of the Bills of Mortality, being* xviii *Years. Taken out of the Regiſter of the Company of Pariſh Clerks of London, &c. By John Bell, Clerk to the ſaid Company. London,* 1665, *Quarto.*

† Extracted from a Bill printed by John Windet, Printer to the Honourable City of London, in the Library of the late Sir HANS SLOANE, Bart. in the Britiſh Muſeum. N. B. Though ſome of the Numbers are evidently erroneous, ſince they do not agree with the Totals; yet it was thought proper to retain them, rather than alter them upon Conjecture; and this hath been likewiſe obſerved in reprinting ſeveral other Bills.

From

From the 11th of Auguſt to the 18th of the ſame	2486	In the Out Pariſhes —	568
Whereof of the Plague — —	2199	Whereof of the Plague	514
		Bridewell — —	7
		Peſt-houſe ——	21
Buried in all this Week	3054	Whereof of the Plague	2713
From the 18th of Auguſt to the 25th of the ſame	2343	In the Out Pariſhes —	510
Whereof of the Plague ——	2091	Whereof of the Plague	448
		In Bridewell ——	8
		Peſt-houſe — —	12
Buried in all this Week	2853	Whereof of the Plague	2539
From the 25th of Auguſt to the firſt of Sept.	2798	In the Out Pariſhes —	587
Whereof of the Plague ——	2495	Whereof of the Plague	540
		In Bridewell ——	5
		Peſt-houſe — —	6
Buried in all this Week	3385	Whereof of the Plague	3035
From the firſt of Sept. to the 8th of the ſame	2583	In the Out Pariſhes —	495
Whereof of the Plague ——	2283	Whereof of the Plague	441
		In Bridewell ——	17
		Peſt-houſe — —	5
Buried in all this Week	3078	Whereof of the Plague	2724
From the 8th of Sept. to the 15th of the ſame	2676	In the Out Pariſhes —	453
Whereof of the Plague ——	2411	Whereof of the Plague	407
		In Bridewell ——	7
		Peſt-houſe — —	10
Buried in all this Week	3129	Whereof of the Plague	2818
From the 15th of Sept. to the 22d of the ſame	2080	In the Out Pariſhes —	376
Whereof of the Plague ——	1851	Whereof of the Plague	344
		In Bridewell ——	19
		Peſt-houſe — —	10
Buried in all this Week	2456	Whereof of the Plague	2195
From the 22d of Sept. to the 29th of the ſame	1666	In the Out Pariſhes —	295
Whereof of the Plague ——	1478	Whereof of the Plague	254
Buried in all this Week	1961	Whereof of the Plague	1732
From the 29th of Sept. to the 6th of October	1525	In the Out Pariſhes —	306
Whereof of the Plague ——	1367	Whereof of the Plague	274
Buried in all this Week	1831	Whereof of the Plague	1641
From the 6th of October to the 13th of the ſame	1109	In the Out Pariſhes —	203
Whereof of the Plague ——	962	Whereof of the Plague	184
Buried in all this Week	1312	Whereof of the Plague	1146
From the 13th of Oct. to the 20th of the ſame	647	In the Out Pariſhes —	119
Whereof of the Plague ——	546	Whereof of the Plague	96
Buried in all this Week	766	Whereof of the Plague	642

From the 20th of Oct. to the 27th of the ſame	536	In the Out Pariſhes —	89
Whereof of the Plague ——	432	Whereof of the Plague	69
Buried in all this Week 625		Whereof of the Plague 508	
From the 27th of Oct. to the 3d of November	609	In the Out Pariſhes —	128
Whereof of the Plague ——	491	Whereof of the Plague	103
Buried in all this Week 737		Whereof of the Plague 594	
From the 3d of Novem. to the 10th of the ſame	473	In the Out Pariſhes —	212
Whereof of the Plague ——	355	Whereof of the Plague	87
Buried in all this Week 685		Whereof of the Plague 442	

Buried in all within London, and the Liberties and Suburbs, ſince the Sickneſs began 37,333
Whereof of the Plague —— —— —— —— 31,919

The Time when it began at Weſtminſter, and theſe Places following;

Buried in Weſtminſter from the 14th of July to the 10th of Nov. in the whole Number 952
Whereof of the Plague —— —— —— —— 831

Buried in the Savoy from the firſt of June to the 10th of Nov. in the whole Number 199
Whereof of the Plague —— —— —— —— 187

Buried in the Pariſh of Stepney from the 25th of March to the 10th of Novem. in all 2050
Whereof of the Plague —— —— —— 1981

Buried at Newington Butts from the 14th of June to the 10th of Novem. in all — 640
Whereof of the Plague —— —— —— — —— 573

Buried in Iſlington —— — —— — —— 258
Whereof of the Plague — —— —— — 224

Buried in Lambeth — — — — — — 399
Whereof of the Plague —— — — —— 378

Buried in Hackney — — — — — 206
Whereof of the Plague —— —— —— —— 183

Buried in all within theſe Places laſt aforenamed —— —— 4709
Whereof of the Plague — — — — — 4350

The whole Number theſe Churches buried in all, both within London and the Liberties, and the ſeven other ſeveral Places laſt before mentioned, is } 42,042
Whereof the Number of the Plague amounts to —— —— 36,269

Another

1603.

Another BILL for the ſame Year. *

BURIED of all Diſeaſes.

			Plague.
March	17.	108	3
	24.	60	2
	31.	78	6
April	7.	66	4
	14.	79	4
	21.	98	8
	28.	109	10
May	5.	90	11
	12.	112	18
	19.	122	22
	26.	122	32
June	2.	114	30
	9.	131	43
	16.	144	39
	23.	182	72
	30.	267	158
July	7.	445	263
	14.	612	424
[From July 21. to Nov. 10. as in the preceding Bill.]			
Nov.	17.	384	251
	24.	198	105
Decem.	1.	223	102
	8.	163	52
	15.	200	96
	22.	168	74

The Total of all the Burials of the Time aboveſaid		37,294
Whereof of the Plague	—— ——	30,561

* Extracted from the Paper, intitled, *The four great Plagues, &c.*

A TABLE

1606.

A TABLE of the
CHRISTENINGS and MORTALITY
For the Year 1605 and 1606.*

Weeks.	Days of the Month.	Chriſt.	Bur.	Pla.	Par. infec.
1	Dec. 26.	100	116	5	5
2	January 2.	117	151	6	5
3	9.	130	138	4	4
4	16.	124	138	3	2
5	23.	143	121	6	4
6	30.	124	101	3	2
7	Febr. 6.	122	105	5	5
8	13.	131	118	7	6
9	20.	126	109	12	6
10	27.	102	117	9	8
11	March 6.	110	98	7	4
12	13.	126	137	9	7
13	20.	123	133	14	11
14	27.	134	123	17	8
15	April 3.	123	114	13	9
16	10.	132	145	27	11
17	17.	139	129	12	8
18	24.	118	110	11	7
19	May 1.	92	136	17	10
20	8.	116	103	13	11
21	15.	128	94	13	8
22	22.	113	132	14	9
23	29.	94	98	9	7
24	June 5.	129	112	16	8
25	12.	127	112	19	14
26	19.	121	119	15	10
27	26.	132	126	24	16
28	July 3.	109	110	25	12
29	10.	111	134	33	18
30	17.	115	146	50	22
31	24.	96	140	46	26
32	31.	132	178	66	29
33	Auguſt 7.	131	181	67	29
34	14.	141	197	75	33
35	21.	133	189	85	28
36	28.	125	207	85	29
37	Septem. 4.	123	241	116	32
38	11.	134	216	105	28
39	18.	121	214	92	36
40	25.	132	204	87	35
41	October 2.	121	256	141	40
42	9.	134	218	106	38
43	16.	142	227	117	37
44	23.	131	224	109	38
45	30.	124	226	101	34
46	Novem. 6.	136	183	68	27
47	13.	125	162	41	20
48	20.	121	145	28	11
49	27.	143	123	22	13
50	Decem. 4.	155	160	45	17
51	11.	135	137	38	20
52	18.	136	132	28	15
53	25.	134	135	38	19

The Totals { Chriſtened — — 6614
Buried — — 7920
Whereof of the Plague 2124

* Bell's London's Remembrancer.

A TABLE

1607.

A TABLE of the
CHRISTENINGS and MORTALITY
For the Year 1606 and 1607.*

Weeks.	Days of the Month.	Chriſt.	Bur.	Pla.	Par. infec.	Weeks.	Days of the Month.	Chriſt.	Bur.	Pla.	Par. infec.
1	January 1.	117	150	38	18	27	July 2.	111	112	27	7
2	8.	161	115	26	12	28	9.	103	117	33	10
3	15.	118	121	16	8	29	16.	89	154	37	12
4	22.	135	106	14	7	30	23.	126	152	51	17
5	29.	135	134	28	12	31	30.	115	156	43	19
6	Febr. 5.	134	158	33	14	32	Auguſt 6.	112	187	77	19
7	12.	130	147	20	12	33	13.	102	172	69	11
8	19.	140	149	17	9	34	20.	134	189	76	32
9	26.	115	120	14	9	35	27.	124	175	71	26
10	March 5.	147	127	20	13	36	Septem. 3.	130	232	105	36
11	12.	133	130	30	14	37	10.	149	243	121	38
12	19.	146	138	33	13	38	17.	137	264	124	36
13	26.	133	124	22	9	39	24.	119	302	177	55
14	April 2.	130	123	13	5	40	October 1.	157	283	150	48
15	9.	145	138	23	12	41	8.	116	230	113	32
16	16.	143	146	27	11	42	15.	110	223	110	45
17	23.	98	133	26	12	43	22.	150	215	82	37
18	30.	115	125	43	14	44	29.	143	198	68	31
19	May 7.	130	94	17	7	45	Novem. 5.	114	196	66	25
20	14.	110	128	15	3	46	12.	135	186	55	24
21	21.	116	126	25	9	47	19.	133	148	46	23
22	28.	120	116	13	5	48	26.	138	130	21	12
23	June 4.	104	100	11	4	49	Decem. 3.	154	126	19	12
24	11.	128	90	10	4	50	10.	121	122	28	16
25	18.	111	86	14	2	51	17.	129	131	7	5
26	25.	122	126	21	10	52	24.	115	129	9	5

The Totals { Chriſtened — — 6582
Buried — — 8022
Whereof of the Plague 2352

* Bell's London's Remembrancer.

A TABLE

1608.

A TABLE of the
CHRISTENINGS and MORTALITY
For the Year 1607 and 1608. *

Weeks.	Days of the Month.	Chriſt.	Bur.	Pla.	Par. infec.	Weeks.	Days of the Month.	Chriſt.	Bur.	Pla.	Par. infec.
1	Dec. 31.	118	148	4	4	27	June 30.	114	116	16	9
2	January 7.	149	120	3	3	28	July 7.	107	134	16	12
3	14.	127	130	4	4	29	14.	119	162	26	17
4	21.	153	130	3	2	30	21.	113	156	24	16
5	28.	160	141	2	2	31	28.	130	233	50	25
6	Febr. 4.	124	112	4	2	32	Auguſt 4.	109	184	45	21
7	11.	129	132	0	0	33	11.	136	191	70	32
8	18.	152	150	6	6	34	18.	130	203	79	29
9	25.	124	117	1	1	35	25.	129	197	73	31
10	March 3.	171	123	7	7	36	Septem. 1.	134	275	123	39
11	10.	162	136	3	3	37	8.	153	250	136	42
12	17.	143	137	2	2	38	15.	155	248	107	38
13	24.	144	127	5	4	39	22.	157	273	143	38
14	31.	144	114	4	3	40	29.	124	296	147	48
15	April 7.	126	140	1	1	41	October 6.	122	239	103	32
16	14.	155	134	4	3	42	13.	140	258	131	43
17	21.	136	163	6	4	43	20.	142	247	124	40
18	28.	126	147	4	3	44	27.	155	241	102	32
19	May 5.	102	125	7	3	45	Novem. 3.	135	236	109	37
20	12.	122	140	6	6	46	10.	136	189	72	29
21	19.	106	125	7	7	47	17.	150	205	69	27
22	26.	95	138	11	8	48	24.	109	205	70	32
23	June 2.	93	133	10	8	49	Decem. 1.	152	240	90	37
24	9.	108	139	14	10	50	8.	134	194	68	29
25	16.	127	122	10	8	51	15.	139	197	75	29
26	23.	104	138	13	9	52	22.	131	190	53	25

The Totals	Chriſtened — —	6845
	Buried — —	9020
	Whereof of the Plague	2262

* Bell's London's Remembrancer.

A TABLE

1609.

A TABLE of the

CHRISTENINGS and MORTALITY

For the Year 1608 and 1609.*

Weeks.	Days of the Month.	Christ.	Bur.	Pla.	Par. infec.	Weeks.	Days of the Month.	Christ.	Bur.	Pla.	Par. infec.
1	Decem. 29.	117	165	39	21	27	June 29.	109	182	47	29
2	January 5.	125	189	56	25	28	July 6.	140	194	60	26
3	12.	117	201	60	32	29	13.	102	198	57	29
4	19.	135	226	81	32	30	20.	104	189	58	21
5	26.	142	197	67	28	31	27.	135	229	91	41
6	Febr. 2.	126	187	56	24	32	August 3.	124	239	100	34
7	9.	138	228	90	33	33	10.	115	280	126	42
8	16.	136	204	62	26	34	17.	127	264	101	37
9	23.	152	177	46	26	35	24.	91	296	150	42
10	March 2.	140	173	32	17	36	31.	123	364	177	48
11	9.	143	184	44	24	37	Septem. 7.	132	300	141	44
12	16.	117	166	33	25	38	14.	107	335	158	47
13	23.	161	230	68	27	39	21.	105	386	210	55
14	30.	127	236	89	36	40	28.	136	311	144	51
15	April 6.	136	232	73	37	41	October 5.	129	306	154	47
16	13.	152	237	93	34	42	12.	123	335	177	54
17	20.	143	235	86	40	43	19.	143	313	131	43
18	27.	105	274	99	39	44	26.	121	199	55	24
19	May 4.	92	252	92	38	45	Novem. 2.	121	237	84	33
20	11.	113	242	89	37	46	9.	116	224	69	29
21	18.	98	222	93	35	47	16.	118	234	67	31
22	25.	114	194	66	33	48	23.	125	187	59	28
23	June 1.	100	188	52	27	49	30.	137	181	51	24
24	8.	91	215	65	26	50	Decem. 7.	139	139	18	13
25	15.	97	158	36	17	51	14.	125	150	23	14
26	22.	89	153	43	25	52	21.	135	148	23	13

The Totals { Christened — — 6388
Buried — — 11785
Whereof of the Plague 4240

* Bell's London's Remembrancer.

1610.

A TABLE of the
CHRISTENINGS and MORTALITY
For the Year 1609 and 1610.*

Weeks.	Days of the Month.	Chriſt.	Bur.	Pla.	Par. infec.	Weeks.	Days of the Month.	Chriſt.	Bur.	Pla.	Par. infec.
1	Decem. 28.	139	161	39	23	27	June 28.	106	162	25	11
2	January 4.	127	168	32	18	28	July 5.	118	194	38	15
3	11.	137	144	19	13	29	12.	118	187	45	18
4	18.	134	159	31	20	30	19.	110	171	45	20
5	25.	141	152	27	16	31	26.	122	187	40	17
6	Febr. 1.	140	140	21	13	32	Auguſt 2.	109	187	47	20
7	8.	170	133	11	9	33	9.	156	234	50	23
8	15.	130	132	18	14	34	16.	131	250	73	26
9	22.	157	149	10	8	35	23.	112	208	60	26
10	March 1.	133	144	7	7	36	30.	134	294	99	37
11	8.	149	142	6	5	37	Septem. 6.	124	286	96	31
12	15.	150	150	17	16	38	13.	135	272	89	33
13	22.	147	137	8	6	39	20.	119	256	86	34
14	29.	126	139	7	6	40	27.	117	254	72	33
15	April 5.	151	140	8	8	41	October 4.	141	219	63	27
16	12.	155	142	13	9	42	11.	143	221	79	35
17	19.	133	168	15	11	43	18.	122	197	59	32
18	26.	135	145	14	10	44	25.	134	187	49	28
19	May 3.	118	160	21	16	45	Novem. 1.	114	187	58	23
20	10.	111	130	19	14	46	8.	152	196	40	19
21	17.	123	131	18	12	47	15.	147	160	22	16
22	24.	121	128	11	10	48	22.	136	163	42	19
23	31.	106	128	13	9	49	29.	142	179	39	19
24	June 7.	100	143	9	8	50	Decem. 6.	140	142	15	12
25	14.	117	158	14	9	51	13.	148	146	12	10
26	21.	91	177	26	14	52	20.	114	148	26	17

The Totals { Chriſtened — — 6785
Buried — — 9087
Whereof of the Plague 1803

* Bell's London's Remembrancer.

The

1624.

The General BILL for the whole Year of all the BURIALS and CHRISTENINGS, as well within the City of LONDON and the Liberties thereof, as in the nine Out Pariſhes adjoining to the City, with the Peſt-houſe belonging to the ſame,

From Thurſday the 18th of December 1623, to Thurſday the 16th of December 1624.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON. *

Buried this Year in fourſcore and ſeventeen Pariſhes of London within the Walls —	3386
Whereof of the Plague — — — — —	1
Buried this Year in the ſixteen Pariſhes of London and the Peſt-houſe, being within the Liberties, and without the Walls — —	5924
Whereof of the Plague — — — — —	5
The whole Sum of the Burials in London and the Liberties thereof is this Year —	9310
Whereof of the Plague — — — —	6
Buried of the Plague without the Liberties, in Middleſex and Surrey, this whole Year	0
Chriſtened in London and the Liberties thereof this Year — —	6368
Buried this Year in the nine Out Pariſhes adjoining to London and out of the Freedom	2900
Whereof of the Plague — — — —	5
The Total of the Burials in the Places aforeſaid is — —	12210
Whereof of the Plague — — — —	11
Chriſtened in all the aforeſaid Places this Year — — —	8299
Pariſhes clear of the Plague — — —	116
Pariſhes that have been infected this Year — — —	6

* GRAUNT.

1625.

A TABLE of the CHRISTENINGS and MORTALITY For the Year 1624 and 1625. *

Weeks.	Days of the Month.	Christ.	Bur.	Pla.	Par. infec.
1	Decem. 23.	165	183	0	0
2	30.	176	211	0	0
3	January 6.	199	220	1	1
4	13.	194	196	1	1
5	20.	160	240	0	0
6	27.	178	226	0	0
7	Febr. 3.	178	174	3	1
8	10.	161	204	5	2
9	17.	181	211	3	1
10	24.	190	252	1	1
11	March 3.	185	207	0	0
12	10.	196	210	0	0
13	17.	175	262	4	3
14	24.	187	226	8	2
15	31.	133	243	11	4
16	April 7.	184	239	10	4
17	14.	154	256	24	10
18	21.	160	230	25	11
19	28.	134	305	26	9
20	May 5.	158	292	30	10
21	12.	140	332	45	13
22	19.	182	379	71	17
23	26.	145	401	78	16
24	June 2.	123	395	69	20
25	9.	125	434	91	25
26	16.	110	510	165	31
27	June 23.	110	640	239	32
28	30.	125	942	390	50
29	July 7.	114	1222	593	57
30	14.	115	1741	1004	82
31	21.	137	2850	1819	96
32	28.	155	3583	2471	103
33	Auguſt 4.	128	4517	3659	114
34	11.	125	4855	4115	112
35	18.	134	5205	4463	114
36	25.	135	4841	4218	114
37	Septem. 1.	117	3897	3344	117
38	8.	112	3157	2550	116
39	15.	100	2148	1672	107
40	22.	75	1994	1551	111
41	29.	78	1236	852	103
42	October 6.	77	838	538	99
43	13.	85	815	511	91
44	20.	91	651	331	76
45	27.	77	375	134	47
46	Novem. 3.	82	357	89	41
47	10.	85	319	92	35
48	17.	88	274	48	22
49	24.	88	231	27	16
50	Decem. 1.	93	190	15	12
51	8.	90	181	15	7
52	15.	94	168	6	5

The Totals { Chriſtened — — 6983
Buried —— — 54265
Whereof of the Plague 35417

* Bell's London's Remembrancer.

A General

1625.

A General BILL of the whole Number of BURIALS, which have been buried of all Diſeaſes, and alſo of the Plague, in every Pariſh within the City of LONDON, and the Liberties thereof, as alſo in the nine Out Pariſhes adjoining to the ſaid City, with the Peſt-houſe belonging to the ſame,

From Thurſday, December 16, 1624, to Thurſday the 15th of December 1625.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON.

LONDON.	Bur.	Pla.
St ALBANS Wood-ſtreet	188	78
Alhallows Barking	397	263
Alhallows Bread-ſtreet	34	14
Alhallows the Great	442	302
Alhallows Honey-lane	18	8
Alhallows the Leſs	259	205
Alhallows Lumbard-ſtreet	86	44
Alhallows Stainings	183	138
Alhallows the Wall	301	155
St Alphage Cripplegate	240	190
St Andrew Hubbard	146	101
St Andrews Underſhaft	219	149
St Andrews Wardrobe	373	191
St Anns Alderſgate	196	128
St Anns Black Friars	336	215
St Antholins Pariſh	62	31
St Auſtins Pariſh	72	40
St Bartholomew Exchange	52	24
St Bennets Fynck	108	57
St Bennets Grace-church	48	14
St Bennets Pauls Wharf	226	131
St Bennets Sherehog	24	8
St Botolphs Billingſgate	99	66
Chriſt Church Pariſh	611	371
St Chriſtophers	48	28
St Clements Eaſtcheap	87	72
St Dionis Back-church	99	59
St Dunſtans in the Eaſt	335	225
St Edmunds Lumbard-ſtreet	78	49
St Ethelborough	205	101
St Faiths	89	45
St Foſters	149	102
St Gabriel Fen-church	71	54
St George Botolph-lane	30	19
St Gregories by Pauls	296	196

	Bur.	Pla.
St Helens Biſhopſgate	136	71
St James Garlickhithe	180	109
St John Baptiſt	122	79
St John Evangeliſt	7	0
St John Zacharies	143	97
St James Dukes-place	310	154
St Katherine Coleman	26	175
St Katherine Cree-church	886	373
St Lawrence Jewry	91	55
St Lawrence Pountney	206	127
St Leonards Eaſtcheap	55	26
St Leonards Foſter-lane	292	209
St Magnus	137	85
St Margarets Lothbury	114	64
St Margarets Moſes	37	25
St Margarets New Fiſh-ſtreet	123	82
St Margaret Pattons	77	50
St Mary Abchurch	98	58
St Mary Aldermanbury	126	79
St Mary Aldermary	92	54
St Mary le Bow	35	19
St Mary Bothaw	22	14
St Mary Cole-church	26	11
St Mary Hill	152	84
St Mary Mounthaw	76	58
St Mary Summerſet	270	192
St Mary Stainings	70	44
St Mary Wool-church	58	35
St Mary Woolnoth	82	50
St Martins Iremonger-lane	25	18
St Martins Ludgate	254	164
St Martins Orgars	88	47
St Martins Outwich	60	30
St Martins in the Vintrey	339	208
St Matthew Friday-ſtreet	24	11

St Maudlins

1625.

	Bur.	Pla.		Bur.	Pla.
St Maudlins Milk-ſtreet	401	23	St Olaves Hart-ſtreet	266	195
St Maudlins Old Fiſh-ſtreet	225	142	St Olaves Jewry	43	25
St Michael Baſſiſhaw	199	139	St Olaves Silver-ſtreet	274	103
St Michael Cornhill	155	79	St Pancras Soper-lane	17	8
St Michael Crooked-lane	144	91	St Peters Cheap	68	44
St Michael Queenhithe	215	157	St Peters Cornhill	318	78
St Michael in the Querne	53	30	St Peter Pauls Wharf	97	68
St Michael Royal	111	61	St Peters Poor	52	27
St Michael Wood-ſtreet	189	68	St Stevens Coleman-ſtreet	506	350
St Mildreds Bread-ſtreet	60	44	St Stevens Walbrooke	25	13
St Mildreds Poultrey	94	45	St Swithins London-ſtone	99	60
St Nicholas Acons	33	13	St Thomas Apoſtles	141	107
St Nicholas Coleabby	87	67	Trinity Pariſh	148	87
St Nicholas Olaves	70	43			

Buried within the ninety-ſeven Pariſhes within the Walls of all Diſeaſes	14340
Of the Plague	9197

	Bur.	Pla.		Bur.	Pla.
St Andrews Holborn	2190	1636	St George Southwark	1068	912
St Bartholomew the Great	516	360	St Giles Cripplegate	3988	2338
St Bartholomew the Leſs	111	65	St Olave's Southwark	3689	2609
St Brides Pariſh	1481	1031	St Savior Southwark	2746	1671
St Botolph Aldgate	2573	1653	St Sepulchres Pariſh	3425	2420
Bridewell Precinct	213	152	St Thomas in Southwark	335	277
St Botolph Biſhopſgate	2334	714	Trinity Minories	131	87
St Botolph Alderſgate	578	307	At the Peſt-houſe	194	189
St Dunſtans Weſt	860	642			

Buried in the ſixteen Pariſhes without the Walls, ſtanding Part within the Liberties, in Middleſex, Surrey, and at the Peſt-houſe	26972
Of the Plague	17153

Buried in the nine Out Pariſhes

	Bur.	Pla.		Bur.	Pla.
St Clements Danes	1284	755	St Martins in the Fields	1470	973
St Giles in the Fields	1333	947	St Mary White-chappel	3305	2272
St James Clarkenwell	1191	903	St Magdalens Bermondſey	1127	889
St Katherines by the Tower	998	744	St Mary Savoy	250	176
St Leonards in Shoreditch	1995	1407			

Buried in the nine Out Pariſhes in Middleſex and Surrey	12953
Whereof of the Plague	9067

The Total within and without the Walls, &c.	54265
Of the Plague	35417
Chriſtnings this preſent Year	6983
Pariſhes clear	1
Pariſhes infected	121

A TABLE

	Pla.	Par. infec.
Cut of the	19	8
Dropſy an	25	12
Drowned	43	16
Exceſſive	50	20
Executed	40	16
Fainted in	77	26
Falling Si	56	15
Flox and	65	19
Found de	54	14
French P	67	22
Frighted	66	19
	63	25
	68	18
	57	22
	56	22
	66	26
	73	28
	60	22
	34	16
	29	16
	29	15
	18	9
	7	6
	20	12
	19	11
	5	4

St Maudlins Milk
St Maudlins Old
St Michael Baſſiſh
St Michael Cornh
St Michael Crook
St Michael Queer
St Michael in the
St Michael Royal
St Michael Wood
St Mildreds Breac
St Mildreds Poult
St Nicholas Acon
St Nicholas Cole
St Nicholas Olav

Buried witl
Of the Pla

St Andrews Holb
St Bartholomew t
St Bartholomew t
St Brides Pariſh
St Botolph Aldga
Bridewell Precinć
St Botolph Biſhoj
St Botolph Alder
St Dunſtans Weſt

Buried in
the Libe
Of the Pla

St Clements Dan
St Giles in the Fi
St James Clarker
St Katherines by
St Leonards in S

Buri
Whi

The
Of t
Chr
Pari
Pari

1630.

A TABLE of the
CHRISTENINGS and MORTALITY
For the Year 1629 and 1630. *

Weeks.	Days of the Month.	Chriſt.	Bur.	Pla.	Par. infec.	Weeks.	Days of the Month.	Chriſt.	Bur.	Pla.	Par. infec.
1	Dec. 24.	198	141	0	0	27	June 24.	174	205	19	8
2	31.	184	145	0	0	28	July 1.	149	209	25	12
3	January 7.	196	156	0	0	29	8.	141	217	43	16
4	14.	198	140	0	0	30	15.	148	250	50	20
5	21.	180	150	0	0	31	22.	163	229	40	16
6	28.	204	147	0	0	32	29.	172	279	77	26
7	Febr. 4.	203	151	0	0	33	Auguſt 5.	140	250	56	15
8	11.	201	124	0	0	34	12.	142	246	65	19
9	18.	201	163	0	0	35	19.	184	269	54	14
10	25.	179	162	0	0	36	26.	163	270	67	22
11	March 4.	219	170	0	0	37	Septem. 2.	159	230	66	19
12	11.	220	161	2	2	38	9.	167	259	63	25
13	18.	187	153	4	1	39	16.	175	264	68	18
14	25.	205	172	0	0	40	23.	168	274	57	22
15	April 1.	189	161	1	1	41	30.	165	269	56	22
16	8.	204	183	2	2	42	October 7.	186	236	66	26
17	15.	203	173	11	6	43	14.	166	261	73	28
18	22.	218	188	7	3	44	21.	191	248	60	22
19	29.	192	165	3	2	45	28.	164	214	34	16
20	May 6.	177	196	15	6	46	Novem. 4.	154	242	29	16
21	13.	175	194	13	9	47	11.	176	215	29	15
22	20.	158	187	20	10	48	18.	201	200	18	9
23	27.	158	209	24	8	49	25.	210	226	7	6
24	June 3.	180	193	17	10	50	Decem. 2.	206	221	20	12
25	10.	159	192	19	13	51	9.	150	198	19	11
26	17.	126	180	13	8	52	16.	187	217	5	4

The Totals { Chriſtened —— —— 9315
Buried — —— 10554
Whereof of the Plague 1317

* Bell's London's Remembrancer.

A TABLE

1636.

A TABLE of the
CHRISTENINGS and MORTALITY
For the Year 1635 and 1636. *

Weeks.	Days of the Month.	Chriſt.	Bur.	Pla.	Par. infec.	Weeks.	Days of the Month.	Chriſt.	Bur.	Pla.	Par. infec.
1	Dec. 24.	231	170	0	0	27	June 23.	149	257	65	12
2	31.	195	174	0	0	28	30.	141	273	82	15
3	January 7.	217	189	0	0	29	July 7.	152	265	64	16
4	14.	242	174	0	0	30	14.	142	298	86	18
5	21.	220	190	0	0	31	21.	146	350	108	19
6	28.	214	171	0	0	32	28.	183	365	136	29
7	Febr. 4.	227	183	0	0	33	Auguſt 4.	152	394	181	35
8	11.	234	160	0	0	34	11.	166	465	244	35
9	18.	207	203	0	0	35	18.	167	546	284	43
10	25.	198	238	0	0	36	25.	161	690	380	45
11	March 3.	212	198	0	0	37	Septem. 1.	163	835	536	51
12	10.	231	194	0	0	38	8.	153	921	567	55
13	17.	244	187	0	0	39	15.	166	1106	728	60
14	24.	215	177	0	0	40	22.	172	1018	645	64
15	31.	193	196	0	0	41	29.	168	1211	796	57
16	April 7.	202	199	2	1	42	October 6.	170	1195	790	62
17	14.	221	205	4	2	43	13.	164	1147	682	59
18	21.	204	205	7	3	44	20.	174	855	476	52
19	28.	271	210	4	3	45	27.	133	779	404	58
20	May 5.	197	206	4	3	46	Novem. 3.	153	1156	755	67
21	12.	199	254	41	11	47	10.	164	966	635	64
22	19.	171	244	22	8	48	17.	143	827	512	59
23	26.	160	263	38	11	49	24.	162	747	408	46
24	June 2.	189	276	51	13	50	Decem. 1.	168	550	291	48
25	9.	153	275	64	15	51	8.	175	385	143	34
26	16.	145	325	86	16	52	15.	134	324	79	23

The Totals { Chriſtened — — 9522
Buried — — 23359
Whereof of the Plague 10400

* Bell's London's Remembrancer.

A General

1636.

A General BILL for this preſent Yeare,

Ending the 15th Day of December 1636.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.	Pla.
St ALBAN Wood-ſtreet —	42	13
Alhallows Barking —	142	32
Alhallows Bread-ſtreet ——	14	2
Alhallows the Great ——	123	42
Alhallows Honey-lane —	3	0
Alhallows the Leſs ——	47	8
Alhallows Lombard-ſtreet ——	22	2
Alhallows Staining ——	28	5
Alhallows the Wall — —	111	40
St Alphage —— ——	62	11
St Andrew Hubbard ——	26	10
St Andrew Underſhaft ——	44	11
St Andrew-Wardrobe ——	120	44
St Anne Alderſgate — ——	104	68
St Anne Black Friars ——	153	59
St Antholin's — —— ——	24	7
St Auſtin's —— — ——	20	3
St Barthol. Exchange —— ——	19	0
St Bennet Fink — ——	25	7
St Bennet Grace-church ——	16	1
St Bennet Paul's Wharf — —	112	49
St Bennet Sherehog ——	9	0
St Botolph Billingſgate ——	30	9
Chriſt Church —— ——	183	70
St Chriſtophers —— ——	13	6
St Clement Eaſtcheap ——	18	3
St Dionis Back-church ——	17	2
St Dunſtan Eaſt — — —	64	8
St Edmund Lombard-ſtreet —	15	2
St Ethelburg —— ——	61	27
St Faith —— ——	33	12
St Foſter —— ——	40	7
St Gabriel Fen-church ——	14	5
St George Botolph-lane ——	19	4
St Gregory by St Paul — —	99	39
St Hellen —— ——	29	2
St James Dukes-place —— —	45	17
St James Garlickhith — ——	37	1
St John Baptiſt —— ——	19	4
St John Evangeliſt —— ——	1	0
St John Zachary's — —	39	14
St Katherine Coleman ——	135	73
St Katherine Cree-church ——	129	37
St Laurence Jewry — ——	26	3
St Laurence Poultney ——	35	9
St Leonard's Eaſtcheap —— —	10	2
St Leonard's Foſter-lane ——	95	40
St Magnus —— ——	42	14
St Margaret Lothbury —— —	26	0
St Margaret Moſes —— ——	24	11
St Margaret New Fiſh-ſtreet —	28	12
St Margaret Pattons —— ——	23	11
St Mary Abchurch —— ——	24	2
St Mary Aldermanbury ——	35	11
St Mary Aldermary —— ——	39	12
St Mary le Bow —— ——	14	4
St Mary Bothaw —— ——	10	1
St Mary Cole-church ——	10	1
St Mary Hill —— ——	42	7
St Mary Mounthaw —— ——	18	1
St Mary Somerſet —— —	83	27
St Mary Staining —— ——	11	3
St Mary Wool-church ——	18	5
St Mary Woolnoth ——	24	3
St Martin Ironmonger-lane ——	8	0
St Martin Ludgate —— ——	51	9
St Martin Orgars —— —	20	2
St Martin Outwich —— ——	17	3
St Martin Vintrey —— ——	85	21
St Matthew Friday-ſtreet ——	14	1

1636.

	Bur.	Pla.
St Magdalen Milk-ſtreet	9	0
St Magdalen Old Fiſh-ſtreet	72	85
St Michael Baſſiſhaw	45	9
St Michael Cornhill	27	9
St Michael Crooked-lane	33	8
St Michael Queenhith	52	17
St Michael Quern	11	1
St Michael Royal	30	0
St Michael Wood-ſtreet	74	21
St Mildred Bread-ſtreet	24	6
St Mildred Poultry	36	7
St Nicholas Acons	16	5
St Nicholas Coleabbey	37	12
St Nicholas Olaves	21	6
St Olave Hart-ſtreet	67	15
St Olave Jewry	18	0
St Olave Silver-ſtreet	39	10
St Pancras Soper-lane	7	0
St Peter's Cheap	18	2
St Peter Cornhill	27	7
St Peter Paul's Wharf	29	12
St Peter Poor	15	0
St Stephen Coleman-ſtreet	92	29
St Stephen Walbrook	8	0
St Swithin	22	3
St Thomas Apoſtle	27	8
Trinity Pariſh	31	7

Buried in the ninety-ſeven Pariſhes within the Walls of all Diſeaſes 4025
Whereof of the Plague 1200

	Bur.	Pla.
St Andrew Holbourn	922	429
St Bartholomew the Great	248	133
St Bartholomew the Leſs	40	18
St Bridget	483	153
Bridewell Precinct	51	13
St Botolph Alderſgate	245	125
St Botolph Aldgate	1501	735
St Botolph Biſhopſgate	1239	515
St Dunſtan Weſt	240	49
St George Southwark	1044	514
St Giles Cripplegate	2374	870
St Olave's Southwark	1537	847
St Saviour's Southwark	1269	742
St Sepulchre's	1327	566
St Thomas Southwark	214	140
Trinity Minories	46	21
At the Peſt-houſe	100	96

Buried in the ſixteen Pariſhes without the Walls, and at the Peſt-houſe 12280
Whereof of the Plague 5956

	Bur.	Pla.
St Clement Danes	470	117
St Giles in the Fields	863	428
St James Clarkenwell	649	364
St Katherines by the Tower	577	318
St Leonard Shoreditch	767	406
St Martin in the Fields	850	294
St Mary White-chapel	1766	1060
St Magdalen Bermondſey	406	203
Savoy Pariſh	106	54

Buried in the nine Out Pariſhes in Middleſex and Surrey 6454
Whereof of the Plague 3244

The Total of all Diſeaſes within the Walls, without the Walls, in the Liberties, in Middleſex and Surrey, with the nine Out Pariſhes, and the Peſt-houſe 23359
Whereof buried of the Plague this preſent Year 10400
The Total of all Chriſtnings this preſent Year 9522
Pariſhes infected 110
Pariſhes clear this Year 12

A TABLE

1637.

A TABLE of the
CHRISTENINGS and MORTALITY
For the Year 1636 and 1637. *

Weeks.	Days of the Month.	Christ.	Bur.	Pla.	Par. infec.	Weeks.	Days of the Month.	Christ.	Bur.	Pla.	Par. infec.
1	Decem. 22.	157	263	67	23	27	June 22.	160	246	83	28
2	29.	156	318	108	26	28	29.	142	314	133	36
3	January 5.	162	333	118	33	29	July 6.	147	303	141	34
4	12.	157	260	66	21	30	13.	145	254	109	32
5	19.	172	223	51	18	31	20.	148	263	125	36
6	26.	199	248	69	24	32	27.	143	256	86	27
7	Febr. 2.	213	293	92	25	33	August 3.	160	223	63	26
8	9.	185	270	92	31	34	10.	146	228	62	27
9	16.	186	250	73	21	35	17.	144	213	49	18
10	23.	166	218	38	17	36	24.	164	178	38	19
11	March 2.	186	214	57	25	37	31.	168	170	25	13
12	9.	204	274	88	29	38	Septem. 7.	152	181	31	14
13	16.	193	255	67	29	39	14.	133	171	19	9
14	23.	177	222	57	25	40	21.	195	150	19	10
15	30.	194	299	101	30	41	28.	176	167	24	13
16	April 6.	171	250	86	30	42	October 5.	212	135	14	9
17	13.	187	235	67	26	43	12.	213	164	14	10
18	20.	188	252	81	32	44	19.	199	135	9	5
19	27.	162	264	92	28	45	26.	225	151	7	5
20	May 4.	168	251	72	31	46	Novem. 2.	210	169	12	7
21	11.	163	242	85	29	47	9.	203	186	9	5
22	18.	157	250	66	27	48	16.	210	190	2	2
23	25.	172	255	67	23	49	23.	218	190	5	3
24	June 1.	135	232	61	25	50	30.	214	173	11	8
25	8.	127	218	58	26	51	Decem. 7.	227	168	10	8
26	15.	140	223	93	29	52	14.	229	173	10	8

The Totals { Christened — — 9160
Buried —— — 11763
Whereof of the Plague 3082

* Bell's London's Remembrancer.

1640.

A TABLE of the
CHRISTENINGS and MORTALITY
For the Year 1639 and 1640. *

Weeks.	Days of the Month.	Christ.	Bur.	Pla.	Par. infec.	Weeks.	Days of the Month.	Christ.	Bur.	Pla.	Par. infec.
1	Decem. 19.	219	197	3	2	28	June 25.	175	207	25	9
2	26.	180	143	4	2	29	July 2.	193	213	26	7
3	January 2.	210	172	8	5	30	9.	179	209	26	11
4	9.	217	184	2	2	31	16.	157	225	30	12
5	16.	186	178	2	2	32	23.	189	250	41	11
6	23.	189	181	1	1	33	30.	181	237	52	17
7	30.	201	220	0	0	34	August 6.	210	266	68	19
8	Febr. 6.	213	213	1	1	35	13.	215	298	81	21
9	13.	215	217	3	3	36	20.	195	320	98	24
10	20.	229	257	1	1	37	27.	209	336	89	25
11	27.	224	222	1	1	38	Septem. 3.	219	343	98	27
12	March 5.	249	233	3	2	39	10.	219	331	105	24
13	12.	229	263	3	3	40	17.	193	331	98	25
14	19.	224	232	4	3	41	24.	210	332	94	23
15	26.	230	236	4	4	42	October 1.	197	314	69	22
16	April 2.	239	247	3	2	43	8.	201	314	63	27
17	9.	188	231	1	1	44	15.	217	294	55	19
18	16.	209	208	4	4	45	22.	158	260	42	18
19	23.	225	219	2	2	46	29.	181	246	24	13
20	30.	213	239	3	3	47	Novem. 5.	192	210	17	12
21	May 7.	217	212	5	3	48	12.	200	240	33	17
22	14.	220	219	6	3	49	19.	201	228	23	12
23	21.	194	219	13	7	50	26.	234	224	13	8
24	28.	198	193	10	4	51	Decem. 3.	208	220	9	6
25	June 4.	209	224	19	8	52	10.	200	219	6	4
26	11.	165	238	34	10	53	17.	245	271	10	5
27	18.	180	236	15	6						

The Totals { Christened — — 10850
Buried — — 12771
Whereof of the Plague 1450

* Bell's London's Remembrancer.

A TABLE

1641.

A TABLE of the
CHRISTENINGS and MORTALITY
For the Year 1640 and 1641. *

Weeks.	Days of the Month.	Chriſt.	Bur.	Pla.	Par. infec.	Weeks.	Days of the Month.	Chriſt.	Bur.	Pla.	Par. infec.
1	Dec. 24.	235	374	4	4	27	June 24.	174	256	15	10
2	31.	202	322	3	2	28	July 1.	171	305	33	15
3	January 7.	210	220	3	2	29	8.	161	304	28	17
4	14.	184	194	4	1	30	15.	163	311	42	17
5	21.	206	222	5	4	31	22.	190	376	56	16
6	28.	210	218	3	3	32	29.	183	458	74	28
7	Febr. 4.	222	214	2	2	33	Auguſt 5.	212	467	100	25
8	11.	230	235	6	6	34	12.	179	507	80	28
9	18.	230	219	5	3	35	19.	192	558	131	30
10	25.	221	259	3	2	36	26.	203	610	139	35
11	March 4.	222	232	2	1	37	Septem. 2.	201	703	183	36
12	11.	209	242	2	2	38	9.	202	659	185	38
13	18.	205	233	3	2	39	16.	206	652	197	38
14	25.	221	234	3	3	40	23.	210	660	239	50
15	April 1.	228	226	8	4	41	30.	176	630	204	50
16	8.	218	272	5	3	42	October 7.	202	654	239	49
17	15.	216	229	4	3	43	14.	196	604	234	54
18	22.	234	267	7	7	44	21.	198	518	184	48
19	29.	193	225	7	6	45	28.	174	464	144	36
20	May 6.	208	241	12	8	46	Novem. 4.	177	408	106	31
21	13.	204	254	13	10	47	11.	183	337	79	25
22	20.	191	234	11	10	48	18.	209	316	61	20
23	27.	192	245	16	10	49	25.	223	296	44	16
24	June 3.	168	289	27	13	50	Decem. 2.	198	279	41	17
25	10.	191	300	20	13	51	9.	209	245	15	10
26	17.	138	268	19	11	52	16.	190	246	17	19

The Totals { Chriſtened —— — 10370
Buried — —— 18291
Whereof of the Plague 3067

* Bell's London's Remembrancer.

A TABLE

1642.

A TABLE of the
CHRISTENINGS and MORTALITY
For the Year 1641 and 1642.*

Weeks.	Days of the Month.	Christ.	Bur.	Pla.	Par. infec.	Weeks.	Days of the Month.	Christ.	Bur.	Pla.	Par. infec.
1	Dec. 23.	213	208	15	9	27	June 23.	177	178	14	10
2	30.	196	267	51	23	28	30.	167	164	15	7
3	January 6.	213	253	26	14	29	July 7.	170	163	18	12
4	13.	193	202	11	9	30	14.	165	165	24	12
5	20.	180	208	14	8	31	21.	192	170	24	12
6	27.	235	234	31	16	32	28.	200	187	29	18
7	Febr. 3.	213	214	29	15	33	Auguſt 4.	213	185	30	13
8	10.	259	250	23	14	34	11.	235	224	48	14
9	17.	215	187	14	7	35	18.	235	224	48	18
10	24.	210	231	26	9	36	25.	219	236	58	13
11	March 3.	237	239	17	10	37	Septem. 1.	237	227	60	20
12	10.	232	232	18	11	38	8.	188	274	70	21
13	17.	206	214	5	5	39	15.	218	279	66	23
14	24.	203	219	13	5	40	22.	228	351	103	23
15	31.	221	204	17	11	41	29.	206	362	126	33
16	April 7.	211	213	23	13	42	October 6.	205	331	83	24
17	14.	191	190	20	11	43	13.	235	281	81	29
18	21.	211	205	22	10	44	20.	227	315	98	29
19	28.	211	239	20	11	45	27.	190	275	51	23
20	May 5.	193	241	21	15	46	Novem. 3.	198	275	51	22
21	12.	198	230	29	11	47	10.	186	232	37	15
22	19.	201	245	25	15	48	17.	217	303	46	21
23	26.	174	217	27	15	49	24.	219	256	13	10
24	June 2.	174	211	37	16	50	Decem. 1.	223	250	19	13
25	9.	165	208	25	14	51	8.	228	250	18	9
26	16.	157	202	23	15	52	15.	181	247	12	10

The Totals { Chriſtened — — 10670
Buried — — 12167
Whereof of the Plague 1824

* Bell's London's Remembrancer.

A TABLE

1643.

A TABLE of the
CHRISTENINGS and MORTALITY
For the Year 1642 and 1643.*

Weeks.	Days of the Month.	Christ.	Bur.	Pla.	Par. infec.	Weeks.	Days of the Month.	Christ.	Bur.	Pla.	Par. infec.
1	Decem. 22.	209	267	10	9	27	June 22.	135	205	2	2
2	29.	174	199	8	6	28	29.	154	219	3	2
3	January 5.	210	248	10	7	29	July 6.	142	209	4	4
4	12.	207	248	11	6	30	13.	158	229	9	6
5	19.	200	273	11	7	31	20.	151	230	7	6
6	26.	234	257	8	7	32	27.	156	214	11	8
7	Febr. 2.	215	234	11	7	33	Auguſt 3.	186	218	8	6
8	9.	207	265	8	6	34	10.	159	285	27	14
9	16.	195	216	1	1	35	17.	188	295	24	11
10	23.	225	244	2	2	36	24.	170	308	26	13
11	March 2.	214	231	4	3	37	31.	175	285	28	16
12	9.	197	264	8	5	38	Septem. 7.	133	313	31	8
13	16.	211	211	3	2	39	14.	152	302	52	20
14	23.	214	224	2	2	40	21.	142	328	61	15
15	30.	216	218	9	5	41	28.	184	318	51	12
16	April 6.	186	212	9	7	42	October 5.	199	354	73	21
17	13.	230	203	6	4	43	12.	178	314	59	18
18	20.	214	247	7	7	44	19.	156	344	67	18
19	27.	188	250	5	4	45	26.	157	387	73	20
20	May 4.	185	233	9	7	46	Novem. 2.	157	309	59	22
21	11.	155	223	13	7	47	9.	169	261	56	18
22	18.	211	249	15	9	48	16.	144	272	27	11
23	25.	169	217	3	2	49	23.	154	238	14	8
24	June 1.	183	211	3	3	50	30.	172	227	14	10
25	8.	171	243	3	2	51	Decem. 7.	163	232	14	6
26	15.	180	208	2	2	52	14.	176	211	15	10

The Totals { Chriſtened — — 9410
Buried —— — 13202
Whereof the Plague 996

* Bell's London's Remembrancer.

A TABLE

1644.

A TABLE of the
CHRISTENINGS and MORTALITY
For the Year 1643 and 1644.*

Weeks.	Days of the Month.	Christ.	Bur.	Pla.	Par. infec.	Weeks.	Days of the Month.	Christ.	Bur.	Pla.	Par. infec.
1	Decem. 21.	157	215	25	12	28	June 27.	116	225	29	15
2	28.	116	176	8	6	29	July 4.	137	222	17	10
3	January 4.	180	194	18	8	30	11.	154	182	32	18
4	11.	156	192	10	5	31	18.	157	198	40	18
5	18.	168	199	19	9	32	25.	135	204	44	21
6	25.	157	216	11	8	33	Auguſt 1.	143	274	61	24
7	Febr. 1.	181	213	7	5	34	8.	126	215	48	17
8	8.	164	176	5	5	35	15.	116	255	58	20
9	15.	164	216	7	6	36	22.	122	219	67	28
10	22.	174	189	16	9	37	29.	132	237	67	24
11	29.	170	197	7	5	38	Septem. 5.	136	266	85	29
12	March 7.	158	203	4	3	39	12.	132	259	85	27
13	14.	158	171	7	3	40	19.	131	231	66	28
14	21.	174	194	5	5	41	26.	150	244	76	28
15	28.	176	158	5	3	42	October 3.	168	290	95	34
16	April 4.	148	170	8	6	43	10.	158	231	58	28
17	11.	169	189	17	9	44	17.	143	225	36	17
18	18.	162	158	17	8	45	24.	158	266	18	11
19	25.	122	175	17	7	46	31.	161	228	23	12
20	May 2.	185	183	17	11	47	Novem. 7.	171	246	25	12
21	9.	182	191	14	9	48	14.	168	200	15	8
22	16.	140	211	27	12	49	21.	172	164	4	4
23	23.	152	224	40	16	50	28.	171	186	15	7
24	30.	163	198	34	16	51	Decem. 5.	175	182	11	10
25	June 6.	125	155	24	14	52	12.	164	168	2	2
26	13.	113	163	20	13	53	19.	156	183	6	5
27	20.	138	207	20	14						

The Totals { Chriſtened — — 8104
Buried — — 10933
Whereof of the Plague 1492

* Bell's London's Remembrancer.

A TABLE

1645.

A TABLE of the

CHRISTENINGS and MORTALITY

For the Year 1644 and 1645. *

Weeks.	Days of the Month.	Chriſt.	Bur.	Pla.	Par. infec.	Weeks.	Days of the Month.	Chriſt.	Bur.	Pla.	Par. infec.
1	Decem. 26.	151	168	4	4	27	June 26.	140	146	18	8
2	January 2.	146	174	8	6	28	July 3.	122	151	15	7
3	9.	181	202	1	1	29	10.	135	170	24	6
4	16.	183	181	3	3	30	17.	134	214	26	10
5	23.	160	152	1	1	31	24.	134	216	41	15
6	30.	189	171	5	5	32	31.	127	235	62	21
7	Febr. 6.	165	158	7	5	33	Auguſt 7.	158	242	74	22
8	13.	165	172	4	4	34	14.	144	346	108	26
9	20.	163	166	5	4	35	21.	129	380	124	25
10	27.	158	162	4	3	36	28.	129	408	142	32
11	March 6.	157	161	2	2	37	Septem. 4.	173	389	151	31
12	13.	191	166	4	4	38	11.	150	325	117	36
13	20.	161	200	6	5	39	18.	169	359	107	34
14	27.	144	176	1	1	40	25.	151	339	122	33
15	April 3.	180	182	8	5	41	October 2.	186	309	98	29
16	10.	155	161	2	2	42	9.	191	328	114	28
17	17.	173	187	4	4	43	16.	191	331	115	31
18	24.	162	172	6	6	44	23.	172	243	57	25
19	May 1.	128	186	3	2	45	30.	135	261	63	22
20	8.	145	164	3	3	46	Novem. 6.	137	266	67	21
21	15.	117	160	4	4	47	13.	163	258	42	21
22	22.	119	186	3	3	48	20.	162	223	17	10
23	29.	133	154	2	1	49	27.	153	253	20	13
24	June 5.	150	152	2	2	50	Decem. 4.	154	222	12	8
25	12.	144	164	15	4	51	11.	137	234	13	9
26	19.	117	149	6	4	52	18.	153	205	9	6

The Totals { Chriſtened — — 7966
Buried —— — 11479
Whereof the Plague 1871

* Bell's London's Remembrancer.

1646.

A TABLE of the

CHRISTENINGS and MORTALITY

For the Year 1645 and 1646. *

Weeks.	Days of the Month.	Chriſt.	Bur.	Pla.	Par. infec.	Weeks.	Days of the Month.	Chriſt.	Bur.	Pla.	Par. infec.
1	Dec. 25.	125	205	6	4	27	June 25.	135	261	10	7
2	January 1.	143	217	2	2	28	July 2.	128	223	25	10
3	8.	161	171	0	0	29	9.	124	235	28	9
4	15.	138	241	2	2	30	16.	129	306	50	16
5	22.	165	200	0	0	31	23.	149	364	58	14
6	29.	160	202	1	1	32	30.	131	341	82	22
7	Febr. 5.	146	192	0	0	33	Auguſt 6.	143	384	106	30
8	12.	152	188	5	3	34	13.	152	419	132	31
9	19.	157	171	1	1	35	20.	155	472	195	43
10	26.	128	155	1	1	36	27.	159	517	207	40
11	March 5.	154	170	5	4	37	Septem. 3.	149	554	238	48
12	12.	146	197	5	2	38	10.	142	444	149	42
13	19.	158	186	3	3	39	17.	164	455	157	34
14	26.	153	158	5	5	40	24.	134	443	175	43
15	April 2.	128	190	2	2	41	October 1.	144	322	114	38
16	9.	167	210	4	3	42	8.	141	341	115	24
17	16.	173	204	8	6	43	15.	153	320	106	31
18	23.	142	209	6	5	44	22.	141	293	67	22
19	30.	155	172	5	4	45	29.	157	245	52	22
20	May 7.	137	186	6	4	46	Novem. 5.	163	275	55	17
21	14.	130	204	9	5	47	12.	159	200	27	13
22	21.	134	199	5	3	48	19.	151	226	37	18
23	28.	142	221	5	3	49	26.	145	223	34	16
24	June 4.	153	205	9	6	50	Decem. 3.	143	224	32	16
25	11.	126	170	13	5	51	10.	140	212	26	12
26	18.	130	225	22	10	52	17.	149	185	29	10

The Totals { Chriſtened — — 7583
Buried — — 3532
Whereof of the Plague 2436

* Bell's London's Remembrancer.

A TABLE

1647.

A TABLE of the
CHRISTENINGS and MORTALITY
For the Year 1646 and 1647. *

Weeks.	Days of the Month.	Chriſt.	Bur.	Pla.	Par. infec.	Weeks.	Days of the Month.	Chriſt.	Bur.	Pla.	Par. infec.
1	Decem. 22.	152	197	27	15	27	June 22.	118	187	16	8
2	29.	147	166	16	11	28	29.	121	197	9	9
3	January 5.	151	182	10	7	29	July 6.	148	268	47	12
4	12.	161	197	6	6	30	13.	147	317	97	20
5	19.	192	206	18	9	31	20.	151	390	128	21
6	26.	139	201	16	12	32	27.	147	363	151	33
7	Febr. 2.	151	184	9	7	33	Auguſt 3.	106	436	209	31
8	9.	138	164	13	9	34	10.	136	439	191	29
9	16.	178	204	2	2	35	17.	142	520	248	31
10	23.	149	205	1	1	36	24.	156	434	161	28
11	March 2.	257	189	4	3	37	31.	157	450	208	35
12	9.	159	199	2	2	38	Septem. 7.	119	546	267	45
13	16.	151	198	5	4	39	14.	142	430	184	40
14	23.	163	225	4	3	40	21.	137	494	215	42
15	30.	162	233	7	4	41	28.	141	432	212	41
16	April 6.	152	225	14	10	42	October 5.	160	403	183	38
17	13.	144	201	9	4	43	12.	145	359	172	49
18	20.	144	223	6	5	44	19.	153	367	163	38
19	27.	154	180	7	5	45	26.	133	331	114	34
20	May 4.	142	167	3	3	46	Novem. 2.	131	304	120	35
21	11.	130	185	11	4	47	9.	112	265	84	23
22	18.	129	176	5	5	48	16.	133	279	66	26
23	25.	119	159	1	1	49	23.	122	261	60	24
24	June 1.	130	197	12	7	50	30.	121	182	18	12
25	8.	107	158	7	4	51	Decem. 7.	117	231	17	9
26	15.	125	181	17	9	52	14.	111	172	15	11

The Totals { Chriſtened — — 7332
Buried —— — 14059
Whereof of the Plague 3597

* Bell's London's Remembrancer.

1657.

A General BILL for this preſent Year,

Ending the 15th of December 1657.

According to the Report made to the Right Hon. the Lord Mayor of the City of LONDON,
By the Company of Pariſh Clerks of London.

	Bur. Pl.
ALBANS Wood-ſtreet	35
Alhallows Barking	95
Alhallows Bread-ſtreet	21
Alhallows Great	91
Alhallows Honi-lane	5
Alhallows Leſſe	43
Alhallows Lumbard-ſtreet	20
Alhallows Staining	38
Alhallows the Wall	44
Alphage	30
Andrew Hubbard	23
Andrew Underſhaft	61
Andrew Wardrobe	76
Anne Alderſgate	34
Anne Black Fryers	79
Antholins	15
Auſtins	16
Barthol. Exchange	15
Bennets Fynck	27
Bennets Grace-church	15
Bennets Pauls Wharf	62
Bennets Sherehog	7
Botolph Billingſgate	25
Chriſt-church	114
Chriſtophers	16
Clements Eaſtcheap	12
Dionis Back-church	31
Dunſtans Eaſt	82
Edmunds Lumbard-ſtreet	20
Ethelborough	16
Faiths	17
Foſters	28
Gabriel Fen-church	15
George Botolph-lane	7
Gregories	89
Hellens	45
James Dukes-place	26
James Garlickhith	32
John Baptiſt	19
John Evangeliſt	6
John Zacharie	28
Katherine Coleman	49
Katherine Cree-church	58
Lawrence Jewrie	48
Lawrence Pountney	31
Leonard Eaſtcheap	9
Leonard Foſter-lane	41
Magnus	25
Margaret Lothbury	25
Margaret Moſes	9
Margaret New Fiſh-ſtreet	23
Margaret Pattons	20
Mary Abchurch	21
Mary Aldermanbury	33
Mary Aldermary	35
Mary le Bow	22
Mary Bothaw	17
Mary Cole-church	17
Mary Hill	35
Mary Mounthaw	12
Mary Summerſet	60
Mary Stainings	6
Mary Wool-church	25
Mary Woolnoth	22
Martins Iremonger	5
Martins Ludgate	50
Martins Orgars	26
Martins Outwich	14
Martins Vintrey	59
Matthew Friday-ſtreet	12
Maudlins Milk-ſtreet	11
Maudlins Old Fiſh-ſtreet	38
Michael Baſſiſhaw	35
Michael Cornhill	30
Michael Crooked-lane	44
Michael Queenhith	37
Michael Querne	16
Michael Royal	15
Michael Wood-ſtreet	17
Mildred Bread-ſtreet	26
Mildred Poultrey	21
Nicholas Acons	10
Nicholas Coleabby	19
Nicholas Olaves	19
Olaves Hart-ſtreet	48
Olaves Jewry	17
Olaves Silver-ſtreet	35
Pancras Soper-lane	5
Peters Cheap	17
Peters Cornhill	22
Peters Pauls Wharfe	29
Peters Poor	24
Stevens Coleman-ſtreet	100
Stevens Walbrook	15
Swithins	29
Thomas Apoſtle	21
Trinity	24

In the ninety-ſeven Pariſhes within 3014 Of the Plague 0

Andrew Holborne	631	Botolph Algate	686	Saviours	466
Bartholomew Great	75	Botolph Biſhopſgate	484	Sepulcres	617
Bartholomew Leſſe	56	Dunſtans Weſt	194	Thomas Southwark	61
Brides	302	Georges Southwark	283 1	Trinity Minories	0
Bridewell	26	Giles Cripplegate	899	Peſt-houſe	0
Botolph Alderſgate	161	Olaves Southwark	691 1		

In the ſixteen Pariſhes without 5648 Of the Plague 2

1657.

Clements Danes —— —417	Katherines Tower——142	Mary Whitechappel ——692 2
Covent Garden — ——117	Leonards Shoreditch - —284	Magdalens Bermond. —302
Giles in the Fields — —613	Martins in the Fields —808	Savoy —— —— —— 60
James Clarkenwell — —333		

In the Ten Out Pariſhes 3772 Of the Plague 2

Total of the { Burials — 12434 / Plague —— 4 / Chriſtenings — 6685

DISEASES and CASUALTIES.

Abortive and Stillborne	463	Flox and Small Pox ——	835	Murthered —— ——	5
Aged —— ——	869	Found dead in the Streets,&c.	9	Overlaid and Starv'd at Nurſe —— ——	44
Ague and Feaver ——	997	French Pox —— ——	25	Palſie —— — ——	20
Apoplexy and Suddenly—	113	Gout — —— ——	8	Plague —— — ——	4
Blaſted and Planet ——	5	Griefe —— — ——	10	Pluriſie —— ——	17
Bleeding —— ——	5	Griping and Plague in the Guts ——	446	Quinſie —— —— ——	7
Bloudy Flux, Scowring, and Flux ——	362	Hang'd and made away 'emſelves ——	24	Rickets —— ——	317
Burnt and Scalded — —	7	Head-ach and Head-mouldſhot — —	4	Riſing of the Lights ——	203
Calenture —— ——	3	Jaundies —— ——	46	Rupture —— — ——	19
Cancer and Wolfe ——	24	Jawfalne —— — ——	3	Scurvy —— ——	71
Childbed —— — ——	236	Impoſtume —— ——	80	Sores, Ulcers, &c. ——	40
Chriſomes and Infants ——	1162	Kill'd by Accidents — —	52	Spleen —— —— ——	2
Cold and Cough — ——	30	King's Evil —— ——	23	Spotted Feaver and Purples	56
Collick and Wind ——	113	Leproſie —— ——	0	Starved — — —— —	3
Conſumption and Tiſſick	2757	Lethargy —— — —	6	Stone and Strangury ——	73
Convulſion and Cramp —	807	Livergrowne —— ——	38	Stopping of the Stomach	129
Cut of the Stone — ——	3	Lunatick and Frenzy——	13	Surfet —— —— ——	137
Dropſie and Tympany —	631	Meagrome —— ——	7	Swine Pox —— ——	1
Drowned —— ——	63	Meaſles —— — ——	15	Teeth and Worms — —	878
Executed —— — ——	20	Mother —— — ——	0	Thruſh —— — ——	57
Falling Sickneſs —— —	1			Vomiting —— ——	16
Fiſtula and Gangrene ——	19			Wen —— —— ——	1

CHRISTENED		BURIED	
Males —	3396	Males —	6578
Females	3289	Females	5856
In all —	6685	In all —	12434

Decreaſed in the Burials in the 123 Pariſhes, and at the Peſt-houſe this Year 1487

Margaret Weſtm.	Chriſtened 473 / Buried — 705	Stepney	Chriſtened 876 / Buried — 1213	Hackney	Chriſtened 42 / Buried — 96
Iſlington	Chriſtened 67 / Buried — 112	Newington	Chriſtened 123 / Buried — 204	Redriff	Chriſtened 31 / Buried — 51
Lambeth	Chriſtened 137 / Buried — 231				

Total of { Burials in the above ſeven Pariſhes 2612 / Chriſtenings —— —— 1749

A General

1659.

A General BILL for this preſent Yeere,

Ending the 13th of December 1659.

According to the Report made to the Right Hon. the Lord Mayor of the City of LONDON,
By the Company of Pariſh Clerks of London, &c.

	Bur. Pl.
ALBANS Wood-ſtreet	44
Alhallowes Barking	120
Alhallowes Bread-ſtreet	12
Alhallowes Great	81
Alhallowes Honi-lane	14
Alhallowes Leſſe	49
Alhallowes Lombard-ſtreet	22
Alhallowes Staining	44
Alhallowes the Wall	69
Alphage	54
Andrew Hubbard	27
Andrew Underſhaft	57
Andrew Wardrobe	98
Anne Alderſgate	58
Anne Blacke Friers	87
Antholins Pariſh	21
Auſtins Pariſh	25
Barthol. Exchange	13
Bennet Finch	19
Bennet Grace-church	6
Bennet Paul's Wharfe	62
Bennet Sherehog	13
Botolph Billingſgate	24
Chriſts Church	111
Chriſtophers	20
Clements Eaſtcheape	10
Dionis Back-church	40
Dunſtans Eaſt	81 1
Edmunds Lombard-ſtreet	28
Ethelborough	23
Faiths	27
Foſters	34
Gabriel Fen-church	15
George Botolph-lane	11
Gregories by Pauls	101
Hellens	36
James Dukes-place	43
James Garlickhythe	42
John Baptiſt	40
John Evangeliſt	5
John Zacharie	34
Katherine Coleman	41
Katherine Cree-church	68
Lawrence Jewry	47
Lawrence Pountney	32
Leonard Eaſtcheap	14
Leonard Foſter-lane	68
Magnus Pariſh	44
Margaret Lothbury	33
Margaret Moſes	12
Margaret New Fiſh-ſtreet	22
Margaret Pattons	17
Mary Abchurch	30
Mary Aldermanbury	41
Mary Aldermary	33
Mary le Bow	18
Mary Bothaw	22
Mary Colchurch	8
Mary Hill	18
Mary Mounthaw	13
Mary Summerſet	73
Mary Staynings	12
Mary Wool-church	21
Mary Woolnoth	26
Martins Iremonger	8
Martins Ludgate	67
Martins Orgars	34
Martins Outwitch	14
Martins Vintrey	47
Matthew Friday-ſtreet	4
Maudlins Milk-ſtreet	16
Maudlins Old Fiſh-ſtreet	42
Michael Baſſiſhaw	47
Michael Cornhill	34
Michael Crooked-lane	29
Michael Queenhithe	54
Michael Querne	19
Michael Royal	35
Michael Wood-ſtreet	25
Michael Bread-ſtreet	20
Mildred Poultry	20
Nicholas Acons	10
Nicholas Coleabby	33
Nicholas Olaves	14
Olaves Hart-ſtreet	49
Olaves Jewry	19
Olaves Silver-ſtreet	27
Pancras Soper-lane	10
Peters Cheape	16
Peters Cornehill	40
Peters Pauls Wharfe	16
Peters Poore	20
Stevens Coleman-ſtreet	127
Stevens Walbrooke	20
Swithins	18
Thomas Apoſtles	32
Trinitie Pariſh	35

Buried in the ninety-ſeven Pariſhes within the Walls 3432 Whereof of the Plague 1

Andrew Holborne	848	Botolph Algate	871 4
Bartholomew Great	81	Botolph Biſhopſgate	511
Bartholomew Leſſe	52	Duſtans Weſt	251
Brides Pariſh	395	Georges Southwarke	243 1
Bridewell Precinct	24	Giles Cripplegate	1170 8
Botolph Alderſgate	162	Olaves Southwarke	924 4
Saviours Southwarke	522		
Sepulchres Pariſh	864 1		
Thomas Southwark	78		
Trinity Minories	10		
At the Peſt-houſe	0		

Buried in the ſixteen Pariſhes without the Walls 7006 Whereof of the Plague 18

1659.

Clement Danes — —479	Katherines Tower — —171	Mary White-chappel —827 16
Covent Garden — —139	Leonards Shoreditch——317	Magdalens Bermondſey 341 1
Giles in the Fields — —677	Martins in the Fields —937	Savoy Pariſh — — 82
James at Clarkenwell —348		

Buried in the ten Out Pariſhes in Middleſex and Surrey 4318 Whereof of the Plague 17

The Total of the Burials this Year	14756
Whereof of the Plague — —	36
The Total of all the Chriſtenings	5690

DISEASES and CASUALTIES.

Abortive and Stillborn — 421	Flox and Small Pox — —1523	Palſy — — — 17
Aged — — — 909	Found dead in the Streets, Fields, &c. — 2	Plague — — — 36
Ague and Fever — —2303	French Pox — — — 51	Pluriſy — — — 12
Apoplexy and Suddenly — — 91	Gout — — — 4	Quinſy and ſore Throat — — 21
Blaſted and Planet — — 3	Grief — — — 13	Rickets — — — 441
Bleeding and bloody Iſſue — 7	Griping in the Guts — — 253	Riſing of the Lights — — 210
Bloody Flux, Scowring, and Flux — 346	Hanged and made away themſelves — 11	Rupture — — — 12
Burnt and Scalded — — 6	Head-ach and Headmouldſhot 35	Scurvy — — — 82
Cancer, Gangrene and Fiſtula 63	Jaundies — — 102	Shot — — — 7
Canker, ſore Mouth and Thruſh 73	Impoſthume — — 105	Shingles — — — 1
Childbed — — — 226	Killed by ſeveral Accidents— 55	Sores, Ulcers, broken and bruiſed Limbs — 61
Chriſomes and Infants — 858	King's Evil — — 28	Spleen — — — 7
Cold, Cough and Hiccough — 33	Lethargy — — — 6	Spotted Fever and Purples — 368
Colick and Wind — — 116	Livergrown — — 8	Starved — — 7
Conſumption and Tiſſick —2982	Lunatick and Frenzy — 14	Strangury — — — 22
Convulſion — — 742	Megrims — — 5	Stopping of the Stomach — — 186
Cut of the Stone and Stone — 46	Meaſles — — — 6	Surfeit — — — 202
Dropſy and Tympany — 646	Mother — — 1	Swine Pox — — 2
Drowned — — 57	Murthered — — 7	Teeth and Worms — — 839
Executed — — — 7	Overlaid and Starved at Nurſe 46	Vomiting — — — 8
Falling Sickneſs — — 4		Wen — — — 1

CHRISTENED	Males — 2909	BURIED	Males — 7451	
	Females 2781		Females 7305	Of the Plague 36
	In all — 5690		In all 14756	

Decreaſed in the Burials in the 123 Pariſhes and at the Peſt-houſe this Year 237
Increaſed of the Plague in the 123 Pariſhes and at the Peſt-houſe this Year 22

Margaret Weſtm.	Chriſtened 415	Stepney	Chriſtened 695	Hackney	Chriſtened 50
	Buried — 822		Buried — 1392		Buried — 83
Iſlington	Chriſtened 56	Newington	Chriſtened 86	Redriff	Chriſtened 13
	Buried — 116		Buried — 138		Buried — 84
Lambeth	Chriſtened 103				
	Buried — 193				

The Total of all the Burials in the ſeven laſt Pariſhes this Year	2828
Whereof of the Plague — —	0
The Total of the Chriſtenings — —	1418

1660.

A General BILL for this preſent Year,

Ending the 11th Day of December 1660.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur. Pl.
St ALBAN Wood-ſtreet	32
Alhallows Barkin	83
Alhallows Bread-ſtreet	17
Alhallows Great	80
Alhallows Honey-lane	10
Alhallows Leſs	43
Alhallows Lombard-ſtreet	30
Alhallows Staining	35
Alhallows the Wall	50
St Alphage	33
St Andrew Hubbard	23
St Andrew Underſhaft	53
St Andrew Wardrobe	94
St Ann Alderſgate	39
St Ann Black Friars	87
St Antholin's Pariſh	18
St Auſtin's Pariſh	15
St Bartholomew Exchange	27
St Bennet Fink	26
St Bennet Gracechurch	4
St Bennet Paul's Wharf	67
St Bennet Sherehog	4
St Botolph Billingſgate	17
Chriſt Church	137
St Chriſtopher	15
St Clement Eaſtcheap	11
St Dionis Backchurch	34
St Dunſtan Eaſt	54
St Edmund Lombard-ſtr.	19
St Ethelborough	24
St Faith's	26
St Foſter's	26
St Gabriel Fenchurch	16
St George Botolph-lane	7
St Gregory by Paul's	94
St Helen's	34
St James Duke's Place	30
St James Garlickhithe	30
St John Baptiſt	34
St John Evangeliſt	6
St John Zachary	20
St Katherine Coleman	41
St Katherine Creechurch	54
St Laurence Jewry	46
St Laurence Pountney	36
St Leonard Eaſtcheap	11
St Leonard Foſter-lane	60
St Magnus Pariſh	32
St Margaret Lothbury	20
St Margaret Moſes	12
St Margaret New Fiſh-ſtr.	27
St Margaret Pattons	20
St Mary Abchurch	37
St Mary Aldermanbury	28
St Mary Aldermary	31
St Mary le Bow	12
St Mary Bothaw	15
St Mary Colechurch	10
St Mary Hill	24
St Mary Mounthaw	13
St Mary Somerſet	47
St Mary Staining	12
St Mary Woolchurch	21
St Mary Woolnoth	15
St Martin Ironmonger-lane	19
St Martin Ludgate	56
St Martin Orgars	24
St Martin Outwich	16
St Martin Vintrey	40
St Matthew Friday-ſtreet	16
St Maudlin Milk-ſtreet	16
St Maudlin Old Fiſh-ſtreet	33
St Michael Baſſiſhaw	50
St Michael Cornhill	32
St Michael Crooked-lane	32
St Michael Queenhithe	35
St Michael Querne	21
St Michael Royal	27
St Michael Wood-ſtreet	18
St Mildred Bread-ſtreet	25
St Mildred Poultry	23
St Nicholas Acons	8
St Nicholas Coleabby	46
St Nicholas Olave	18
St Olave Hart-ſtreet	63
St Olave Jewry	10
St Olave Silver-ſtreet	38
St Pancras Soper-lane	13
St Peter Cheap	12
St Peter Cornhill	28
St Peter Paul's Wharf	22
St Peter Poor	21
St Stephen Coleman-ſtreet	120
St Stephen Walbrook	15
St Swithin	25
St Thomas Apoſtle	28
Trinity Pariſh	20

Buried in the ninety-ſeven Pariſhes within the Walls 3098 Whereof of the Plague 0

St Andrew Holborn	665	St Botolph Aldgate	695	1	St Saviour Southwark 426
St Bartholomew Great	81	St Botolph Biſhopſgate	552	3	St Sepulchre's Pariſh 686
St Bartholomew Leſs	43	St Dunſtan Weſt	198		St Thomas Southwark 44
St Bride's Pariſh	349	St George Southwark	194		Trinity Minories 18
Bridewell Precinct	25	St Giles Cripplegate	962	7	At the Peſt-houſe 0
St Botolph Alderſgate	143	St Olave Southwark	575		

Buried in the ſixteen Pariſhes without the Walls 5656 Whereof of the Plague 12

1660.

St Giles in the Fields —606	Lambeth Parish — —183	St Mary Islington — — 108
Hackney Parish — — 65	St Leonard Shoreditch —285	St Mary Whitechapel — 665 1
St James Clarkenwell —333	St Magdalen Bermondsey 259	Rotherhith Parish — 33
St Katherine's Tower —155	St Mary Newington —114 1	Stepney Parish — — —1151

Buried in the twelve Out Parishes in Middlesex and Surrey 3957
Whereof of the Plague — — 2

St Clement Danes — —441	St Martin in the Fields 979	St Margaret Westminster 783
St Paul Covent Garden 113	St Mary Savoy — 91	At the Pest-house — — 0

Buried in the five Parishes in the City and Liberties of Westminster 2407
Whereof of the Plague — — — 0

The Total of all the Christenings — 6971
The Total of all the Burials this Year 15118
Whereof of the Plague — — 14

DISEASES and CASUALTIES.

Abortive and Stillborn 544	Falling Sickness — — 5	Mother — — 3
Aged — — —1095	Frighted — — 9	Murdered, Slain and Shot 20
Ague and Fever — —2148	Flox and Small Pox — 354	Overlaid and Starved — 43
Apoplexy and Suddenly— 68	Found dead in the Streets, Fields, &c. — 6	Palsy — — — 21
Blasted and Planet — — 8	French Pox — — — 31	Plague — — 14
Bleeding — — — 2	Gout — — — 2	Plurisy — — — 10
Bloody Flux, Scowring, and Flux — 251	Grief — — — 4	Quinsy and sore Throat — 14
Burnt and Scalded — — 6	Griping in the Guts — — 402	Rickets — — 521
Cancer, Gangrene, and Fistula — 52	Hanged and made away themselves — 36	Rising of the Lights — 249
Canker, sore Mouth and Thrush — 68	Head-ach and Head-mouldshot — 26	Rupture — — 28
Childbed — — — 194	Jaundies — — — 76	Scurvy — — — — 95
Chrisomes and Infants —1123	Imposthume — — — 96	Shingles — — 1
Cold, Cough, and Hic-cough — 24	Killed by several Accidents 47	Sores, Ulcers, broken and bruised Limbs — 48
Colick and Wind — 167	King's Evil — — — 54	Spleen — — 7
Consumption and Tissick 3414	Lethargy — — — 4	Spotted Fever and Purples 146
Convulsion — — —1031	Leprosy — — — — 2	Sciatica — — — — — 2
Cut of the Stone and Stone 48	Livergrown — — 15	Strangury — — — 30
Dropsy and Tympany — — 872	Lunatick, Distracted and Frenzy — 14	Stopping of the Stomach 214
Drowned — — 48	Megrims and Calenture — 4	Surfeit — — — 192
Executed — — — — 18	Measles — — 74	Tetter — — — — 1
		Teeth and Worms — —1008
		Vomiting — — 10

CHRISTENED	Males — 3724	BURIED	Males — 7960	Of the Plague 14
	Females 3247		Females 7158	
	In all — 6971		In all 15118	

Decreased in the Burials in the 130 Parishes and at the Pest-house this Year 2466
Decreased of the Plague in the 130 Parishes and at the Pest-house this Year 22

1661.

A General BILL for this preſent Year,

Ending the 17th Day of December 1661.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur. Pl.
St ALBAN Wood-ſtreet	85
Alhallows Barkin	109
Alhallows Bread-ſtreet	21
Alhallows Great	87
Alhallows Honey-lane	9
Alhallows Leſs	27
Alhallows Lombard-ſtreet	29
Alhallows Staining	39
Alhallows the Wall	71
St Alphage	48
St Andrew Hubbard	36
St Andrew Underſhaft	79
St Andrew Wardrobe	96
St Ann Alderſgate	49
St Ann Black Friars	138
St Antholin's Pariſh	26
St Auſtin's Pariſh	19
St Bartholomew Exchange	27
St Bennet Fink	29
St Bennet Gracechurch	15
St Bennet Paul's Wharf	53
St Bennet Sherehog	13
St Botolph Billingſgate	24
Chriſt Church	171
St Chriſtopher	26
St Clement Eaſtcheap	18
St Dionis Backchurch	40
St Dunſtan Eaſt	82
St Edmund Lombard-ſtr.	32
St Ethelborough	23
St Faith's	22
St Foſter's	36
St Gabriel Fenchurch	18
St George Botolph-lane	12
St Gregory by Paul's	145
St Helen's	32
St James Duke's Place	36
St James Garlickhithe	39
St John Baptiſt	34
St John Evangeliſt	9
St John Zachary	32
St Katherine Coleman	15
St Katherine Creechurch	84
St Laurence Jewry	59
St Laurence Pountney	47
St Leonard Eaſtcheap	24
St Leonard Foſter-lane	84
St Magnus Pariſh	32
St Margaret Lothbury	34
St Margaret Moſes	16
St Margaret New Fiſh-ſtr.	33
St Margaret Pattons	16
St Mary Abchurch	37
St Mary Aldermanbury	42
St Mary Aldermary	37
St Mary le Bow	23
St Mary Bothaw	14
St Mary Colechurch	19
St Mary Hill	24
St Mary Mounthaw	17
St Mary Somerſet	66
St Mary Staining	12
St Mary Woolchurch	19
St Mary Woolnoth	29
St Martin Ironmonger-lane	9
St Martin Ludgate	71
St Martin Orgars	33
St Martin Outwich	24
St Martin Vintrey	54
St Matthew Friday-ſtreet	22
St Maudlin Milk-ſtreet	13
St Maudlin Old Fiſh-ſtreet	36
St Michael Baſſiſhaw	57
St Michael Cornhill	26
St Michael Crooked-lane	33
St Michael Queenhithe	60
St Michael Querne	25
St Michael Royal	25
St Michael Wood-ſtreet	30
St Mildred Bread-ſtreet	22
St Mildred Poultry	19
St Nicholas Acons	17
St Nicholas Coleabby	31
St Nicholas Olave	23
St Olave Hart-ſtreet	55
St Olave Jewry	13
St Olave Silver-ſtreet	33
St Pancras Soper-lane	17
St Peter Cheap	24
St Peter Cornhill	37
St Peter Paul's Wharf	21
St Peter Poor	26
St Stephen Coleman-ſtreet	120
St Stephen Walbrook	29
St Swithin	37
St Thomas Apoſtle	31
Trinity Pariſh	34

Buried in the ninety-ſeven Pariſhes within the Walls 3804 Whereof of the Plague 0

St Andrew Holborn	755	St Botolph Aldgate	752	1	St Saviour Southwark 685
St Bartholomew Great	80	St Botolph Biſhopſgate	583		St Sepulchre's Pariſh 849
St Bartholomew Leſs	54	St Dunſtan Weſt	293		St Thomas Southwark 54
St Bride's Pariſh	438	St George Southwark	342		Trinity Minories 13
Bridewell Precinct	32	St Giles Cripplegate	1361	8	At the Peſt-houſe 0
St Botolph Alderſgate	171	St Olave Southwark	862	6	

Buried in the ſixteen Pariſhes without the Walls 7324 Whereof of the Plague 15

St Giles in the Fields —850	Lambeth Pariſh ——330	St Mary Iſlington — —102
Hackney Pariſh — ——102	St Leonard Shoreditch—403	St Mary Whitechapel —781 4
St James Clarkenwell —375	St Magdalen Bermondſey547	Rotherhith Pariſh —— 87
St Katherine's Tower —190	St Mary Newington——340	Stepney Pariſh ——1561 1

Buried in the twelve Out Pariſhes in Middleſex and Surrey 5668
Whereof of the Plague —— —— 5

St Clement Danes — —537	St Martin in the Fields 1193	St Margaret Weſtminſter 984
St Paul Covent Garden 159	St Mary Savoy —— 102	At the Peſt-houſe—— 0

Buried in the five Pariſhes in the City and Liberties of Weſtminſter 2975
Whereof of the Plague —— —— 0

The Total of all the Chriſtenings — 8855
The Total of all the Burials this Year 19771
Whereof of the Plague —— 20

DISEASES and CASUALTIES.

Abortive and Stillborn 511	Frighted —— —— 2	Mother —— — —— 4
Aged —— ——1302	Flox and Small Pox — —1246	Murdered, Slain and Shot 52
Ague and Fever — ——3490	Found dead in the Streets, Fields, &c. — 8	Overlaid and Starved—— 37
Apoplexy and Suddenly— 108	French Pox —— —— 44	Palſy —— — —— 26
Bedrid —— —— 3	Gout and Sciatica —— 11	Plague —— — —— 20
Bleeding —— —— 5	Grief —— — —— 17	Planet —— —— 3
Bloody Flux, Scowring, and Flux —— 314	Griping in the Guts — —1061	Pluriſy —— —— 11
Burnt and Scalded — — 4	Hang'd and made away themſelves — 13	Poiſoned —— —— 2
Cancer, Gangrene, and Fiſtula —— 69	Headmouldſhot and Mouldfallen — 28	Quinſy and ſore Throat— 13
Canker, ſore Mouth and Thruſh —— 95	Jawfallen —— — —— 2	Rickets —— —— 413
Childbed —— — —— 224	Jaundies —— —— 141	Riſing of the Lights —— 227
Chriſomes and Infants —1400	Impoſthume —— —— 160	Rupture —— — —— 18
Cold, Cough, and Hic-cough — — 14	Kill'd by ſeveral Accidents 26	Scurvy —— —— 85
Colick and Wind — —— 186	King's Evil —— —— 48	Sores, Ulcers, broken and bruiſed Limbs 61
Conſumption and Tiſſick 3788	Lethargy —— — — 11	Spleen —— —— —— 5
Convulſion —— ——1198	Leproſy —— —— 1	Spotted Fever and Purples 335
Cut of the Stone and Stone 36	Livergrown —— —— 19	Strangury —— —— 23
Dropſy and Tympany — 967	Lunatick, Diſtracted and Frenzy — 11	Stopping of the Stomach 176
Drowned —— —— 57	Megrims —— —— 3	Surfeit —— —— —— 212
Executed —— — —— 16	Meaſles —— — —— 188	Swine Pox —— —— 6
		Teeth and Worms — —1195
		Vomiting —— —— 20

CHRISTENED	Males — 4748 Females 4107 In all — 8855	BURIED	Males — 10484 Females 9287 In all — 19771

Of the Plague 20

Increaſed in the Burials in the 130 Pariſhes and at the Peſt-houſe this Year 4653
Increaſed of the Plague in the 130 Pariſhes and at the Peſt-houſe this Year 6

A General

1662.

A General BILL for this preſent Year,

Ending the 16th Day of December 1662.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.	Pl.
St ALBAN Wood-ſtreet	33	
Alhallows Barkin	104	
Alhallows Bread-ſtreet	—	14
Alhallows Great	—	86
Alhallows Honey-lane	—	6
Alhallows Leſs	—	54
Alhallows Lombard-ſtreet	22	
Alhallows Staining	—	35
Alhallows the Wall	—	63
St Alphage	—	49
St Andrew Hubbard	—	23
St Andrew Underſhaft	—	42
St Andrew Wardrobe	—	84
St Ann Alderſgate	—	43
St Ann Black Friars	—	90
St Antholin's Pariſh	—	23
St Auſtin's Pariſh	—	21
St Bartholomew Exchange		27
St Bennet Fink	—	22
St Bennet Gracechurch	—	6
St Bennet Paul's Wharf	—	40
St Bennet Sherehog	—	8
St Botolph Billingſgate	—	24
Chriſt Church	—	130
St Chriſtopher	—	11
St Clement Eaſtcheap	—	18
St Dionis Backchurch	—	29
St Dunſtan Eaſt	—	74
St Edmund Lombard-ſtr.		20
St Ethelborough	—	21
St Faith's	—	18
St Foſter's	—	35
St Gabriel Fenchurch	—	25
St George Botolph-lane	—	11
St Gregory by Paul's	—	85
St Helen's	—	32
St James Duke's Place	—	24
St James Garlickhithe	—	30
St John Baptiſt	—	32
St John Evangeliſt	—	5
St John Zachary	—	17
St Katherine Coleman	—	33
St Katherine Creechurch		39
St Laurence Jewry	—	51
St Laurence Pountney	—	29
St Leonard Eaſtcheap	—	12
St Leonard Foſter-lane	—	54
St Magnus Pariſh	—	32
St Margaret Lothbury	—	41
St Margaret Moſes	—	20
St Margaret New Fiſh-ſtr.		18
St Margaret Pattons	—	11
St Mary Abchurch	—	32
St Mary Aldermanbury	—	32
St Mary Aldermary	—	20
St Mary le Bow	—	19
St Mary Bothaw	—	22
St Mary Colechurch	—	6
St Mary Hill	—	27
St Mary Mounthaw	—	12
St Mary Somerſet	—	34
St Mary Staining	—	12
St Mary Woolchurch	—	23
St Mary Woolnoth	—	25
St Martin Ironmonger-lane		6
St Martin Ludgate	—	45
St Martin Orgars	—	35
St Martin Outwich	—	14
St Martin Vintrey	—	47
St Matthew Friday-ſtreet		11
St Maudlin Milk-ſtreet	—	14
St Maudlin Old Fiſh-ſtreet		39
St Michael Baſſiſhaw	—	41
St Michael Cornhill	—	27
St Michael Crooked-lane		31
St Michael Queenhithe	—	40
St Michael Querne	—	24
St Michael Royal	—	21
St Michael Wood-ſtreet	—	11
St Mildred Bread-ſtreet	—	18
St Mildred Poultry	—	28
St Nicholas Acons	—	18
St Nicholas Coleabby	—	28
St Nicholas Olave	—	10
St Olave Hart-ſtreet	—	51
St Olave Jewry	—	19
St Olave Silver-ſtreet	—	49
St Pancras Soper-lane	—	12
St Peter Cheap	—	21
St Peter Cornhill	—	32
St Peter Paul's Wharf	—	18
St Peter Poor	—	18
St Stephen Coleman-ſtreet		122
St Stephen Walbrook	—	17
St Swithin	—	32
St Thomas Apoſtle	—	28
Trinity Pariſh	—	26

Buried in the ninety-ſeven Pariſhes within the Walls 3123 Whereof of the Plague 0

	Bur.	Pl.
St Andrew Holborn	—	595
St Bartholomew Great	—	98
St Bartholomew Leſs	—	41
St Bride's Pariſh	—	343
Bridewell Precinct	—	34
St Botolph Alderſgate	—	133
St Botolph Aldgate	—	690 7
St Botolph Biſhopſgate	—	456
St Dunſtan Weſt	—	213
St George Southwark	—	254
St Giles Cripplegate	—	1068 1
St Olave Southwark	—	761 2
St Saviour Southwark	—	594
St Sepulchre's Pariſh	—	733
St Thomas Southwark	—	68
Trinity Minories	—	14
At the Peſt-houſe	—	0

Buried in the ſixteen Pariſhes without the Walls 6104 Whereof of the Plague 10

1662.

St Giles in the Fields —719	Lambeth Pariſh ——210	St Mary Iſlington — — 59
Hackney Pariſh ——101	St Leonard Shoreditch—290	St Mary Whitechapel —711 2
St James Clarkenwell —317	St Magdalen Bermondſey387	Rotherhith Pariſh —— 77
St Katherine's Tower —211	St Mary Newington—— 76	Stepney Pariſh —— —1531

Buried in the twelve Out Pariſhes in Middleſex and Surrey 4689
Whereof of the Plague —— —— 2

St Clement Danes — —495	St Martin in the Fields 1107	St Margaret Weſtminſter 848
St Paul Covent Garden 114	St Mary Savoy —— 74	At the Peſt-houſe — — 0

Buried in the five Pariſhes in the City and Liberties of Weſtminſter 2638
Whereof of the Plague —— —— —— 0

The Total of all the Chriſtenings — 10019
The Total of all the Burials this Year 16554
Whereof of the Plague — — 12

DISEASES and CASUALTIES.

Abortive and Stillborn 523	Flox and Small Pox —— 768	Murdered, Slain and Shot 11
Aged —— ——1215	Found dead in the Streets, Fields, &c. — 12	Overlaid and Starved—— 50
Ague and Fever —— —2601	French Pox —— —— 44	Palſy —— — —— 27
Apoplexy and Suddenly— 86	Frighted —— —— 1	Plague —— —— 12
Bedrid —— —— 1	Gout —— —— 8	Planet —— — —— 3
Bleeding —— —— 2	Grief —— — —— 6	Pluriſy —— —— 14
Bloody Flux, Scowring, and Flux — 203	Griping in the Guts — — 835	Poiſoned — — —— 1
Burnt and Scalded — — 4	Hang'd and made away themſelves — 14	Quinſy and ſore Throat— 14
Cancer, Gangrene, and Fiſtula — 54	Headmouldſhot and Mouldfallen — 34	Rickets —— —— 395
Canker, ſore Mouth, and Thruſh — 71	Jawfallen —— —— 2	Riſing of the Lights —— 197
Calenture —— —— 1	Jaundies —— —— 76	Rupture —— — —— 26
Childbed —— —— 175	Impoſthume — — —— 113	Scurvy —— —— 70
Chriſomes and Infants —1315	Kill'd by ſeveral Accidents 46	Sores, Ulcers, broken and bruiſed Limbs 54
Cold and Cough —— 29	King's Evil — — —— 49	Spleen —— — —— 9
Colick and Wind — —— 142	Lethargy —— —— 9	Spotted Fever and Purples 148
Conſumption and Tiſſick 3485	Livergrown — — —— 25	Stifled and Smothered —— 3
Convulſion — — ——1053	Lunatick, Diſtracted and Frenzy — 12	Stopping of the Stomach 153
Cut of the Stone and Stone 34	Megrims and Head-ach— 5	Strangury —— —— 16
Dropſy and Tympany — 990	Meaſles —— —— 20	Surfeit —— — —— 186
Drowned — — —— 43		Swine Pox —— — — 3
Executed —— —— 14		Teeth and Worms —— 1032
		Vomiting — — —— 10

CHRISTENED	Males — 5216	BURIED	Males — 8623	Of the Plague	12
	Females 4803		Females 7931		
	In all — 10019		In all — 16554		

Decreaſed in the Burials in the 130 Pariſhes and at the Peſt-houſe this Year 3217
Decreaſed of the Plague in the 130 Pariſhes and at the Peſt-houſe this Year 8

A General

1663.

A General BILL for this preſent Year,

Ending the 15th Day of December 1663.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.	Pl.
St ALBAN Wood-ſtreet	28	
Alhallows Barkin	75	
Alhallows Bread-ſtreet	17	
Alhallows Great	82	
Alhallows Honey-lane	6	
Alhallows Leſs	38	
Alhallows Lombard-ſtreet	17	
Alhallows Staining	29	
Alhallows the Wall	58	
St Alphage	30	
St Andrew Hubbard	19	
St Andrew Underſhaft	47	
St Andrew Wardrobe	73	
St Ann Alderſgate	39	
St Ann Black Friars	97	
St Antholin's Pariſh	19	
St Auſtin's Pariſh	19	
St Bartholomew Exchange	20	
St Bennet Fink	26	
St Bennet Gracechurch	8	
St Bennet Paul's Wharf	58	
St Bennet Sherehog	6	
St Botolph Billingſgate	19	
Chriſt Church	126	
St Chriſtopher	20	
St Clement Eaſtcheap	17	
St Dionis Backchurch	34	
St Dunſtan Eaſt	76	
St Edmund Lombard-ſtr.	14	
St Ethelborough	27	
St Faith's	22	
St Foſter's	34	
St Gabriel Fenchurch	18	
St George Botolph-lane	6	
St Gregory by Paul's	89	
St Helen's	29	
St James Duke's Place	45	
St James Garlickhithe	55	
St John Baptiſt	17	
St John Evangeliſt	4	
St John Zachary	23	
St Katherine Coleman	32	
St Katherine Creechurch	46	
St Laurence Jewry	35	
St Laurence Pountney	39	
St Leonard Eaſtcheap	12	
St Leonard Foſter-lane	45	
St Magnus Pariſh	36	
St Margaret Lothbury	43	
St Margaret Moſes	10	
St Margaret New Fiſh-ſtr.	27	
St Margaret Pattons	6	
St Mary Abchurch	40	
St Mary Aldermanbury	35	
St Mary Aldermary	24	
St Mary le Bow	21	
St Mary Bothaw	18	
St Mary Colechurch	14	
St Mary Hill	19	
St Mary Mounthaw	13	
St Mary Somerſet	65	
St Mary Staining	6	
St Mary Woolchurch	19	
St Mary Woolnoth	23	
St Martin Ironmonger-lane	14	
St Martin Ludgate	42	
St Martin Orgars	19	
St Martin Outwich	15	
St Martin Vintrey	63	
St Matthew Friday-ſtreet	17	
St Maudlin Milk-ſtreet	12	
St Maudlin Old Fiſh-ſtreet	32	
St Michael Baſſiſhaw	34	
St Michael Cornhill	23	
St Michael Crooked-lane	31	
St Michael Queenhithe	55	
St Michael Querne	12	
St Michael Royal	21	
St Michael Wood-ſtreet	20	
St Mildred Bread-ſtreet	25	
St Mildred Poultry	26	
St Nicholas Acons	15	
St Nicholas Coleabby	20	
St Nicholas Olave	19	
St Olave Hart-ſtreet	34	
St Olave Jewry	11	
St Olave Silver-ſtreet	32	
St Pancras Soper-lane	9	
St Peter Cheap	11	
St Peter Cornhill	20	
St Peter Paul's Wharf	24	
St Peter Poor	28	
St Stephen Coleman-ſtreet	119	
St Stephen Walbrook	9	
St Swithin	20	
St Thomas Apoſtle	26	
Trinity Pariſh	31	

Buried in the ninety-ſeven Pariſhes within the Walls 3002 Whereof of the Plague 1

St Andrew Holborn	652	St Botolph Aldgate	637	1	St Saviour Southwark 479
St Bartholomew Great	73	St Botolph Biſhopſgate	460	5	St Sepulchre's Pariſh 685
St Bartholomew Leſs	47	St Dunſtan Weſt	214		St Thomas Southwark 51
St Bride's Pariſh	321	St George Southwark	211		Trinity Minories 8
Bridewell Precinct	41	St Giles Cripplegate	1003		At the Peſt-houſe 0
St Botolph Alderſgate	129	St Olave Southwark	597		

Buried in the ſixteen Pariſhes without the Walls 5608 Whereof of the Plague 6

St Giles in the Fields — 793	Lambeth Pariſh — — 199	St Mary Iſlington — — 41
Hackney Pariſh — — 73	St Leonard Shoreditch — 306	St Mary Whitechapel — 559 1
St James Clarkenwell — 318	St Magdalen Bermondſey 318	Rotherhith Pariſh — 80
St Katherine's Tower — 153 1	St Mary Newington — 188	Stepney Pariſh — — — 1241

Buried in the twelve Out Pariſhes in Middleſex and Surrey 4269
Whereof of the Plague — — 2

St Clement Danes — — 406	St Martin in the Fields 1090	St Margaret Weſtminſter 793
St Paul Covent Garden 117	St Mary Savoy — 71	At the Peſt-houſe — — 0

Buried in the five Pariſhes in the City and Liberties of Weſtminſter 2477
Whereof of the Plague — — — 0

The Total of all the Chriſtenings — 10292
The Total of all the Burials this Year 15356
Whereof of the Plague — — 9

DISEASES and CASUALTIES.

Abortive and Stillborn 550	Executed — — — 31	Palſy — — — 30
Aged — — 1171	Flox and Small Pox — 411	Plague — — 9
Ague and Fever — 2107	Found dead in the Streets, Fields, &c. — 8	Planet — — — 3
Apoplexy and Suddenly — 99	French Pox — — — 72	Pluriſy — — — 18
Bedrid — — — 6	Gout — — — 9	Poiſoned — — 3
Bleeding — — — 2	Grief — — — 5	Quinſy and ſore Throat — 8
Bloody Flux, Scowring, and Flux — 192	Green Sickneſs — — 1	Rickets — — 364
Burnt and Scalded — — 14	Griping in the Guts — — 866	Riſing of the Lights — 217
Cancer, Gangrene, and Fiſtula — 59	Hanged and made away themſelves — 12	Rupture — — 12
Canker, Thruſh and Wolf 58	Headmouldſhot and Mouldfallen — 25	Scurvy — — — — 56
Childbed — — — 206	Jaundies — — — 55	Sores, Ulcers, broken and bruiſed Limbs — 73
Choaked — — 1	Impoſthume — — — 109	Spleen — — 3
Chriſomes and Infants — 1299	Killed by ſeveral Accidents 44	Spotted Fever and Purples 128
Colick and Wind — 115	King's Evil — — — 42	Stifled and Smothered — 3
Conſumption and Tiſſick 3260	Lethargy — — — 9	Stopping of the Stomach 184
Convulſion — — — 1011	Livergrown — — 23	Strangury — — — 15
Cough — — — 20	Megrims and Head-ach — 3	Surfeit — — — 191
Cut of the Stone and Stone 58	Meaſles — — 42	Teeth — — — — 904
Diſtracted — — 6	Murdered, Slain and Shot 15	Vertigo — — — 1
Dropſy and Tympany — 934	Overlaid and Starved — 36	Vomiting — — 17
Drowned — — 56		Worms — — 75

CHRISTENED { Males — 5411, Females 4881, In all — 10292 } | BURIED { Males — 8035, Females 7321, In all 15356 } Of the Plague 9

Decreaſed in the Burials in the 130 Pariſhes and at the Peſt-houſe this Year 1198
Decreaſed of the Plague in the 130 Pariſhes and at the Peſt-houſe this Year 3

1664.

A General BILL for this preſent Year,

Ending the 20th Day of December 1664.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur. Pl.
St ALBAN Wood-ſtreet	46
Alhallows Barkin	86
Alhallows Bread-ſtreet	20
Alhallows Great	90
Alhallows Honey-lane	9
Alhallows Leſs	43
Alhallows Lombard-ſtreet	18
Alhallows Staining	38
Alhallows the Wall	93
St Alphage	51
St Andrew Hubbard	27
St Andrew Underſhaft	56
St Andrew Wardrobe	81
St Ann Alderſgate	42
St Ann Black Friars	97
St Antholin's Pariſh	13
St Auſtin's Pariſh	13
St Bartholomew Exchange	22
St Bennet Fink	29
St Bennet Gracechurch	13
St Bennet Paul's Wharf	70
St Bennet Sherehog	13
St Botolph Billingſgate	23
Chriſt Church	140
St Chriſtopher	16
St Clement Eaſtcheap	15
St Dionis Backchurch	31
St Dunſtan Eaſt	102
St Edmund Lombard-ſtr.	20
St Ethelborough	23
St Faith's	30
St Foſter's	25
St Gabriel Fenchurch	18
St George Botolph-lane	13
St Gregory by Paul's	118
St Helen's	25
St James Duke's Place	41
St James Garlickhithe	40
St John Baptiſt	31
St John Evangeliſt	5
St John Zachary	23
St Katherine Coleman	44
St Katherine Creechurch	87
St Laurence Jewry	45
St Laurence Pountney	38
St Leonard Eaſtcheap	14
St Leonard Foſter-lane	37
St Magnus Pariſh	36
St Margaret Lothbury	33
St Margaret Moſes	14
St Margaret New Fiſh-ſtr.	26
St Margaret Pattons	17
St Mary Abchurch	30
St Mary Aldermanbury	46
St Mary Aldermary	20
St Mary le Bow	21
St Mary Bothaw	22
St Mary Colechurch	5
St Mary Hill	23
St Mary Mounthaw	12
St Mary Somerſet	73
St Mary Staining	7
St Mary Woolchurch	22
St Mary Woolnoth	21
St Martin Ironmonger-lane	11
St Martin Ludgate	51
St Martin Orgars	25
St Martin Outwich	17
St Martin Vintrey	76
St Matthew Friday-ſtreet	9
St Maudlin Milk-ſtreet	19
St Maudlin Old Fiſh-ſtreet	42
St Michael Baſſiſhaw	38
St Michael Cornhill	36
St Michael Crooked-lane	46
St Michael Queenhithe	47
St Michael Querne	17
St Michael Royal	22
St Michael Wood-ſtreet	24
St Mildred Bread-ſtreet	12
St Mildred Poultry	24
St Nicholas Acons	14
St Nicholas Coleabby	31
St Nicholas Olave	18
St Olave Hart-ſtreet	37
St Olave Jewry	29
St Olave Silver-ſtreet	42
St Pancras Soper-lane	12
St Peter Cheap	13
St Peter Cornhill	36
St Peter Paul's Wharf	23
St Peter Poor	22
St Stephen Coleman-ſtreet	133
St Stephen Walbrook	19
St Swithin	41
St Thomas Apoſtle	29
Trinity Pariſh	31

Buried in the ninety-ſeven Pariſhes within the Walls 3448 Whereof of the Plague 0

St Andrew Holborn	843
St Bartholomew Great	90
St Bartholomew Leſs	44
St Bride's Pariſh	412
Bridewell Precinct	34
St Botolph Alderſgate	187
St Botolph Aldgate	785 1
St Botolph Biſhopſgate	545
St Dunſtan Weſt	265
St George Southwark	259
St Giles Cripplegate	1353 1
St Olave Southwark	829
St Saviour Southwark	605
St Sepulchre's Pariſh	851
St Thomas Southwark	54
Trinity Minories	12
At the Peſt-houſe	0

Buried in the ſixteen Pariſhes without the Walls 7168 Whereof of the Plague 2

1664.

St Giles in the Fields —931 1	Lambeth Pariſh ——236	St Mary Iſlington — — 58
Hackney Pariſh —— 80	St Leonard Shoreditch—424	St Mary Whitechapel —671 3
St James Clarkenwell —313	St Magdalen Bermondſey305	Rotherhith Pariſh —— 40
St Katherine's Tower —200	St Mary Newington——235	Stepney Pariſh —— —1392

Buried in the twelve Out Pariſhes in Middleſex and Surrey 4885
Whereof of the Plague —— —— 4

St Clement Danes — —534	St Martin in the Fields 1242	St Margaret Weſtminſter 807
St Paul Covent Garden 133	St Mary Savoy —— 80	At the Peſt-houſe — — 0

Buried in the five Pariſhes in the City and Liberties of Weſtminſter 2796
Whereof of the Plague —— —— —— 0

The Total of all the Chriſtenings — 11722
The Total of all the Burials this Year 18297
Whereof of the Plague — — 6

DISEASES and CASUALTIES.

Abortive and Stillborn 523	Drowned — — —— 62	Megrims, Head-ach and Vertigo — } 8
Aged —— ——1154	Executed —— —— 38	Murdered and Shot — — 9
Ague and Fever —— —2258	Falling Sickneſs — —— 1	Overlaid and Starved—— 50
Apoplexy and Suddenly— 95	Flox and Small Pox ——1233	Palſy —— —— — 26
Bedrid —— —— 3	Found dead in the Streets, Fields, &c. — } 6	Plague —— —— 6
Blaſted —— — — 1	French Pox —— —— 80	Pluriſy —— —— 6
Bleeding —— —— 4	Frighted —— —— 1	Poiſoned — —— — 1
Bloody Flux, Scowring, and Flux — } 296	Gout and Sciatica — — 12	Quinſy —— — —— 12
Burnt and Scalded — — 3	Grief —— — —— 7	Rickets —— —— 482
Cancer, Gangrene, and Fiſtula — } 57	Griping in the Guts — —1146	Riſing of the Lights —— 281
Canker and Thruſh — — 63	Hang'd and made away themſelves — } 18	Rupture —— — —— 21
Childbed —— —— 250	Headmouldſhot and Mouldfallen — } 19	Scurvy —— —— 54
Choaked — —— 1	Jaundies —— —— 72	Sores, Ulcers, broken and bruiſed Limbs } 64
Chriſomes and Infants —1491	Jawfallen —— —— 1	Spleen —— — —— 9
Cold and Cough —— 27	Impoſthume — — —— 111	Spotted Fever and Purples 116
Colick and Wind — —— 120	Kill'd by ſeveral Accidents 48	Stopping of the Stomach 197
Conſumption and Tiſſick 3645	King's Evil — — —— 47	Strangury —— —— 9
Convulſion — — ——1181	Lethargy —— —— 10	Surfeit —— — —— 244
Cut of the Stone and Stone 45	Livergrown — — —— 23	Swine Pox —— — — 2
Diſtracted — —— 6	Meaſles —— —— 311	Teeth and Worms ——1122
Dropſy and Tympany —1079		Vomiting — — —— 30

CHRISTENED { Males — 6041 / Females 5681 / In all — 11722 } | BURIED { Males — 9369 / Females 8928 / In all — 18297 } Of the Plague 6

Increaſed in the Burials in the 130 Pariſhes and at the Peſt-houſe this Year 2941
Decreaſed of the Plague in the 130 Pariſhes and at the Peſt-houſe this Year 3

1665.

A TABLE of the
CHRISTENINGS and MORTALITY
For the Year 1664 and 1665. *

Weeks.	Days of the Month.	Chriſt.	Bur.	Pla.	Par. infec.	Weeks.	Days of the Month.	Chriſt.	Bur.	Pla.	Par. infec.
1	Dec. 27.	229	291	1	1	27	June 27.	199	684	267	20
2	January 3.	239	349	0	0	28	July 4.	207	1006	470	33
3	10.	235	394	0	0	29	11.	197	1268	725	40
4	17.	223	415	0	0	30	18.	194	1761	1089	54
5	24.	237	474	0	0	31	25.	193	2785	1843	68
6	31.	216	409	0	0	32	Auguſt 1.	215	3014	2010	73
7	Febr. 7.	221	393	0	0	33	8.	178	4030	2817	86
8	14.	224	462	1	1	34	15.	166	5319	3880	96
9	21.	232	393	0	0	35	22.	171	5568	4237	103
10	28.	233	396	0	0	36	29.	169	7496	6102	113
11	March 7.	236	441	0	0	37	Septem. 5.	167	8252	6988	118
12	14.	236	433	0	0	38	12.	168	7690	6544	119
13	21.	221	363	0	0	39	19.	176	8297	7165	126
14	28.	238	353	0	0	40	26.	146	6460	5533	123
15	April 4.	242	344	0	0	41	October 3.	142	5720	4929	124
16	11.	245	382	0	0	42	10.	141	5068	4327	126
17	18.	237	344	0	0	43	17.	147	3219	2665	114
18	25.	229	398	2	1	44	24.	104	1806	1421	104
19	May 2.	237	388	0	0	45	31.	104	1388	1031	97
20	9.	211	347	9	4	46	Novem. 7.	95	1787	1414	110
21	16.	227	353	3	2	47	14.	113	1359	1050	99
22	23.	231	385	14	3	48	21.	108	905	652	84
23	30.	229	400	17	5	49	28.	112	544	333	60
24	June 6.	234	405	43	7	50	Decem. 5.	123	428	210	48
25	13.	206	558	112	12	51	12.	133	442	243	57
26	20.	204	615	168	19	52	19.	147	525	281	68

The Totals { Chriſtened — — 9967
Buried — — 97306
Whereof of the Plague 68596

* Bell's London's Remembrancer.

A General

1665.

A General BILL for this preſent Year,

Ending the 19th Day of December 1665.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.	Pla.
St ALBAN Wood-ſtreet	200	121
Alhallows Barkin	514	330
Alhallows Bread-ſtreet	35	16
Alhallows Great	455	426
Alhallows Honey-lane	10	5
Alhallows Leſs	239	175
Alhallows Lombard-ſtreet	90	62
Alhallows Staining	185	112
Alhallows the Wall	500	356
St Alphage	271	115
St Andrew Hubbard	71	25
St Andrew Underſhaft	274	189
St Andrew Wardrobe	476	308
St Ann Alderſgate	282	197
St Ann Black Friars	652	467
St Antholin's Pariſh	58	33
St Auſtin's Pariſh	43	20
St Bartholomew Exchange	73	51
St Bennet Fink	47	22
St Bennet Gracechurch	57	41
St Bennet Paul's Wharf	355	172
St Bennet Sherehog	11	1
St Botolph Billingſgate	83	50
Chriſt Church	653	467
St Chriſtopher	60	47
St Clement Eaſtcheap	38	20
St Dionis Backchurch	78	27
St Dunſtan Eaſt	265	150
St Edmund Lombard-ſtreet	70	36
St Ethelborough	195	106
St Faith's	104	70
St Foſter's	144	105
St Gabriel Fenchurch	69	39
St George Botolph-lane	41	27
St Gregory by Paul's	376	232
St Helen's	108	75
St James Duke's Place	262	190
St James Garlickhithe	189	118
St John Baptiſt	138	83
St John Evangeliſt	9	0
St John Zachary	85	54
St Katherine Coleman	299	213
St Katherine Creechurch	335	231
St Laurence Jewry	94	48
St Laurence Pountney	214	140
St Leonard Eaſtcheap	42	27
St Leonard Foſter-lane	335	255
St Magnus Pariſh	103	60
St Margaret Lothbury	100	66
St Margaret Moſes	38	25
St Margaret New Fiſh-ſtreet	114	66
St Margaret Pattons	49	24
St Mary Abchurch	99	54
St Mary Aldermanbury	181	109
St Mary Aldermary	105	75
St Mary le Bow	64	36
St Mary Bothaw	55	30
St Mary Colechurch	17	6
St Mary Hill	94	64
St Mary Mounthaw	56	37
St Mary Somerſet	342	262
St Mary Staining	47	27
St Mary Woolchurch	65	33
St Mary Woolnoth	75	38
St Martin Ironmonger-lane	21	11
St Martin Ludgate	196	128
St Martin Orgars	110	71
St Martin Outwich	60	34
St Martin Vintrey	417	349
St Matthew Friday-ſtreet	24	6

St Maudlin

1665.

	Bur.	Pla.		Bur.	Pla.
St Maudlin Milk-ſtreet	44	22	St Olave Hart-ſtreet	237	160
St Maudlin Old Fiſh-ſtreet	176	121	St Olave Jewry	54	32
St Michael Baſſiſhaw	253	164	St Olave Silver-ſtreet	250	132
St Michael Cornhill	104	52	St Pancras Soper-lane	30	15
St Michael Crooked-lane	179	133	St Peter Cheap	61	35
St Michael Queenhithe	203	122	St Peter Cornhill	136	76
St Michael Querne	44	18	St Peter Paul's Wharf	114	86
St Michael Royal	152	116	St Peter Poor	79	47
St Michael Wood-ſtreet	122	62	St Stephen Coleman-ſtreet	560	391
St Mildred Bread-ſtreet	59	26	St Stephen Walbrook	34	17
St Mildred Poultry	68	46	St Swithin	93	56
St Nicholas Acons	46	28	St Thomas Apoſtle	163	110
St Nicholas Coleabby	125	91	Trinity Pariſh	115	79
St Nicholas Olave	90	62			

Buried in the ninety-ſeven Pariſhes within the Walls 15207
Whereof of the Plague — — 9887

St Andrew Holborn	3958	3103	St George Southwark	1613	1260
St Bartholomew Great	493	344	St Giles Cripplegate	8069	4838
St Bartholomew Leſs	193	139	St Olave Southwark	4793	2785
St Bridget	2111	1427	St Saviour Southwark	4235	3446
Bridewell Precinct	230	179	St Sepulchre's Pariſh	4509	2746
St Botolph Alderſgate	997	755	St Thomas Southwark	475	371
St Botolph Aldgate	4926	4051	Trinity Minories	168	123
St Botolph Biſhopſgate	3464	2500	At the Peſt-houſe	159	156
St Dunſtan Weſt	958	665			

Buried in the ſixteen Pariſhes without the Walls 41351
Whereof of the Plague — — 28888

St Giles in the Fields	4457	3216	St Magdalen Bermondſey	1943	1363
Hackney Pariſh	232	132	St Mary Newington	1272	1004
St James Clarkenwell	1863	1377	St Mary Iſlington	696	593
St Katherine's Tower	956	601	St Mary Whitechapel	4766	3855
Lambeth Pariſh	798	537	Rotherhith Pariſh	304	210
St Leonard Shoreditch	2669	1949	Stepney Pariſh	8598	6583

Buried in the twelve Out Pariſhes in Middleſex and Surrey 28554
Whereof of the Plague — — — 21429

St Clement Danes	1969	1319	St Mary Savoy	303	198
St Paul Covent Garden	408	261	St Margaret Weſtminſter	4710	3472
St Martin in the Fields	4804	2883	Whereof at the Peſt-houſe	—	156

Buried in the five Pariſhes in the City and Liberties of Weſtminſter 12194
Whereof of the Plague — — — 8403

The Total of all the Chriſtenings — 9967
The Total of all the Burials this Year 97306
Whereof of the Plague — 68596

DISEASES

1665.

DISEASES and CASUALTIES.

Abortive and Stillborn	617	Executed	21	Overlaid and Starved	45
Aged	1545	Flox and Small Pox	655	Palſy	30
Ague and Fever	5257	Found dead in the Streets, Fields, &c.	20	Plague	68596
Apoplexy and Suddenly	116	French Pox	86	Planet	6
Bedrid	10	Frighted	23	Pluriſy	15
Blaſted	5	Gout and Sciatica	27	Poiſoned	1
Bleeding	16	Grief	46	Quinſy	35
Bloody Flux, Scowring, and Flux	185	Griping in the Guts	1288	Rickets	557
Burnt and Scalded	8	Hang'd and made away themſelves	7	Riſing of the Lights	397
Calenture	3	Headmouldſhot and Mouldfallen	14	Rupture	34
Cancer, Gangrene, and Fiſtula	56	Jaundies	110	Scurvy	105
Canker and Thruſh	111	Impoſthume	227	Shingles and Swine Pox	2
Childbed	625	Kill'd by ſeveral Accidents	46	Sores, Ulcers, broken and bruiſed Limbs	82
Chriſomes and Infants	1258	King's Evil	86	Spleen	14
Cold and Cough	68	Leproſy	2	Spotted Fever and Purples	1929
Colick and Wind	134	Lethargy	14	Stopping of the Stomach	332
Conſumption and Tiſſick	4808	Livergrown	20	Stone and Strangury	98
Convulſion and Mother	2036	Megrims and Head-ach	12	Surfeit	1251
Diſtracted	5	Meaſles	7	Teeth and Worms	2614
Dropſy and Tympany	1478	Murdered and Shot	9	Vomiting	51
Drowned	50			Wen	1

CHRISTENED	Males — 5114	BURIED	Males — 48569	Of the Plague	68596
	Females 4853		Females 48737		
	In all — 9967		In all — 97306		

Increaſed in the Burials in the 130 Pariſhes and at the Peſt-houſe this Year 79009
Increaſed of the Plague in the 130 Pariſhes and at the Peſt-houſe this Year 68590

A General

1666.

A General BILL for this preſent Year,

From the 19th of December 1665, to the 18th of December 1666.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.	Pl.
St ALBAN Wood-ſtreet	17	2
Alhallows Barkin	95	9
Alhallows Bread-ſtreet	7	0
Alhallows Great	40	8
Alhallows Honey-lane	4	0
Alhallows Leſs	23	9
Alhallows Lombard-ſtreet	8	1
Alhallows Staining	34	8
Alhallows the Wall	72	10
St Alphage	27	3
St Andrew Hubbard	21	4
St Andrew Underſhaft	30	2
St Andrew Wardrobe	35	4
St Ann Alderſgate	34	5
St Ann Black Friars	56	17
St Antholin's Pariſh	11	3
St Auſtin's Pariſh	11	3
St Bartholomew Exchange	14	1
St Bennet Fink	11	3
St Bennet Gracechurch	8	0
St Bennet Paul's Wharf	25	2
St Bennet Sherehog	4	0
St Botolph Billingſgate	16	5
Chriſt Church	74	7
St Chriſtopher	12	2
St Clement Eaſtcheap	12	5
St Dionis Backchurch	15	4
St Dunſtan Eaſt	65	17
St Edmund Lombard-ſtreet	13	7
St Ethelborough	16	2
St Faith's	20	1
St Gabriel Fenchurch	6	1
St George Botolph-lane	3	0
St Gregory by Paul's	30	1
St Helen's	28	0
St James Duke's Place	40	9
St James Garlickhithe	23	5
St John Baptiſt	13	2
St John Evangeliſt	4	0
St John Zachary	11	0
St Katherine Coleman	46	7
St Katherine Creechurch	69	10
St Laurence Jewry	14	0
St Laurence Pountney	24	8
St Leonard Eaſtcheap	8	0
St Leonard Foſter-lane	25	1
St Magnus Pariſh	18	0
St Margaret Lothbury	16	3
St Margaret Moſes	7	0
St Margaret New Fiſh-ſtreet	16	2
St Margaret Pattons	19	3
St Martin Ironmonger-lane	6	1
St Martin Ludgate	23	0
St Martin Orgars	19	4
St Martin Outwich	9	0
St Martin Vintrey	27	3
St Mary Abchurch	18	2
St Mary Aldermanbury	23	1
St Mary Aldermary	11	3
St Mary le Bow	17	1
St Mary Bothaw	9	2
St Mary Colechurch	2	0
St Mary Hill	17	5
St Mary Magd. Milk-ſtreet	5	0
St Mary Magd. Old Fiſh-ſtr.	20	2
St Mary Mounthaw	8	4
St Mary Somerſet	29	2
St Mary Staining	3	0
St Mary Woolchurch	13	0
St Mary Woolnoth	14	1
St Matthew Friday-ſtreet	9	0
St Michael Baſſiſhaw	26	1
St Michael Cornhill	24	3
St Michael Crooked-lane	23	7
St Michael Queenhithe	30	6
St Michael Querne	12	0
St Michael Royal	11	0
St Michael Wood-ſtreet	18	0
St Mildred Bread-ſtreet	10	1
St Mildred Poultry	15	2
St Nicholas Acons	4	1
St Nicholas Coleabby	10	0
St Nicholas Olave	5	1
St Olave Hart-ſtreet	36	4
St Olave Jewry	6	1
St Olave Silver-ſtreet	16	1
St Pancras Soper-lane	6	0
St Peter Cheap	10	0
St Peter Cornhill	24	4
St Peter Paul's Wharf	11	1
St Peter Poor	28	6
St Stephen Coleman-ſtreet	59	16
St Stephen Walbrook	11	0
St Swithin	16	1
St Thomas Apoſtle	11	3
Trinity Pariſh	16	1
St Vedaſt alias Foſter	7	1

Chriſtened in the ninety-ſeven Pariſhes within the Walls of London, from the 19th of December 1665, to the 28th of Auguſt 1666	1165	
Buried	1796	
Plague		284
Since which Time the late dreadful Fire hath conſumed and laid waſte eighty-one Pariſhes;		
So that there hath been Chriſtened in the ſixteen Pariſhes now ſtanding, from the 28th of Auguſt 1666, to the 18th of Decem. following	151	
Buried	181	
Plague		4
Chriſtened in all	1316	
Buried	1977	
Plague		288

St Andrew

1666.

St Andrew Holborn	490	48	St Botolph Aldgate	592	105	St Saviour Southwark	577	165
St Bartholomew Great	81	16	St Botolp Biſhopſgate	270	16	St Sepulchre's Pariſh	430	24
St Bartholomew Leſs	19	0	St Dunſtan Weſt	156	15	St Thomas Southwark	41	4
St Bride's Pariſh	194	12	St George Southwark	169	16	Trinity Minories	23	4
Bridewell Precinct	10	1	St Giles Cripplegate	776	47	At the Peſt-houſe	41	37
St Botolph Alderſgate	136	11	St Olave Southwark	538	53			

Chriſtened in the ſixteen Pariſhes without the Walls, from the 19th of December 1665, to the 28th of Auguſt 1666	1871	Since which Time alſo have been conſumed two Pariſhes; So there have been Chriſtened in the fourteen Pariſhes now ſtanding, from the 28th of Auguſt 1666, to the 18th of Decem. following	1558
Buried	3001	Buried	1501
Plague	464	Plague	73

Chriſtened in all 3429 Buried, and at the Peſt-houſe 4543 Plague 574

St Giles in the Fields	484	39	Lambeth Pariſh	372	205	St Mary Newington	135	12
St John at Hackney	103	15	St Leonard Shoreditch	283	15	St Mary Whitechapel	521	72
St James Clarkenwell	209	12	St Magdalen Bermondſey	450	165	Rotherhith Pariſh	153	67
St Katherine by the Tower	202	21	St Mary Iſlington	100	1	Stepney Pariſh	1453	315

Chriſtened in the twelve Out Pariſhes in Middleſex and Surrey 2786 Buried 4465 Plague 939

St Clement Danes	320	46	St Martin in the Fields	731	61	St Margaret Weſtminſter	541	87
St Paul Covent Garden	89	6	St Mary Savoy	72	6	At the Peſt-houſe		9

Chriſtened in the five Pariſhes in the City and Liberties of Weſtminſter 1466 Buried 1753 Plague 197

DISEASES and CASUALTIES.

Abortive and Stillborn	477		Flox and Small Pox		38	Overlaid and Starved		32
Aged and Bedrid	611		Found dead in the Streets, Fields, &c.		10	Palſy		31
Ague and Fever	741		French Pox		49	Plague		1998
Apoplexy and Suddenly	57		Frighted		16	Pleuriſy		15
Bleeding	1		Gout and Sciatica		14	Poiſoned		1
Bloody Flux, Scowring, and Flux	82		Grief		11	Quinſy		20
Burnt and Scalded	11		Griping in the Guts		676	Rickets		171
Calenture	2		Hanged and made away themſelves		9	Riſing of the Lights		173
Cancer, Gangrene and Fiſtula	48		Headmouldſhot		1	Rupture		34
Canker and Thruſh	103		Jaundies		90	Scurvy		25
Childbed	253		Impoſthume		72	Sores, Ulcers, broken and bruiſed Limbs		44
Chriſomes and Infants	749		Killed by ſeveral Accidents		43	Spleen		5
Cold and Cough	32		King's Evil		26	Spotted Fever and Purples		141
Colick and Wind	40		Leproſy and Itch		2	Strangury		3
Conſumption and Tiſſick	2592		Lethargy		7	Stopping of the Stomach		107
Convulſion	825		Livergrown		5	Surfeit		345
Cut of the Stone and Stone	67		Lunatick and Frenzy		3	Swine Pox		3
Diſtracted	1		Megrims		1	Teeth and Worms		715
Dropſy and Tympany	983		Meaſles		3	Vomiting		18
Drowned	68		Murdered and Shot		4	Wen		1
Executed	10					Wounded at Sea		23

CHRISTENED	Males — 4678 Females 4319 In all — 8997	BURIED	Males — 6847 Females 6251 In all — 12738	Of the Plague 1998

Decreaſed in the Burials this Year	84568	Pariſhes clear of the Plague	26
Decreaſed of the Plague	66598	Pariſhes infected	104

1667.

A General BILL of all the Chriſtenings and Burials,

From the 18th of December 1666, to the 17th of December 1667.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.	Pla.
ALHALLOWS Barkin	58	
Alhallows Staining	36	
Alhallows the Wall	84	
St Alphage	23	
St Andrew Underſhaft	94	
St Ethelborough	37	
St Helen's	31	
St James Duke's Place	29	
St Katherine Coleman	72	
St Katherine Creechurch	92	
St Magnus Pariſh	22	
St Martin Outwich	13	
St Olave Hart-ſtreet	73	
St Peter Cornhill	13	
St Peter Poor	12	
St Stephen Coleman-ſtreet	72	

Chriſtened in the ſixteen Pariſhes (now ſtanding) within the Walls 440
Buried 761 Plague 0

	Bur.	Pla.
St Andrew Holborn	822	2
St Bartholomew Great	98	1
St Bartholomew Leſs	36	1
St Botolph Alderſgate	211	1
St Botolph Aldgate	800	2
St Botolph Biſhopſgate	421	1
St Dunſtan Weſt	197	
St George Southwark	211	1
St Giles Cripplegate	1456	1
St Olave Southwark	780	1
St Saviour Southwark	674	12
St Sepulchre's Pariſh	642	
St Thomas Southwark	55	
Trinity Minories	25	

Chriſtened in the fourteen Pariſhes (now ſtanding) without the Walls 4286
Buried 6428 Plague 23

	Bur.	Pla.
St Giles in the Fields	972	
St John at Hackney	108	
St James Clerkenwell	363	
St Katherine by the Tower	230	
Lambeth Pariſh	223	
St Leonard Shoreditch	507	
St Magdalen Bermondſey	374	1
St Mary Iſlington	104	
St Mary Newington	230	1
St Mary Whitechapel	755	
Rotherhith Pariſh	103	
Stepney Pariſh	1641	9

Chriſtened in the twelve Out Pariſhes in Middleſex and Surrey 4068
Buried 5610 Plague 11

	Bur.	Pla.
St Clement Danes	564	1
St Paul Covent Garden	140	
St Martin in the Fields	1427	
St Mary Savoy	89	
St Margaret Weſtminſter	822	
Whereof at the Peſt-houſe		

Chriſtened in the five Pariſhes in the City and Liberties of Weſtminſter 2144
Buried 3043 Plague 1

DISEASES and CASUALTIES.

Abortive and Stillborn	488	Flox and Small Pox	1196	Planet	2
Aged	952	Found dead in the Streets	10	Pleurisy	14
Ague	31	French Pox	65	Poisoned	4
Apoplexy	11	Frighted	7	Quinsy	14
Bedridden	4	Gout and Sciatica	14	Rickets	202
Bleeding	5	Grief	11	Rising of the Lights	309
Bloody Flux and Flux	94	Griping in the Guts	2108	Rupture	19
Burnt and Scalded	7	Hanged and made away themselves	9	Scowring	55
Calenture	2	Head-ach	1	Scurvy	39
Cancer, Gangrene, and Fistula	65	Jaundies	74	Smothered and Stifled	3
Canker and Thrush	90	Jawfallen	2	Sores, Ulcers, broken and bruised Limbs	50
Childbed	262	Impostthume	90	Spleen	10
Chrisomes	490	Infants	411	Spotted Fever and Purples	96
Cold, Cough, and Hic-cough	45	Kill'd by several Accidents	63	Starved	2
Colick and Wind	54	King's Evil	38	Strangury	12
Consumption and Tissick	3087	Lethargy	4	Stopping of the Stomach	202
Convulsion	1210	Livergrown	15	Suddenly	37
Cut of the Stone and Stone	34	Lunatick	14	Surfeit	417
Distracted	2	Megrims	4	Swine Pox	3
Dropsy and Tympany	1134	Measles	83	Teeth	812
Drowned	72	Murdered	4	Vomiting	38
Executed	9	Overlaid	40	Wen	1
Falling Sickness	4	Palsy	25	Worms	102
Fever	916	Piles	1	Wounded	7
		Plague	35		

CHRISTENED		BURIED		
Males —	5616	Males —	8223	
Females	5322	Females	7619	Of the Plague 35
In all —	10938	In all	15842	

Increased in the Burials this Year	3104	Parishes clear of the Plague —	33
Decreased of the Plague —	1963	Parishes infected — —	14

1668.

A General BILL of all the Chriſtenings and Burials,

From the 17th of December 1667, to the 22d of December 1668.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.	Pla.
ALHALLOWS Barkin	88	
Alhallows Staining	43	
Alhallows the Wall	67	
St Alphage	20	
St Andrew Underſhaft	78	
St Ethelborough	37	
St Helen's	42	
St James Duke's Place	60	
St Katherine Coleman	63	
St Katherine Creechurch	77	
St Magnus Pariſh	10	
St Martin Outwich	13	
St Olave Hart-ſtreet	75	
St Peter Cornhill	22	
St Peter Poor	24	
St Stephen Coleman-ſtreet	77	

Chriſtened in the ſixteen Pariſhes (now ſtanding) within the Walls 446
Buried 796 Plague 0

	Bur.	Pla.
St Andrew Holborn	853	
St Bartholomew Great	87	
St Bartholomew Leſs	48	
St Botolph Alderſgate	217	
St Botolph Aldgate	861	2
St Botolph Biſhopſgate	420	
St Dunſtan Weſt	164	
St George Southwark	281	3
St Giles Cripplegate	1544	
St Olave Southwark	921	1
St Saviour Southwark	793	
St Sepulchre's Pariſh	601	
St Thomas Southwark	46	
Trinity Minories	29	

Chriſtened in the fourteen Pariſhes (now ſtanding) without the Walls 4517
Buried 6865 Plague 6

	Bur.	Pla.
St Giles in the Fields	1049	
St John at Hackney	83	
St James Clerkenwell	339	
St Katherine by the Tower	265	
Lambeth Pariſh	263	1
St Leonard Shoreditch	489	
St Magdalen Bermondſey	517	3
St Mary Iſlington	143	
St Mary Newington	287	
St Mary Whitechapel	913	
Rotherhith Pariſh	112	
Stepney Pariſh	2061	4

Chriſtened in the twelve Out Pariſhes in Middleſex and Surrey 4272
Buried 6521 Plague 8

St Clement Danes	520
St Paul Covent Garden	177
St Martin in the Fields	1422
St Mary Savoy	88
St Margaret Weſtminſter	889
Whereof at the Peſt-houſe	

Chriſtened in the five Pariſhes in the City and Liberties of Weſtminſter 2398
Buried 3096 Plague 0

1668.

DISEASES and CASUALTIES.

Abortive and Stillborn	571	Frighted	1	Pleuriſy	12
Aged	863	Gout	7	Poiſoned	3
Ague	21	Green Sickneſs	1	Quinſy	13
Apoplexy	20	Grief	12	Rickets	252
Bedridden	4	Griping in the Guts	2415	Riſing of the Lights	175
Bleeding	5	Hang'd and made away themſelves	16	Running of the Reins	1
Bloody Flux and Flux	86	Headmouldſhot	1	Rupture	13
Burſten	1	Jaundies	71	Scowring	72
Cancer, Gangrene, and Fiſtula	47	Impoſthume	122	Scurvy	31
Canker and Thruſh	93	Infants	334	Slain	1
Childbed	271	Kill'd by ſeveral Accidents	69	Sores, Ulcers, broken and bruiſed Limbs	49
Chriſomes	417	King's Evil	39	Spleen	3
Cold and Cough	14	Leproſy	1	Spotted Fever and Purples	148
Colick and Wind	55	Lethargy	6	Starved	1
Conſumption and Tiſſick	2856	Livergrown	1	Stone	35
Convulſion	1417	Lunatick	2	Strangury	10
Cut of the Stone	1	Megrims	3	Stopping of the Stomach	232
Diſtracted	6	Meaſles	200	Suddenly	48
Dropſy and Tympany	948	Mother	3	Surfeit	438
Drowned	68	Murdered	10	Swine Pox	3
Executed	12	Overlaid	59	Teeth	1077
Fever	1247	Palſy	19	Vomiting	95
Flox and Small Pox	1987	Plague	14	Worms	101
Found dead in the Streets, &c.	6	Planet	2	Wounded	2
French Pox	39				

CHRISTENED	Males — 6073	BURIED	Males — 9111	Of the Plague	14
	Females 5560		Females 8167		
	In all — 11633		In all — 17278		

Increaſed in the Burials this Year	1436	Pariſhes clear of the Plague	41
Decreaſed of the Plague	21	Pariſhes infected	6

A General

1669.

A General BILL of all the Chriſtenings and Burials,

From the 22d of December 1668, to the 21ſt of December 1669.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.	Pl.
St ALBAN Wood-ſtreet	4	
Alhallows Barkin	98	
Alhallows Bread-ſtreet	4	
Alhallows Great	19	
Alhallows Honey-lane	0	
Alhallows Leſs	1	
Alhallows Lombard-ſtreet	9	
Alhallows Staining	45	
Alhallows the Wall	92	
St Alphage	24	
St Andrew Hubbard	0	
St Andrew Underſhaft	61	
St Andrew Wardrobe	23	
St Ann Alderſgate	12	
St Ann Black Friars	24	
St Antholin's Pariſh	0	
St Auſtin's Pariſh	2	
St Bartholomew Exchange	13	
St Bennet Fink	9	
St Bennet Gracechurch	1	
St Bennet Paul's Wharf	11	
St Bennet Sherehog	0	
St Botolph Billingſgate	0	
Chriſt Church	34	
St Chriſtopher	5	
St Clement Eaſtcheap	0	
St Dionis Backchurch	6	
St Dunſtan Eaſt	31	
St Edmund Lombard-ſtr.	0	
St Ethelborough	30	
St Faith's	6	
St Gabriel Fenchurch	2	
St George Botolph-lane	2	
St Gregory by Paul's	15	
St Helen's	44	
St James Duke's Place	47	
St James Garlickhithe	1	
St John Baptiſt	4	
St John Evangeliſt	0	
St John Zachary	3	
St Katherine Coleman	51	
St Katherine Creechurch	80	
St Laurence Jewry	21	
St Laurence Pountney	2	
St Leonard Eaſtcheap	1	
St Leonard Foſter-lane	0	
St Magnus Pariſh	18	
St Margaret Lothbury	13	
St Margaret Moſes	0	
St Margaret New Fiſh-ſtr.	0	
St Margaret Pattons	4	
St Mary Abchurch	10	
St Mary Aldermanbury	9	
St Mary Aldermary	11	
St Mary le Bow	6	
St Mary Bothaw	1	
St Mary Colechurch	0	
St Mary Hill	7	
St Mary Magd. Milk-ſtr.	0	
St Mary Mag. Old Fiſh-ſtr.	1	
St Mary Mounthaw	0	
St Mary Somerſet	12	
St Mary Staining	4	
St Mary Woolchurch	0	
St Mary Woolnoth	7	
St Martin Ironmonger-lane	0	
St Martin Ludgate	7	
St Martin Orgars	3	
St Martin Outwich	17	
St Martin Vintrey	3	
St Matthew Friday-ſtreet	2	
St Michael Baſſiſhaw	5	
St Michael Cornhill	13	
St Michael Crooked-lane	7	
St Michael Queenhithe	18	
St Michael Querne	3	
St Michael Royal	0	
St Michael Wood-ſtreet	2	
St Mildred Bread-ſtreet	11	
St Mildred Poultry	9	
St Nicholas Acons	6	
St Nicholas Coleabby	4	
St Nicholas Olave	4	
St Olave Hart-ſtreet	53	
St Olave Jewry	4	
St Olave Silver-ſtreet	0	
St Pancras Soper-lane	0	
St Peter Cheap	1	
St Peter Cornhill	32	
St Peter Paul's Wharf	2	
St Peter Poor	38	
St Stephen Coleman-ſtreet	109	
St Stephen Walbrook	4	
St Swithin	8	
St Thomas Apoſtle	2	
Trinity Pariſh	3	
St Vedaſt, alias Foſter	13	

Chriſtened in the ninety-ſeven Pariſhes within the Walls 571 Buried 1323 Plague 0

St Andrew Holborn	977	St Botolph Aldgate	868	St Saviour Southwark	859
St Bartholomew Great	116	St Botolph Biſhopſgate	540	St Sepulchre's Pariſh	675
St Bartholomew Leſs	31	St Dunſtan Weſt	169	St Thomas Southwark	62
St Bride's Pariſh	94	St George Southwark	317	Trinity Minories	30
Bridewell Precinct	2	St Giles Cripplegate	1577	At the Peſt-houſe	0
St Botolph Alderſgate	260	St Olave Southwark	924		

Chriſtened in the ſixteen Pariſhes without the Walls 4665 Buried 7501 Plague 1

1669.

St Giles in the Fields—1100	Lambeth Pariſh ——343	St Mary Newington——275 1
St John at Hackney——140	St Leonard Shoreditch—741	St Mary Whitechapel --1006
St James Clarkenwell —446	St Magdalen Bermondſey477 1	Rotherhith Pariſh ——131
St Katherine by the Tower248	St Mary Iſlington — —225	Stepney Pariſh ——2087

Chriſtened in the twelve Out Pariſhes in Middleſex and Surrey 4662
Buried 7219 Plague 2

St Clement Danes — —750	St Martin in the Fields 1537	St Margaret Weſtminſter 865
St Paul Covent Garden 147	St Mary Savoy —— 104	At the Peſt-houſe—— 0

Chriſtened in the five Pariſhes in the City and Liberties of Weſtminſter 2404
Buried 3223 Plague 0

In the demoliſhed Pariſhes to the 11th of May 1669,
Chriſtened 33 Buried 166 Plague 0

DISEASES and CASUALTIES.

Abortive and Stillborn 517	French Pox —— —— 51	Plague —— — —— 3
Aged and Bedridden 964	Frets —— —— 1	Planet —— —— 1
Ague and Fever — ——1499	Frighted —— —— 1	Pleuriſy —— —— 19
Apoplexy and Suddenly— 76	Gout and Sciatica —— 9	Poiſoned —— —— 2
Bleeding —— —— 3	Grief —— — —— 13	Quinſy —— —— — 17
Bloody Flux, Scowring, and Flux —— } 165	Griping in the Guts — —4385	Rickets —— —— 343
	Hang'd and made away themſelves — } 20	Riſing of the Lights —— 225
Cancer, Gangrene, and Fiſtula —— } 55		Rupture —— — —— 23
	Headmouldſhot — — 5	Scurvy —— —— 39
Canker and Thruſh —— 115	Jaundies —— —— 63	Sores, Ulcers, broken and bruiſed Limbs } 81
Childbed —— — —— 277	Impoſthume —— —— 117	
Chriſomes and Infants — 755	Kill'd by ſeveral Accidents 72	Spleen —— —— —— 3
Cold and Cough — — 27	King's Evil —— —— 45	Spotted Fever and Purples 114
Conſumption and Tiſſick 3162	Lethargy —— — — 4	Strangury —— —— 18
Convulſion —— ——1730	Livergrown —— —— 5	Stopping of the Stomach 268
Cut of the Stone and Stone 38	Lunatick —— —— 7	Surfeit —— —— —— 446
Dropſy and Tympany — 871	Megrims —— —— 4	Swine Pox —— —— 2
Drowned —— —— 62	Meaſles —— — —— 15	Teeth and Worms — —1463
Executed —— — —— 11	Mother —— —— 2	Vomiting —— —— 120
Falling Sickneſs — —— 2	Murdered —— —— 4	Wen — —— —— 1
Flox and Small Pox —— 951	Overlaid and Starved—— 54	Wind —— —— —— 59
Found dead in the Streets,&c. 12	Palſy —— — —— 16	

CHRISTENED { Males — 6506 / Females 5829 / In all 12335 }	BURIED { Males — 10206 / Females 9226 / In all — 19432 }	Of the Plague 3

Increaſed in the Burials this Year 2154	Pariſhes clear of the Plague — 127
Decreaſed of the Plague —— 11	Pariſhes infected — —— 3

A General

1670.

A General BILL of all the Chriſtenings and Burials,

From the 21ſt of December 1669, to the 22d of December 1670.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.	Pl.
St ALBAN Wood-ſtreet	27	
Alhallows Barkin	82	
Alhallows Bread-ſtreet	16	
Alhallows Great	19	
Alhallows Honey-lane	1	
Alhallows Leſs	9	
Alhallows Lombard-ſtreet	13	
Alhallows Staining	42	
Alhallows the Wall	94	
St Alphage	26	
St Andrew Hubbard	1	
St Andrew Underſhaft	59	
St Andrew Wardrobe	25	
St Ann Alderſgate	39	
St Ann Black Friars	44	
St Antholin's Pariſh	6	
St Auſtin's Pariſh	6	
St Bartholomew Exchange	23	
St Bennet Fink	11	
St Bennet Gracechurch	12	
St Bennet Paul's Wharf	22	
St Bennet Sherehog	5	
St Botolph Billingſgate	3	
Chriſt Church	59	
St Chriſtopher	4	
St Clement Eaſtcheap	1	
St Dionis Backchurch	13	
St Dunſtan Eaſt	63	
St Edmund Lombard-ſtr.	11	
St Ethelborough	36	
St Faith's	20	
St Gabriel Fenchurch	0	
St George Botolph-lane	10	
St Gregory by Paul's	23	
St Helen's	41	
St James Duke's Place	47	
St James Garlickhithe	11	
St John Baptiſt	1	
St John Evangeliſt	0	
St John Zachary	3	
St Katherine Coleman	56	
St Katherine Creechurch	89	
St Laurence Jewry	22	
St Laurence Pountney	2	
St Leonard Eaſtcheap	3	
St Leonard Foſter-lane	0	
St Magnus Pariſh	25	
St Margaret Lothbury	25	
St Margaret Moſes	1	
St Margaret New Fiſh-ſtr.	3	
St Margaret Pattons	9	
St Mary Abchurch	18	
St Mary Aldermanbury	22	
St Mary Aldermary	15	
St Mary le Bow	11	
St Mary Bothaw	1	
St Mary Colechurch	3	
St Mary Hill	11	
St Mary Magd. Milk-ſtr.	0	
St Mary Mag. Old Fiſh-ſtr.	5	
St Mary Mounthaw	0	
St Mary Somerſet	26	
St Mary Staining	4	
St Mary Woolchurch	0	
St Mary Woolnoth	22	
St Martin Ironmonger-lane	1	
St Martin Ludgate	11	
St Martin Orgars	7	
St Martin Outwich	24	
St Martin Vintrey	24	
St Matthew Friday-ſtreet	10	
St Michael Baſſiſhaw	14	
St Michael Cornhill	24	
St Michael Crooked-lane	26	
St Michael Queenhithe	39	
St Michael Querne	0	
St Michael Royal	2	
St Michael Wood-ſtreet	11	
St Mildred Bread-ſtreet	14	
St Mildred Poultry	24	
St Nicholas Acons	9	
St Nicholas Coleabby	13	
St Nicholas Olave	5	
St Olave Hart-ſtreet	62	
St Olave Jewry	11	
St Olave Silver-ſtreet	0	
St Pancras Soper-lane	2	
St Peter Cheap	4	
St Peter Cornhill	39	
St Peter Paul's Wharf	4	
St Peter Poor	24	
St Stephen Coleman-ſtreet	110	
St Stephen Walbrook	9	
St Swithin	14	
St Thomas Apoſtle	5	
Trinity Pariſh	9	
St Vedaſt, alias Foſter	38	

Chriſtened in the ninety-ſeven Pariſhes within the Walls 788 Buried 1890 Plague 0

St Andrew Holborn	1055	St Botolph Aldgate	858
St Bartholomew Great	104	St Botolph Biſhopſgate	489
St Bartholomew Leſs	41	St Dunſtan Weſt	256
St Bride's Pariſh	179	St George Southwark	347
Bridewell Precinct	16	St Giles Cripplegate	1607
St Botolph Alderſgate	207	St Olave Southwark	981
St Saviour Southwark	815		
St Sepulchre's Pariſh	783		
St Thomas Southwark	44		
Trinity Minories	26		
At the Peſt-houſe	0		

Chriſtened in the ſixteen Pariſhes without the Walls 4718 Buried 7808 Plague 0

St Giles in the Fields —1236	Lambeth Pariſh — ——307	St Mary Newington ——341
St John at Hackney——108	St Leonard Shoreditch —559	St Mary Whitechapel —1048
St James Clarkenwell —398	St Magdalen Bermondſey 482	Rotherhith Pariſh —— 119
St Katherine by the Tower262	St Mary Iſlington — — 134	Stepney Pariſh ———1898

Chriſtened in the twelve Out Pariſhes in Middleſex and Surrey 4092
Buried 6892 Plague 0

St Clement Danes — —544	St Martin in the Fields 1733	St Margaret Weſtminſt. 1058
St Paul Covent Garden 169	St Mary Savoy ——— 104	At the Peſt-houſe — — 0

Chriſtened in the five Pariſhes in the City and Liberties of Weſtminſter 2399
Buried 3608 Plague 0

DISEASES and CASUALTIES.

Abortive and Stillborn 632	Executed — — ——— 12	Overlaid —— ——— 57
Aged and Bedridden 923	Falling Sickneſs — —— 3	Palſy ——— — ——— 22
Ague and Fever —— —1729	Flox and Small Pox ——1465	Pleuriſy ——— —— 14
Apoplexy and Suddenly— 76	Found dead in the Streets,&c. 5	Quinſy ——— ——— 19
Blaſted and Planet ——— 4	French Pox —— — — 52	Rickets ——— ——— 346
Bleeding ——— — —— 1	Frighted —— ——— 1	Riſing of the Lights —— 169
Bloody Flux, Scowring, and Flux — 142	Gout ——— — —— 15	Rupture —— ——— 19
	Grief —— —— ——— 13	Scalded ——— — —— 5
Burnt and Blown up —— 8	Griping in the Guts — —3690	Scurvy —— — — — 37
Burſten ——— ——— 1	Hanged and made away themſelves — 13	Smothered ——— —— 2
Cancer, Gangrene, and Fiſtula — 54	Jaundies —— — —— 106	Sores, Ulcers, broken and bruiſed Limbs — 70
Canker and Thruſh —— 107	Impoſthume — —— — 136	Spleen ——— ——— 6
Catarrh ——— ——— 1	Killed by ſeveral Accidents 94	Spotted Fever — —— 121
Childbed ——— — — 288	King's Evil —— — — 44	Starved —— —— 2
Chriſomes and Infants — 746	Leproſy ——— ——— 1	Stopping of the Stomach 374
Cold and Cough — —— 39	Lethargy —— — —— 5	Strangury —— — —— 16
Colick and Wind ——— 100	Livergrown —— ——— 12	Surfeit —— — ——— 524
Conſumption and Tiſſick 3272	Lunatick ——— —— 4	Swine Pox —— —— 1
Convulſion ——— — —1695	Meaſles ——— ——— 295	Teeth and Worms ———1470
Cut of the Stone and Stone 42	Megrims ——— —— 5	Vomiting ——— —— 76
Dropſy and Tympany - — 919	Mother ——— ——— 1	Wolf —— —— 1
Drowned ——— ——— 82	Murdered —— — —— 11	

CHRISTENED	Males — 6278	BURIED	Males — 10614
	Females 5719		Females 9584
	In all — 11997		In all — 20198

Of the Plague 0

Increaſed in the Burials this Year 766
Decreaſed in the Plague this Year 3

1671.

A General BILL of all the Chriſtenings and Burials,

From the 22d of December 1670, to the 19th of December 1671.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.	Pl.
St ALBAN Wood-ſtreet	25	
Alhallows Barkin	79	
Alhallows Bread-ſtreet	17	
Alhallows Great	21	
Alhallows Honey-lane	0	
Alhallows Leſs	11	
Alhallows Lombard-ſtreet	19	
Alhallows Staining	22	
Alhallows the Wall	61	
St Alphage	18	
St Andrew Hubbard	5	
St Andrew Underſhaft	60	
St Andrew Wardrobe	32	
St Ann Alderſgate	30	
St Ann Black Friars	64	
St Antholin's Pariſh	18	
St Auſtin's Pariſh	4	
St Bartholomew Exchange	15	
St Bennet Fink	13	
St Bennet Gracechurch	7	
St Bennet Paul's Wharf	21	
St Bennet Sherehog	4	
St Botolph Billingſgate	2	
Chriſt Church	65	
St Chriſtopher	10	
St Clement Eaſtcheap	4	
St Dionis Backchurch	13	
St Dunſtan Eaſt	55	
St Edmund Lombard-ſtr.	4	
St Ethelborough	31	
St Faith's	18	
St Gabriel Fenchurch	3	
St George Botolph-lane	6	
St Gregory by St Paul's	32	
St Helen's	29	
St James Duke's Place	39	
St James Garlickhithe	20	
St John Baptiſt	6	
St John Evangeliſt	5	
St John Zachary	2	
St Katherine Coleman	37	
St Katherine Creechurch	62	
St Laurence Jewry	19	
St Laurence Pountney	3	
St Leonard Eaſtcheap	5	
St Leonard Foſter-lane	0	
St Magnus Pariſh	23	
St Margaret Lothbury	18	
St Margaret Moſes	2	
St Margaret New Fiſh-ſtr.	2	
St Margaret Pattons	7	
St Mary Abchurch	17	
St Mary Aldermanbury	26	
St Mary Aldermary	19	
St Mary le Bow	16	
St Mary Bothaw	0	
St Mary Colechurch	2	
St Mary Hill	11	
St Mary Magd. Milk-ſtr.	0	
St Mary Mag. Old Fiſh-ſtr.	12	
St Mary Mounthaw	4	
St Mary Somerſet	18	
St Mary Staining	6	
St Mary Woolchurch	0	
St Mary Woolnoth	20	
St Martin Ironmonger-lane	3	
St Martin Ludgate	15	
St Martin Orgars	9	
St Martin Outwich	24	
St Martin Vintrey	21	
St Matthew Friday-ſtreet	14	
St Michael Baſſiſhaw	10	
St Michael Cornhill	22	
St Michael Crooked-lane	17	
St Michael Queenhithe	28	
St Michael Querne	0	
St Michael Royal	4	
St Michael Wood-ſtreet	18	
St Mildred Bread-ſtreet	17	
St Mildred Poultry	23	
St Nicholas Acons	12	
St Nicholas Coleabby	12	
St Nicholas Olave	7	
St Olave Hart-ſtreet	47	
St Olave Jewry	6	
St Olave Silver-ſtreet	5	
St Pancras Soper-lane	5	
St Peter Cheap	2	
St Peter Cornhill	16	
St Peter Paul's Wharf	2	
St Peter Poor	7	
St Stephen Coleman-ſtreet	77	
St Stephen Walbrook	10	
St Swithin	24	
St Thomas Apoſtle	0	
Trinity Pariſh	4	
St Vedaſt, alias Foſter	23	

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1038 Buried 1723 Plague 0

St Andrew Holborn	837	
St Bartholomew Great	61	
St Bartholomew Leſs	35	
St Bride's Pariſh	181	
Bridewell Precinct	16	
St Botolph Alderſgate	165	
St Botolph Aldgate	640	
St Botolph Biſhopſgate	331	
St Dunſtan Weſt	185	
St George Southwark	238	
St Giles Cripplegate	1184	
St Olave Southwark	750	
St Saviour Southwark	610	
St Sepulchre's Pariſh	647	
St Thomas Southwark	47	
Trinity Minories	14	
At the Peſt-houſe	0	

Chriſtened in the ſixteen Pariſhes without the Walls 4715 Buried 5938 Plague 0

1671.

St Giles in the Fields —963	St Leonard Shoreditch—392	St Mary Whitechapel —750
St John at Hackney— 77	St Magdalen Bermondſey365 1	St Paul Shadwell —281 2
St James Clarkenwell —387	St Mary Iſlington —104	Rotherhith Pariſh — —106 2
St Katherine by the Tower191	St Mary Newington—192	Stepney Pariſh — —1324
Lambeth Pariſh —226		

Chriſtened in the thirteen Out Pariſhes in Middleſex and Surrey 4242
Buried 5358 Plague 5

St Clement Danes — —407	St Martin in the Fields 1252	St Margaret Weſtminſter 844
St Paul Covent Garden 132	St Mary Savoy — 75	At the Peſt-houſe — 0

Chriſtened in the five Pariſhes in the City and Liberties of Weſtminſter 2515
Buried 2710 Plague 0

DISEASES and CASUALTIES.

Abortive and Stillborn 600	Executed — — 11	Palſy — — — 15
Aged and Bedridden 725	Falling Sickneſs — — 2	Plague — — 5
Ague and Fever — —1343	Flox and Small Pox — 696	Planet — — 2
Apoplexy and Suddenly— 63	Found dead in the Streets 17	Pleuriſy — — 16
Bleeding — — 4	French Pox — — 50	Quinſy — — — 17
Bloody Flux, Scowring, and Flux — 86	Gout — — — 11	Rickets — — — 265
	Grief — — 14	Riſing of the Lights — 169
Burnt and Scalded — 5	Griping in the Guts — —2537	Scurvy — — — 58
Burſten and Rupture — 21	Hanged and made away themſelves — 10	Smothered — — 4
Calenture — — 3		Sores, Ulcers, broken and bruiſed Limbs 73
Cancer, Gangrene, and Fiſtula — 49	Head-ach — — 2	
	Headmouldſhot — — 2	Spleen — — 6
Canker and Thruſh — 76	Jaundies — — 80	Spotted Fever — — 77
Childbed — — 262	Impoſthume — — 102	Stabbed — — 1
Chriſomes and Infants — 650	Kill'd by ſeveral Accidents 62	Starved — — — — 3
Cold and Cough — — 25	King's Evil — — 43	Stopping of the Stomach 323
Colick and Wind — 84	Lethargy — — — 3	Strangury — — 13
Conſumption and Tiſſick 2710	Lunatick and Diſtracted— 6	Surfeit — — 457
Convulſion — —1650	Meaſles — — 7	Swine Pox — — 2
Cut of the Stone and Stone 44	Megrims — — — 3	Teeth and Worms — —1079
Devoured by Lice — 1	Mother — — 1	Vomiting — — 52
Dropſy and Tympany — 887	Murdered — — 12	Wen — — — 2
Drowned — — 78	Overlaid — — 53	

CHRISTENED	Males — 6449	BURIED	Males — 8475	Of the Plague 5
	Females 6061		Females 7254	
	In all — 12510		In all 15729	

Decreaſed in the Burials this Year 4469	Pariſhes clear of the Plague — 128
Increaſed of the Plague — 5	Pariſhes infected — — 3

1672.

A General BILL of all the Chriſtenings and Burials,

From the 19th of December 1671, to the 17th of December 1672.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.	Pl.
St ALBAN Wood-ſtreet	34	
Alhallows Barkin	85	
Alhallows Bread-ſtreet	19	
Alhallows Great	26	
Alhallows Honey-lane	0	
Alhallows Leſs	17	
Alhallows Lombard-ſtreet	23	
Alhallows Staining	33	
Alhallows the Wall	65	
St Alphage	41	
St Andrew Hubbard	18	
St Andrew Underſhaft	68	
St Andrew Wardrobe	34	
St Ann Alderſgate	34	
St Ann Black Friars	67	
St Antholin's Pariſh	15	
St Auſtin's Pariſh	8	
St Bartholomew Exchange	29	
St Bennet Fink	15	
St Bennet Gracechurch	13	
St Bennet Paul's Wharf	27	
St Bennet Sherehog	5	
St Botolph Billingſgate	16	
Chriſt Church	76	
St Chriſtopher	14	
St Clement Eaſtcheap	9	
St Dionis Backchurch	22	
St Dunſtan Eaſt	89	
St Edmund Lombard-ſtr.	15	
St Ethelborough	25	
St Faith's	22	
St Gabriel Fenchurch	6	
St George Botolph-lane	6	
St Gregory by St Paul's	40	
St Helen's	34	
St James Duke's Place	48	
St James Garlickhithe	34	
St John Baptiſt	14	
St John Evangeliſt	4	
St John Zachary	10	
St Katherine Coleman	37	
St Katherine Creechurch	65	
St Laurence Jewry	46	
St Laurence Pountney	9	
St Leonard Eaſtcheap	11	
St Leonard Foſter-lane	14	
St Magnus Pariſh	36	
St Margaret Lothbury	24	
St Margaret Moſes	2	
St Margaret New Fiſh-ſtr.	0	
St Margaret Pattons	6	
St Mary Abchurch	20	
St Mary Aldermanbury	28	
St Mary Aldermary	16	
St Mary le Bow	19	
St Mary Bothaw	1	
St Mary Colechurch	3	
St Mary Hill	21	
St Mary Magd. Milk-ſtr.	2	
St Mary Mag. Old Fiſh-ſtr.	10	
St Mary Mounthaw	6	
St Mary Somerſet	27	
St Mary Staining	5	
St Mary Woolchurch	0	
St Mary Woolnoth	30	
St Martin Ironmonger-lane	7	
St Martin Ludgate	15	
St Martin Orgars	12	
St Martin Outwich	12	
St Martin Vintrey	17	
St Matthew Friday-ſtreet	18	
St Michael Baſſiſhaw	15	
St Michael Cornhill	31	
St Michael Crooked-lane	18	
St Michael Queenhithe	35	
St Michael Querne	0	
St Michael Royal	5	
St Michael Wood-ſtreet	15	
St Mildred Bread-ſtreet	12	
St Mildred Poultry	35	
St Nicholas Acons	12	
St Nicholas Coleabby	2	
St Nicholas Olave	24	
St Olave Hart-ſtreet	58	
St Olave Jewry	12	
St Olave Silver-ſtreet	12	
St Pancras Soper-lane	4	
St Peter Cheap	0	
St Peter Cornhill	32	
St Peter Paul's Wharf	1	
St Peter Poor	28	
St Stephen Coleman-ſtreet	113	
St Stephen Walbrook	13	
St Swithin	28	
St Thomas Apoſtle	1	
Trinity Pariſh	3	
St Vedaſt, alias Foſter	49	
Chriſtened in the ninety-ſeven Pariſhes within the Walls	1327	
Buried 2237	Plague 0	

St Andrew Holborn	944	St Botolph Aldgate	723	1	St Olave Southwark 864 1
St Bartholomew Great	79	St Botolph Biſhopſgate	420		St Saviour Southwark 606
St Bartholomew Leſs	34	Chriſt Church	110		St Sepulchre's Pariſh 685
St Bride's Pariſh	203	St Dunſtan Weſt	204		St Thomas Southwark 80
Bridewell Precinct	11	St George Southwark	288		Trinity Minories 27
St Botolph Alderſgate	213	St Giles Cripplegate	1299		At the Peſt-houſe 0
Chriſtened in the ſeventeen Pariſhes without the Walls	4655				Buried 6790 Plague 2

1672.

St Giles in the Fields —1147	St Leonard Shoreditch—423	St Mary Whitechapel —808
St John at Hackney—— 99	St Magdalen Bermondſey440	St Paul Shadwell ——453 1
St James Clarkenwell —393	St Mary Iſlington — —110	Rotherhith Pariſh — — 98 1
St Katherine by the Tower169	St Mary Newington——220	Stepney Pariſh —— —1531
Lambeth Pariſh ——249 1		

Chriſtened in the thirteen Out Pariſhes in Middleſex and Surrey 4214
Buried 6140 Plague 3

St Clement Danes — —490	St Martin in the Fields 1505	St Margaret Weſtminſter 855
St Paul Covent Garden 139	St Mary Savoy —— 74	Whereof at the Peſt-houſe 0

Chriſtened in the five Pariſhes in the City and Liberties of Weſtminſter 2367
Buried 3063 Plague 0

DISEASES and CASUALTIES.

Abortive and Stillborn 580	Drowned — — —— 74	Plague —— —— 5
Aged and Bedridden 912	Executed —— — 9	Pleuriſy —— —— 16
Ague and Fever —— —1615	Falling Sickneſs — —— 3	Poiſoned — —— — 5
Apoplexy-and Suddenly— 65	Flox and Small Pox ——1116	Quinſy —— — —— 14
Bleeding —— —— 1	Found dead in the Streets,&c. 9	Rickets —— —— 325
Bloody Flux, Scowring, and Flux — 127	French Pox —— —— 64	Riſing of the Lights —— 163
	Frighted —— —— 2	Scalded —— —— 3
Burnt and Blown up —— 10	Gout and Sciatica — — 24	Scald Head —— —— 1
Burſten and Rupture —— 23	Grief —— — —— 12	Scurvy —— —— 51
Calenture and Megrims— 4	Griping in the Guts — —2645	Smothered and Stifled - — 4
Cancer, Gangrene, and Fiſtula — 57	Hang'd and made away themſelves — 18	Sores, Ulcers, broken and bruiſed Limbs 61
Canker and Thruſh — — 76	Headmouldſhot — —— 2	Spleen —— — —— 5
Childbed —— —— 265	Jaundies —— —— 99	Spotted Fever and Purples 112
Choaked —— —— 1	Impoſthume — — —— 106	Starved — — — —— 2
Chriſomes and Infants -— 599	Kill'd by ſeveral Accidents 71	Stone and Strangury —— 59
Cold and Cough —— 48	King's Evil — — —— 43	Stopping of the Stomach 400
Colick and Wind — —— 99	Lethargy —— —— 6	Surfeit —— — —— 472
Conſumption and Tiſſick 3165	Livergrown — — —— 11	Teeth —— ——1299
Convulſion — — ——1965	Meaſles —— —— 118	Vomiting — — —— 39
Devoured by Lice —— 1	Murdered — — —— 6	Worms —— —— 65
Diſtracted and Lunatick— 9	Overlaid —— —— 56	Wounded and Shot —— 21
Dropſy and Tympany —— 971	Palſy —— —— — 21	

CHRISTENED	Males — 6443 Females 6120 In all — 12563	BURIED	Males — 9560 Females 8670 In all — 18230

Of the Plague 5

Increaſed in the Burials this Year 2501	Pariſhes clear of the Plague — 127
Increaſed in the Plague this Year 0	Pariſhes infected —— 5

A General

1673.

A General BILL of all the Chriſtenings and Burials,

From the 17th of December 1672, to the 16th of December 1673.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.	Pl.
St ALBAN Wood-ſtreet	26	
Alhallows Barkin	95	
Alhallows Bread-ſtreet	28	
Alhallows Great	42	
Alhallows Honey-lane	0	
Alhallows Leſs	16	
Alhallows Lombard-ſtreet	31	
Alhallows Staining	36	
Alhallows the Wall	80	
St Alphage	31	
St Andrew Hubbard	14	
St Andrew Underſhaft	53	
St Andrew Wardrobe	28	
St Ann Alderſgate	29	
St Ann Black Friars	87	
St Antholin's Pariſh	17	
St Auſtin's Pariſh	10	
St Bartholomew Exchange	14	
St Bennet Fink	15	
St Bennet Gracechurch	17	
St Bennet Paul's Wharf	29	
St Bennet Sherehog	4	
St Botolph Billingſgate	10	
Chriſt Church	86	
St Chriſtopher	9	
St Clement Eaſtcheap	7	
St Dionis Backchurch	17	
St Dunſtan Eaſt	81	
St Edmund Lombard-ſtr.	15	
St Ethelborough	23	
St Faith's	30	
St Gabriel Fenchurch	5	
St George Botolph-lane	4	
St Gregory by St Paul's	44	
St Helen's	41	
St James Duke's Place	32	
St James Garlickhithe	22	
St John Baptiſt	13	
St John Evangeliſt	1	
St John Zachary	14	
St Katherine Coleman	43	
St Katherine Creechurch	60	
St Laurence Jewry	39	
St Laurence Pountney	12	
St Leonard Eaſtcheap	13	
St Leonard Foſter-lane	11	
St Magnus Pariſh	31	
St Margaret Lothbury	25	
St Margaret Moſes	1	
St Margaret New Fiſh-ſtr.	0	
St Margaret Pattons	11	
St Mary Abchurch	27	
St Mary Aldermanbury	36	
St Mary Aldermary	23	
St Mary le Bow	17	
St Mary Bothaw	0	
St Mary Colechurch	5	
St Mary Hill	22	
St Mary Magd. Milk-ſtr.	3	
St Mary Mag. Old Fiſh-ſtr.	19	
St Mary Mounthaw	1	
St Mary Somerſet	26	
St Mary Staining	11	
St Mary Woolchurch	0	
St Mary Woolnoth	29	
St Martin Ironmonger-lane	2	
St Martin Ludgate	30	
St Martin Orgars	18	
St Martin Outwich	23	
St Martin Vintrey	29	
St Matthew Friday-ſtreet	19	
St Michael Baſſiſhaw	22	
St Michael Cornhill	28	
St Michael Crooked-lane	23	
St Michael Queenhithe	28	
St Michael Querne	0	
St Michael Royal	6	
St Michael Wood-ſtreet	14	
St Mildred Bread-ſtreet	13	
St Mildred Poultry	30	
St Nicholas Acons	12	
St Nicholas Coleabby	10	
St Nicholas Olave	8	
St Olave Hart-ſtreet	37	
St Olave Jewry	14	
St Olave Silver-ſtreet	24	
St Pancras Soper-lane	9	
St Peter Cheap	4	
St Peter Cornhill	36	
St Peter Paul's Wharf	6	
St Peter Poor	30	
St Stephen Coleman-ſtreet	110	
St Stephen Walbrook	10	
St Swithin	18	
St Thomas Apoſtle	18	
Trinity Pariſh	7	
St Vedaſt, alias Foſter	48	

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1419 Buried 2307 Plague 0

St Andrew Holborn	876	St Botolph Aldgate	685	1	St Olave Southwark 786
St Bartholomew Great	66	St Botolph Biſhopſgate	360		St Saviour Southwark 586 1
St Bartholomew Leſs	35	Chriſt Church	100		St Sepulchre's Pariſh 616
St Bride's Pariſh	228	St Dunſtan Weſt	216		St Thomas Southwark 53
Bridewell Precinct	16	St George Southwark	245	1	Trinity Minories 20
St Botolph Alderſgate	190	St Giles Cripplegate	1228	1	At the Peſt-houſe 0

Chriſtened in the ſeventeen Pariſhes without the Walls 4236 Buried 6306 Plague 4

1673.

St Giles in the Fields—1039	St Leonard Shoreditch—395	St Mary Whitechapel —723
St John at Hackney—— 75	St Magdalen Bermondſey442 1	St Paul Shadwell ——420
St James Clarkenwell —326	St Mary Iſlington — —101	Rotherhith Pariſh ——166
St Katherine by the Tower181	St Mary Newington——197	Stepney Pariſh ——1409
Lambeth Pariſh ——233		

Chriſtened in the thirteen Out Pariſhes in Middleſex and Surrey 3909
Buried 5707 Plague 1

St Clement Danes — —434	St Martin in the Fields 1523	St Margaret Weſtminſter 985
St Paul Covent Garden 159	St Mary Savoy —— 83	At the Peſt-houſe—— 0

Chriſtened in the five Pariſhes in the City and Liberties of Weſtminſter 2331
Buried 3184 Plague 0

DISEASES and CASUALTIES.

Abortive and Stillborn 616	Flox and Small Pox —— 853	Pleuriſy —— —— 11
Aged and Bedridden 866	Found dead in the Streets,&c. 4	Poiſoned —— —— 2
Ague and Fever — ——1804	French Pox —— —— 48	Quinſy and Thruſh —— 64
Apoplexy and Suddenly— 84	Gangrene and Fiſtula—— 17	Rickets —— —— 339
Bleeding —— —— 5	Gout —— —— —— 22	Riſing of the Lights —— 133
Bloody Flux, Scowring, and Flux —— 70	Grief —— — —— 12	Scurvy —— —— 53
	Griping in the Guts — —2624	Smothered and Stifled —— 6
Burnt and Scalded — — 8	Hang'd and made away themſelves — 13	Sores, Ulcers, broken and bruiſed Limbs 49
Burſten and Rupture —— 36		
Calenture —— —— 3	Head-ach —— —— 1	Spleen —— —— —— 3
Cancer, Canker and Wolf 38	Jaundies —— —— 75	Spotted Fever and Purples 144
Childbed —— — —— 224	Impoſthume —— —— 102	St Anthony's Fire —— 5
Chriſomes and Infants —— 493	Kill'd by ſeveral Accidents 72	Starved —— —— 1
Colick and Wind — —— 87	King's Evil —— —— 60	Stopping of the Stomach 304
Cold and Cough — — 31	Lethargy —— — — 3	Strangury —— —— 18
Conſumption and Tiſſick 3320	Livergrown —— —— 15	Surfeit —— —— —— 477
Convulſion —— ——1761	Meaſles —— — —— 15	Swine Pox —— —— 3
Cut of the Stone and Stone 65	Mother —— —— 2	Teeth —— — —1131
Diſtracted and Lunatick— 7	Murdered —— —— 14	Vomiting —— —— 32
Dropſy and Tympany — 900	Overlaid —— —— 53	Wen — —— —— 2
Drowned —— —— 153	Palſy —— — —— 24	Worms —— —— 66
Executed —— — —— 31	Plague —— — —— 5	Wounded and Shot —— 22
Falling Sickneſs — —— 2	Planet —— —— 1	

CHRISTENED	Males — 6073	BURIED	Males — 9302	Of the Plague	5
	Females 5822		Females 8202		
	In all 11895		In all — 17504		

Decreaſed in the Burials this Year	726	Pariſhes clear of the Plague —	127
Increaſed in the Plague ——	0	Pariſhes infected — ——	5

A General

1674.

A General BILL of all the Chriſtenings and Burials,

From the 16th of December 1673, to the 15th of December 1674.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.	Pl.
St ALBAN Wood-ſtreet	40	
Alhallows Barkin	116	
Alhallows Bread-ſtreet	24	
Alhallows Great	51	
Alhallows Honey-lane	0	
Alhallows Leſs	12	
Alhallows Lombard-ſtreet	23	
Alhallows Staining	35	
Alhallows the Wall	70	
St Alphage	35	
St Andrew Hubbard	21	
St Andrew Underſhaft	66	
St Andrew Wardrobe	43	
St Ann Alderſgate	42	
St Ann Black Friars	115	
St Antholin's Pariſh	20	
St Auſtin's Pariſh	10	
St Bartholomew Exchange	20	
St Bennet Fink	18	
St Bennet Gracechurch	10	
St Bennet Paul's Wharf	37	
St Bennet Sherehog	4	
St Botolph Billingſgate	12	
Chriſt Church	82	
St Chriſtopher	18	
St Clement Eaſtcheap	11	
St Dionis Backchurch	28	
St Dunſtan Eaſt	81	
St Edmund Lombard-ſtr.	24	
St Ethelborough	30	
St Faith's	26	
St Gabriel Fenchurch	6	
St George Botolph-lane	8	
St Gregory by St Paul's	75	
St Helen's	42	
St James Duke's Place	42	
St James Garlickhithe	27	
St John Baptiſt	16	
St John Evangeliſt	3	
St John Zachary	20	
St Katherine Coleman	52	
St Katherine Creechurch	89	
St Laurence Jewry	41	
St Laurence Pountney	36	
St Leonard Eaſtcheap	25	
St Leonard Foſter-lane	23	
St Magnus Pariſh	45	
St Margaret Lothbury	46	
St Margaret Moſes	5	
St Margaret New Fiſh-ſtr.	0	
St Margaret Pattons	21	
St Mary Abchurch	41	
St Mary Aldermanbury	31	
St Mary Aldermary	31	
St Mary le Bow	26	
St Mary Bothaw	5	
St Mary Colechurch	7	
St Mary Hill	27	
St Mary Magd. Milk-ſtr.	2	
St Mary Mag. Old Fiſh-ſtr.	17	
St Mary Mounthaw	4	
St Mary Somerſet	36	
St Mary Staining	13	
St Mary Woolchurch	3	
St Mary Woolnoth	37	
St Martin Ironmonger-lane	7	
St Martin Ludgate	45	
St Martin Orgars	21	
St Martin Outwich	14	
St Martin Vintrey	36	
St Matthew Friday-ſtreet	17	
St Michael Baſſiſhaw	21	
St Michael Cornhill	40	
St Michael Crooked-lane	22	
St Michael Queenhithe	50	
St Michael Querne	1	
St Michael Royal	15	
St Michael Wood-ſtreet	14	
St Mildred Bread-ſtreet	12	
St Mildred Poultry	20	
St Nicholas Acons	12	
St Nicholas Coleabby	16	
St Nicholas Olave	14	
St Olave Hart-ſtreet	45	
St Olave Jewry	15	
St Olave Silver-ſtreet	30	
St Pancras Soper-lane	21	
St Peter Cheap	1	
St Peter Cornhill	27	
St Peter Paul's Wharf	2	
St Peter Poor	32	
St Stephen Coleman-ſtreet	107	
St Stephen Walbrook	20	
St Swithin	36	
St Thomas Apoſtle	23	
Trinity Pariſh	1	
St Vedaſt, alias Foſter	44	

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1560 Buried 2801 Plague 0

St Andrew Holborn	1036	St Botolph Aldgate	875
St Bartholomew Great	83	St Botolph Biſhopſgate	412
St Bartholomew Leſs	49	St Dunſtan Weſt	295
St Bride's Pariſh	365	St George Southwark	339
Bridewell Precinct	26	St Giles Cripplegate	1330 3
St Botolph Alderſgate	197	St Olave Southwark	966
St Saviour Southwark	717		
St Sepulchre's Pariſh	721		
St Thomas Southwark	96		
Trinity Minories	18		
At the Peſt-houſe	0		

Chriſtened in the ſixteen Pariſhes without the Walls 3873 Buried 7525 Plague 3

1674.

Chriſt Church — ——162	Lambeth Pariſh — ——279	St Mary Whitechapel —921
St Giles in the Fields —1359	St Leonard Shoreditch —514	St Paul Shadwell ——451
St John at Hackney—— 80	St Magdalen Bermondſey 519	Rotherhith Pariſh — —124
St James Clarkenwell —406	St Mary Iſlington — — 112	Stepney Pariſh — ——1675
St Katherine by the Tower178	St Mary Newington ——238	

Chriſtened in the fourteen Out Pariſhes in Middleſex and Surrey 4091
Buried 7017 Plague 0

St Clement Danes — —538	St Martin in the Fields 1949	St Margaret Weſtminſt. 1085
St Paul Covent Garden 187	St Mary Savoy —— 99	At the Peſt-houſe — — 0

Chriſtened in the five Pariſhes in the City and Liberties of Weſtminſter 2327
Buried 3858 Plague 0

DISEASES and CASUALTIES.

Abortive and Stillborn 569	Found dead in the Streets,&c. 7	Plague —— —— 3
Aged and Bedridden 1032	French Pox —— — — 51	Pleuriſy —— —— 9
Ague and Fever —— —2164	Gangrene and Fiſtula—— 39	Quinſy and Thruſh —— 54
Apoplexy and Suddenly— 101	Gout —— — —— 12	Rickets —— —— 497
Blaſted and Planet —— 3	Grief —— —— —— 23	Riſing of the Lights —— 178
Bleeding —— — —— 1	Griping in the Guts — —1777	Sciatica —— —— 1
Bloody Flux, Scowring, and Flux — } 188	Hanged and made away themſelves — } 18	Scurvy —— — — — 70
		Smothered and Suffocated 6
Burnt and Scalded — — 3	Head-ach —— —— 2	Sores, Ulcers, broken and bruiſed Limbs — } 55
Burſten and Rupture —— 54	Headmouldſhot —— 1	
Cancer and Canker —— 39	Jaundies —— — —— 84	Spleen —— —— 9
Childbed —— — — 217	Impoſthume — —— — 104	Spotted Fever and Purples 285
Chriſomes and Infants — 541	Killed by ſeveral Accidents 59	St Anthony's Fire —— 6
Cold and Cough — —— 21	King's Evil —— — — 77	Starved at Nurſe —— 1
Colick and Wind —— 133	Lethargy —— — —— 29	Stopping of the Stomach 376
Conſumption and Tiſſick 3785	Livergrown —— —— 39	Strangury —— — —— 13
Convulſion —— — —2256	Meaſles —— —— 795	Surfeit —— — —— 391
Cramp —— —— 1	Megrims —— —— 6	Swine Pox —— —— 3
Cut of the Stone and Stone 60	Murdered —— — —— 14	Teeth — — — —1265
Dropſy and Tympany - — 912	Noli me tangere —— — 1	Vomiting —— —— 11
Drowned —— —— 83	Overlaid —— —— 68	Worms —— —— 55
Executed — — —— 17	Palſy —— — —— 10	Wounded —— —— 4
Flox and Small Pox —— 2507		

CHRISTENED { Males — 6113 / Females 5738 / In all — 11851 }	BURIED { Males — 11005 / Females 10196 / In all — 21201 }	Of the Plague	3

Increaſed in the Burials this Year	3697	Pariſhes clear of the Plague —	131
Decreaſed in the Plague —	2	Pariſhes infected ——	1

1675.

A General BILL of all the Chriſtenings and Burials,

From the 15th of December 1674, to the 14th of December 1675.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.	Pl.
St ALBAN Wood-ſtreet	38	
Alhallows Barkin	109	
Alhallows Bread-ſtreet	18	
Alhallows Great	43	
Alhallows Honey-lane	0	
Alhallows Leſs	11	
Alhallows Lombard-ſtreet	23	
Alhallows Staining	41	
Alhallows the Wall	62	
St Alphage	31	
St Andrew Hubbard	16	
St Andrew Underſhaft	39	
St Andrew Wardrobe	27	
St Ann Alderſgate	29	
St Ann Black Friars	79	
St Antholin's Pariſh	22	
St Auſtin's Pariſh	10	
St Bartholomew Exchange	19	
St Bennet Fink	16	
St Bennet Gracechurch	13	
St Bennet Paul's Wharf	36	
St Bennet Sherehog	4	
St Botolph Billingſgate	21	
Chriſt Church	80	
St Chriſtopher	20	
St Clement Eaſtcheap	10	
St Dionis Backchurch	35	
St Dunſtan Eaſt	73	
St Edmund Lombard-ſtr.	18	
St Ethelborough	22	
St Faith's	29	
St Gabriel Fenchurch	14	
St George Botolph-lane	12	
St Gregory by St Paul's	62	
St Helen's	39	
St James Duke's Place	38	
St James Garlickhithe	28	
St John Baptiſt	13	
St John Evangeliſt	5	
St John Zachary	12	
St Katherine Coleman	34	
St Katherine Creechurch	76	
St Laurence Jewry	69	
St Laurence Pountney	28	
St Leonard Eaſtcheap	12	
St Leonard Foſter-lane	22	
St Magnus Pariſh	31	
St Margaret Lothbury	27	
St Margaret Moſes	5	
St Margaret New Fiſh-ſtr.	0	
St Margaret Pattons	15	
St Mary Abchurch	30	
St Mary Aldermanbury	32	
St Mary Aldermary	37	
St Mary le Bow	25	
St Mary Bothaw	1	
St Mary Colechurch	3	
St Mary Hill	27	
St Mary Magd. Milk-ſtr.	2	
St Mary Mag. Old Fiſh-ſtr.	22	
St Mary Mounthaw	6	
St Mary Somerſet	29	
St Mary Staining	8	
St Mary Woolchurch	0	
St Mary Woolnoth	39	
St Martin Ironmonger-lane	9	
St Martin Ludgate	33	
St Martin Orgars	29	
St Martin Outwich	11	
St Martin Vintrey	43	
St Matthew Friday-ſtreet	25	
St Michael Baſſiſhaw	19	
St Michael Cornhill	30	
St Michael Crooked-lane	23	
St Michael Queenhithe	31	
St Michael Querne	3	
St Michael Royal	16	
St Michael Wood-ſtreet	22	
St Mildred Bread-ſtreet	10	
St Mildred Poultry	26	
St Nicholas Acons	13	
St Nicholas Coleabby	11	
St Nicholas Olave	13	
St Olave Hart-ſtreet	48	
St Olave Jewry	17	
St Olave Silver-ſtreet	30	
St Pancras Soper-lane	4	
St Peter Cheap	2	
St Peter Cornhill	31	
St Peter Paul's Wharf	9	
St Peter Poor	32	
St Stephen Coleman-ſtreet	100	
St Stephen Walbrook	13	
St Swithin	32	
St Thomas Apoſtle	21	
Trinity Pariſh	4	
St Vedaſt, alias Foſter	48	
Chriſtened in the ninety-ſeven Pariſhes within the Walls	1650	
Buried 2555	Plague 0	

St Andrew Holborn	832	St Botolph Aldgate	664
St Bartholomew Great	74	St Botolph Biſhopſgate	354
St Bartholomew Leſs	28	St Dunſtan Weſt	251
St Bride's Pariſh	303	St George Southwark	277
Bridewell Precinct	25	St Giles Cripplegate	1145
St Botolph Alderſgate	171	St Olave Southwark	644
St Saviour Southwark	511		
St Sepulchre's Pariſh	629		
St Thomas Southwark	56		
Trinity Minories	22		
At the Peſt-houſe	0		
Chriſtened in the ſixteen Pariſhes without the Walls	3903		
Buried 5986	Plague 0		

1675.

Chriſt Church — —109	Lambeth Pariſh —237	St Mary Whitechapel —746
St Giles in the Fields —977	St Leonard Shoreditch—456	St Paul Shadwell —380
St John at Hackney—112	St Magdalen Bermondſey382	Rotherhith Pariſh — —128
St James Clarkenwell —324	St Mary Iſlington — 91	Stepney Pariſh — —1358 1
St Katherine by the Tower165	St Mary Newington—212	

Chriſtened in the fourteen Out Pariſhes in Middleſex and Surrey 3846
Buried 5677 Plague 1

St Clement Danes — —455	St Martin in the Fields 1475	St Margaret Weſtminſter 877
St Paul Covent Garden 156	St Mary Savoy — 63	At the Peſt-houſe — 0

Chriſtened in the five Pariſhes in the City and Liberties of Weſtminſter 2376
Buried 3026 Plague 0

DISEASES and CASUALTIES.

Abortive and Stillborn 712	Gangrene and Fiſtula— 26	Quinſy and Thruſh — 64
Aged and Bedridden 1014	Gout — — — 15	Rickets — — — 488
Ague and Fever — —2154	Grief — — 15	Riſing of the Lights — 172
Apoplexy and Suddenly— 86	Griping in the Guts — —2083	Sciatica — — 1
Blaſted and Planet — 2	Hanged and made away themſelves — 19	Scurvy — — — 43
Bleeding, Bloody Flux, and Flux — 108	Headmouldſhot — — 10	Shot — — 4
Burnt and Scalded — 9	Hiccough — — 1	Smothered — — 3
Burſten and Rupture — 34	Jaundies — — 73	Sores, Ulcers, and bruiſed Limbs — 53
Cancer and Canker — 50	Jawfallen — — 2	Spleen — — 3
Childbed — — 284	Impoſthume — — 107	Spotted Fever — — 143
Chriſomes and Infants — 400	Kill'd by ſeveral Accidents 67	St Anthony's Fire — 5
Cold and Cough — — 13	King's Evil — — 60	Starved — — — — 2
Colick and Wind — 120	Lethargy — — — 50	Stone — — — 48
Conſumption and Tiſſick 3148	Livergrown — — 27	Stopping of the Stomach 308
Convulſion — —1961	Meaſles — — 1	Strangury — — 17
Diſtracted and Lunatick— 12	Megrims — — — 5	Surfeit — — 283
Dropſy and Tympany — 655	Murdered — — 15	Swine Pox — — 1
Drowned — — 57	Overlaid — — 83	Teeth — — — 910
Executed — — 18	Palſy — — — 16	Vomiting — — 24
Flox and Small Pox — 997	Plague — — 1	Worms — — — 44
Found dead in the Streets 8	Pleuriſy — — 30	Wounded — — 1
French Pox — — 75	Poiſoned — — 4	

CHRISTENED { Males — 6058 / Females 5717 / In all — 11775 } | BURIED { Males — 8934 / Females 8310 / In all 17244 } Of the Plague 1

Decreaſed in the Burials this Year 3957	Pariſhes clear of the Plague — 131
Decreaſed in the Plague — 2	Pariſhes infected — — 1

1676.

A General BILL of all the Chriſtenings and Burials,

From the 14th of December 1675, to the 19th of December 1676.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.	Pl.
St ALBAN Wood-ſtreet	35	
Alhallows Barkin	94	
Alhallows Bread-ſtreet	19	
Alhallows Great	52	
Alhallows Honey-lane	0	
Alhallows Leſs	11	
Alhallows Lombard-ſtreet	27	
Alhallows Staining	38	
Alhallows the Wall	77	
St Alphage	40	
St Andrew Hubbard	10	
St Andrew Underſhaft	43	
St Andrew Wardrobe	48	
St Ann Alderſgate	25	
St Ann Black Friars	83	
St Antholin's Pariſh	20	
St Auſtin's Pariſh	10	
St Bartholomew Exchange	25	
St Bennet Fink	29	
St Bennet Gracechurch	16	
St Bennet Paul's Wharf	31	
St Bennet Sherehog	6	
St Botolph Billingſgate	10	
Chriſt Church	91	
St Chriſtopher	25	
St Clement Eaſtcheap	9	
St Dionis Backchurch	36	
St Dunſtan Eaſt	75	
St Edmund Lombard-ſtr.	21	
St Ethelborough	18	
St Faith's	26	
St Gabriel Fenchurch	21	
St George Botolph-lane	9	
St Gregory by St Paul's	67	
St Helen's	36	
St James Duke's Place	24	
St James Garlickhithe	41	
St John Baptiſt	30	
St John Evangeliſt	7	
St John Zachary	16	
St Katherine Coleman	40	
St Katherine Creechurch	74	
St Laurence Jewry	70	
St Laurence Pountney	23	
St Leonard Eaſtcheap	8	
St Leonard Foſter-lane	32	
St Magnus Pariſh	59	
St Margaret Lothbury	46	
St Margaret Moſes	4	
St Margaret New Fiſh-ſtr.	3	
St Margaret Pattons	9	
St Mary Abchurch	33	
St Mary Aldermanbury	29	
St Mary Aldermary	29	
St Mary le Bow	27	
St Mary Bothaw	1	
St Mary Colechurch	7	
St Mary Hill	23	
St Mary Magd. Milk-ſtr.	1	
St Mary Mag. Old Fiſh-ſtr.	30	
St Mary Mounthaw	6	
St Mary Somerſet	22	
St Mary Staining	10	
St Mary Woolchurch	6	
St Mary Woolnoth	26	
St Martin Ironmonger-lane	10	
St Martin Ludgate	34	
St Martin Orgars	30	
St Martin Outwich	22	
St Martin Vintrey	46	
St Matthew Friday-ſtreet	26	
St Michael Baſſiſhaw	24	
St Michael Cornhill	29	
St Michael Crooked-lane	31	
St Michael Queenhithe	46	
St Michael Querne	2	
St Michael Royal	12	
St Michael Wood-ſtreet	29	
St Mildred Bread-ſtreet	11	
St Mildred Poultry	28	
St Nicholas Acons	14	
St Nicholas Coleabby	17	
St Nicholas Olave	11	
St Olave Hart-ſtreet	48	
St Olave Jewry	20	
St Olave Silver-ſtreet	32	
St Pancras Soper-lane	13	
St Peter Cheap	2	
St Peter Cornhill	29	
St Peter Paul's Wharf	12	
St Peter Poor	30	
St Stephen Coleman-ſtreet	96	
St Stephen Walbrook	21	
St Swithin	41	
St Thomas Apoſtle	22	
Trinity Pariſh	1	
St Vedaſt, alias Foſter	48	

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1754 Buried 2756 Plague 0

St Andrew Holborn	918	St Botolph Aldgate	723	St Saviour Southwark	520
St Bartholomew Great	76	St Botolph Biſhopſgate	387	St Sepulchre's Pariſh	673
St Bartholomew Leſs	29	St Dunſtan Weſt	274	St Thomas Southwark	69
St Bride's Pariſh	335	St George Southwark	328	Trinity Minories	26
Bridewell Precinct	22	St Giles Cripplegate	1239	At the Peſt-houſe	0
St Botolph Alderſgate	178	St Olave Southwark	711		

Chriſtened in the ſixteen Pariſhes without the Walls 4239 Buried 6508 Plague 0

1676.

Chriſt Church —— —108	Lambeth Pariſh ——253	St Mary Whitechapel —849
St Giles in the Fields —1070	St Leonard Shoreditch—444	St Paul Shadwell ——414
St John at Hackney—— 74	St Magdalen Bermondſey408	Rotherhith Pariſh — —139 1
St James Clarkenwell —329	St Mary Iſlington — —111	Stepney Pariſh—— —1541 1
St Katherine by the Tower165	St Mary Newington——242	

Chriſtened in the fourteen Out Pariſhes in Middleſex and Surrey 3864
Buried 6147 Plague 2

St Clement Danes — —425	St Martin in the Fields 1825	St Margaret Weſtminſter 868
St Paul Covent Garden 141	St Mary Savoy —— 62	Whereof at the Peſt-houſe 0

Chriſtened in the five Pariſhes in the City and Liberties of Weſtminſter 2542
Buried 3321 Plague 0

DISEASES and CASUALTIES.

Abortive and Stillborn 679	Found dead in the Streets, &c. 4	Pleuriſy —— —— 25
Aged and Bedridden1007	French Pox —— —— 97	Poiſoned — —— — 6
Ague and Fever —— —2112	Frighted —— —— 1	Quinſy and Thruſh —— 62
Apoplexy and Suddenly— 84	Gout —— —— 15	Rickets —— —— 442
Bleeding, Bloody Flux, and Flux — 63	Gangrene and Fiſtula —— 23	Riſing of the Lights —— 159
Burnt and Blown up —— 13	Grief —— — —— 22	Scalded —— —— 4
Burſten and Rupture —— 35	Griping in the Guts — —3321	Scowring —— —— 8
Calenture —— —— 2	Hang'd and made away themſelves — 17	Scurvy —— —— 59
Cancer, Canker, and Wolf 42	Headmouldſhot — —— 8	Shot —— —— —— 3
Childbed —— —— 258	Jaundies —— —— 72	Smothered and Stifled - — 4
Chriſomes and Infants —— 385	Impoſthume — — —— 108	Sores, Ulcers, broken and bruiſed Limbs 46
Cold and Cough —— 8	Kill'd by ſeveral Accidents 67	Spleen —— — —— 1
Colick and Wind — —— 126	Leproſy —— — — 1	Spotted Fever and Purples 156
Conſumption and Tiſſick 3223	Lethargy —— —— 80	St Anthony's Fire —— 1
Convulſion and Mother —2363	Livergrown — — —— 29	Stopping of the Stomach 373
Cut of the Stone and Stone 66	Meaſles —— —— 83	Strangury —— —— 11
Diſtracted and Lunatick— 8	Megrims —— —— 1	Surfeit —— — —— 335
Dropſy and Tympany —— 675	Murdered — — —— 14	Swine Pox —— — — 1
Drowned — — —— 83	Overlaid —— —— 84	Teeth —— ——1216
Evil —— —— 53	Palſy —— —— — 23	Vomiting — — —— 49
Executed —— —— 17	Plague —— —— 2	Worms —— —— 37
Flox and Small Pox —— 359	Planet —— —— 1	

CHRISTENED	Males — 6552 Females 5847 In all — 12399	BURIED	Males — 9734 Females 8998 In all — 18732

Of the Plague 2

Increaſed in the Burials this Year 1488	Pariſhes clear of the Plague — 130
Increaſed in the Plague this Year 1	Pariſhes infected —— 2

A General

1677.

A General BILL of all the Chriſtenings and Burials,

From the 19th of December 1676, to the 18th of December 1677.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.	Pl.
St ALBAN Wood-ſtreet	27	
Alhallows Barkin	78	
Alhallows Bread-ſtreet	30	
Alhallows Great	62	
Alhallows Honey-lane	0	
Alhallows Leſs	23	
Alhallows Lombard-ſtreet	31	
Alhallows Staining	35	
Alhallows the Wall	78	
St Alphage	42	
St Andrew Hubbard	19	
St Andrew Underſhaft	43	
St Andrew Wardrobe	55	
St Ann Alderſgate	25	
St Ann Black Friars	118	
St Antholin's Pariſh	22	
St Auſtin's Pariſh	12	
St Bartholomew Exchange	25	
St Bennet Fink	25	
St Bennet Gracechurch	8	
St Bennet Paul's Wharf	53	
St Bennet Sherehog	8	
St Botolph Billingſgate	14	
Chriſt Church	95	
St Chriſtopher	20	
St Clement Eaſtcheap	7	
St Dionis Backchurch	35	
St Dunſtan Eaſt	94	
St Edmund Lombard-ſtr.	25	
St Ethelborough	26	
St Faith's	39	
St Gabriel Fenchurch	13	
St George Botolph-lane	9	
St Gregory by St Paul's	70	
St Helen's	33	
St James Duke's Place	25	
St James Garlickhithe	45	
St John Baptiſt	16	
St John Evangeliſt	6	
St John Zachary	24	
St Katherine Coleman	47	
St Katherine Creechurch	74	
St Laurence Jewry	50	
St Laurence Pountney	24	
St Leonard Eaſtcheap	18	
St Leonard Foſter-lane	23	
St Magnus Pariſh	60	
St Margaret Lothbury	41	
St Margaret Moſes	1	
St Margaret New Fiſh-ſtr.	1	
St Margaret Pattons	22	
St Mary Abchurch	38	
St Mary Aldermanbury	28	
St Mary Aldermary	25	
St Mary le Bow	21	
St Mary Bothaw	2	
St Mary Colechurch	1	
St Mary Hill	24	
St Mary Magd. Milk-ſtr.	3	
St Mary Mag. Old Fiſh-ſtr.	34	
St Mary Mounthaw	6	
St Mary Somerſet	32	
St Mary Staining	12	
St Mary Woolchurch	1	
St Mary Woolnoth	29	
St Martin Ironmonger-lane	7	
St Martin Ludgate	39	
St Martin Orgars	31	
St Martin Outwich	25	
St Martin Vintrey	48	
St Matthew Friday-ſtreet	25	
St Michael Baſſiſhaw	27	
St Michael Cornhill	32	
St Michael Crooked-lane	26	
St Michael Queenhithe	40	
St Michael Querne	1	
St Michael Royal	11	
St Michael Wood-ſtreet	16	
St Mildred Bread-ſtreet	15	
St Mildred Poultry	33	
St Nicholas Acons	5	
St Nicholas Coleabby	20	
St Nicholas Olave	7	
St Olave Hart-ſtreet	39	
St Olave Jewry	17	
St Olave Silver-ſtreet	29	
St Pancras Soper-lane	7	
St Peter Cheap	3	
St Peter Cornhill	36	
St Peter Paul's Wharf	15	
St Peter Poor	14	
St Stephen Coleman-ſtreet	101	
St Stephen Walbrook	20	
St Swithin	13	
St Thomas Apoſtle	24	
Trinity Pariſh	0	
St Vedaſt, alias Foſter	59	

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1865 Buried 2817 Plague 0

St Andrew Holborn	922	St Botolph Aldgate	681	St Saviour Southwark	490
St Bartholomew Great	70	St Botolph Biſhopſgate	428	St Sepulchre's Pariſh	684
St Bartholomew Leſs	33	St Dunſtan Weſt	243	St Thomas Southwark	78
St Bride's Pariſh	318	St George Southwark	333	Trinity Minories	24
Bridewell Precinct	36	St Giles Cripplegate	1314	At the Peſt-houſe	0
St Botolph Alderſgate	214	St Olave Southwark	764		

Chriſtened in the ſixteen Pariſhes without the Walls 4276 Buried 6632 Plague 0

1677.

Chriſt Church — ——129	Lambeth Pariſh ——204	St Mary Whitechapel —877
St Giles in the Fields—1157	St Leonard Shoreditch—446	St Paul Shadwell ——372 1
St John at Hackney—— 86	St Magdalen Bermondſey417	Rotherhith Pariſh —— 89 1
St James Clarkenwell —340	St Mary Iſlington — — 92	Stepney Pariſh ——1593
St Katherine by the Tower173	St Mary Newington——178	

Chriſtened in the fourteen Out Pariſhes in Middleſex and Surrey 4029
Buried 6153 Plague 2

St Clement Danes — —529	St Martin in the Fields 1741	St Margaret Weſtminſter 928
St Paul Covent Garden 172	St Mary Savoy —— 95	At the Peſt-houſe—— 0

Chriſtened in the five Pariſhes in the City and Liberties of Weſtminſter 2456
Buried 3465 Plague 0

DISEASES and CASUALTIES.

Abortive and Stillborn 664	French Pox —— —— 109	Planet —— —— 1
Aged and Bedridden 934	Frighted —— — 1	Pleuriſy —— —— 23
Ague and Fever — ——1749	Gangrene and Fiſtula—— 34	Poiſoned —— — 3
Apoplexy and Suddenly— 66	Gout —— —— —— 16	Quinſy and Thruſh —— 96
Bleeding, Bloody Flux, and Flux — 150	Grief —— — — 12	Rickets —— —— 458
	Griping in the Guts — —2602	Riſing of the Lights —— 169
Burnt and Scalded — — 14	Hang'd and made away themſelves — 22	Scowring —— —— 3
Burſten and Rupture —— 47		Scurvy —— —— 74
Cancer and Canker —— 43	Head-ach —— —— 2	Shot —— — — 1
Childbed —— — —— 236	Headmouldſhot — — 1	Smothered —— —— 3
Chriſomes and Infants — 389	Jaundies —— —— 74	Sores, Ulcers, and bruiſed Limbs —— 34
Cold and Cough — — 19	Jawfallen —— — —— 1	
Colick and Wind — —— 143	Impoſthume —— —— 113	Spleen —— —— —— 6
Conſumption and Tiſſick 3272	Kill'd by ſeveral Accidents 67	Spotted Fever and Purples 155
Convulſion —— ——2357	Leproſy —— —— 1	St Anthony's Fire —— 2
Diſtracted and Lunatick— 7	Lethargy —— — — 51	Starved —— —— 2
Dropſy and Tympany — 809	Livergrown —— —— 24	Stone and Strangury —— 73
Drowned —— —— 69	Meaſles —— — —— 87	Stopping of the Stomach 343
Evil —— —— 63	Megrims —— —— 2	Surfeit —— —— —— 252
Executed —— — —— 8	Murdered —— —— 20	Teeth —— — —1196
Falling Sickneſs and Epilepſy 4	Overlaid —— —— 107	Vomiting —— —— 30
Flox and Small Pox ——1678	Palſy —— — —— 26	Worms —— —— 40
Found dead in the Streets, &c. 8	Plague —— — —— 2	

CHRISTENED { Males — 6423, Females 6203, In all 12626 }	BURIED { Males — 9836, Females 9231, In all — 19067 }	Of the Plague 2	

Increaſed in the Burials this Year	344	Pariſhes clear of the Plague —	130
Increaſed in the Plague ——	0	Pariſhes infected — ——	2

A General

1678.

A General BILL of all the Chriſtenings and Burials,

From the 18th of December 1677, to the 17th of December 1678.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur. Pl.
St ALBAN Wood-ſtreet	33
Alhallows Barkin	112
Alhallows Bread-ſtreet	22
Alhallows Great	60
Alhallows Honey-lane	0
Alhallows Leſs	24
Alhallows Lombard-ſtreet	26
Alhallows Staining	42
Alhallows the Wall	74
St Alphage	39
St Andrew Hubbard	16
St Andrew Underſhaft	64
St Andrew Wardrobe	66
St Ann Alderſgate	49
St Ann Black Friars	109
St Antholin's Pariſh	25
St Auſtin's Pariſh	14
St Bartholomew Exchange	28
St Bennet Fink	18
St Bennet Gracechurch	18
St Bennet Paul's Wharf	39
St Bennet Sherehog	10
St Botolph Billingſgate	14
Chriſt Church	116
St Chriſtopher	22
St Clement Eaſtcheap	12
St Dionis Backchurch	40
St Dunſtan Eaſt	98
St Edmund Lombard-ſtr.	31
St Ethelborough	33
St Faith's	45
St Gabriel Fenchurch	6
St George Botolph-lane	15
St Gregory by St Paul's	63
St Helen's	35
St James Duke's Place	34
St James Garlickhithe	57
St John Baptiſt	20
St John Evangeliſt	6
St John Zachary	17
St Katherine Coleman	40
St Katherine Creechurch	71
St Laurence Jewry	62
St Laurence Pountney	20
St Leonard Eaſtcheap	14
St Leonard Foſter-lane	36
St Magnus Pariſh	50
St Margaret Lothbury	46
St Margaret Moſes	5
St Margaret New Fiſh-ſtr.	1
St Margaret Pattons	18
St Mary Abchurch	38
St Mary Aldermanbury	35
St Mary Aldermary	38
St Mary le Bow	29
St Mary Bothaw	7
St Mary Colechurch	4
St Mary Hill	26
St Mary Magd. Milk-ſtr.	0
St Mary Mag. Old Fiſh-ſtr.	26
St Mary Mounthaw	6
St Mary Somerſet	33
St Mary Staining	11
St Mary Woolchurch	1
St Mary Woolnoth	29
St Martin Ironmonger-lane	7
St Martin Ludgate	47
St Martin Orgars	21
St Martin Outwich	21
St Martin Vintrey	43
St Matthew Friday-ſtreet	23
St Michael Baſſiſhaw	22
St Michael Cornhill	35
St Michael Crooked-lane	24
St Michael Queenhithe	42
St Michael Querne	14
St Michael Royal	22
St Michael Wood-ſtreet	15
St Mildred Bread-ſtreet	22
St Mildred Poultry	26
St Nicholas Acons	11
St Nicholas Coleabby	21
St Nicholas Olave	13
St Olave Hart-ſtreet	54
St Olave Jewry	19
St Olave Silver-ſtreet	39
St Pancras Soper-lane	8
St Peter Cheap	5
St Peter Cornhill	29
St Peter Paul's Wharf	17
St Peter Poor	33
St Stephen Coleman-ſtreet	96
St Stephen Walbrook	32
St Swithin	33
St Thomas Apoſtle	28
Trinity Pariſh	0
St Vedaſt, alias Foſter	40

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1948 Buried 3060 Plague 0

St Andrew Holborn	912
St Bartholomew Great	70
St Bartholomew Leſs	43
St Bride's Pariſh	349
Bridewell Precinct	31
St Botolph Alderſgate	198
St Botolph Aldgate	702
St Botolph Biſhopſgate	389
St Dunſtan Weſt	219
St George Southwark	340
St Giles Cripplegate	1350
St Olave Southwark	779
St Saviour Southwark	545
St Sepulchre's Pariſh	678
St Thomas Southwark	77
Trinity Minories	24
At the Peſt-houſe	0

Chriſtened in the ſixteen Pariſhes without the Walls 4186 Buried 6706 Plague 1

1678.

Chriſt Church — ——161	Lambeth Pariſh — ——339	St Mary Whitechapel -—899
St Giles in the Fields —1202	St Leonard Shoreditch —423	St Paul Shadwell ———600
St John at Hackney——112	St Magdalen Bermondſey 495	Rotherhith Pariſh — —142 3
St James Clarkenwell —352	St Mary Iſlington — — 137	Stepney Pariſh — ——1868 1
St Katherine by the Tower216	St Mary Newington ——228	

Chriſtened in the fourteen Out Pariſhes in Middleſex and Surrey 3952
Buried 7174 Plague 4

St Clement Danes — —498	St Martin in the Fields 2091	St Margaret Weſtminſter 843
St Paul Covent Garden 198	St Mary Savoy ——— 108	At the Peſt-houſe — — 0

Chriſtened in the five Pariſhes in the City and Liberties of Weſtminſter 2515
Buried 3738 Plague 0

DISEASES and CASUALTIES.

Abortive and Stillborn 710	French Pox —— — — 101	Pleuriſy —— ——— 14
Aged and Bedridden1021	Frighted ——— ——— 2	Quinſy and Thruſh —— 101
Ague and Fever —— —2376	Gangrene and Fiſtula—— 37	Rickets ——— ——— 427
Apoplexy and Suddenly— 83	Gout and Sciatica ——— 14	Riſing of the Lights —— 123
Bleeding, Bloody Flux, and Flux — 55	Grief —— ——— —— 15	Scald Head —— —— 1
	Griping in the Guts — —3150	Scowring —— —— 2
Burnt ——— ——— 7	Hanged and made away themſelves — 12	Scurvy —— — — — 48
Burſten and Rupture —— 47		Shingles —— —— 1
Calenture —— ——— 2	Headmouldſhot ——— 2	Smothered —— —— 2
Cancer and Canker ——— 51	Jaundies —— — —— 61	Sores, Ulcers, and bruiſed Limbs — 60
Childbed ——— — — 272	Impoſthume — —— — 106	
Chriſomes and Infants — 301	Killed by ſeveral Accidents 61	Spleen ——— ——— 1
Colick and Wind ——— 161	Leproſy —— —— 1	Spotted Fever and Purples 204
Conſumption and Tiſſick 3448	Lethargy —— — —— 72	St Anthony's Fire ——— 4
Convulſion ——— — —2525	Livergrown —— ——— 52	Starved — — —— — 1
Cough and Chincough — 5	Meaſles ——— ——— 93	Stone and Cut of the Stone 63
Diſtracted and Lunatick— 13	Megrims and Falling Sickneſs — 3	Stopping of the Stomach 339
Dropſy and Tympany - — 812		Strangury —— — —— 9
Drowned ——— ——— 85	Murdered —— — —— 12	Surfeit —— — ——— 283
Evil —— —— —— 66	Overlaid ——— —— 112	Teeth — — — —1110
Executed — — ——— 23	Palſy ——— — ——— 24	Vomiting ——— —— 39
Flox and Small Pox — —1798	Plague ——— ——— 5	Worms ——— ——— 44
Found dead in the Streets,&c. 4	Planet —— — —— 1	Wounded ——— —— 1

CHRISTENED	Males — 6568	BURIED	Males — 10681	Of the Plague	5
	Females 6033		Females 9997		
	In all — 12601		In all — 20678		

Increaſed in the Burials this Year 1611
Increaſed in the Plague — 3

1679.

A General BILL of all the Chriſtenings and Burials,

From the 17th of December 1678, to the 16th of December 1679.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, .&c.

	Bur.	Pl.
St ALBAN Wood-ſtreet	30	
Alhallows Barkin	118	
Alhallows Bread-ſtreet	26	
Alhallows Great	54	
Alhallows Honey-lane	0	
Alhallows Leſs	15	
Alhallows Lombard-ſtreet	20	
Alhallows Staining	36	
Alhallows the Wall	70	
St Alphage	48	
St Andrew Hubbard	15	
St Andrew Underſhaft	56	
St Andrew Wardrobe	63	
St Ann Alderſgate	39	
St Ann Black Friars	106	
St Antholin's Pariſh	11	
St Auſtin's Pariſh	15	
St Bartholomew Exchange	29	
St Bennet Fink	18	
St Bennet Gracechurch	18	
St Bennet Paul's Wharf	49	
St Bennet Sherehog	1	
St Botolph Billingſgate	15	
Chriſt Church	113	
St Chriſtopher	14	
St Clement Eaſtcheap	11	
St Dionis Backchurch	39	
St Dunſtan Eaſt	92	
St Edmund Lombard-ſtr.	37	
St Ethelborough	26	
St Faith's	43	
St Gabriel Fenchurch	12	
St George Botolph-lane	15	
St Gregory by St Paul's	80	
St Helen's	30	
St James Duke's Place	20	
St James Garlickhithe	40	
St John Baptiſt	19	
St John Evangeliſt	4	
St John Zachary	16	
St Katherine Coleman	51	
St Katherine Creechurch	78	
St Laurence Jewry	60	
St Laurence Pountney	26	
St Leonard Eaſtcheap	18	
St Leonard Foſter-lane	46	
St Magnus Pariſh	39	
St Margaret Lothbury	43	
St Margaret Moſes	5	
St Margaret New Fiſh-ſtr.	0	
St Margaret Pattons	13	
St Mary Abchurch	25	
St Mary Aldermanbury	33	
St Mary Aldermary	37	
St Mary le Bow	28	
St Mary Bothaw	2	
St Mary Colechurch	3	
St Mary Hill	18	
St Mary Magd. Milk-ſtr.	0	
St Mary Mag. Old Fiſh-ſtr.	25	
St Mary Mounthaw	11	
St Mary Somerſet	37	
St Mary Staining	13	
St Mary Woolchurch	3	
St Mary Woolnoth	29	
St Martin Ironmonger-lane	13	
St Martin Ludgate	36	
St Martin Orgars	32	
St Martin Outwich	19	
St Martin Vintrey	61	
St Matthew Friday-ſtreet	15	
St Michael Baſſiſhaw	36	
St Michael Cornhill	34	
St Michael Crooked-lane	42	
St Michael Queenhithe	51	
St Michael Querne	24	
St Michael Royal	17	
St Michael Wood-ſtreet	17	
St Mildred Bread-ſtreet	24	
St Mildred Poultry	40	
St Nicholas Acons	9	
St Nicholas Coleabby	27	
St Nicholas Olave	11	
St Olave Hart-ſtreet	64	
St Olave Jewry	16	
St Olave Silver-ſtreet	33	
St Pancras Soper-lane	14	
St Peter Cheap	6	
St Peter Cornhill	33	
St Peter Paul's Wharf	9	
St Peter Poor	32	
St Stephen Coleman-ſtreet	126	
St Stephen Walbrook	29	
St Swithin	32	
St Thomas Apoſtle	21	
Trinity Pariſh	0	
St Vedaſt, alias Foſter	48	

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1876 Buried 3074 Plague 0

St Andrew Holborn	937	St Botolph Aldgate	681	St Saviour Southwark	614
St Bartholomew Great	89	St Botolph Biſhopſgate	465	St Sepulchre's Pariſh	727
St Bartholomew Leſs	25	St Dunſtan Weſt	341	St Thomas Southwark	105
St Bride's Pariſh	413	St George Southwark	375	Trinity Minories	21
Bridewell Precinct	23	St Giles Cripplegate	1466	At the Peſt-houſe	0
St Botolph Alderſgate	245	St Olave Southwark	954		

Chriſtened in the ſixteen Pariſhes without the Walls 4023 Buried 7481 Plague 0

1679.

Chriſt Church — ——159	Lambeth Pariſh ——337	St Mary Whitechapel —924
St Giles in the Fields—1245	St Leonard Shoreditch—423	St Paul Shadwell ——475
St John at Hackney—— 88	St Magdalen Bermondſey598	Rotherhith Pariſh — —197 2
St James Clarkenwell —416	St Mary Iſlington ——132	Stepney Pariſh — ——1749
St Katherine by the Tower181	St Mary Newington——199	

Chriſtened in the fourteen Out Pariſhes in Middleſex and Surrey 3769
Buried 7123 Plague 2

St Clement Danes — —621	St Martin in the Fields 2147	St Margaret Weſtminſt. 1004
St Paul Covent Garden 177	St Mary Savoy —— 103	At the Peſt-houſe —— 0

Chriſtened in the five Pariſhes in the City and Liberties of Weſtminſter 2620
Buried 4052 Plague 0

DISEASES and CASUALTIES.

Abortive and Stillborn 669	Executed —— —— 30	Palſy —— — — 26
Aged and Bedridden1141	Falling Sickneſs —— — 2	Plague —— —— 2
Ague and Fever —— —2763	Flox and Small Pox ——1967	Planet —— —— 4
Apoplexy and Suddenly— 103	Found dead in the Streets 5	Pleuriſy —— —— 16
Bleeding —— —— 2	French Pox —— —— 104	Poiſoned —— —— 4
Bloody Flux, Scowring, and Flux — 61	Frighted —— —— 1	Quinſy —— —— — 17
	Gangrene and Fiſtula—— 40	Rickets — — —— 394
Burnt and Scalded —— 13	Gout and Sciatica — — 24	Riſing of the Lights —— 116
Burſten and Rupture —— 35	Grief —— —— 14	Scurvy —— — — 47
Calenture —— —— 2	Griping in the Guts — —2996	Shot —— —— 2
Cancer —— — —— 52	Hanged and made away themſelves — 19	Smothered —— —— 1
Canker and Thruſh —— 91		Sores, Ulcers, and bruiſed Limbs — 50
Childbed —— —— 300	Headmouldſhot — —— 7	
Chriſomes and Infants —— 274	Jaundies —— —— 67	Spleen —— —— 8
Cold, Cough, and Chin-cough — 11	Impoſthume —— —— 99	Spotted Fever and Purples 160
	Kill'd by ſeveral Accidents 74	St Anthony's Fire —— 3
Colick and Wind —— 133	Leproſy —— —— 1	Stone and Cut of the Stone 68
Conſumption and Tiſſick 3675	Lethargy —— — —— 49	Stopping of the Stomach 327
Convulſion —— ——2837	Livergrown —— — 20	Strangury —— —— 5
Diſtracted and Lunatick— 12	Meaſles —— —— 117	Surfeit —— —— 466
Dropſy and Tympany —— 852	Megrims — — —— 3	Teeth —— — ——1034
Drowned —— —— 69	Murdered — —— 14	Vomiting —— —— 27
Evil —— —— —— 67	Overlaid —— —— 100	Worms —— — —— 38

CHRISTENED	Males — 6247 Females 6041 In all — 12288	BURIED	Males — 11154 Females 10576 In all — 21730

Of the Plague 2

Increaſed in the Burials this Year 1052
Decreaſed in the Plague — 3

1680.

A General BILL of all the Chriſtenings and Burials,

From the 16th of December 1679, to the 14th of December 1680.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.	Pl.
St ALBAN Wood-ſtreet	25	
Alhallows Barkin	104	
Alhallows Bread-ſtreet	20	
Alhallows Great	57	
Alhallows Honey-lane	0	
Alhallows Leſs	23	
Alhallows Lombard-ſtreet	28	
Alhallows Staining	37	
Alhallows the Wall	76	
St Alphage	42	
St Andrew Hubbard	14	
St Andrew Underſhaft	67	
St Andrew Wardrobe	57	
St Ann Alderſgate	46	
St Ann Black Friars	10	
St Antholin's Pariſh	17	
St Auſtin's Pariſh	154	
St Bartholomew Exchange	30	
St Bennet Fink	22	
St Bennet Gracechurch	10	
St Bennet Paul's Wharf	46	
St Bennet Sherehog	4	
St Botolph Billingſgate	12	
Chriſt Church	95	
St Chriſtopher	17	
St Clement Eaſtcheap	12	
St Dionis Backchurch	30	
St Dunſtan Eaſt	119	
St Edmund Lombard-ſtr.	35	
St Ethelborough	19	
St Faith's	41	
St Gabriel Fenchurch	7	
St George Botolph-lane	9	
St Gregory by St Paul's	88	
St Helen's	31	
St James Duke's Place	34	
St James Garlickhithe	57	
St John Baptiſt	24	
St John Evangeliſt	10	
St John Zachary	20	
St Katherine Coleman	52	
St Katherine Creechurch	75	
St Laurence Jewry	54	
St Laurence Pountney	15	
St Leonard Eaſtcheap	13	
St Leonard Foſter-lane	35	
St Magnus Pariſh	55	
St Margaret Lothbury	39	
St Margaret Moſes	2	
St Margaret New Fiſh-ſtr.	0	
St Margaret Pattons	22	
St Mary Abchurch	36	
St Mary Aldermanbury	27	
St Mary Aldermary	42	
St Mary le Bow	21	
St Mary Bothaw	5	
St Mary Colechurch	5	
St Mary Hill	22	
St Mary Magd. Milk-ſtr.	1	
St MaryMag. Old Fiſh-ſtr.	38	
St Mary Mounthaw	5	
St Mary Somerſet	34	
St Mary Staining	23	
St Mary Woolchurch	2	
St Mary Woolnoth	33	
St Martin Ironmonger-lane	14	
St Martin Ludgate	58	
St Martin Orgars	22	
St Martin Outwich	22	
St Martin Vintrey	43	
St Matthew Friday-ſtreet	20	
St Michael Baſſiſhaw	30	
St Michael Cornhill	33	
St Michael Crooked-lane	28	
St Michael Queenhithe	66	
St Michael Querne	22	
St Michael Royal	13	
St Michael Wood-ſtreet	14	
St Mildred Bread-ſtreet	18	
St Mildred Poultry	38	
St Nicholas Acons	9	
St Nicholas Coleabby	23	
St Nicholas Olave	9	
St Olave Hart-ſtreet	59	
St Olave Jewry	15	
St Olave Silver-ſtreet	26	
St Pancras Soper-lane	8	
St Peter Cheap	10	
St Peter Cornhill	29	
St Peter Paul's Wharf	16	
St Peter Poor	20	
St Stephen Coleman-ſtreet	113	
St Stephen Walbrook	32	
St Swithin	25	
St Thomas Apoſtle	34	
Trinity Pariſh	0	
St Vedaſt, alias Foſter	47	

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1954 Buried 3076 Plague 0

St Andrew Holborn	788	St Botolph Aldgate	763	St Saviour Southwark	588
St Bartholomew Great	88	St Botolph Biſhopſgate	542	St Sepulchre's Pariſh	701
St Bartholomew Leſs	22	St Dunſtan Weſt	273	St Thomas Southwark	67
St Bride's Pariſh	363	St George Southwark	338	Trinity Minories	27
Bridewell Precinct	27	St Giles Cripplegate	1409	At the Peſt-houſe	0
St Botolph Alderſgate	209	St Olave Southwark	861		

Chriſtened in the ſixteen Pariſhes without the Walls 4040 Buried 7066 Plague 0

1680.

Chriſt Church —— —154	Lambeth Pariſh ——295	St Mary Whitechapel —996
St Giles in the Fields —1036	St Leonard Shoreditch—554	St Paul Shadwell ——529
St John at Hackney——155	St Magdalen Bermondſey520	Rotherhith Pariſh — —187
St James Clarkenwell —387	St Mary Iſlington — —156	Stepney Pariſh —— —1851
St Katherine by the Tower207	St Mary Newington——199	

Chriſtened in the fourteen Out Pariſhes in Middleſex and Surrey 4107
Buried 7226 Plague 0

St Clement Danes — —513	St Martin in the Fields 1950	St Margaret Weſtminſter 907
St Paul Covent Garden 194	St Mary Savoy —— 121	Whereof at the Peſt-houſe 0

Chriſtened in the five Pariſhes in the City and Liberties of Weſtminſter 2646
Buried 3685 Plague 0

DISEASES and CASUALTIES.

Abortive and Stillborn 641	Falling Sickneſs — —— 1	Pleuriſy —— —— 16
Aged and Bedridden1081	Flox and Small Pox —— 689	Poiſoned — —— — 5
Ague and Fever —— —3324	Found dead in the Streets,&c. 3	Quinſy and Thruſh —— 132
Apoplexy and Suddenly— 93	French Pox —— —— 114	Rickets —— —— 341
Blaſted —— —— 1	Gangrene and Fiſtula —— 27	Riſing of the Lights —— 116
Bleeding, Bloody Flux, and Flux — 68	Gout and Sciatica —— 23	Scowring —— —— 4
	Grief —— — —— 16	Scurvy —— —— 59
Burnt and Scalded — — 7	Griping in the Guts — —3271	Shingles —— —— 1
Burſten and Rupture —— 29	Hang'd and made away themſelves — 23	Shot —— —— —— 1
Calenture —— —— 1		Smothered —— —— 2
Cancer and Canker — — 65	Head-ach —— —— 1	Sores, Ulcers, &c. —— 61
Childbed —— —— 302	Headmouldſhot — —— 5	Spleen —— — —— 1
Chriſomes and Infants —— 183	Jaundies —— —— 66	Spotted Fever and Purples 193
Cold, Cough, and Chin-cough —— 14	Impoſthume — — —— 118	St Anthony's Fire —— 7
	Kill'd by ſeveral Accidents 65	Starved —— —— 1
Colick and Wind — —— 127	Leproſy —— — — 1	Stone —— — —— 60
Conſumption and Tiſſick 3427	Lethargy —— —— 21	Stopping of the Stomach 286
Convulſion —— ——3055	Livergrown — — —— 12	Strangury —— —— 2
Diſtracted and Lunatick— 14	Meaſles —— —— 49	Surfeit —— — —— 410
Dropſy and Tympany —— 776	Megrims —— —— 5	Teeth —— ——1141
Drowned — — —— 83	Murdered — — —— 8	Vomiting — — —— 18
Evil —— —— 66	Overlaid —— —— 89	Worms —— —— 35
Executed —— —— 24	Palſy —— —— — 25	

CHRISTENED	Males — 6548	BURIED	Males — 11039
	Females 6199		Females 10014
	In all — 12747		In all — 21053

Of the Plague 0

Decreaſed in the Burials this Year 677
Decreaſed in the Plague — 2

A General

1681.

A General BILL of all the Chriſtenings and Burials,

From the 14th of December 1680, to the 19th of December 1681.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.	Pl.
St ALBAN Wood-ſtreet	31	
Alhallows Barkin	110	
Alhallows Bread-ſtreet	29	
Alhallows Great	96	
Alhallows Honey-lane	0	
Alhallows Leſs	26	
Alhallows Lombard-ſtreet	27	
Alhallows Staining	41	
Alhallows the Wall	104	
St Alphage	56	
St Andrew Hubbard	20	
St Andrew Underſhaft	77	
St Andrew Wardrobe	82	
St Ann Alderſgate	50	
St Ann Black Friars	134	
St Antholin's Pariſh	23	
St Auſtin's Pariſh	21	
St Bartholomew Exchange	34	
St Bennet Fink	20	
St Bennet Gracechurch	22	
St Bennet Paul's Wharf	56	
St Bennet Sherehog	5	
St Botolph Billingſgate	16	
Chriſt Church	131	
St Chriſtopher	20	
St Clement Eaſtcheap	19	
St Dionis Backchurch	43	
St Dunſtan Eaſt	96	
St Edmund Lombard-ſtr.	30	
St Ethelborough	31	
St Faith's	42	
St Gabriel Fenchurch	24	
St George Botolph-lane	9	

	Bur.	Pl.
St Gregory by St Paul's	94	
St Helen's	50	
St James Duke's Place	53	
St James Garlickhithe	55	
St John Baptiſt	24	
St John Evangeliſt	16	
St John Zachary	25	
St Katherine Coleman	62	
St Katherine Creechurch	80	
St Laurence Jewry	78	
St Laurence Pountney	22	
St Leonard Eaſtcheap	18	
St Leonard Foſter-lane	47	
St Magnus Pariſh	41	
St Margaret Lothbury	48	
St Margaret Moſes	5	
St Margaret New Fiſh-ſtr.	0	
St Margaret Pattons	17	
St Mary Abchurch	30	
St Mary Aldermanbury	46	
St Mary Aldermary	37	
St Mary le Bow	37	
St Mary Bothaw	3	
St Mary Colechurch	2	
St Mary Hill	32	
St Mary Magd. Milk-ſtr.	1	
St Mary Mag. Old Fiſh-ſtr.	54	
St Mary Mounthaw	11	
St Mary Somerſet	49	
St Mary Staining	17	
St Mary Woolchurch	1	
St Mary Woolnoth	54	

	Bur.	Pl.
St Martin Ironmonger-lane	7	
St Martin Ludgate	49	
St Martin Orgars	39	
St Martin Outwich	16	
St Martin Vintrey	37	
St Matthew Friday-ſtreet	31	
St Michael Baſſiſhaw	33	
St Michael Cornhill	35	
St Michael Crooked-lane	28	
St Michael Queenhithe	58	
St Michael Querne	22	
St Michael Royal	19	
St Michael Wood-ſtreet	23	
St Mildred Bread-ſtreet	17	
St Mildred Poultry	33	
St Nicholas Acons	3	
St Nicholas Coleabby	21	
St Nicholas Olave	17	
St Olave Hart-ſtreet	64	
St Olave Jewry	21	
St Olave Silver-ſtreet	36	
St Pancras Soper-lane	14	
St Peter Cheap	12	
St Peter Cornhill	40	
St Peter Paul's Wharf	16	
St Peter Poor	30	
St Stephen Coleman-ſtreet	167	
St Stephen Walbrook	29	
St Swithin	41	
St Thomas Apoſtle	29	
Trinity Pariſh	0	
St Vedaſt, alias Foſter	42	

Chriſtened in the ninety-ſeven Pariſhes within the Walls 2188 — Buried 3669 — Plague 0

St Andrew Holborn	952
St Bartholomew Great	109
St Bartholomew Leſs	39
St Bride's Pariſh	467
Bridewell Precinct	30
St Botolph Alderſgate	214
St Botolph Aldgate	793
St Botolph Biſhopſgate	618
St Dunſtan Weſt	334
St George Southwark	369
St Giles Cripplegate	1700
St Olave Southwark	936
St Saviour Southwark	627
St Sepulchre's Pariſh	830
St Thomas Southwark	88
Trinity Minories	30
At the Peſt-houſe	0

Chriſtened in the ſixteen Pariſhes without the Walls 4192 — Buried 8136 — Plague 0

1681.

Chriſt Church — ——158	Lambeth Pariſh ——304	St Mary Whitechapel—1098
St Giles in the Fields—1249	St Leonard Shoreditch—611	St Paul Shadwell ——541
St John at Hackney——117	St Magdalen Bermondſey570	Rotherhith Pariſh ——174
St James Clarkenwell —394	St Mary Iſlington — —141	Stepney Pariſh ——2112
St Katherine by the Tower198	St Mary Newington——273	

Chriſtened in the fourteen Out Pariſhes in Middleſex and Surrey 4161
Buried 7940 Plague 0

St Clement Danes — —594	St Martin in the Fields 2387	St Margaret Weſtminſter 880
St Paul Covent Garden 218	St Mary Savoy —— 147	At the Peſt-houſe—— 0

Chriſtened in the five Pariſhes in the City and Liberties of Weſtminſter 2814
Buried 4226 Plague 0

DISEASES and CASUALTIES.

Abortive and Stillborn 653	French Pox —— —— 97	Poiſoned —— —— 1
Aged and Bedridden1301	Frighted —— —— 3	Quinſy and Thruſh —— 128
Ague and Fever — ——3174	Gangrene and Fiſtula—— 46	Rickets —— —— 376
Apoplexy and Suddenly— 94	Gout and Sciatica —— 30	Riſing of the Lights —— 143
Bleeding, Bloody Flux, and Flux — 116	Grief —— — —— 11	Scalded —— — —— 3
	Griping in the Guts — —2827	Scowring —— —— 2
Burnt and Blown up — — 19	Hang'd and made away themſelves — 17	Scurvy —— —— 83
Burſten and Rupture —— 37		Smothered —— —— 3
Cancer and Canker —— 72	Headmouldſhot — — 7	Sores, Ulcers, and bruiſed Limbs —— 97
Childbed —— — —— 354	Jaundies —— —— 75	
Chriſomes and Infants — 303	Jawfallen —— — —— 1	Spleen —— —— —— 6
Cold and Cough — — 2	Impoſthume —— —— 101	Spotted Fever and Purples 199
Colick and Wind — —— 105	Kill'd by ſeveral Accidents 71	St Anthony's Fire —— 10
Conſumption and Tiſſick 3784	Leproſy —— —— 2	Stone and Strangury —— 70
Convulſion —— ——3270	Lethargy —— — — 11	Stopping of the Stomach 351
Diſtracted and Lunatick— 16	Livergrown —— —— 15	Surfeit —— —— —— 436
Dropſy and Tympany — 958	Meaſles —— — —— 121	Swine Pox —— —— 1
Drowned —— —— 80	Megrims —— —— 2	Teeth —— — — 995
Evil —— —— 51	Murdered —— —— 14	Vomiting —— —— 15
Executed —— — —— 8	Overlaid —— —— 135	Wen — —— —— 1
Falling Sickneſs —— — 6	Palſy —— — —— 20	Wolf —— —— 1
Flox and Small Pox — —2982	Planet —— —— 1	Worms —— —— 39
Found dead in the Streets, &c. 7	Pleuriſy —— —— 12	

CHRISTENED	Males — 6822	BURIED	Males — 12386	Of the Plague 0
	Females 6533		Females 11585	
	In all 13355		In all — 23971	

Increaſed in the Burials this Year 2918
Decreaſed in the Plague —— 0

A General

1682.

A General BILL of all the Chriſtenings and Burials,

From the 19th of December 1681, to the 19th of December 1682.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.	Pl.
St ALBAN Wood-ſtreet	33	
Alhallows Barkin	111	
Alhallows Bread-ſtreet	18	
Alhallows Great	60	
Alhallows Honey-lane	0	
Alhallows Leſs	22	
Alhallows Lombard-ſtreet	29	
Alhallows Staining	22	
Alhallows the Wall	60	
St Alphage	44	
St Andrew Hubbard	14	
St Andrew Underſhaft	42	
St Andrew Wardrobe	54	
St Ann Alderſgate	40	
St Ann Black Friars	139	
St Antholin's Pariſh	19	
St Auſtin's Pariſh	14	
St Bartholomew Exchange	18	
St Bennet Fink	29	
St Bennet Gracechurch	5	
St Bennet Paul's Wharf	56	
St Bennet Sherehog	1	
St Botolph Billingſgate	9	
Chriſt Church	88	
St Chriſtopher	16	
St Clement Eaſtcheap	8	
St Dionis Backchurch	36	
St Dunſtan Eaſt	70	
St Edmund Lombard-ſtr.	26	
St Ethelborough	28	
St Faith's	44	
St Gabriel Fenchurch	18	
St George Botolph-lane	11	
St Gregory by St Paul's	76	
St Helen's	38	
St James Duke's Place	45	
St James Garlickhithe	47	
St John Baptiſt	17	
St John Evangeliſt	9	
St John Zachary	24	
St Katherine Coleman	51	
St Katherine Creechurch	72	
St Laurence Jewry	60	
St Laurence Pountney	22	
St Leonard Eaſtcheap	7	
St Leonard Foſter-lane	42	
St Magnus Pariſh	39	
St Margaret Lothbury	44	
St Margaret Moſes	2	
St Margaret New Fiſh-ſtr.	0	
St Margaret Pattons	10	
St Mary Abchurch	25	
St Mary Aldermanbury	25	
St Mary Aldermary	31	
St Mary le Bow	34	
St Mary Bothaw	10	
St Mary Colechurch	5	
St Mary Hill	34	
St Mary Magd. Milk-ſtr.	0	
St Mary Mag. Old Fiſh-ſtr.	44	
St Mary Mounthaw	9	
St Mary Somerſet	43	
St Mary Staining	20	
St Mary Woolchurch	1	
St Mary Woolnoth	27	
St Martin Ironmonger-lane	3	
St Martin Ludgate	45	
St Martin Orgars	22	
St Martin Outwich	14	
St Martin Vintrey	41	
St Matthew Friday-ſtreet	22	
St Michael Baſſiſhaw	26	
St Michael Cornhill	32	
St Michael Crooked-lane	26	
St Michael Queenhithe	69	
St Michael Querne	10	
St Michael Royal	11	
St Michael Wood-ſtreet	19	
St Mildred Bread-ſtreet	10	
St Mildred Poultry	30	
St Nicholas Acons	5	
St Nicholas Coleabby	24	
St Nicholas Olave	18	
St Olave Hart-ſtreet	42	
St Olave Jewry	21	
St Olave Silver-ſtreet	37	
St Pancras Soper-lane	10	
St Peter Cheap	9	
St Peter Cornhill	41	
St Peter Paul's Wharf	10	
St Peter Poor	32	
St Stephen Coleman-ſtreet	130	
St Stephen Walbrook	24	
St Swithin	27	
St Thomas Apoſtle	23	
Trinity Pariſh	0	
St Vedaſt, alias Foſter	31	

Chriſtened in the ninety-ſeven Pariſhes within the Walls 2091 Buried 2975 Plague 0

St Andrew Holborn	841	St Botolph Aldgate	840
St Bartholomew Great	74	St Botolph Biſhopſgate	535
St Bartholomew Leſs	31	St Dunſtan Weſt	269
St Bride's Pariſh	381	St George Southwark	329
Bridewell Precinct	25	St Giles Cripplegate	1315
St Botolph Alderſgate	209	St Olave Southwark	804
St Saviour Southwark	594		
St Sepulchre's Pariſh	649		
St Thomas Southwark	75		
Trinity Minories	38		
At the Peſt-houſe	0		

Chriſtened in the ſixteen Pariſhes without the Walls 4493 Buried 7009 Plague 0

1682.

Chriſt Church — ——143	Lambeth Pariſh — ——297	St Mary Whitechapel—1030
St Giles in the Fields —1120	St Leonard Shoreditch —452	St Paul Shadwell ——593
St John at Hackney——108	St Magdalen Bermondſey 504	Rotherhith Pariſh — —153
St James Clerkenwell —312	St Mary Iſlington — — 123	Stepney Pariſh — ——1823
St Katherine by the Tower224	St Mary Newington ——202	

Chriſtened in the fourteen Out Pariſhes in Middleſex and Surrey 4365
Buried 7084 Plague 0

St Clement Danes — —522	St Martin in the Fields 2059	St Margaret Weſtminſter 779
St Paul Covent Garden 152	St Mary Savoy —— 111	At the Peſt-houſe — — 0

Chriſtened in the five Pariſhes in the City and Liberties of Weſtminſter 2704
Buried 3623 Plague 0

DISEASES and CASUALTIES.

Abortive and Stillborn 686	French Pox —— — — 80	Pleuriſy —— —— 17
Aged and Bedridden1059	Frighted —— —— 1	Poiſoned —— —— 3
Ague and Fever —— —2696	Gangrene and Fiſtula—— 54	Quinſy and Thruſh —— 130
Apoplexy and Suddenly— 100	Gout and Sciatica —— 35	Rickets —— —— 434
Bleeding, Bloody Flux, and Flux — 55	Grief —— —— —— 12	Riſing of the Lights —— 143
	Griping in the Guts — —2631	Scald Head —— —— 2
Burnt and Scalded — — 7	Hanged and made away themſelves — 16	Scowring —— —— 1
Burſten and Rupture —— 28		Scurvy —— — — — 71
Calenture —— —— 1	Head-ach —— —— 1	Shot —— — —— 1
Cancer and Canker —— 61	Headmouldſhot —— 4	Smothered and Stifled - — 2
Childbed —— — — 342	Jaundies —— — —— 51	Sores, Ulcers, and bruiſed Limbs — 83
Chriſomes and Infants — 257	Impoſthume — —— — 94	
Cough and Chincough — 12	Killed by ſeveral Accidents 75	Spleen —— —— 5
Colick and Wind —— 76	Leproſy —— —— 1	Spotted Fever and Purples 140
Conſumption and Tiſſick 3464	Lethargy —— — —— 6	St Anthony's Fire —— 18
Convulſion —— — —3404	Livergrown —— —— 16	Stone and Cut of the Stone 62
Diſtracted and Lunatick— 15	Meaſles —— —— 50	Stopping of the Stomach 360
Dropſy and Tympany - — 640	Megrims —— —— 4	Strangury —— — —— 1
Drowned —— —— 91	Mother —— —— 1	Surfeit —— — —— 361
Evil —— —— —— 66	Murdered —— — —— 16	Teeth — — — —1058
Executed — — —— 10	Overlaid —— —— 104	Vomiting —— —— 16
Flox and Small Pox ——1408	Palſy —— — —— 24	Worms —— —— 27
Found dead in the Streets,&c. 5		

CHRISTENED	Males — 6909 Females 6744 In all — 12653	BURIED	Males — 10617 Females 10074 In all — 20691

Of the Plague 0

Decreaſed in the Burials this Year 3280

1683.

A General BILL of all the Chriſtenings and Burials,

From the 19th of December 1682, to the 18th of December 1683.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.	Pl.
St ALBAN Wood-ſtreet	26	
Alhallows Barkin	104	
Alhallows Bread-ſtreet	14	
Alhallows Great	47	
Alhallows Honey-lane	0	
Alhallows Leſs	22	
Alhallows Lombard-ſtreet	24	
Alhallows Staining	28	
Alhallows the Wall	71	
St Alphage	27	
St Andrew Hubbard	16	
St Andrew Underſhaft	39	
St Andrew Wardrobe	47	
St Ann Alderſgate	58	
St Ann Black Friars	102	
St Antholin's Pariſh	29	
St Auſtin's Pariſh	13	
St Bartholomew Exchange	17	
St Bennet Fink	24	
St Bennet Gracechurch	15	
St Bennet Paul's Wharf	46	
St Bennet Sherehog	2	
St Botolph Billingſgate	9	
Chriſt Church	85	
St Chriſtopher	15	
St Clement Eaſtcheap	24	
St Dionis Backchurch	39	
St Dunſtan Eaſt	85	
St Edmund Lombard-ſtr.	30	
St Ethelborough	15	
St Faith's	39	
St Gabriel Fenchurch	18	
St George Botolph-lane	11	
St Gregory by St Paul's	82	
St Helen's	30	
St James Duke's Place	22	
St James Garlickhithe	63	
St John Baptiſt	18	
St John Evangeliſt	9	
St John Zachary	28	
St Katherine Coleman	48	
St Katherine Creechurch	79	
St Laurence Jewry	46	
St Laurence Pountney	15	
St Leonard Eaſtcheap	14	
St Leonard Foſter-lane	29	
St Magnus Pariſh	45	
St Margaret Lothbury	33	
St Margaret Moſes	2	
St Margaret New Fiſh-ſtr.	0	
St Margaret Pattons	12	
St Mary Abchurch	27	
St Mary Aldermanbury	30	
St Mary Aldermary	42	
St Mary le Bow	11	
St Mary Bothaw	7	
St Mary Colechurch	5	
St Mary Hill	31	
St Mary Magd. Milk-ſtr.	0	
St Mary Mag. Old Fiſh-ſtr.	36	
St Mary Mounthaw	14	
St Mary Somerſet	57	
St Mary Staining	12	
St Mary Woolchurch	0	
St Mary Woolnoth	37	
St Martin Ironmonger-lane	6	
St Martin Ludgate	42	
St Martin Orgars	26	
St Martin Outwich	8	
St Martin Vintrey	39	
St Matthew Friday-ſtreet	15	
St Michael Baſſiſhaw	29	
St Michael Cornhill	33	
St Michael Crooked-lane	34	
St Michael Queenhithe	46	
St Michael Querne	12	
St Michael Royal	19	
St Michael Wood-ſtreet	22	
St Mildred Bread-ſtreet	19	
St Mildred Poultry	36	
St Nicholas Acons	4	
St Nicholas Coleabby	30	
St Nicholas Olave	6	
St Olave Hart-ſtreet	49	
St Olave Jewry	12	
St Olave Silver-ſtreet	34	
St Pancras Soper-lane	11	
St Peter Cheap	4	
St Peter Cornhill	26	
St Peter Paul's Wharf	12	
St Peter Poor	2	
St Stephen Coleman-ſtreet	134	
St Stephen Walbrook	27	
St Swithin	24	
St Thomas Apoſtle	23	
Trinity Pariſh	11	
St Vedaſt, alias Foſter	30	

Chriſtened in the ninety-ſeven Pariſhes within the Walls 2355 Buried 2876 Plague 0

St Andrew Holborn	831	St Botolph Aldgate	663	St Saviour Southwark	589
St Bartholomew Great	79	St Botolph Biſhopſgate	576	St Sepulchre's Pariſh	599
St Bartholomew Leſs	29	St Dunſtan Weſt	252	St Thomas Southwark	69
St Bride's Pariſh	375	St George Southwark	339	Trinity Minories	31
Bridewell Precinct	37	St Giles Cripplegate	1406	At the Peſt-houſe	0
St Botolph Alderſgate	207	St Olave Southwark	756		

Chriſtened in the ſixteen Pariſhes without the Walls 4756 Buried 6838 Plague 0

1683.

Chriſt Church — —168	Lambeth Pariſh —325	St Mary Whitechapel —866
St Giles in the Fields—1181	St Leonard Shoreditch—442	St Paul Shadwell —463
St John at Hackney— 74	St Magdalen Bermondſey433	Rotherhith Pariſh — —162
St James Clerkenwell —348	St Mary Iſlington —115	Stepney Pariſh — —1843
St Katherine by the Tower202	St Mary Newington—204	

Chriſtened in the fourteen Out Pariſhes in Middleſex and Surrey 4638
Buried 6826 Plague 0

St Clement Danes — —509	St Martin in the Fields 2340	St Margaret Weſtminſter 887
St Paul Covent Garden 188	St Mary Savoy — 123	At the Peſt-houſe — 0

Chriſtened in the five Pariſhes in the City and Liberties of Weſtminſter 2986
Buried 4047 Plague 0

DISEASES and CASUALTIES.

Abortive and Stillborn 692	Executed — — 6	Pleuriſy — — 12
Aged and Bedridden1065	Flox and Small Pox —2096	Poiſoned — — 3
Ague and Fever — —2250	Found dead in the Streets, &c. 4	Purples — — 11
Apoplexy and Suddenly— 108	French Pox — — 85	Quinſy and Thruſh — 132
Bleeding, Bloody Flux, and Flux — 68	Gangrene and Fiſtula— 76	Rickets — — — 503
Burnt and Scalded — 11	Gout — — 17	Riſing of the Lights — 174
Burſten and Rupture — 31	Grief — — 7	Scurvy — — — 65
Calenture — — 1	Griping in the Guts — —2438	Shot — — 3
Cancer and Canker — 50	Hanged and made away themſelves — 18	Smothered — — 5
Childbed — — 334	Headmouldſhot — — 10	Sores, Ulcers, and bruiſed Limbs — 76
Chincough — — 4	Jaundies — — 62	Spleen — — 3
Chriſomes and Infants — 250	Jawfallen — — 1	Spotted Fever — — 148
Cold and Cough — 9	Impoſthume — — 103	St Anthony's Fire — 19
Colick and Wind — 70	Kill'd by ſeveral Accidents 83	Stone — — 59
Conſumption and Tiſſick 3241	Lethargy — — — 11	Stopping of the Stomach 405
Convulſion — —3235	Livergrown — — 16	Strangury — — 3
Cut of the Stone — — 2	Meaſles — — 39	Surfeit — — 343
Diſtracted and Lunatick— 25	Megrims — — — 1	Teeth — — —1074
Dropſy and Tympany — 633	Murdered — — 13	Vomiting — — 14
Drowned — — 79	Overlaid — — 121	Wen — — — 1
Epilepſy — — 1	Palſy — — — 19	Worms — — — 46
Evil — — — 101	Planet — — 2	

CHRISTENED	Males — 7577	BURIED	Males — 10702	Of the Plague 0
	Females 7158		Females 9885	
	In all — 14735		In all — 20587	

Decreaſed in the Burials this Year 104

1684.

A General BILL of all the Chriſtenings and Burials,

From the 18th of December 1683, to the 16th of December 1684.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.	Pl.
St ALBAN Wood-ſtreet	41	
Alhallows Barkin	109	
Alhallows Bread-ſtreet	21	
Alhallows Great	77	
Alhallows Honey-lane	0	
Alhallows Leſs	26	
Alhallows Lombard-ſtreet	29	
Alhallows Staining	38	
Alhallows the Wall	69	
St Alphage	36	
St Andrew Hubbard	22	
St Andrew Underſhaft	68	
St Andrew Wardrobe	63	
St Ann Alderſgate	47	
St Ann Black Friars	121	
St Antholin's Pariſh	22	
St Auſtin's Pariſh	21	
St Bartholomew Exchange	16	
St Bennet Fink	22	
St Bennet Gracechurch	16	
St Bennet Paul's Wharf	71	
St Bennet Sherehog	0	
St Botolph Billingſgate	16	
Chriſt Church	121	
St Chriſtopher	24	
St Clement Eaſtcheap	14	
St Dionis Backchurch	28	
St Dunſtan Eaſt	99	
St Edmund Lombard-ſtr.	31	
St Ethelborough	23	
St Faith's	39	
St Gabriel Fenchurch	16	
St George Botolph-lane	8	
St Gregory by St Paul's	85	
St Helen's	40	
St James Duke's Place	42	
St James Garlickhithe	48	
St John Baptiſt	26	
St John Evangeliſt	6	
St John Zachary	21	
St Katherine Coleman	65	
St Katherine Creechurch	69	
St Laurence Jewry	52	
St Laurence Pountney	27	
St Leonard Eaſtcheap	13	
St Leonard Foſter-lane	37	
St Magnus Pariſh	59	
St Margaret Lothbury	36	
St Margaret Moſes	7	
St Margaret New Fiſh-ſtr.	1	
St Margaret Pattons	24	
St Mary Abchurch	34	
St Mary Aldermanbury	28	
St Mary Aldermary	48	
St Mary le Bow	23	
St Mary Bothaw	5	
St Mary Colechurch	3	
St Mary Hill	31	
St Mary Magd. Milk-ſtr.	0	
St Mary Mag. Old Fiſh-ſtr.	38	
St Mary Mounthaw	10	
St Mary Somerſet	46	
St Mary Staining	11	
St Mary Woolchurch	1	
St Mary Woolnoth	47	
St Martin Ironmonger-lane	5	
St Martin Ludgate	42	
St Martin Orgars	20	
St Martin Outwich	19	
St Martin Vintrey	55	
St Matthew Friday-ſtreet	16	
St Michael Baſſiſhaw	33	
St Michael Cornhill	28	
St Michael Crooked-lane	29	
St Michael Queenhithe	41	
St Michael Querne	14	
St Michael Royal	12	
St Michael Wood-ſtreet	10	
St Mildred Bread-ſtreet	25	
St Mildred Poultry	46	
St Nicholas Acons	3	
St Nicholas Coleabby	20	
St Nicholas Olave	14	
St Olave Hart-ſtreet	59	
St Olave Jewry	16	
St Olave Silver-ſtreet	35	
St Pancras Soper-lane	7	
St Peter Cheap	9	
St Peter Cornhill	38	
St Peter Paul's Wharf	22	
St Peter Poor	30	
St Stephen Coleman-ſtreet	153	
St Stephen Walbrook	27	
St Swithin	42	
St Thomas Apoſtle	14	
Trinity Pariſh	29	
St Vedaſt, alias Foſter	29	

Chriſtened in the ninety-ſeven Pariſhes within the Walls 2193 Buried 3279 Plague 0

St Andrew Holborn	923	St Botolph Aldgate	883	St Saviour Southwark	652
St Bartholomew Great	85	St Botolph Biſhopſgate	613	St Sepulchre's Pariſh	723
St Bartholomew Leſs	34	St Dunſtan Weſt	285	St Thomas Southwark	78
St Bride's Pariſh	432	St George Southwark	401	Trinity Minories	29
Bridewell Precinct	39	St Giles Cripplegate	1527	At the Peſt-houſe	0
St Botolph Alderſgate	227	St Olave Southwark	806		

Chriſtened in the ſixteen Pariſhes without the Walls 4736 Buried 7737 Plague 0

1684.

Chriſt Church —— —195	Lambeth Pariſh ——387	St Mary Whitechapel—1060
St Giles in the Fields —1318	St Leonard Shoreditch—539	St Paul Shadwell ——522
St John at Hackney——106	St Magdalen Bermondſey516	Rotherhith Pariſh — —188
St James Clerkenwell —400	St Mary Iſlington — —127	Stepney Pariſh —— —2171
St Katherine by the Tower134	St Mary Newington——280	

Chriſtened in the fourteen Out Pariſhes in Middleſex and Surrey 4660
Buried 8043 Plague 0

St Clement Danes — —582	St Martin in the Fields 2362	St Margaret Weſtminſter 861
St Paul Covent Garden 203	St Mary Savoy —— 135	Whereof at the Peſt-houſe 0

Chriſtened in the five Pariſhes in the City and Liberties of Weſtminſter. 3113
Buried 4143 Plague 0

DISEASES and CASUALTIES.

Abortive and Stillborn 752	French Pox —— —— 108	Quinſy and Thruſh —— 143
Aged and Bedridden1476	Gangrene and Fiſtula —— 59	Rickets —— —— 576
Ague and Fever —— —2836	Gout —— —— —— 18	Riſing of the Lights —— 150
Apoplexy and Suddenly— 152	Grief —— — —— 11	Scald Head —— —— 1
Bleeding, Bloody Flux, and Flux — 33	Griping in the Guts — —2981	Sciatica —— —— 2
	Hang'd and made away themſelves — 10	Scurvy —— —— 74
Burnt and Scalded — — 8		Shot —— —— —— 2
Burſten and Rupture —— 44	Head-ach —— —— 1	Smothered —— —— 1
Cancer and Canker — — 51	Headmouldſhot — —— 8	Sores, Ulcers, and bruiſed Limbs —— 99
Childbed —— —— 322	Jaundies —— —— 74	
Chriſomes and Infants —— 277	Impoſthume — — —— 99	Spleen —— — —— 3
Colick and Wind — —— 69	Kill'd by ſeveral Accidents 89	Spotted Fever and Purples 139
Conſumption and Tiſſick 3862	Leproſy —— — — 2	St Anthony's Fire —— 11
Convulſion —— ——3772	Lethargy —— —— 7	Starved —— —— 1
Cough and Chincough —— 3	Livergrown — — —— 18	Stone —— — —— 44
Diabetes —— —— 2	Meaſles and Chicken Pox 6	Stopping of the Stomach 431
Diſtracted and Lunatick— 38	Megrims —— —— 6	Strangury —— —— 3
Dropſy and Tympany —— 758	Murdered — — —— 14	Surfeit —— — —— 392
Drowned — — —— 65	Overlaid —— —— 113	Teeth —— ——1198
Evil —— —— 105	Palſy —— —— — 29	Vomiting — — —— 26
Executed —— —— 15	Planet —— —— 1	Wolf —— —— 1
Flox and Small Pox ——1560	Pleuriſy —— —— 13	Worms —— —— 29
Found dead in the Streets, &c. 7	Poiſoned — —— — 2	

CHRISTENED	Males — 7575	BURIED	Males — 11919	Of the Plague	0
	Females 7127		Females 11283		
	In all — 14702		In all — 23202		

Increaſed in the Burials this Year 2615

A General

1685.

A General BILL of all the Chriſtenings and Burials,

From the 16th of December 1684, to the 15th of December 1685.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.	Pl.
St ALBAN Wood-ſtreet	36	
Alhallows Barkin	76	
Alhallows Bread-ſtreet	23	
Alhallows Great	58	
Alhallows Honey-lane	0	
Alhallows Leſs	12	
Alhallows Lombard-ſtreet	35	
Alhallows Staining	34	
Alhallows the Wall	64	
St Alphage	39	
St Andrew Hubbard	16	
St Andrew Underſhaft	48	
St Andrew Wardrobe	74	
St Ann Alderſgate	59	
St Ann Black Friars	133	
St Antholin's Pariſh	20	
St Auſtin's Pariſh	27	
St Bartholomew Exchange	14	
St Bennet Fink	33	
St Bennet Gracechurch	10	
St Bennet Paul's Wharf	56	
St Bennet Sherehog	2	
St Botolph Billingſgate	8	
Chriſt Church	126	
St Chriſtopher	21	
St Clement Eaſtcheap	14	
St Dionis Backchurch	33	
St Dunſtan Eaſt	101	
St Edmund Lombard-ſtr.	34	
St Ethelborough	28	
St Faith's	44	
St Gabriel Fenchurch	12	
St George Botolph-lane	11	
St Gregory by St Paul's	85	
St Helen's	30	
St James Duke's Place	43	
St James Garlickhithe	66	
St John Baptiſt	27	
St John Evangeliſt	8	
St John Zachary	23	
St Katherine Coleman	45	
St Katherine Creechurch	73	
St Laurence Jewry	56	
St Laurence Pountney	24	
St Leonard Eaſtcheap	13	
St Leonard Foſter-lane	53	
St Magnus Pariſh	56	
St Margaret Lothbury	42	
St Margaret Moſes	4	
St Margaret New Fiſh-ſtr.	0	
St Margaret Pattons	18	
St Mary Abchurch	24	
St Mary Aldermanbury	35	
St Mary Aldermary	58	
St Mary le Bow	33	
St Mary Bothaw	9	
St Mary Colechurch	1	
St Mary Hill	34	
St Mary Magd. Milk-ſtr.	0	
St Mary Mag. Old Fiſh-ſtr.	37	
St Mary Mounthaw	11	
St Mary Somerſet	36	
St Mary Staining	20	
St Mary Woolchurch	0	
St Mary Woolnoth	34	
St Martin Ironmonger-lane	5	
St Martin Ludgate	72	
St Martin Orgars	24	
St Martin Outwich	12	
St Martin Vintrey	45	
St Matthew Friday-ſtreet	23	
St Michael Baſſiſhaw	31	
St Michael Cornhill	32	
St Michael Crooked-lane	31	
St Michael Queenhithe	51	
St Michael Querne	18	
St Michael Royal	17	
St Michael Wood-ſtreet	18	
St Mildred Bread-ſtreet	19	
St Mildred Poultry	51	
St Nicholas Acons	1	
St Nicholas Coleabby	24	
St Nicholas Olave	16	
St Olave Hart-ſtreet	67	
St Olave Jewry	20	
St Olave Silver-ſtreet	43	
St Pancras Soper-lane	17	
St Peter Cheap	5	
St Peter Cornhill	35	
St Peter Paul's Wharf	17	
St Peter Poor	30	
St Stephen Coleman-ſtreet	155	
St Stephen Walbrook	23	
St Swithin	30	
St Thomas Apoſtle	9	
Trinity Pariſh	13	
St Vedaſt, alias Foſter	46	

Chriſtened in the ninety-ſeven Pariſhes within the Walls 2312 Buried 3299 Plague 0

St Andrew Holborn	1004	St Botolph Aldgate	896	St Saviour Southwark	635
St Bartholomew Great	79	St Botolph Biſhopſgate	620	St Sepulchre's Pariſh	787
St Bartholomew Leſs	33	St Dunſtan Weſt	290	St Thomas Southwark	87
St Bride's Pariſh	400	St George Southwark	354	Trinity Minories	28
Bridewell Precinct	47	St Giles Cripplegate	1482	At the Peſt-houſe	0
St Botolph Alderſgate	253	St Olave Southwark	903		

Chriſtened in the ſixteen Pariſhes without the Walls 4878 Buried 7898 Plague 0

Chriſt Church — —171	Lambeth Pariſh ——254	St Mary Whitechapel —923
St Giles in the Fields—1350	St Leonard Shoreditch—549	St Paul Shadwell ——468
St John at Hackney——115	St Magdalen Bermondſey507	Rotherhith Pariſh —140
St James Clerkenwell —385	St Mary Iſlington — —108	Stepney Pariſh ——1984
St Katherine by the Tower222	St Mary Newington——215	

Chriſtened in the fourteen Out Pariſhes in Middleſex and Surrey 4551
Buried 7391 Plague 0

St Clement Danes — —528	St Paul Covent Garden 194	St Mary Savoy —— 143
St James Weſtminſter —429	St Martin in the Fields 2317	St Margaret Weſtminſt. 1013

Chriſtened in the ſix Pariſhes in the City and Liberties of Weſtminſter 2989
Buried 4634 Plague 0

DISEASES and CASUALTIES.

Abortive and Stillborn 759	Found dead in the Streets, &c. 10	Quinſy and Thruſh — 126
Aged and Bedridden1163	French Pox —— — 82	Rickets —— —— 349
Ague and Fever — —3832	Frighted — —— 1	Riſing of the Lights and Mother — 137
Apoplexy and Suddenly— 112	Gangrene and Fiſtula— 50	Rupture — — — 31
Bleeding, Bloody Flux, and Flux — 47	Gout — — —— 7	Sciatica —— —— 2
Burnt and Scalded — — 14	Grief —— — — 9	Scurvy —— —— 90
Calenture —— —— 3	Griping in the Guts — —2203	Shot and Blown up — 6
Cancer and Canker —— 66	Hang'd and made away themſelves — 22	Smothered —— —— 2
Childbed —— — — 315	Headmouldſhot — — 6	Sores, Ulcers, broken and bruiſed Limbs — 109
Chriſomes and Infants — 254	Jaundies —— —— 84	Spleen —— — — 3
Colick and Wind — —— 51	Impoſthume —— — 106	Spotted Fever and Purples 333
Conſumption and Tiſſick 3502	Kill'd by ſeveral Accidents 76	St Anthony's Fire —— 19
Convulſion —— ——3420	Leproſy —— —— 2	Stone and Cut of the Stone 50
Cough and Chincough — 9	Lethargy —— — — 8	Stopping of the Stomach 403
Diabetes —— —— 2	Livergrown —— —— 4	Strangury —— —— 5
Diſtracted and Lunatick— 30	Meaſles —— — — 197	Surfeit —— —— — 399
Dropſy and Tympany — 703	Megrims —— —— 3	Teeth —— — —1138
Drowned —— —— 66	Murdered —— —— 22	Vomiting —— —— 4
Evil —— —— 103	Overlaid —— —— 101	Wen — —— —— 1
Executed —— — — 19	Palſy —— — — 19	Worms —— —— 17
Falling Sickneſs —— — 1	Pleuriſy —— —— 16	
Flox and Small Pox — —2496	Poiſoned —— —— 3	

CHRISTENED	Males — 7484	BURIED	Males — 11891	Of the Plague 0
	Females 7246		Females 11331	
	In all 14730		In all — 23222	

Increaſed in the Burials this Year 20

A General

1686.

A General BILL of all the Chriſtenings and Burials,

From the 15th of December 1685, to the 14th of December 1686.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.	Pl.
St ALBAN Wood-ſtreet	33	
Alhallows Barkin	86	
Alhallows Bread-ſtreet	17	
Alhallows Great	64	
Alhallows Honey-lane	0	
Alhallows Leſs	20	
Alhallows Lombard-ſtreet	31	
Alhallows Staining	39	
Alhallows the Wall	88	
St Alphage	46	
St Andrew Hubbard	16	
St Andrew Underſhaft	53	
St Andrew Wardrobe	48	
St Ann Alderſgate	51	
St Ann Black Friars	127	
St Antholin's Pariſh	11	
St Auſtin's Pariſh	27	
St Bartholomew Exchange	18	
St Bennet Fink	22	
St Bennet Gracechurch	13	
St Bennet Paul's Wharf	69	
St Bennet Sherehog	3	
St Botolph Billingſgate	18	
Chriſt-Church	100	
St Chriſtopher	21	
St Clement Eaſtcheap	7	
St Dionis Backchurch	39	
St Dunſtan Eaſt	105	
St Edmund Lombard-ſtr.	27	
St Ethelborough	33	
St Faith's	39	
St Gabriel Fenchurch	9	
St George Botolph-lane	16	
St Gregory by St Paul's	81	
St Helen's	39	
St James Duke's Place	31	
St James Garlickhithe	61	
St John Baptiſt	31	
St John Evangeliſt	11	
St John Zachary	18	
St Katherine Coleman	40	
St Katherine Creechurch	74	
St Laurence Jewry	66	
St Laurence Pountney	17	
St Leonard Eaſtcheap	9	
St Leonard Foſter-lane	42	
St Magnus Pariſh	38	
St Margaret Lothbury	30	
St Margaret Moſes	1	
St Margaret New Fiſh-ſtr.	0	
St Margaret Pattons	12	
St Mary Abchurch	38	
St Mary Aldermanbury	27	
St Mary Aldermary	57	
St Mary le Bow	23	
St Mary Bothaw	5	
St Mary Colechurch	1	
St Mary Hill	36	
St Mary Magd. Milk-ſtr.	0	
St Mary Mag. Old Fiſh-ſtr.	31	
St Mary Mounthaw	17	
St Mary Somerſet	35	
St Mary Staining	25	
St Mary Woolchurch	3	
St Mary Woolnoth	34	
St Martin Ironmonger-lane	14	
St Martin Ludgate	46	
St Martin Orgars	23	
St Martin Outwich	15	
St Martin Vintrey	43	
St Matthew Friday-ſtreet	17	
St Michael Baſſiſhaw	36	
St Michael Cornhill	30	
St Michael Crooked-lane	37	
St Michael Queenhithe	52	
St Michael Querne	9	
St Michael Royal	19	
St Michael Wood-ſtreet	10	
St Mildred Bread-ſtreet	27	
St Mildred Poultry	38	
St Nicholas Acons	12	
St Nicholas Coleabby	18	
St Nicholas Olave	17	
St Olave Hart-ſtreet	55	
St Olave Jewry	18	
St Olave Silver-ſtreet	27	
St Pancras Soper-lane	9	
St Peter Cheap	8	
St Peter Cornhill	44	
St Peter Paul's Wharf	27	
St Peter Poor	33	
St Stephen Coleman-ſtreet	136	
St Stephen Walbrook	22	
St Swithin	18	
St Thomas Apoſtle	14	
Trinity Pariſh	18	
St Vedaſt, alias Foſter	42	

Chriſtened in the ninety-ſeven Pariſhes within the Walls 2211 Buried 3163 Plague 0

St Andrew Holborn	978	St Botolph Aldgate	776
St Bartholomew Great	79	St Botolph Biſhopſgate	611
St Bartholomew Leſs	45	St Dunſtan Weſt	274
St Bride's Pariſh	435	St George Southwark	391
Bridewell Precinct	35	St Giles Cripplegate	1522
St Botolph Alderſgate	239	St Olave Southwark	780
St Saviour Southwark	585		
St Sepulchre's Pariſh	739		
St Thomas Southwark	82		
Trinity Minories	16		
At the Peſt-houſe	0		

Chriſtened in the ſixteen Pariſhes without the Walls 4927 Buried 7587 Plague 0

Chriſt Church — —178	Lambeth Pariſh — —303	St Mary Whitechapel —978
St John at Hackney——110	St Leonard Shoreditch —493	St Paul Shadwell ——525
St Giles in the Fields —1374	St Magdalen Bermondſey 464	Rotherhith Pariſh — —171
St James Clerkenwell —413	St Mary Iſlington — — 129	Stepney Pariſh — ——1882
St Katherine by the Tower220	St Mary Newington ——242	

Chriſtened in the fourteen Out Pariſhes in Middleſex and Surrey 4574
Buried 7482 Plague 0

St Ann Weſtminſter - —244	St Paul Covent Garden 214	St Mary Savoy —— 140
St Clement Danes ——606	St Martin in the Fields 1471	St Margaret Weſtminſter 865
St James Weſtminſter —837		

Chriſtened in the ſeven Pariſhes in the City and Liberties of Weſtminſter 2982
Buried 4377 Plague 0

DISEASES and CASUALTIES.

Abortive and Stillborn 597	Found dead in the Streets,&c. 11	Pleuriſy —— —— 9
Aged and Bedridden 1165	French Pox —— — — 94	Poiſoned —— —— 2
Ague and Fever —— —4185	Frighted —— —— 1	Quinſy and Thruſh —— 132
Apoplexy and Suddenly— 129	Gangrene and Fiſtula—— 58	Rickets —— —— 349
Bleeding, Bloody Flux, and Flux — 47	Gout —— — —— 13	Riſing of the Lights —— 113
	Grief —— —— —— 10	Scurvy —— — — — 66
Burnt and Scalded — — 9	Griping in the Guts — —2605	Shot —— — —— 3
Burſten and Rupture —— 25	Hanged and made away themſelves — 14	Smothered —— —— 4
Cancer and Canker —— 65		Sores, Ulcers, and broken Limbs — 107
Childbed —— — — 288	Head-ach and Megrims— 7	
Chincough —— —— 2	Headmouldſhot —— 5	Spleen —— —— 3
Chriſomes and Infants — 224	Jaundies —— — —— 82	Spotted Fever and Purples 314
Colick and Wind —— 38	Impoſthume — —— — 114	St Anthony's Fire —— 13
Conſumption and Tiſſick 3569	Killed by ſeveral Accidents 69	Starved — — —— 1
Convulſion —— — —3731	Leproſy —— —— 2	Stone and Cut of the Stone 51
Diabetes —— —— 1	Lethargy —— — —— 2	Stopping of the Stomach 388
Diſtracted and Lunatick— 31	Livergrown —— —— 17	Strangury —— — —— 2
Dropſy and Tympany - — 842	Meaſles —— —— 25	Surfeit —— — —— 338
Drowned —— —— 92	Mother —— —— 1	Teeth — — — —1178
Evil —— —— —— 108	Murdered —— — —— 14	Vomiting —— —— 18
Exceſſive Drinking —— 2	Overlaid —— —— 96	Wen —— —— 1
Executed — — —— 16	Palſy —— — —— 21	Worms —— —— 26
Flox and Small Pox ——1062	Planet —— — —— 2	

CHRISTENED	Males — 7575 Females 7119 In all — 14694	BURIED	Males — 11828 Females 10781 In all — 22609

Of the Plague 0

Decreaſed in the Burials this Year 613

1687.

A General BILL of all the Chriſtenings and Burials,

From the 14th of December 1686, to the 13th of December 1687.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.	Pl.
St ALBAN Wood-ſtreet	26	
Alhallows Barkin	98	
Alhallows Bread-ſtreet	18	
Alhallows Great	61	
Alhallows Honey-lane	0	
Alhallows Leſs	13	
Alhallows Lombard-ſtreet	26	
Alhallows Staining	42	
Alhallows the Wall	62	
St Alphage	45	
St Andrew Hubbard	17	
St Andrew Underſhaft	52	
St Andrew Wardrobe	43	
St Ann Alderſgate	31	
St Ann Black Friars	107	
St Antholin's Pariſh	26	
St Auſtin's Pariſh	26	
St Bartholomew Exchange	20	
St Bennet Fink	15	
St Bennet Gracechurch	9	
St Bennet Paul's Wharf	48	
St Bennet Sherehog	3	
St Botolph Billingſgate	10	
Chriſt Church	103	
St Chriſtopher	8	
St Clement Eaſtcheap	12	
St Dionis Backchurch	36	
St Dunſtan Eaſt	99	
St Edmund Lombard-ſtr.	29	
St Ethelborough	18	
St Faith's	47	
St Gabriel Fenchurch	14	
St George Botolph-lane	17	
St Gregory by St Paul's	87	
St Helen's	40	
St James Duke's Place	33	
St James Garlickhithe	48	
St John Baptiſt	29	
St John Evangeliſt	9	
St John Zachary	26	
St Katherine Coleman	43	
St Katherine Creechurch	63	
St Laurence Jewry	66	
St Laurence Pountney	15	
St Leonard Eaſtcheap	6	
St Leonard Foſter-lane	38	
St Magnus Pariſh	43	
St Margaret Lothbury	41	
St Margaret Moſes	3	
St Margaret New Fiſh-ſtr.	0	
St Margaret Pattons	7	
St Martin Ironmonger-lane	7	
St Martin Ludgate	48	
St Martin Orgars	20	
St Martin Outwich	14	
St Martin Vintrey	48	
St Mary Abchurch	28	
St Mary Aldermanbury	38	
St Mary Aldermary	40	
St Mary le Bow	22	
St Mary Bothaw	5	
St Mary Colechurch	3	
St Mary Hill	31	
St Mary Magd. Milk-ſtr.	0	
St Mary Mag. Old Fiſh-ſtr.	40	
St Mary Mounthaw	17	
St Mary Somerſet	29	
St Mary Staining	14	
St Mary Woolchurch	0	
St Mary Woolnoth	29	
St Matthew Friday-ſtreet	19	
St Michael Baſſiſhaw	34	
St Michael Cornhill	25	
St Michael Crooked-lane	25	
St Michael Queenhithe	47	
St Michael Querne	18	
St Michael Royal	7	
St Michael Wood-ſtreet	11	
St Mildred Bread-ſtreet	25	
St Mildred Poultry	37	
St Nicholas Acons	2	
St Nicholas Coleabby	20	
St Nicholas Olave	6	
St Olave Hart-ſtreet	51	
St Olave Jewry	16	
St Olave Silver-ſtreet	34	
St Pancras Soper-lane	12	
St Peter Cheap	5	
St Peter Cornhill	38	
St Peter Paul's Wharf	12	
St Peter Poor	27	
St Stephen Coleman-ſtreet	116	
St Stephen Walbrook	19	
St Swithin	25	
St Thomas Apoſtle	14	
Trinity Pariſh	11	
St Vedaſt, alias Foſter	40	

Chriſtened in the ninety-ſeven Pariſhes within the Walls 2104 Buried 2907 Plague 0

St Andrew Holborn	842	St Botolph Aldgate	756	St Saviour Southwark	575
St Bartholomew Great	92	St Botolph Biſhopſgate	552	St Sepulchre's Pariſh	669
St Bartholomew Leſs	45	St Dunſtan Weſt	242	St Thomas Southwark	85
St Bride's Pariſh	345	St George Southwark	291	Trinity Minories	19
Bridewell Precinct	34	St Giles Cripplegate	1463	At the Peſt-houſe	0
St Botolph Alderſgate	199	St Olave Southwark	683		

Chriſtened in the ſixteen Pariſhes without the Walls 4781 Buried 6892 Plague 0

Chriſt Church — —183	St Katherine by the Tower 216	St Mary Newington —269
St Dunſtan at Stepney—1984	Lambeth Pariſh — —279	St Mary Whitechapel —941
St Giles in the Fields —1283	St Leonard Shoreditch —515	St Paul Shadwell —421
St James Clerkenwell —373	St Mary Iſlington —105	Rotherhith Pariſh — —136
St John at Hackney — 86	St Magdalen Bermondſey 395	

Chriſtened in the fourteen Out Pariſhes in Middleſex and Surrey 4821
Buried 7186 Plague 0

St Ann Weſtminſter —388	St Margaret Weſtminſter 885	St Mary Savoy — 116
St Clement Danes — —555	St Martin in the Fields 1379	St Paul Covent Garden 219
St James Weſtminſter—933		

Chriſtened in the ſeven Pariſhes in the City and Liberties of Weſtminſter 3245
Buried 4475 Plague 0

DISEASES and CASUALTIES.

Abortive and Stillborn 733	Falling Sickneſs — — 1	Planet and Blaſted — 5
Aged and Bedridden 1231	Flox, Small Pox and Meaſles 1551	Pleuriſy — — 28
Ague, Calenture and Fever 2847	Found dead in the Streets, &c. 7	Poiſoned — — 1
Apoplexy and Suddenly — 110	French Pox — — 87	Quinſy and Thruſh — 87
Bleeding, Bloody Flux, and Flux — 26	Frighted — — 1	Rickets — — — 377
Burnt and Scalded — 19	Gangrene and Fiſtula — 52	Riſing of the Lights — 92
Burſten and Rupture — 24	Gout and Sciatica — 11	Scurvy — — — 57
Cancer and Canker — 61	Grief — — 1	Shot and Wounded — 6
Childbed — — 306	Griping in the Guts — —2542	Smothered — — 3
Choaked — — 1	Hanged and made away themſelves — 22	Sores, Ulcers, bruiſed and broken Limbs 87
Chriſomes and Infants — 182	Head-ach and Megrims — 4	Spleen — — 2
Colick and Wind — 36	Headmouldſhot — — 9	Spotted Fever and Purples 144
Conſumption and Tiſſick 3473	Jaundies — — 61	St Anthony's Fire — 10
Convulſion — —3967	Impoſthume — — 80	Stone and Cut of the Stone 62
Cough and Chincough — 10	Kill'd by ſeveral Accidents 66	Stopping of the Stomach 379
Diabetes — — 3	Leproſy — — 2	Strangury — — 4
Diſtracted and Lunatick— 36	Lethargy — — — 4	Surfeit — — 292
Dropſy and Tympany — 747	Livergrown — — 17	Teeth — — —1152
Drowned — — 74	Murdered — — 20	Vomiting — — 17
Evil — — — 99	Overlaid — — 79	Wen — — — 1
Exceſſive Drinking — 1	Palſy — — — 20	Worms — — — 19
Executed — — 12		

CHRISTENED { Males — 7737, Females 7214, In all — 14951 } BURIED { Males — 11174, Females 10286, In all — 21460 } Of the Plague 0

Decreaſed in the Burials this Year 1149

1688.

A General BILL of all the Chriſtenings and Burials,

From the 13th of December 1687, to the 11th of December 1688.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.	Pl.
St ALBAN Wood-ſtreet	33	
Alhallows Barkin	88	
Alhallows Bread-ſtreet	20	
Alhallows Great	61	
Alhallows Honey-lane	0	
Alhallows Leſs	19	
Alhallows Lombard-ſtreet	26	
Alhallows Staining	50	
Alhallows the Wall	67	
St Alphage	40	
St Andrew Hubbard	20	
St Andrew Underſhaft	51	
St Andrew Wardrobe	58	
St Ann Alderſgate	36	
St Ann Black Friars	148	
St Antholin's Pariſh	10	
St Auſtin's Pariſh	24	
St Bartholomew Exchange	14	
St Bennet Fink	21	
St Bennet Gracechurch	7	
St Bennet Paul's Wharf	54	
St Bennet Sherehog	4	
St Botolph Billingſgate	14	
Chriſt Church	110	
St Chriſtopher	8	
St Clement Eaſtcheap	18	
St Dionis Backchurch	32	
St Dunſtan Eaſt	98	
St Edmund Lombard-ſtr.	29	
St Ethelborough	22	
St Faith's	53	
St Gabriel Fenchurch	10	
St George Botolph-lane	14	
St Gregory by St Paul's	91	
St Helen's	44	
St James Duke's Place	39	
St James Garlickhithe	57	
St John Baptiſt	24	
St John Evangeliſt	12	
St John Zachary	18	
St Katherine Coleman	42	
St Katherine Creechurch	79	
St Laurence Jewry	47	
St Laurence Pountney	18	
St Leonard Eaſtcheap	12	
St Leonard Foſter-lane	34	
St Magnus Pariſh	52	
St Margaret Lothbury	37	
St Margaret Moſes	11	
St Margaret New Fiſh-ſtr.	0	
St Margaret Pattons	18	
St Martin Ironmonger-lane	8	
St Martin Ludgate	53	
St Martin Orgars	18	
St Martin Outwich	17	
St Martin Vintrey	54	
St Mary Abchurch	33	
St Mary Aldermanbury	25	
St Mary Aldermary	33	
St Mary le Bow	31	
St Mary Bothaw	5	
St Mary Colechurch	2	
St Mary Hill	30	
St Mary Magd. Milk-ſtr.	0	
St Mary Mag. Old Fiſh-ſtr.	42	
St Mary Mounthaw	5	
St Mary Somerſet	33	
St Mary Staining	17	
St Mary Woolchurch	0	
St Mary Woolnoth	29	
St Matthew Friday-ſtreet	17	
St Michael Baſſiſhaw	35	
St Michael Cornhill	39	
St Michael Crooked-lane	35	
St Michael Queenhithe	35	
St Michael Querne	25	
St Michael Royal	7	
St Michael Wood-ſtreet	11	
St Mildred Bread-ſtreet	29	
St Mildred Poultry	43	
St Nicholas Acons	1	
St Nicholas Coleabby	15	
St Nicholas Olave	14	
St Olave Hart-ſtreet	63	
St Olave Jewry	18	
St Olave Silver-ſtreet	36	
St Pancras Soper-lane	11	
St Peter Cheap	12	
St Peter Cornhill	30	
St Peter Paul's Wharf	20	
St Peter Poor	34	
St Stephen Coleman-ſtreet	124	
St Stephen Walbrook	17	
St Swithin	24	
St Thomas Apoſtle	39	
Trinity Pariſh	19	
St Vedaſt, alias Foſter	42	

Chriſtened in the ninety-ſeven Pariſhes within the Walls 2070 Buried 3124 Plague 0

St Andrew Holborn	871	St Botolph Aldgate	780	St Saviour Southwark	628
St Bartholomew Great	76	St Botolph Biſhopſgate	558	St Sepulchre's Pariſh	728
St Bartholomew Leſs	37	St Dunſtan Weſt	297	St Thomas Southwark	86
St Bride's Pariſh	356	St George Southwark	382	Trinity Minories	18
Bridewell Precinct	26	St Giles Cripplegate	1502	At the Peſt-houſe	0
St Botolph Alderſgate	213	St Olave Southwark	825		

Chriſtened in the ſixteen Pariſhes without the Walls 4701 Buried 7383 Plague 0

1688.

Chriſt Church —— —161	St Katherine by the Tower211	St Mary Newington ——270
St Dunſtan at Stepney—2226	Lambeth Pariſh ——306	St Mary Whitechapel—1073
St Giles in the Fields —1375	St Leonard Shoreditch—487	St Paul Shadwell ——391
St James Clerkenwell —391	St Mary Iſlington — —162	Rotherhith Pariſh — —169
St John at Hackney——122	St Magdalen Bermondſey484	

Chriſtened in the fourteen Out Pariſhes in Middleſex and Surrey 4666
Buried 7828 Plague 0

St Ann Weſtminſter - —432	St Margaret Weſtminſter937	St Mary Savoy — —— 99
St Clement Danes ——567	St Martin in the Fields 1394	St Paul Covent Garden 195
St James Weſtminſter —962		

Chriſtened in the ſeven Pariſhes in the City and Liberties of Weſtminſter 3151
Buried 4586 Plague 0

DISEASES and CASUALTIES.

Abortive and Stillborn 651	Exceſſive Drinking —— 1	Palſy —— —— — 19
Aged and Bedridden1382	Executed —— —— 17	Pleuriſy —— —— 15
Ague and Fever —— —3196	Falling Sickneſs —— — 2	Poiſoned — —— — 2
Apoplexy and Suddenly— 119	Flox, Small Pox and Meaſles1318	Quinſy —— —— — 9
Bleeding, Bloody Flux, and Flux — 26	Found dead in the Streets, &c. 14	Rickets —— —— 346
	French Pox —— —— 76	Riſing of the Lights —— 89
Burnt and Scalded — — 3	Frighted —— —— 2	Scurvy —— —— 55
Burſten and Rupture —— 24	Gangrene and Fiſtula —— 62	Shot —— —— —— 2
Calenture —— —— 2	Gout and Sciatica — — 22	Smothered and Stifled — 2
Cancer —— — —— 54	Grief —— — —— 4	Sores, Ulcers, and bruiſed broken Limbs 80
Canker and Thruſh — — 53	Griping in the Guts — —2393	
Childbed —— —— 355	Hang'd and made away themſelves — 20	Spleen —— — —— 1
Chincough, Cold, and Cough — 5		Spotted Fever and Purples 139
	Head-ach and Megrims— 5	St Anthony's Fire —— 6
Chriſomes and Infants —— 209	Headmouldſhot — —— 15	Stone —— — —— 51
Colick and Wind — —— 25	Jaundies —— —— 83	Stopping of the Stomach 398
Conſumption and Tiſſick 3867	Impoſthume — — —— 77	Strangury —— —— 5
Convulſion —— ——4438	Kill'd by ſeveral Accidents 97	Surfeit —— — —— 330
Diabetes —— —— 4	Leproſy —— — — 1	Teeth —— ——1497
Diſtracted and Lunatick— 26	Lethargy —— —— 2	Vomiting — — —— 10
Dropſy and Tympany —— 842	Livergrown — — —— 31	Wen —— —— 1
Drowned — — —— 66	Murdered — — —— 30	Worms —— —— 40
Evil —— —— 100	Overlaid —— —— 105	

CHRISTENED	Males — 7487	BURIED	Males — 11763	Of the Plague	0
	Females 7101		Females 11158		
	In all — 14588		In all — 22921		

Increaſed in the Burials this Year 1461

A General

1689.

A General BILL of all the Chriſtenings and Burials,

From the 11th of December 1688, to the 17th of December 1689.

According to the Report made to the King and Queen their moſt excellent Majeſties,
By the Company of Pariſh Clerks of LONDON, &c.

	Bur. Pl.
St ALBAN Wood-ſtreet	25
Alhallows Barkin	97
Alhallows Bread-ſtreet	24
Alhallows Great	61
Alhallows Honey-lane	0
Alhallows Leſs	15
Alhallows Lombard-ſtreet	25
Alhallows Staining	39
Alhallows the Wall	81
St Alphage	42
St Andrew Hubbard	20
St Andrew Underſhaft	50
St Andrew Wardrobe	75
St Ann Alderſgate	42
St Ann Black Friars	118
St Antholin's Pariſh	14
St Auſtin's Pariſh	25
St Bartholomew Exchange	20
St Bennet Fink	18
St Bennet Gracechurch	13
St Bennet Paul's Wharf	52
St Bennet Sherehog	3
St Botolph Billingſgate	14
Chriſt Church	133
St Chriſtopher	11
St Clement Eaſtcheap	19
St Dionis Backchurch	31
St Dunſtan Eaſt	110
St Edmund Lombard-ſtr.	32
St Ethelborough	22
St Faith's	44
St Gabriel Fenchurch	9
St George Botolph-lane	14
St Gregory by St Paul's	70
St Helen's	46
St James Duke's Place	52
St James Garlickhithe	58
St John Baptiſt	20
St John Evangeliſt	10
St John Zachary	17
St Katherine Coleman	45
St Katherine Creechurch	77
St Laurence Jewry	67
St Laurence Pountney	18
St Leonard Eaſtcheap	9
St Leonard Foſter-lane	30
St Magnus Pariſh	45
St Margaret Lothbury	30
St Margaret Moſes	3
St Margaret New Fiſh-ſtr.	0
St Margaret Pattons	15
St Martin Ironmonger-lane	5
St Martin Ludgate	44
St Martin Orgars	18
St Martin Outwich	6
St Martin Vintrey	52
St Mary Abchurch	31
St Mary Aldermanbury	34
St Mary Aldermary	34
St Mary le Bow	23
St Mary Bothaw	5
St Mary Colechurch	3
St Mary Hill	36
St Mary Magd. Milk-ſtr.	0
St Mary Mag. Old Fiſh-ſtr.	41
St Mary Mounthaw	10
St Mary Somerſet	38
St Mary Staining	10
St Mary Woolchurch	1
St Mary Woolnoth	26
St Matthew Friday-ſtreet	26
St Michael Baſſiſhaw	21
St Michael Cornhill	35
St Michael Crooked-lane	27
St Michael Queenhithe	36
St Michael Querne	11
St Michael Royal	10
St Michael Wood-ſtreet	13
St Mildred Bread-ſtreet	23
St Mildred Poultry	28
St Nicholas Acons	2
St Nicholas Coleabby	17
St Nicholas Olave	6
St Olave Hart-ſtreet	61
St Olave Jewry	19
St Olave Silver-ſtreet	32
St Pancras Soper-lane	7
St Peter Cheap	10
St Peter Cornhill	27
St Peter Paul's Wharf	17
St Peter Poor	29
St Stephen Coleman-ſtreet	137
St Stephen Walbrook	15
St Swithin	31
St Thomas Apoſtle	20
Trinity Pariſh	15
St Vedaſt, alias Foſter	33

Chriſtened in the ninety-ſeven Pariſhes within the Walls 2079 Buried 3035 Plague 0

St Andrew Holborn	961
St Bartholomew Great	83
St Bartholomew Leſs	47
St Bride's Pariſh	358
Bridewell Precinct	15
St Botolph Alderſgate	227
St Botolph Aldgate	771
St Botolph Biſhopſgate	603
St Dunſtan Weſt	279
St George Southwark	327
St Giles Cripplegate	1530
St Olave Southwark	757
St Saviour Southwark	655
St Sepulchre's Pariſh	747
St Thomas Southwark	81
Trinity Minories	36
At the Peſt-houſe	0

Chriſtened in the ſixteen Pariſhes without the Walls 4705 Buried 7477 Plague 0

Chriſt Church — ——171	St Katherine by the Tower 242	St Mary Newington ——271
St Dunſtan at Stepney—2187	Lambeth Pariſh — ——299	St Mary Whitechapel—1128
St Giles in the Fields —1515	St Leonard Shoreditch —556	St Paul Shadwell ——454
St James Clerkenwell —454	St Mary Iſlington — —111	Rotherhith Pariſh —— 139
St John at Hackney ——130	St Magdalen Bermondſey 454	

Chriſtened in the fourteen Out Pariſhes in Middleſex and Surrey 4650
Buried 8132 Plague 0

St Ann Weſtminſter - —455	St Margaret Weſtminſt. 1044	St Mary Savoy —— 124
St Clement Danes — —556	St Martin in the Fields 1454	St Paul Covent Garden 210
St James Weſtminſter 1015		

Chriſtened in the ſeven Pariſhes in the City and Liberties of Weſtminſter 3337
Buried 4858 Plague 0

DISEASES and CASUALTIES.

Abortive and Stillborn 635	Executed —— — —— 12	Pleuriſy —— —— 9
Aged and Bedridden 1242	Falling Sickneſs —— — 1	Poiſoned —— —— 2
Ague and Fever — ——3313	Flox, Small Pox and Meaſles 1389	Quinſy —— —— 13
Apoplexy and Suddenly— 106	Found dead in the Streets, &c. 16	Rheumatiſm —— —— 1
Bleeding, Bloody Flux, and Flux — 20	French Pox —— —— 111	Rickets —— —— 356
Burnt and Scalded — — 9	Gangrene and Fiſtula—— 60	Riſing of the Lights —— 88
Burſten and Rupture —— 22	Gout and Sciatica —— 10	Scurvy —— —— 63
Calenture —— —— 2	Grief —— — —— 5	Shot —— —— 14
Cancer, Canker and Thruſh 122	Griping in the Guts — —2804	Smothered —— —— 2
Childbed —— — —— 316	Hang'd and made away themſelves — 10	Sores, Ulcers, bruiſed and broken Limbs — 77
Chriſomes and Infants —— 229	Head-ach and Megrims— 4	Spleen —— —— —— 7
Colick and Wind —— —— 51	Headmouldſhot — — 13	Spotted Fever and Purples 129
Conſumption and Tiſſick 3981	Jaundies —— —— 66	St Anthony's Fire —— 14
Convulſion —— ——4452	Impoſthume —— —— 65	Stabbed and Wounded — 2
Cough —— — —— 1	Kill'd by ſeveral Accidents 105	Starved — — —— 1
Cut of the Stone and Stone 50	Leproſy and Scald Head 2	Stopping of the Stomach 425
Diabetes —— —— 1	Lethargy —— — — 9	Strangury —— —— 4
Diſtracted and Lunatick— 22	Livergrown —— —— 13	Surfeit —— —— —— 327
Dropſy and Tympany — 971	Murdered —— —— 18	Teeth —— — —1390
Drowned —— —— 71	Overlaid —— —— 109	Vomiting —— —— 10
Evil —— —— 66	Palſy —— — —— 17	Worms —— —— 42
Exceſſive Drinking —— 5		

CHRISTENED	Males — 7604 Females 7167 In all 14771	BURIED	Males — 12374 Females 11128 In all — 23502	Of the Plague 0

Increaſed in the Burials this Year 581

A General

1690.

A General BILL of all the Chriſtenings and Burials,

From the 17th of December 1689, to the 16th of December 1690.

According to the Report made to the King and Queen their moſt excellent Majeſties,
By the Company of Pariſh Clerks of LONDON, &c.

	Bur. Pl.
St ALBAN Wood-ſtreet	25
Alhallows Barkin	123
Alhallows Bread-ſtreet	13
Alhallows Great	75
Alhallows Honey-lane	0
Alhallows Leſs	25
Alhallows Lombard-ſtreet	28
Alhallows Staining	20
Alhallows the Wall	77
St Alphage	31
St Andrew Hubbard	19
St Andrew Underſhaft	41
St Andrew Wardrobe	51
St Ann Alderſgate	31
St Ann Black Friars	149
St Antholin's Pariſh	19
St Auſtin's Pariſh	20
St Bartholomew Exchange	20
St Bennet Fink	20
St Bennet Gracechurch	13
St Bennet Paul's Wharf	35
St Bennet Sherehog	1
St Botolph Billingſgate	10
Chriſt Church	93
St Chriſtopher	24
St Clement Eaſtcheap	13
St Dionis Backchurch	40
St Dunſtan Eaſt	107
St Edmund Lombard-ſtr.	26
St Ethelborough	30
St Faith's	38
St Gabriel Fenchurch	11
St George Botolph-lane	14
St Gregory by St Paul's	67
St Helen's	39
St James Duke's Place	28
St James Garlickhithe	45
St John Baptiſt	21
St John Evangeliſt	8
St John Zachary	19
St Katherine Coleman	45
St Katherine Creechurch	69
St Laurence Jewry	45
St Laurence Pountney	16
St Leonard Eaſtcheap	4
St Leonard Foſter-lane	57
St Magnus Pariſh	40
St Margaret Lothbury	34
St Margaret Moſes	7
St Margaret New Fiſh-ſtr.	0
St Margaret Pattons	14
St Martin Ironmonger-lane	4
St Martin Ludgate	49
St Martin Orgars	14
St Martin Outwich	18
St Martin Vintrey	44
St Mary Abchurch	24
St Mary Aldermanbury	32
St Mary Aldermary	24
St Mary le Bow	22
St Mary Bothaw	9
St Mary Colechurch	4
St Mary Hill	23
St Mary Magd. Milk-ſtr.	0
St Mary Mag. Old Fiſh-ſtr.	40
St Mary Mounthaw	14
St Mary Somerſet	24
St Mary Staining	16
St Mary Woolchurch	0
St Mary Woolnoth	34
St Matthew Friday-ſtreet	9
St Michael Baſſiſhaw	27
St Michael Cornhill	23
St Michael Crooked-lane	41
St Michael Queenhithe	33
St Michael Querne	11
St Michael Royal	17
St Michael Wood-ſtreet	13
St Mildred Bread-ſtreet	13
St Mildred Poultry	30
St Nicholas Acons	4
St Nicholas Coleabby	17
St Nicholas Olave	12
St Olave Hart-ſtreet	48
St Olave Jewry	13
St Olave Silver-ſtreet	23
St Pancras Soper-lane	13
St Peter Cheap	9
St Peter Cornhill	43
St Peter Paul's Wharf	15
St Peter Poor	26
St Stephen Coleman-ſtreet	146
St Stephen Walbrook	18
St Swithin	31
St Thomas Apoſtle	22
Trinity Pariſh	17
St Vedaſt, alias Foſter	38
Chriſtened in the ninety-ſeven Pariſhes within the Walls	2228
Buried	2907
Plague	0
St Andrew Holborn	915
St Bartholomew Great	70
St Bartholomew Leſs	33
St Bride's Pariſh	357
Bridewell Precinct	29
St Botolph Alderſgate	170
St Botolph Aldgate	667
St Botolph Biſhopſgate	542
St Dunſtan Weſt	277
St George Southwark	400
St Giles Cripplegate	1325
St Olave Southwark	739
St Saviour Southwark	582
St Sepulchre's Pariſh	653
St Thomas Southwark	91
Trinity Minories	19
At the Peſt-houſe	0
Chriſtened in the ſixteen Pariſhes without the Walls	4827
Buried	6869
Plague	0

Chriſt Church — ——139	St Katherine by the Tower200	St Mary Newington ——298
St Dunſtan at Stepney—1872	Lambeth Pariſh — ——290	St Mary Whitechapel—1019
St Giles in the Fields —1274	St Leonard Shoreditch —513	St Paul Shadwell ——445
St James Clerkenwell —383	St Mary Iſlington — — 94	Rotherhith Pariſh — —167
St John at Hackney——100	St Magdalen Bermondſey 450	

Chriſtened in the fourteen Out Pariſhes in Middleſex and Surrey 4811
Buried 7244 Plague 0

St Ann Weſtminſter - —410	St Margaret Weſtminſter 931	St Mary Savoy —— 100
St Clement Danes ——537	St Martin in the Fields 1358	St Paul Covent Garden 197
St James Weſtminſter —908		

Chriſtened in the ſeven Pariſhes in the City and Liberties of Weſtminſter 3345
Buried 4441 Plague 0

DISEASES and CASUALTIES.

Abortive and Stillborn 568	Falling Sickneſs — —— 1	Pleuriſy —— —— 14
Aged and Bedridden1365	Flox, Small Pox and Meaſles 778	Poiſoned —— —— 1
Ague and Fever —— —3350	Found dead in the Streets,&c. 9	Quinſy —— —— 13
Apoplexy and Suddenly— 106	French Pox —— — — 93	Rheumatiſm — —— 7
Bleeding, Bloody Flux, and Flux — 23	Gangrene and Fiſtula—— 53	Rickets —— —— 334
	Gout and Sciatica —— 30	Riſing of the Lights —— 90
Burnt and Scalded — — 7	Grief —— —— —— 12	Scurvy —— — — — 73
Burſten and Rupture —— 28	Griping in the Guts — —2269	Shot —— — —— 7
Calenture —— —— 1	Hanged and made away themſelves — 23	Smothered —— —— 8
Cancer, Canker and Thruſh 118		Sores and Ulcers —— 69
Childbed —— — — 236	Head-ach and Megrims— 6	Spleen —— —— 1
Chriſomes and Infants — 221	Headmouldſhot —— 6	Spotted Fever and Purples 203
Colick and Wind —— 51	Jaundies —— — —— 74	St Anthony's Fire —— 17
Conſumption and Tiſſick 3783	Impoſthume — —— — 68	Stabbed — — —— 3
Convulſion —— — —3830	Killed by ſeveral Accidents 72	Stone —— — —— 50
Cough and Chincough — 10	Leproſy —— —— 1	Stopping in the Stomach 549
Diabetes —— —— 4	Lethargy —— — —— 5	Strangury —— — —— 2
Diſtracted and Lunatick— 24	Livergrown —— —— 12	Surfeit —— — —— 316
Dropſy and Tympany - — 943	Murdered —— — —— 19	Teeth — — — —1145
Drowned —— —— 72	Overlaid —— —— 125	Vomiting —— —— 3
Evil —— —— —— 82	Palſy —— — —— 20	Worms —— —— 29
Exceſſive Drinking —— 2	Planet-ſtruck —— —— 1	Wounded —— —— 4
Executed — — —— 22		

CHRISTENED { Males — 7909 / Females 7302 / In all — 15211 } | BURIED { Males — 11144 / Females 10317 / In all — 21461 } Of the Plague 0

Decreaſed in the Burials this Year 2041

1691.

A General BILL of all the Chriſtenings and Burials,

From the 16th of December 1690, to the 15th of December 1691.

According to the Report made to the King and Queen their moſt excellent Majeſties,
By the Company of Pariſh Clerks of LONDON, &c.

	Bur.	Pl.
St ALBAN Wood-ſtreet	23	
Alhallows Barkin	90	
Alhallows Bread-ſtreet	30	
Alhallows Great	71	
Alhallows Honey-lane	0	
Alhallows Leſs	20	
Alhallows Lombard-ſtreet	31	
Alhallows Staining	38	
Alhallows the Wall	48	
St Alphage	25	
St Andrew Hubbard	21	
St Andrew Underſhaft	48	
St Andrew Wardrobe	65	
St Ann Alderſgate	26	
St Ann Black Friars	150	
St Antholin's Pariſh	14	
St Auſtin's Pariſh	24	
St Bartholomew Exchange	10	
St Bennet Fink	16	
St Bennet Gracechurch	8	
St Bennet Paul's Wharf	46	
St Bennet Sherehog	3	
St Botolph Billingſgate	14	
Chriſt Church	99	
St Chriſtopher	14	
St Clement Eaſtcheap	17	
St Dionis Backchurch	24	
St Dunſtan Eaſt	90	
St Edmund Lombard-ſtr.	44	
St Ethelborough	24	
St Faith's	37	
St Gabriel Fenchurch	18	
St George Botolph-lane	13	
St Gregory by St Paul's	74	
St Helen's	29	
St James Duke's Place	38	
St James Garlickhithe	38	
St John Baptiſt	16	
St John Evangeliſt	8	
St John Zachary	10	
St Katherine Coleman	46	
St Katherine Creechurch	92	
St Laurence Jewry	60	
St Laurence Pountney	20	
St Leonard Eaſtcheap	9	
St Leonard Foſter-lane	37	
St Magnus Pariſh	39	
St Margaret Lothbury	33	
St Margaret Moſes	6	
St Margaret New Fiſh-ſtr.	0	
St Margaret Pattons	19	
St Martin Ironmonger-lane	7	
St Martin Ludgate	47	
St Martin Orgars	16	
St Martin Outwich	14	
St Martin Vintrey	53	
St Mary Abchurch	36	
St Mary Aldermanbury	36	
St Mary Aldermary	34	
St Mary le Bow	21	
St Mary Bothaw	8	
St Mary Colechurch	1	
St Mary Hill	29	
St Mary Magd. Milk-ſtr.	0	
St Mary Mag. Old Fiſh-ſtr.	33	
St Mary Mounthaw	16	
St Mary Somerſet	34	
St Mary Staining	16	
St Mary Woolchurch	0	
St Mary Woolnoth	33	
St Matthew Friday-ſtreet	16	
St Michael Baſſiſhaw	36	
St Michael Cornhill	24	
St Michael Crooked-lane	31	
St Michael Queenhithe	37	
St Michael Querne	15	
St Michael Royal	26	
St Michael Wood-ſtreet	23	
St Mildred Bread-ſtreet	17	
St Mildred Poultry	23	
St Nicholas Acons	0	
St Nicholas Coleabby	17	
St Nicholas Olave	9	
St Olave Hart-ſtreet	50	
St Olave Jewry	22	
St Olave Silver-ſtreet	26	
St Pancras Soper-lane	7	
St Peter Cheap	17	
St Peter Cornhill	35	
St Peter Paul's Wharf	15	
St Peter Poor	15	
St Stephen Coleman-ſtreet	136	
St Stephen Walbrook	19	
St Swithin	24	
St Thomas Apoſtle	17	
Trinity Pariſh	22	
St Vedaſt, alias Foſter	33	
Chriſtened in the ninety-ſeven Pariſhes within the Walls	2179	
Buried	2921	
Plague	0	

St Andrew Holborn	1005	St Botolph Aldgate	726	St Saviour Southwark	555
St Bartholomew Great	84	St Botolph Biſhopſgate	517	St Sepulchre's Pariſh	755
St Bartholomew Leſs	41	St Dunſtan Weſt	295	St Thomas Southwark	93
St Bride's Pariſh	360	St George Southwark	360	Trinity Minories	22
Bridewell Precinct	28	St Giles Cripplegate	1448	At the Peſt-houſe	0
St Botolph Alderſgate	196	St Olave Southwark	793		
Chriſtened in the ſixteen Pariſhes without the Walls	4906				
Buried	7278				
Plague	0				

1691.

Chriſt Church — ——167	St Katherine by the Tower 170	St Mary Newington ——279
St Dunſtan at Stepney—2064	Lambeth Pariſh — ——268	St Mary Whitechapel—1062
St Giles in the Fields —1436	St Leonard Shoreditch —528	St Paul Shadwell ———453
St James Clerkenwell —423	St Mary Iſlington ——114	Rotherhith Pariſh — —136
St John at Hackney ——101	St Magdalen Bermondſey 410	

Chriſtened in the fourteen Out Pariſhes in Middleſex and Surrey 4913
Buried 7611 Plague 0

St Ann Weſtminſter —508	St Margaret Weſtminſt. 1012	St Mary Savoy ——— 145
St Clement Danes — —508	St Martin in the Fields 1491	St Paul Covent Garden 188
St James Weſtminſter 1029		

Chriſtened in the ſeven Pariſhes in the City and Liberties of Weſtminſter 3056
Buried 4881 Plague 0

DISEASES and CASUALTIES.

Abortive and Stillborn 551	Flox, Small Pox and Meaſles 1241	Poiſoned —— —— 3
Aged and Bedridden 1677	Found dead in the Streets, &c. 11	Quinſy —— — —— 19
Ague and Fever —— —3490	French Pox —— —— 63	Rheumatiſm —— —— 2
Apoplexy and Suddenly— 111	Frighted —— —— 1	Rickets — — ——— 264
Bleeding, Bloody Flux, and Flux — 21	Gangrene and Fiſtula—— 52	Riſing of the Lights —— 88
	Gout and Sciatica ——— 20	Scurvy ——— — — 42
Burnt and Scalded ——— 4	Grief —— —— 12	Shot ——— ——— 4
Burſten and Rupture —— 31	Griping in the Guts — —2511	Smothered ——— —— 1
Calenture —— ——— 1	Hanged and made away themſelves — 10	Sores, Ulcers, bruiſed and broken Limbs 49
Cancer, Canker and Thruſh 140	Head-ach and Megrims— 6	Spleen —— ——— 4
Childbed —— ——— 245	Headmouldſhot — —— 19	Spotted Fever and Purples 193
Chriſomes and Infants —— 260	Jaundies —— ——— 75	St Anthony's Fire ——— 9
Colick and Wind ——— 33	Impoſthume —— —— 91	Stabbed and Wounded —— 4
Conſumption and Tiſſick 3928	Kill'd by ſeveral Accidents 56	Stone ——— ——— 59
Convulſion —— ——4132	Leproſy ——— ——— 1	Stopping in the Stomach 470
Cough and Chincough — 5	Lethargy —— — —— 3	Strangled — — ——— 1
Diabetes ——— —— 1	Livergrown —— — 4	Strangury ——— —— 1
Diſtracted and Lunatick— 19	Murdered — ——— 25	Surfeit ——— —— 248
Dropſy and Tympany —— 677	Overlaid ——— —— 85	Teeth —— — ——1320
Drowned —— ——— 81	Palſy ——— — — 14	Vomiting ——— —— 40
Evil —— —— —— 66	Pleuriſy ——— ——— 6	Worms —— — ——— 54
Executed —— ——— 36		
Falling Sickneſs — —— 1		

CHRISTENED	Males — 7662	BURIED	Males — 11491
	Females 7392		Females 11200
	In all — 15054		In all — 22691

Of the Plague 0

Increaſed in the Burials this Year 1230

1692.

A General BILL of all the Chriſtenings and Burials,

From the 15th of December 1691, to the 13th of December 1692.

According to the Report made to the King and Queen their moſt excellent Majeſties,
By the Company of Pariſh Clerks of LONDON, &c.

	Bur.	Pl.
St ALBAN Wood-ſtreet	17	
Alhallows Barkin	80	
Alhallows Bread-ſtreet	15	
Alhallows Great	56	
Alhallows Honey-lane	0	
Alhallows Leſs	15	
Alhallows Lombard-ſtreet	28	
Alhallows Staining	26	
Alhallows the Wall	63	
St Alphage	36	
St Andrew Hubbard	13	
St Andrew Underſhaft	44	
St Andrew Wardrobe	56	
St Ann Alderſgate	29	
St Ann Black Friars	131	
St Antholin's Pariſh	14	
St Auſtin's Pariſh	11	
St Bartholomew Exchange	19	
St Bennet Fink	20	
St Bennet Gracechurch	9	
St Bennet Paul's Wharf	51	
St Bennet Sherehog	4	
St Botolph Billingſgate	11	
Chriſt Church	93	
St Chriſtopher	13	
St Clement Eaſtcheap	10	
St Dionis Backchurch	29	
St Dunſtan Eaſt	77	
St Edmund Lombard-ſtr.	35	
St Ethelborough	28	
St Faith's	52	
St Gabriel Fenchurch	13	
St George Botolph-lane	10	
St Gregory by St Paul's	69	
St Helen's	39	
St James-Duke's Place	34	
St James Garlickhithe	39	
St John Baptiſt	22	
St John Evangeliſt	3	
St John Zachary	17	
St Katherine Coleman	41	
St Katherine Creechurch	55	
St Laurence Jewry	43	
St Laurence Pountney	13	
St Leonard Eaſtcheap	1	
St Leonard Foſter-lane	34	
St Magnus Pariſh	46	
St Margaret Lothbury	24	
St Margaret Moſes	2	
St Margaret New Fiſh-ſtr.	0	
St Margaret Pattons	14	
St Martin Ironmonger-lane	2	
St Martin Ludgate	30	
St Martin Orgars	24	
St Martin Outwich	12	
St Martin Vintrey	32	
St Mary Abchurch	31	
St Mary Aldermanbury	21	
St Mary Aldermary	27	
St Mary le Bow	18	
St Mary Bothaw	6	
St Mary Colechurch	1	
St Mary Hill	37	
St Mary Magd. Milk-ſtr.	0	
St Mary Mag. Old Fiſh-ſtr.	32	
St Mary Mounthaw	6	
St Mary Somerſet	33	
St Mary Staining	15	
St Mary Woolchurch	0	
St Mary Woolnoth	34	
St Matthew Friday-ſtreet	15	
St Michael Baſſiſhaw	27	
St Michael Cornhill	21	
St Michael Crooked-lane	31	
St Michael Queenhithe	24	
St Michael Querne	14	
St Michael Royal	19	
St Michael Wood-ſtreet	5	
St Mildred Bread-ſtreet	16	
St Mildred Poultry	29	
St Nicholas Acons	1	
St Nicholas Coleabby	14	
St Nicholas Olave	10	
St Olave Hart-ſtreet	53	
St Olave Jewry	10	
St Olave Silver-ſtreet	29	
St Pancras Soper-lane	5	
St Peter Cheap	14	
St Peter Cornhill	39	
St Peter Paul's Wharf	13	
St Peter Poor	30	
St Stephen Coleman-ſtreet	94	
St Stephen Walbrook	29	
St Swithin	25	
St Thomas Apoſtle	18	
Trinity Pariſh	15	
St Vedaſt, alias Foſter	31	

Chriſtened in the ninety-ſeven Pariſhes within the Walls 2136 Buried 2596 Plague 0

St Andrew Holborn	871	St Botolph Aldgate	713	St Saviour Southwark	535
St Bartholomew Great	73	St Botolph Biſhopſgate	527	St Sepulchre's Pariſh	598
St Bartholomew Leſs	27	St Dunſtan Weſt	262	St Thomas Southwark	87
St Bride's Pariſh	365	St George Southwark	332	Trinity Minories	23
Bridewell Precinct	27	St Giles Cripplegate	1246	At the Peſt-houſe	0
St Botolph Alderſgate	200	St Olave Southwark	785		

Chriſtened in the ſixteen Pariſhes without the Walls 4865 Buried 6671 Plague 0

1692.

Chriſt Church —— —142	St Katherine by the Tower188	St Mary Newington——232
St Dunſtan at Stepney—2051	Lambeth Pariſh ——250	St Mary Whitechapel —983
St Giles in the Fields —1353	St Leonard Shoreditch—498	St Paul Shadwell ——430
St James Clerkenwell —353	St Mary Iſlington — —122	Rotherhith Pariſh — —137
St John at Hackney—— 93	St Magdalen Bermondſey402	

Chriſtened in the fourteen Out Pariſhes in Middleſex and Surrey 4881
Buried 7234 Plague 0

St Ann Weſtminſter - —462	St Margaret Weſtminſter907	St Mary Savoy — ——141
St Clement Danes ——473	St Martin in the Fields 1323	St Paul Covent Garden 193
St James Weſtminſter —874		

Chriſtened in the ſeven Pariſhes in the City and Liberties of Weſtminſter 3036
Buried 4373 Plague 0

DISEASES and CASUALTIES.

Abortive and Stillborn 521	Exceſſive Drinking —— 3	Palſy —— —— — 17
Aged and Bedridden1412	Executed —— —— 18	Pleuriſy —— —— 16
Ague and Fever —— —3205	Falling Sickneſs —— — 1	Poiſoned — — —— 3
Apoplexy and Suddenly— 104	Flox, Small Pox and Meaſles1592	Quinſy —— —— — 5
Bleeding, Bloody Flux, and Flux — 21	Found dead in the Streets,&c. 5	Rheumatiſm — —— 7
	French Pox —— —— 54	Rickets —— —— 276
Burnt and Scalded — — 11	Frighted —— —— 1	Riſing of the Lights —— 112
Burſten and Rupture —— 36	Gangrene and Fiſtula —— 34	Scurvy —— —— 45
Calenture —— —— 3	Gout and Sciatica — — 18	Shot —— —— —— 5
Cancer, Canker and Thruſh 141	Grief —— — —— 8	Sores and Ulcers —— 44
Childbed —— —— 218	Griping in the Guts — —1756	Spleen —— — —— 1
Chriſomes and Infants —— 240	Hang'd and made away themſelves — 24	Spotted Fever and Purples 161
Colick and Wind — —— 36		St Anthony's Fire —— 7
Conſumption and Tiſſick 3512	Head-ach and Megrims— 4	Stabbed and Wounded — 7
Convulſion —— ——3942	Headmouldſhot — —— 11	Stopping in the Stomach 468
Cough, Chincough and Cold — 6	Jaundies —— —— 71	Strangled —— —— 1
	Impoſthume — — —— 73	Strangury —— —— 8
Cut of the Stone and Stone 66	Kill'd by ſeveral Accidents 70	Suffocated — —— 1
Diſtracted and Lunatick— 23	Leproſy —— — — 1	Surfeit —— — —— 197
Dropſy and Tympany —— 671	Lethargy —— —— 3	Teeth —— ——1288
Drowned —— — — 43	Livergrown —— — — 7	Vomiting — — —— 2
Eaten up by Lice —— 1	Murdered — — —— 19	Worms —— —— 55
Evil —— —— 77	Overlaid —— —— 86	

CHRISTENED { Males — 7602, Females 7316, In all — 14918 } | BURIED { Males — 10651, Females 10223, In all — 20874 } Of the Plague 0

Decreaſed in the Burials this Year 1817

A General

1693.

A General BILL of all the Chriſtenings and Burials,

From the 13th of December 1692, to the 19th of December 1693.

According to the Report made to the King and Queen their moſt excellent Majeſties,
By the Company of Pariſh Clerks of LONDON, &c.

	Bur. Pl.
St ALBAN Wood-ſtreet	31
Alhallows Barkin	80
Alhallows Bread-ſtreet	25
Alhallows Great	39
Alhallows Honey-lane	0
Alhallows Leſs	18
Alhallows Lombard-ſtreet	32
Alhallows Staining	40
Alhallows the Wall	68
St Alphage	37
St Andrew Hubbard	8
St Andrew Underſhaft	46
St Andrew Wardrobe	42
St Ann Alderſgate	47
St Ann Black Friars	129
St Antholin's Pariſh	19
St Auſtin's Pariſh	16
St Bartholomew Exchange	22
St Bennet Fink	20
St Bennet Gracechurch	8
St Bennet Paul's Wharf	44
St Bennet Sherehog	5
St Botolph Billingſgate	10
Chriſt Church	104
St Chriſtopher	12
St Clement Eaſtcheap	13
St Dionis Backchurch	33
St Dunſtan Eaſt	69
St Edmund Lombard-ſtr.	39
St Ethelborough	34
St Faith's	48
St Gabriel Fenchurch	13
St George Botolph-lane	15
St Gregory by St Paul's	89
St Helen's	29
St James Duke's Place	21
St James Garlickhithe	35
St John Baptiſt	23
St John Evangeliſt	5
St John Zachary	15
St Katherine Coleman	42
St Katherine Creechurch	65
St Laurence Jewry	60
St Laurence Pountney	15
St Leonard Eaſtcheap	9
St Leonard Foſter-lane	40
St Magnus Pariſh	32
St Margaret Lothbury	31
St Margaret Moſes	6
St Margaret New Fiſh-ſtr.	0
St Margaret Pattons	17
St Martin Ironmonger-lane	6
St Martin Ludgate	43
St Martin Orgars	18
St Martin Outwich	16
St Martin Vintrey	42
St Mary Abchurch	29
St Mary Aldermanbury	21
St Mary Aldermary	31
St Mary le Bow	21
St Mary Bothaw	4
St Mary Colechurch	0
St Mary Hill	27
St Mary Magd. Milk-ſtr.	0
St Mary Mag. Old Fiſh-ſtr.	33
St Mary Mounthaw	9
St Mary Somerſet	26
St Mary Staining	14
St Mary Woolchurch	0
St Mary Woolnoth	42
St Matthew Friday-ſtreet	20
St Michael Baſſiſhaw	36
St Michael Cornhill	30
St Michael Crooked-lane	29
St Michael Queenhithe	36
St Michael Querne	18
St Michael Royal	20
St Michael Wood-ſtreet	17
St Mildred Bread-ſtreet	6
St Mildred Poultry	20
St Nicholas Acons	1
St Nicholas Coleabby	17
St Nicholas Olave	14
St Olave Hart-ſtreet	52
St Olave Jewry	14
St Olave Silver-ſtreet	34
St Pancras Soper-lane	7
St Peter Cheap	10
St Peter Cornhill	30
St Peter Paul's Wharf	8
St Peter Poor	21
St Stephen Coleman-ſtreet	90
St Stephen Walbrook	28
St Swithin	17
St Thomas Apoſtle	20
Trinity Pariſh	12
St Vedaſt, alias Foſter	41

Chriſtened in the ninety-ſeven Pariſhes within the Walls 2106 Buried 2740 Plague 0

St Andrew Holborn	940
St Bartholomew Great	78
St Bartholomew Leſs	35
St Bride's Pariſh	307
Bridewell Precinct	33
St Botolph Alderſgate	177
St Botolph Aldgate	555
St Botolph Biſhopſgate	499
St Dunſtan Weſt	242
St George Southwark	402
St Giles Cripplegate	1342
St Olave Southwark	741
St Saviour Southwark	567
St Sepulchre's Pariſh	543
St Thomas Southwark	96
Trinity Minories	25
At the Peſt-houſe	0

Chriſtened in the ſixteen Pariſhes without the Walls 5050 Buried 6582 Plague 0

1693.

Chriſt Church — ——134	St Katherine by the Tower 181	St Mary Newington ——249
St Dunſtan at Stepney—2024	Lambeth Pariſh — ——306	St Mary Whitechapel —1048
St Giles in the Fields —1209	St Leonard Shoreditch —484	St Paul Shadwell ——428
St James Clerkenwell —393	St Mary Iſlington — —150	Rotherhith Pariſh ——152
St John at Hackney —— 77	St Magdalen Bermondſey 387	

Chriſtened in the fourteen Out Pariſhes in Middleſex and Surrey 5017
Buried 7222 Plague 0

St Ann Weſtminſter - —426	St Margaret Weſtminſter 934	St Mary Savoy —— 130
St Clement Danes — —445	St Martin in the Fields 1365	St Paul Covent Garden 193
St James Weſtminſter —922		

Chriſtened in the ſeven Pariſhes in the City and Liberties of Weſtminſter 2986
Buried 4415 Plague 0

DISEASES and CASUALTIES.

Abortive and Stillborn 599	Executed —— — —— 29	Pleuriſy —— —— 16
Aged and Bedridden 1262	Falling Sickneſs —— — 1	Poiſoned —— —— 3
Ague and Fever — ——3211	Flox, Small Pox and Meaſles 1164	Quinſy —— —— 3
Apoplexy and Suddenly— 87	Found dead in the Streets, &c. 10	Rheumatiſm —— —— 4
Bleeding, Bloody Flux, and Flux — 18	French Pox —— —— 95	Rickets —— —— 278
	Gangrene and Fiſtula—— 49	Riſing of the Lights —— 132
Burnt and Scalded — — 10	Gout and Sciatica —— 16	Scald Head —— —— 1
Burſten and Rupture —— 29	Grief —— — —— 15	Scurvy —— —— 36
Calenture —— —— 2	Griping in the Guts — —1871	Shot —— —— 5
Cancer, Canker and Thruſh 132	Hang'd and made away themſelves — 17	Smothered —— —— 2
Childbed —— — —— 224		Spleen —— —— —— 5
Chriſomes and Infants —— 235	Head-ach and Megrims— 3	Spotted Fever and Purples 199
Colick and Wind — —— 34	Headmouldſhot — — 11	St Anthony's Fire —— 4
Conſumption and Tiſſick 3547	Jaundies —— —— 66	Stabbed —— —— 1
Convulſion —— ——4218	Impoſthume —— —— 61	Stopping in the Stomach 485
Cough and Chincough — 7	Kill'd by ſeveral Accidents 85	Strangury —— —— 4
Cut of the Stone and Stone 75	Leproſy —— —— 1	Surfeit —— —— —— 187
Diabetes —— —— 1	Lethargy —— — — 9	Teeth —— — —1364
Diſtracted and Lunatick— 16	Livergrown —— —— 7	Ulcer —— —— 62
Dropſy and Tympany — 608	Murdered —— —— 19	Vomiting —— —— 8
Drowned —— —— 66	Overlaid —— —— 95	Worms —— —— 44
Evil —— —— 83	Palſy —— — —— 27	Wounded —— —— 1
Exceſſive Drinking —— 1		

CHRISTENED	Males — 7676	BURIED	Males — 10655	Of the Plague 0
	Females 7483		Females 10304	
	In all 15159		In all — 20959	

Increaſed in the Burials this Year 85

A General

1694.

A General BILL of all the Chriſtenings and Burials,

From the 19th of December 1693, to the 18th of December 1694.

According to the Report made to the King and Queen their moſt excellent Majeſties,
By the Company of Pariſh Clerks of LONDON, &c.

	Bur.	Pl.
St ALBAN Wood-ſtreet	31	
Alhallows Barkin	81	
Alhallows Bread-ſtreet	16	
Alhallows Great	55	
Alhallows Honey-lane	0	
Alhallows Leſs	18	
Alhallows Lombard-ſtreet	28	
Alhallows Staining	44	
Alhallows the Wall	93	
St Alphage	34	
St Andrew Hubbard	25	
St Andrew Underſhaft	62	
St Andrew Wardrobe	64	
St Ann Alderſgate	35	
St Ann Black Friars	132	
St Antholin's Pariſh	17	
St Auſtin's Pariſh	19	
St Bartholomew Exchange	28	
St Bennet Fink	32	
St Bennet Gracechurch	14	
St Bennet Paul's Wharf	45	
St Bennet Sherehog	3	
St Botolph Billingſgate	11	
Chriſt Church	111	
St Chriſtopher	12	
St Clement Eaſtcheap	22	
St Dionis Backchurch	31	
St Dunſtan Eaſt	101	
St Edmund Lombard-ſtr.	37	
St Ethelborough	41	
St Faith's	59	
St Gabriel Fenchurch	14	
St George Botolph-lane	12	
St Gregory by St Paul's	88	
St Helen's	25	
St James Duke's Place	38	
St James Garlickhithe	35	
St John Baptiſt	24	
St John Evangeliſt	4	
St John Zachary	12	
St Katherine Coleman	71	
St Katherine Creechurch	76	
St Laurence Jewry	65	
St Laurence Pountney	19	
St Leonard Eaſtcheap	9	
St Leonard Foſter-lane	57	
St Magnus Pariſh	44	
St Margaret Lothbury	31	
St Margaret Moſes	6	
St Margaret New Fiſh-ſtr.	2	
St Margaret Pattons	18	
St Martin Ironmonger-lane	9	
St Martin Ludgate	39	
St Martin Orgars	16	
St Martin Outwich	28	
St Martin Vintrey	28	
St Mary Abchurch	35	
St Mary Aldermanbury	39	
St Mary Aldermary	34	
St Mary le Bow	31	
St Mary Bothaw	2	
St Mary Colechurch	5	
St Mary Hill	37	
St Mary Magd. Milk-ſtr.	0	
St Mary Mag. Old Fiſh-ſtr.	28	
St Mary Mounthaw	11	
St Mary Somerſet	31	
St Mary Staining	16	
St Mary Woolchurch	0	
St Mary Woolnoth	30	
St Matthew Friday-ſtreet	15	
St Michael Baſſiſhaw	28	
St Michael Cornhill	24	
St Michael Crooked-lane	41	
St Michael Queenhithe	45	
St Michael Querne	18	
St Michael Royal	24	
St Michael Wood-ſtreet	17	
St Mildred Bread-ſtreet	19	
St Mildred Poultry	28	
St Nicholas Acons	4	
St Nicholas Coleabby	16	
St Nicholas Olave	8	
St Olave Hart-ſtreet	68	
St Olave Jewry	12	
St Olave Silver-ſtreet	40	
St Pancras Soper-lane	8	
St Peter Cheap	12	
St Peter Cornhill	46	
St Peter Paul's Wharf	17	
St Peter Poor	45	
St Stephen Coleman-ſtreet	108	
St Stephen Walbrook	20	
St Swithin	24	
St Thomas Apoſtle	27	
Trinity Pariſh	15	
St Vedaſt, alias Foſter	35	

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1951 Buried 3134 Plague 0

St Andrew Holborn	1105	St Botolph Aldgate	738	St Saviour Southwark	580
St Bartholomew Great	83	St Botolph Biſhopſgate	674	St Sepulchre's Pariſh	668
St Bartholomew Leſs	35	St Dunſtan Weſt	264	St Thomas Southwark	91
St Bride's Pariſh	383	St George Southwark	423	Trinity Minories	22
Bridewell Precinct	24	St Giles Cripplegate	1535	At the Peſt-houſe	0
St Botolph Alderſgate	235	St Olave Southwark	730		

Chriſtened in the ſixteen Pariſhes without the Walls 4488 Buried 7590 Plague 0

1694.

Chriſt Church — ——167	St John at Wapping—— 96	St Magdalen Bermondſey 453
St Dunſtan at Stepney—2298	St Katherine by the Tower120	St Mary Newington ——233
St Giles in the Fields —1490	Lambeth Pariſh — ——323	St Mary Whitechapel —937
St James Clerkenwell —438	St Leonard Shoreditch —516	St Paul Shadwell ———491
St John at Hackney—— 93	St Mary Iſlington — — 121	Rotherhith Pariſh — —159

Chriſtened in the fifteen Out Pariſhes in Middleſex and Surrey 4218
Buried 8035 Plague 0

St Ann Weſtminſter - —617	St Margaret Weſtminſt. 1057	St Mary Savoy ——— 160
St Clement Danes ——545	St Martin in the Fields 1643	St Paul Covent Garden 195
St James Weſtminſter 1124		

Chriſtened in the ſeven Pariſhes in the City and Liberties of Weſtminſter 2975
Buried 5341 Plague 0

DISEASES and CASUALTIES.

Abortive and Stillborn 519	Falling Sickneſs — —— 2	Poiſoned ——— —— 3
Aged and Bedridden1249	Flox, Small Pox and Meaſles1683	Quinſy ——— ——— 11
Ague and Fever —— —5036	Found dead in the Streets,&c. 14	Rheumatiſm — —— 7
Apoplexy and Suddenly— 89	French Pox —— — — 104	Rickets ——— ——— 358
Bleeding, Bloody Flux, and Flux — 25	Gangrene and Fiſtula—— 54	Riſing of the Lights —— 88
	Gout —— — ——— 9	Scurvy —— — — — 38
Burnt and Scalded — — 7	Grief —— ——— —— 10	Shot ——— — —— 2
Burſten and Rupture —— 20	Griping in the Guts — —1443	Smothered —— —— 2
Cancer, Canker and Thruſh 105	Hanged and made away themſelves — 17	Spleen ——— ——— 4
Childbed ——— — — 262		Spotted Fever and Purples 423
Chriſomes and Infants — 199	Head-ach and Megrims— 3	St Anthony's Fire ——— 12
Colick and Wind ——— 48	Headmouldſhot ——— 11	Starved — — —— 4
Conſumption and Tiſſick 3702	Jaundies —— — —— 73	Stopping in the Stomach 440
Convulſion ——— — —5024	Impoſthume — —— — 65	Strangury —— — —— 2
Cough and Chincough — 21	Killed by ſeveral Accidents 55	Surfeit —— — ——— 167
Cut of the Stone and Stone 42	Leproſy —— ——— 1	Teeth — — — —1445
Diabetes ——— —— 1	Lethargy —— — —— 2	Vapours ——— —— 2
Diſtracted and Lunatick— 20	Livergrown —— ——— 9	Ulcer ——— ——— 38
Dropſy and Tympany - — 778	Murdered —— — —— 11	Vomiting ——— —— 3
Drowned ——— ——— 61	Overlaid ——— —— 89	Water in the Head ——— 3
Evil —— —— —— 78	Palſy ——— — ——— 18	Worms ——— ——— 40
Executed — — ——— 40	Pleuriſy —— ——— 9	

CHRISTENED	Males — 6985 Females 6647 In all — 13632	BURIED	Males — 12107 Females 11993 In all — 24100

Of the Plague 0

Increaſed in the Burials this Year 3141

1695.

A General BILL of all the Chriſtenings and Burials,

From the 18th of December 1694, to the 17th of December 1695.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.	Pl.
St ALBAN Wood-ſtreet	15	
Alhallows Barkin	84	
Alhallows Bread-ſtreet	21	
Alhallows Great	51	
Alhallows Honey-lane	0	
Alhallows Leſs	14	
Alhallows Lombard-ſtreet	19	
Alhallows Staining	38	
Alhallows the Wall	57	
St Alphage	32	
St Andrew Hubbard	8	
St Andrew Underſhaft	47	
St Andrew Wardrobe	41	
St Ann Alderſgate	29	
St Ann Black Friars	124	
St Antholin's Pariſh	8	
St Auſtin's Pariſh	21	
St Bartholomew Exchange	22	
St Bennet Fink	20	
St Bennet Gracechurch	10	
St Bennet Paul's Wharf	46	
St Bennet Sherehog	1	
St Botolph Billingſgate	8	
Chriſt Church	98	
St Chriſtopher	13	
St Clement Eaſtcheap	18	
St Dionis Backchurch	28	
St Dunſtan Eaſt	68	
St Edmund Lombard-ſtr.	28	
St Ethelborough	18	
St Faith's	45	
St Gabriel Fenchurch	10	
St George Botolph-lane	9	
St Gregory by St Paul's	75	
St Helen's	25	
St James Duke's Place	19	
St James Garlickhithe	45	
St John Baptiſt	21	
St John Evangeliſt	5	
St John Zachary	12	
St Katherine Coleman	42	
St Katherine Creechurch	66	
St Laurence Jewry	45	
St Laurence Pountney	13	
St Leonard Eaſtcheap	7	
St Leonard Foſter-lane	41	
St Magnus Pariſh	31	
St Margaret Lothbury	23	
St Margaret Moſes	3	
St Margaret New Fiſh-ſtr.	0	
St Margaret Pattons	11	
St Martin Ironmonger-lane	3	
St Martin Ludgate	37	
St Martin Orgars	9	
St Martin Outwich	12	
St Martin Vintrey	35	
St Mary Abchurch	18	
St Mary Aldermanbury	27	
St Mary Aldermary	22	
St Mary le Bow	19	
St Mary Bothaw	4	
St Mary Colechurch	1	
St Mary Hill	34	
St Mary Magd. Milk-ſtr.	0	
St Mary Mag. Old Fiſh-ſtr.	23	
St Mary Mounthaw	6	
St Mary Somerſet	28	
St Mary Staining	17	
St Mary Woolchurch	3	
St Mary Woolnoth	31	
St Matthew Friday-ſtreet	14	
St Michael Baſſiſhaw	26	
St Michael Cornhill	26	
St Michael Crooked-lane	17	
St Michael Queenhithe	45	
St Michael Querne	13	
St Michael Royal	11	
St Michael Wood-ſtreet	12	
St Mildred Bread-ſtreet	11	
St Mildred Poultry	20	
St Nicholas Acons	6	
St Nicholas Coleabby	26	
St Nicholas Olave	7	
St Olave Hart-ſtreet	41	
St Olave Jewry	15	
St Olave Silver-ſtreet	26	
St Pancras Soper-lane	15	
St Peter Cheap	5	
St Peter Cornhill	28	
St Peter Paul's Wharf	16	
St Peter Poor	30	
St Stephen Coleman-ſtreet	91	
St Stephen Walbrook	21	
St Swithin	29	
St Thomas Apoſtle	20	
Trinity Pariſh	19	
St Vedaſt, alias Foſter	32	

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1970 Buried 2486 Plague 0

St Andrew Holborn	960	St Botolph Aldgate	508	St Saviour Southwark	479
St Bartholomew Great	61	St Botolph Biſhopſgate	483	St Sepulchre's Pariſh	589
St Bartholomew Leſs	22	St Dunſtan Weſt	187	St Thomas Southwark	73
St Bride's Pariſh	285	St George Southwark	295	Trinity Minories	15
Bridewell Precinct	24	St Giles Cripplegate	1180	At the Peſt-houſe	0
St Botolph Alderſgate	196	St Olave Southwark	628		

Chriſtened in the ſixteen Pariſhes without the Walls 4920 Buried 5985 Plague 0

Chriſt Church — ——142	St John at Wapping——221	St Magdalen Bermondſey 336
St Dunſtan at Stepney—1807	St Katherine by the Tower 174	St Mary Newington ——161
St Giles in the Fields —1169	Lambeth Pariſh — ——220	St Mary Whitechapel —646
St James Clerkenwell -—329	St Leonard Shoreditch —429	St Paul Shadwell ———361
St John at Hackney —— 92	St Mary Iſlington ——112	Rotherhith Pariſh — —133

Chriſtened in the fifteen Out Pariſhes in Middleſex and Surrey 4468
Buried 6332 Plague 0

St Ann Weſtminſter -—426	St Margaret Weſtminſt. 815	St Mary Savoy ——— 128
St Clement Danes — —468	St Martin in the Fields 1328	St Paul Covent Garden 203
St James Weſtminſter —876		

Chriſtened in the ſeven Pariſhes in the City and Liberties of Weſtminſter 2918
Buried 4244 Plague 0

DISEASES and CASUALTIES.

Abortive and Stillborn 613	Flox, Small Pox and Meaſles 784	Quinſy —— — —— 10
Aged and Bedridden 1025	Found dead in the Streets, &c. 15	Rheumatiſm —— —— 6
Ague and Fever —— —3019	French Pox —— —— 69	Rickets — — ——— 338
Apoplexy and Suddenly— 103	Gangrene and Fiſtula—— 38	Riſing of the Lights —— 84
Bleeding, Bloody Flux, and Flux — 10	Gout and Sciatica ——— 15	Scurvy ——— — — 25
	Grief —— —— 5	Shot ——— ——— 7
Burnt and Scalded ——— 6	Griping in the Guts — —1115	Smothered ——— —— 1
Burſten and Rupture —— 18	Hanged and made away themſelves — 25	Sores, Ulcers, &c. ——— 55
Calenture —— ——— 1		Spitting of Blood ——— 1
Cancer, Canker and Thruſh 105	Head-ach and Megrims— 2	Spleen —— ——— 2
Childbed —— ——— 250	Headmouldſhot — —— 9	Spotted Fever and Purples 105
Chriſomes and Infants -— 106	Jaundies —— ——— 55	St Anthony's Fire ——— 8
Colick and Wind ——— 58	Impoſthume —— —— 57	Starved ——— —— 1
Conſumption and Tiſſick 3181	Kill'd by ſeveral Accidents 60	Stopping in the Stomach 480
Convulſion —— ——4496	Leproſy and ſcald Head— 3	Surfeit ——— ——— 96
Cut of the Stone and Stone 41	Lethargy —— — —— 6	Teeth —— — ——1302
Diabetes and Strangury — 3	Livergrown —— — 20	Vapours and Mother —— 5
Diſtracted and Lunatick— 8	Murdered — ——— 12	Vomiting ——— ——— 4
Dropſy and Tympany -— 850	Overlaid ——— —— 81	Water in the Head ——— 2
Drowned —— ——— 46	Palſy ——— — — 22	Wen ——— ——— 1
Evil —— —— —— 58	Pleuriſy ——— ——— 18	Worms —— — ——— 76
Exceſſive Drinking ——— 1	Poiſoned ——— ——— 1	Wounded ——— ——— 1
Executed —— ——— 27		

CHRISTENED	Males — 7163 Females 6713 In all — 13876	BURIED	Males — 9639 Females 9408 In all — 19047

Of the Plague 0

Decreaſed in the Burials this Year 5053

1696.

A General BILL of all the Chriſtenings and Burials,

From the 17th of December 1695, to the 15th of December 1696.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.	Pl.
St ALBAN Wood-ſtreet	27	
Alhallows Barkin	93	
Alhallows Bread-ſtreet	26	
Alhallows Great	54	
Alhallows Honey-lane	0	
Alhallows Leſs	17	
Alhallows Lombard-ſtreet	10	
Alhallows Staining	28	
Alhallows the Wall	52	
St Alphage	24	
St Andrew Hubbard	19	
St Andrew Underſhaft	36	
St Andrew Wardrobe	40	
St Ann Alderſgate	35	
St Ann Black Friars	129	
St Antholin's Pariſh	13	
St Auſtin's Pariſh	11	
St Bartholomew Exchange	20	
St Bennet Fink	12	
St Bennet Gracechurch	19	
St Bennet Paul's Wharf	35	
St Bennet Sherehog	1	
St Botolph Billingſgate	13	
Chriſt Church	106	
St Chriſtopher	14	
St Clement Eaſtcheap	8	
St Dionis Backchurch	37	
St Dunſtan Eaſt	66	
St Edmund Lombard-ſtr.	22	
St Ethelborough	20	
St Faith's	50	
St Gabriel Fenchurch	9	
St George Botolph-lane	8	
St Gregory by St Paul's	65	
St Helen's	34	
St James Duke's Place	24	
St James Garlickhithe	40	
St John Baptiſt	22	
St John Evangeliſt	5	
St John Zachary	12	
St Katherine Coleman	40	
St Katherine Creechurch	61	
St Laurence Jewry	51	
St Laurence Pountney	9	
St Leonard Eaſtcheap	12	
St Leonard Foſter-lane	39	
St Magnus Pariſh	40	
St Margaret Lothbury	29	
St Margaret Moſes	5	
St Margaret New Fiſh-ſtr.	0	
St Margaret Pattons	16	
St Martin Ironmonger-lane	3	
St Martin Ludgate	34	
St Martin Orgars	13	
St Martin Outwich	13	
St Martin Vintrey	33	
St Mary Abchurch	27	
St Mary Aldermanbury	33	
St Mary Aldermary	30	
St Mary le Bow	31	
St Mary Bothaw	8	
St Mary Colechurch	1	
St Mary Hill	30	
St Mary Magd. Milk-ſtr.	0	
St MaryMag.Old Fiſh-ſtr.	36	
St Mary Mounthaw	13	
St Mary Somerſet	38	
St Mary Staining	16	
St Mary Woolchurch	0	
St Mary Woolnoth	29	
St Matthew Friday-ſtreet	15	
St Michael Baſſiſhaw	31	
St Michael Cornhill	24	
St Michael Crooked-lane	25	
St Michael Queenhithe	47	
St Michael Querne	10	
St Michael Royal	21	
St Michael Wood-ſtreet	11	
St Mildred Bread-ſtreet	17	
St Mildred Poultry	16	
St Nicholas Acons	5	
St Nicholas Coleabby	10	
St Nicholas Olave	7	
St Olave Hart-ſtreet	41	
St Olave Jewry	11	
St Olave Silver-ſtreet	27	
St Pancras Soper-lane	2	
St Peter Cheap	20	
St Peter Cornhill	35	
St Peter Paul's Wharf	14	
St Peter Poor	21	
St Stephen Coleman-ſtreet	95	
St Stephen Walbrook	16	
St Swithin	20	
St Thomas Apoſtle	11	
Trinity Pariſh	10	
St Vedaſt, alias Foſter	27	

Chriſtened in the ninety-ſeven Pariſhes within the Walls 2028 Buried 2534 Plague 0

St Andrew Holborn	933	St Botolph Aldgate	487	St Saviour Southwark	447
St Bartholomew Great	55	St Botolph Biſhopſgate	450	St Sepulchre's Pariſh	600
St Bartholomew Leſs	26	St Dunſtan Weſt	169	St Thomas Southwark	95
St Bride's Pariſh	300	St George Southwark	324	Trinity Minories	14
Bridewell Precinct	28	St Giles Cripplegate	1044	At the Peſt-houſe	0
St Botolph Alderſgate	209	St Olave Southwark	629		

Chriſtened in the ſixteen Pariſhes without the Walls 4795 Buried 5810 Plague 0

1696.

Chriſt Church —— —105	St John at Wapping——274	St Magdalen Bermondſey364
St Dunſtan at Stepney—1759	St Katherine by the Tower167	St Mary Newington——177
St Giles in the Fields —1093	Lambeth Pariſh ——226	St Mary Whitechapel —624
St James Clerkenwell —325	St Leonard Shoreditch—384	St Paul Shadwell ——367
St John at Hackney—— 82	St Mary Iſlington — —126	Rotherhith Pariſh — —145

Chriſtened in the fifteen Out Pariſhes in Middleſex and Surrey 4970
Buried 6218 Plague 0

St Ann Weſtminſter - —404	St Margaret Weſtminſter790	St Mary Savoy — ——120
St Clement Danes ——415	St Martin in the Fields 1228	St Paul Covent Garden 204
St James Weſtminſter —915		

Chriſtened in the ſeven Pariſhes in the City and Liberties of Weſtminſter 3068
Buried 4076 Plague 0

DISEASES and CASUALTIES.

Abortive and Stillborn 602	Evil —— —— 88	Overlaid —— —— 63
Aged and Bedridden 946	Exceſſive Drinking —— 1	Palſy —— —— — 17
Ague and Fever —— —2775	Executed —— —— 17	Pleuriſy —— —— 14
Apoplexy and Suddenly— 109	Flox, Small Pox and Meaſles 196	Poiſoned — — —— 3
Bleeding, Bloody Flux, and Flux — 13	Found dead in the Streets,&c. 12	Quinſy —— —— — 9
Burnt and Scalded — — 2	French Pox —— —— 76	Rheumatiſm — —— 16
Burſten and Rupture —— 36	Frighted —— —— 1	Rickets —— —— 426
Calenture —— —— 1	Gangrene and Fiſtula —— 37	Riſing of the Lights —— 117
Cancer, Canker and Thruſh 113	Gout and Sciatica — — 18	Scurvy —— —— 28
Childbed —— —— 232	Grief —— — —— 11	Shot —— —— —— 5
Chriſomes and Infants —— 102	Griping in the Guts — —1187	Sores and Ulcers —— 55
Colick and Wind — —— 78	Hang'd and made away themſelves — 21	Spleen —— — —— 2
Conſumption and Tiſſick 3471	Headmouldſhot — —— 10	Spotted Fever and Purples 102
Convulſion —— ——4480	Jaundies —— —— 69	St Anthony's Fire —— 7
Cough —— — —— 3	Impoſthume — — —— 50	Stopping in the Stomach 459
Cut of the Stone, Gravel and Stone — 49	Kill'd by ſeveral Accidents 48	Surfeit —— — —— 10
Diabetes —— —— 1	Leproſy and ſcald Head— 2	Teeth —— ——1225
Diſtracted and Lunatick— 4	Lethargy —— —— 11	Vomiting — — —— 3
Dropſy and Tympany —— 916	Livergrown —— — — 11	Water in the Head, Vapours and Megrims 11
Drowned —— — — 80	Murdered — — —— 19	Worms —— —— 75

CHRISTENED	Males — 7632	BURIED	Males — 9712	Of the Plague	0
	Females 7229		Females 8926		
	In all — 14861		In all — 18638		

Decreaſed in the Burials this Year 409

A General

1697.

A General BILL of all the Chriſtenings and Burials,

From the 15th of December 1696, to the 14th of December 1697.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.	Pl.
St ALBAN Wood-ſtreet	21	
Alhallows Barkin	99	
Alhallows Bread-ſtreet	22	
Alhallows Great	72	
Alhallows Honey-lane	0	
Alhallows Leſs	30	
Alhallows Lombard-ſtreet	36	
Alhallows Staining	29	
Alhallows the Wall	55	
St Alphage	43	
St Andrew Hubbard	14	
St Andrew Underſhaft	46	
St Andrew Wardrobe	42	
St Ann Alderſgate	28	
St Ann Black Friars	147	
St Antholin's Pariſh	11	
St Auſtin's Pariſh	23	
St Bartholomew Exchange	21	
St Bennet Fink	18	
St Bennet Gracechurch	20	
St Bennet Paul's Wharf	39	
St Bennet Sherehog	4	
St Botolph Billingſgate	13	
Chriſt Church	135	
St Chriſtopher	14	
St Clement Eaſtcheap	15	
St Dionis Backchurch	30	
St Dunſtan Eaſt	100	
St Edmund Lombard-ſtr.	30	
St Ethelborough	30	
St Faith's	31	
St Gabriel Fenchurch	9	
St George Botolph-lane	3	
St Gregory by St Paul's	85	
St Helen's	42	
St James Duke's Place	25	
St James Garlickhithe	45	
St John Baptiſt	26	
St John Evangeliſt	7	
St John Zachary	23	
St Katherine Coleman	51	
St Katherine Creechurch	78	
St Laurence Jewry	57	
St Laurence Pountney	17	
St Leonard Eaſtcheap	12	
St Leonard Foſter-lane	38	
St Magnus Pariſh	38	
St Margaret Lothbury	27	
St Margaret Moſes	5	
St Margaret New Fiſh-ſtr.	0	
St Margaret Pattons	16	
St Martin Ironmonger-lane	7	
St Martin Ludgate	36	
St Martin Orgars	24	
St Martin Outwich	8	
St Martin Vintrey	41	
St Mary Abchurch	21	
St Mary Aldermanbury	28	
St Mary Aldermary	28	
St Mary le Bow	18	
St Mary Bothaw	5	
St Mary Colechurch	3	
St Mary Hill	42	
St Mary Magd. Milk-ſtr.	0	
St Mary Mag. Old Fiſh-ſtr.	31	
St Mary Mounthaw	3	
St Mary Somerſet	33	
St Mary Staining	17	
St Mary Woolchurch	0	
St Mary Woolnoth	27	
St Matthew Friday-ſtreet	14	
St Michael Baſſiſhaw	36	
St Michael Cornhill	30	
St Michael Crooked-lane	38	
St Michael Queenhithe	53	
St Michael Querne	24	
St Michael Royal	16	
St Michael Wood-ſtreet	15	
St Mildred Bread-ſtreet	18	
St Mildred Poultry	25	
St Nicholas Acons	0	
St Nicholas Coleabby	16	
St Nicholas Olave	10	
St Olave Hart-ſtreet	53	
St Olave Jewry	14	
St Olave Silver-ſtreet	37	
St Pancras Soper-lane	7	
St Peter Cheap	18	
St Peter Cornhill	30	
St Peter Paul's Wharf	15	
St Peter Poor	26	
St Stephen Coleman-ſtreet	117	
St Stephen Walbrook	17	
St Swithin	29	
St Thomas Apoſtle	17	
Trinity Pariſh	18	
St Vedaſt, alias Foſter	18	

Chriſtened in the ninety-ſeven Pariſhes within the Walls 2113 Buried 2905 Plague 0

St Andrew Holborn	952	St Botolph Aldgate	610
St Bartholomew Great	77	St Botolph Biſhopſgate	535
St Bartholomew Leſs	26	St Dunſtan Weſt	222
St Bride's Pariſh	325	St George Southwark	342
Bridewell Precinct	32	St Giles Cripplegate	1295
St Botolph Alderſgate	166	St Olave Southwark	665
St Saviour Southwark	503		
St Sepulchre's Pariſh	605		
St Thomas Southwark	79		
Trinity Minories	17		
At the Peſt-houſe	0		

Chriſtened in the ſixteen Pariſhes without the Walls 5021 Buried 6451 Plague 0

1697.

Chriſt Church — ——128	St John at Wapping ——330	St Magdalen Bermondſey 397
St Dunſtan at Stepney—2008	St Katherine by the Tower 192	St Mary Newington ——185
St Giles in the Fields —1287	Lambeth Pariſh — ——210	St Mary Whitechapel —731
St James Clerkenwell —357	St Leonard Shoreditch —495	St Paul Shadwell ——432
St John at Hackney —— 94	St Mary Iſlington — — 73	Rotherhith Pariſh ——160

Chriſtened in the fifteen Out Pariſhes in Middleſex and Surrey 5355
Buried 7079 Plague 0

St Ann Weſtminſter - —507	St Margaret Weſtminſter 812	St Mary Savoy —— 124
St Clement Danes — —501	St Martin in the Fields 1436	St Paul Covent Garden 232
St James Weſtminſter —923		

Chriſtened in the ſeven Pariſhes in the City and Liberties of Weſtminſter 3340
Buried 4535 Plague 0

DISEASES and CASUALTIES.

Abortive and Stillborn 604	Executed —— — —— 31	Palſy —— — —— 27
Aged and Bedridden 1314	Flox, Small Pox and Meaſles 634	Planet-ſtruck —— —— 1
Ague and Fever — ——3111	Found dead in the Streets, &c. 19	Pleuriſy —— —— 42
Apoplexy and Suddenly— 117	French Pox —— —— 59	Poiſoned —— —— 2
Bleeding, Bloody Flux, and Flux — 16	Frighted —— —— 1	Quinſy —— —— 9
	Gangrene and Fiſtula—— 49	Rheumatiſm —— —— 12
Burnt and Scalded — — 6	Gout —— —— 16	Rickets —— —— 522
Burſten and Rupture —— 22	Grief —— — —— 5	Riſing of the Lights —— 133
Cancer, Canker and Thruſh 102	Griping in the Guts — —1136	Scurvy —— —— 17
Childbed —— — —— 293	Hang'd and made away themſelves — 21	Shot —— —— 8
Chriſomes and Infants —— 85		Spleen —— —— —— 6
Colick and Wind —— —— 91	Head-ach —— —— 1	Spotted Fever and Purples 137
Conſumption and Tiſſick 3820	Headmouldſhot — — 15	St Anthony's Fire —— 9
Convulſion —— ——4944	Jaundies —— —— 71	Stopping in the Stomach 658
Cough and Chincough —— 12	Impoſthume —— —— 55	Surfeit —— —— —— 101
Cut of the Stone and Stone 46	Kill'd by ſeveral Accidents 59	Teeth —— — —1353
Diabetes and Strangury — 8	Leproſy —— —— 1	Vapours and Water in the Head — 13
Diſtracted and Lunatick— 27	Lethargy —— — — 7	
Dropſy and Tympany — 811	Livergrown —— —— 10	Ulcer —— —— 47
Drowned —— —— 50	Murdered —— —— 20	Vomiting —— —— 6
Evil —— —— 71	Overlaid —— —— 57	Worms —— —— 50

CHRISTENED	Males — 8062	BURIED	Males — 10819	Of the Plague 0
	Females 7767		Females 10151	
	In all 15829		In all — 20970	

Increaſed in the Burials this Year 2332

A General

1698.

A General BILL of all the Chriſtenings and Burials,

From the 14th of December 1697, to the 20th of December 1698.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur. Pl.
St ALBAN Wood-ſtreet	10
Alhallows Barkin	72
Alhallows Bread-ſtreet	15
Alhallows Great	40
Alhallows Honey-lane	0
Alhallows Leſs	19
Alhallows Lombard-ſtreet	24
Alhallows Staining	36
Alhallows the Wall	61
St Alphage	42
St Andrew Hubbard	19
St Andrew Underſhaft	32
St Andrew Wardrobe	45
St Ann Alderſgate	28
St Ann Black Friars	125
St Antholin's Pariſh	10
St Auſtin's Pariſh	23
St Bartholomew Exchange	23
St Bennet Fink	21
St Bennet Gracechurch	10
St Bennet Paul's Wharf	43
St Bennet Sherehog	2
St Botolph Billingſgate	8
Chriſt Church	156
St Chriſtopher	11
St Clement Eaſtcheap	16
St Dionis Backchurch	34
St Dunſtan Eaſt	61
St Edmund Lombard-ſtr.	31
St Ethelborough	35
St Faith's	31
St Gabriel Fenchurch	15
St George Botolph-lane	8
St Gregory by St Paul's	65
St Helen's	28
St James Duke's Place	16
St James Garlickhithe	39
St John Baptiſt	15
St John Evangeliſt	3
St John Zachary	22
St Katherine Coleman	51
St Katherine Creechurch	72
St Laurence Jewry	57
St Laurence Pountney	10
St Leonard Eaſtcheap	9
St Leonard Foſter-lane	30
St Magnus Pariſh	41
St Margaret Lothbury	26
St Margaret Moſes	6
St Margaret New Fiſh-ſtr.	0
St Margaret Pattons	16
St Martin Ironmonger-lane	4
St Martin Ludgate	40
St Martin Orgars	13
St Martin Outwich	7
St Martin Vintrey	30
St Mary Abchurch	21
St Mary Aldermanbury	24
St Mary Aldermary	32
St Mary le Bow	28
St Mary Bothaw	3
St Mary Colechurch	2
St Mary Hill	33
St Mary Magd. Milk-ſtr.	0
St Mary Mag. Old Fiſh-ſtr.	27
St Mary Mounthaw	3
St Mary Somerſet	35
St Mary Staining	18
St Mary Woolchurch	0
St Mary Woolnoth	40
St Matthew Friday-ſtreet	22
St Michael Baſſiſhaw	23
St Michael Cornhill	24
St Michael Crooked-lane	29
St Michael Queenhithe	40
St Michael Querne	24
St Michael Royal	18
St Michael Wood-ſtreet	16
St Mildred Bread-ſtreet	21
St Mildred Poultry	22
St Nicholas Acons	0
St Nicholas Coleabby	26
St Nicholas Olave	5
St Olave Hart-ſtreet	51
St Olave Jewry	16
St Olave Silver-ſtreet	30
St Pancras Soper-lane	9
St Peter Cheap	8
St Peter Cornhill	26
St Peter Paul's Wharf	21
St Peter Poor	34
St Stephen Coleman-ſtreet	125
St Stephen Walbrook	18
St Swithin	30
St Thomas Apoſtle	11
Trinity Pariſh	13
St Vedaſt, alias Foſter	32

Chriſtened in the ninety-ſeven Pariſhes within the Walls 2171 Buried 2666 Plague 0

St Andrew Holborn	853
St Bartholomew Great	71
St Bartholomew Leſs	30
St Bride's Pariſh	270
Bridewell Precinct	31
St Botolph Alderſgate	188
St Botolph Aldgate	541
St Botolph Biſhopſgate	452
St Dunſtan Weſt	168
St George Southwark	280
St Giles Cripplegate	1062
St Olave Southwark	667
St Saviour Southwark	500
St Sepulchre's Pariſh	611
St Thomas Southwark	78
Trinity Minories	19
At the Peſt-houſe	0

Chriſtened in the ſixteen Pariſhes without the Walls 5120 Buried 5821 Plague 0

1698.

Chriſt Church — ——158	St John at Wapping——339	St Magdalen Bermondſey 425
St Dunſtan at Stepney—2131	St Katherine by the Tower174	St Mary Newington ——179
St Giles in the Fields —1307	Lambeth Pariſh — ——263	St Mary Whitechapel —691
St James Clerkenwell —390	St Leonard Shoreditch —429	St Paul Shadwell ———482
St John at Hackney——118	St Mary Iſlington — — 88	Rotherhith Pariſh — —188

Chriſtened in the fifteen Out Pariſhes in Middleſex and Surrey 5686
Buried 7362 Plague 0

St Ann Weſtminſter - —412	St Margaret Weſtminſt. 834	St Mary Savoy ——— 82
St Clement Danes ——435	St Martin in the Fields 1385	St Paul Covent Garden 211
St James Weſtminſter —975		

Chriſtened in the ſeven Pariſhes in the City and Liberties of Weſtminſter 3075
Buried 4334 Plague 0

DISEASES and CASUALTIES.

Abortive and Stillborn 427	Exceſſive Drinking —— 1	Overlaid ——— —— 33
Aged and Bedridden1023	Executed — — ——— 22	Palſy ——— — ——— 21
Ague and Fever —— —3343	Falling Sickneſs — —— 1	Pleuriſy —— ——— 32
Apoplexy and Suddenly— 116	Flox, Small Pox and Meaſles1813	Quinſy ——— ——— 10
Aſthma ——— —— 1	Found dead in the Streets,&c. 14	Rheumatiſm — —— 16
Bleeding, Bloody Flux, and Flux — } 25	French Pox —— — — 66	Rickets ——— ——— 278
	Frenzy —— —— 1	Riſing of the Lights —— 99
Burnt and Scalded — — 3	Gangrene and Fiſtula—— 35	St Anthony's Fire —— 4
Burſten and Rupture —— 29	Gout and Sciatica ——— 14	Scurvy —— — — — 8
Calenture —— ——— 1	Grief —— ——— —— 3	Shot ——— — —— 1
Cancer, Canker and Thruſh 98	Griping in the Guts — —1165	Smothered —— —— 3
Childbed ——— — — 169	Hanged and made away themſelves — } 20	Spleen ——— ——— 3
Choaked —— ——— 1		Spotted Fever and Purples 274
Chriſomes and Infants — 59	Headmouldſhot ——— 15	Stopping in the Stomach 409
Colick and Wind ——— 64	Jaundies —— — —— 68	Strangury —— — —— 5
Conſumption and Tiſſick 3583	Impoſthume — —— — 59	Surfeit —— — ——— 63
Convulſion ——— — —4480	Itch —— —— — 1	Teeth — — — — 135
Cough and Chincough — 7	Killed by ſeveral Accidents 72	Vapours and Water in the Head — } 4
Cut of the Stone and Stone 34	Leproſy and ſcald Head— 2	
Diſtracted and Lunatick— 19	Lethargy —— — —— 7	Ulcer ——— ——— 22
Dropſy and Tympany - — 508	Livergrown —— ——— 12	Vomiting ——— —— 3
Drowned ——— ——— 59	Megrims ——— —— 1	Worms ——— ——— 31
Evil —— —— —— 59	Murdered —— — —— 13	

CHRISTENED	Males — 8426	BURIED	Males — 10925	Of the Plague	0
	Females 7626		Females 9258		
	In all — 16052		In all — 20183		

Decreaſed in the Burials this Year 787

1699.

A General BILL of all the Chriſtenings and Burials,

From the 20th of December 1698, to the 19th of December 1699.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.	Pl.
St ALBAN Wood-ſtreet	33	
Alhallows Barkin	82	
Alhallows Bread-ſtreet	9	
Alhallows Great	50	
Alhallows Honey-lane	4	
Alhallows Leſs	11	
Alhallows Lombard-ſtreet	30	
Alhallows Staining	24	
Alhallows the Wall	53	
St Alphage	32	
St Andrew Hubbard	13	
St Andrew Underſhaft	46	
St Andrew Wardrobe	65	
St Ann Alderſgate	37	
St Ann Black Friars	122	
St Antholin's Pariſh	13	
St Auſtin's Pariſh	13	
St Bartholomew Exchange	16	
St Bennet Fink	16	
St Bennet Gracechurch	18	
St Bennet Paul's Wharf	45	
St Bennet Sherehog	1	
St Botolph Billinſgate	11	
Chriſt Church	118	
St Chriſtopher	19	
St Clement Eaſtcheap	12	
St Dionis Backchurch	23	
St Dunſtan Eaſt	87	
St Edmund Lombard-ſtr.	32	
St Ethelborough	23	
St Faith's	41	
St Gabriel Fenchurch	6	
St George Botolph-lane	17	
St Gregory by St Paul's	83	
St Helen's	28	
St James Duke's Place	13	
St James Garlickhithe	32	
St John Baptiſt	25	
St John Evangeliſt	3	
St John Zachary	21	
St Katherine Coleman	61	
St Katherine Creechurch	68	
St Laurence Jewry	48	
St Laurence Pountney	19	
St Leonard Eaſtcheap	17	
St Leonard Foſter-lane	45	
St Magnus Pariſh	51	
St Margaret Lothbury	27	
St Margaret Moſes	11	
St Margaret New Fiſh-ſtr.	0	
St Margaret Pattons	20	
St Martin Ironmonger-lane	3	
St Martin Ludgate	43	
St Martin Orgars	24	
St Martin Outwich	16	
St Martin Vintrey	43	
St Mary Abchurch	32	
St Mary Aldermanbury	26	
St Mary Aldermary	33	
St Mary le Bow	25	
St Mary Bothaw	4	
St Mary Colechurch	2	
St Mary Hill	34	
St Mary Magd. Milk-ſtr.	0	
St Mary Mag. Old Fiſh-ſtr.	25	
St Mary Mounthaw	7	
St Mary Somerſet	40	
St Mary Staining	18	
St Mary Woolchurch	0	
St Mary Woolnoth	31	
St Matthew Friday-ſtreet	13	
St Michael Baſſiſhaw	30	
St Michael Cornhill	29	
St Michael Crooked-lane	22	
St Michael Queenhithe	43	
St Michael Querne	15	
St Michael Royal	12	
St Michael Wood-ſtreet	9	
St Mildred Bread-ſtreet	16	
St Mildred Poultry	21	
St Nicholas Acons	0	
St Nicholas Coleabby	23	
St Nicholas Olave	6	
St Olave Hart-ſtreet	46	
St Olave Jewry	15	
St Olave Silver-ſtreet	30	
St Pancras Soper-lane	5	
St Peter Cheap	15	
St Peter Cornhill	27	
St Peter Paul's Wharf	15	
St Peter Poor	30	
St Stephen Coleman-ſtreet	129	
St Stephen Walbrook	19	
St Swithin	21	
St Thomas Apoſtle	26	
Trinity Pariſh	19	
St Vedaſt, alias Foſter	30	

Chriſtened in the ninety-ſeven Pariſhes within the Walls 2072 Buried 2766 Plague 0

St Andrew Holborn	873	St Botolph Aldgate	601	St Saviour Southwark	517
St Bartholomew Great	73	St Botolph Biſhopſgate	514	St Sepulchre's Pariſh	588
St Bartholomew Leſs	37	St Dunſtan Weſt	205	St Thomas Southwark	67
St Bride's Pariſh	316	St George Southwark	358	Trinity Minories	21
Bridewell Precinct	31	St Giles Cripplegate	1177	The Peſt-houſe	0
St Botolph Alderſgate	203	St Olave Southwark	746		

Chriſtened in the ſixteen Pariſhes without the Walls 4706 Buried 6327 Plague 0

1699.

Chriſt Church — ——167	St John at Wapping——301	St Magdalen Bermondſey 454
St Dunſtan at Stepney—2093	St Katherine by the Tower 121	St Mary Newington ——193
St Giles in the Fields —1252	Lambeth Pariſh — ——278	St Mary Whitechapel —841
St James Clerkenwell —331	St Leonard Shoreditch —481	St Paul Shadwell ———460
St John at Hackney ——113	St Mary Iſlington —— 94	Rotherhith Pariſh — —153

Chriſtened in the fifteen Out Pariſhes in Middleſex and Surrey 5360
Buried 7332 Plague 0

St Ann Weſtminſter —401	St Margaret Weſtminſt. 885	St Mary Savoy ——— 114
St Clement Danes — —431	St Martin in the Fields 1411	St Paul Covent Garden 212
St James Weſtminſter—916		

Chriſtened in the ſeven Pariſhes in the City and Liberties of Weſtminſter 3269
Buried 4370 Plague 0

DISEASES and CASUALTIES.

Abortive and Stillborn 533	Executed —— ——— 18	Quinſy —— — —— 10
Aged and Bedridden1211	Flox, Small Pox and Meaſles 890	Raſh —— — —— 1
Ague and Fever —— —3505	Found dead in the Streets,&c. 15	Rheumatiſm —— —— 14
Apoplexy and Suddenly— 106	French Pox —— —— 64	Rickets — — ——— 306
Bleeding, Bloody Flux, and Flux — 21	Gangrene and Fiſtula—— 45	Riſing of the Lights —— 81
	Gout and Sciatica ——— 13	St Anthony's Fire ——— 4
Burnt and Scalded ——— 4	Grief —— —— 8	Scurvy ——— — — 3
Burſten and Rupture —— 24	Griping in the Guts — —1225	Shot ——— ——— 1
Cancer, Canker and Thruſh 90	Hanged and made away themſelves — 30	Smothered ——— —— 2
Childbed —— ——— 244		Sores, Ulcers and Bruiſed 46
Choaked and Suffocated— 2	Head-ach and Megrims— 6	Spleen —— ——— 2
Chriſomes and Infants -— 70	Headmouldſhot — —— 22	Spotted Fever and Purples 306
Colick and Wind ——— 75	Jaundies —— ——— 82	Stabbed and Wounded -— 3
Conſumption and Tiſſick 3351	Impoſthume —— —— 42	Stopping in the Stomach 389
Convulſion —— ——4513	Itch —— —— —— 1	Strangury ——— —— 12
Cough —— — —— 3	Kill'd by ſeveral Accidents 62	Surfeit ——— ——— 87
Cut of the Stone and Stone 40	Lethargy —— — —— 6	Teeth —— — ——2268
Diabetes ——— —— 3	Livergrown —— — 12	Vapours and Water in the Head — 2
Diſtracted and Lunatick— 20	Murdered — ——— 12	
Dropſy and Tympany -— 602	Overlaid ——— —— 55	Vomiting —— —— 6
Drowned —— ——— 58	Palſy ——— — — 24	Wen ——— ——— 1
Evil —— —— —— 64	Pleuriſy ——— —— 25	Worms —— — —— 50
Exceſſive Drinking ——— 4	Poiſoned ——— —— 1	

CHRISTENED	Males — 7911 Females 7452 In all — 15363	BURIED	Males — 11020 Females 9775 In all — 20795	Of the Plague 0	

Increaſed in the Burials this Year 612

1700.

A General BILL of all the Chriſtenings and Burials,

From the 19th of December 1699, to the 17th of December 1700.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	29
Alhallows Barkin	83
Alhallows in Bread-ſtreet	17
Alhallows the Great	63
Alhallows in Honey-lane	4
Alhallows the Leſs	14
Alhallows in Lombard-ſtreet	23
Alhallows Staining	27
Alhallows on London Wall	60
St Alphage near Sion College	37
St Andrew Hubbard	14
St Andrew Underſhaft	39
St Andrew Wardrobe	53
St Ann within Alderſgate	30
St Ann in Black Friars	125
St Anthony, vulg. Antholin	12
St Auguſtin, vulg. Auſtin	16
St Bartholomew by Exchange	15
St Benedict, v. Bennet Fink	18
St Bennet Gracechurch	16
St Bennet at Paul's Wharf	29
St Bennet Sherehog	1
St Botolph at Billinſgate	10
Chriſt Church Pariſh	135
St Chriſtopher's Pariſh	21
St Clement near Eaſtcheap	13
St Dionis Backchurch	28
St Dunſtan in the Eaſt	82
St Edmund the King	15
St Ethelburga's Pariſh	28
St Faith under St Paul's	37
St Gabriel in Fenchurch-ſtr.	5
St George in Botolph-lane	13
St Gregory by St Paul's	77
St Helen near Biſhopſgate	30
St James in Duke's Place	14
St James at Garlickhithe	41
St John Baptiſt by Dowgate	19
St John the Evangeliſt	4
St John Zachary	26
St Katherine Coleman	52
St Katherine Creechurch	61
St Laurence Jewry	53
St Laurence Pountney	17
St Leonard in Eaſtcheap	5
St Leonard in Foſter-lane	38
St Magnus by London Bridge	49
St Margaret in Lothbury	21
St Margaret Moſes	5
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattons	22
St Martin Ironmonger-lane	3
St Martin at Ludgate	49
St Martin Orgars	18
St Martin Outwich	9
St Martin Vintrey	33
St Mary Abchurch	24
St Mary in Aldermanbury	26
St Mary Aldermary	22
St Mary le Bow in Cheapſide	18
St Mary Bothaw at Dowgate	2
St Mary Colechurch	0
St Mary Hill by Billinſgate	28
St Mary Magd. in Milk-ſtr.	0
St Mary Magd. Old Fiſh-ſtr.	34
St Mary Mounthaw	7
St Mary Somerſet	29
St Mary Staining	14
St Mary Woolchurch	0
St Mary Woolnoth	33
St Matthew in Friday-ſtreet	11
St Michael Baſſiſhaw	27
St Michael in Cornhill	21
St Michael in Crooked-lane	27
St Michael at Queenhithe	36
St Michael at Quern	16
St Michael Royal	27
St Michael in Wood-ſtreet	8
St Mildred in Bread-ſtreet	22
St Mildred in the Poultry	18
St Nicholas Acons	2
St Nicholas Coleabby	12
St Nicholas Olave	7
St Olave in Hart-ſtreet	45
St Olave in the Old Jewry	8
St Olave in Silver-ſtreet	28
St Pancras in Pancras-lane	6
St Peter in Cheapſide	9
St Peter in Cornhill	25
St Peter near Paul's Wharf	13
St Peter Poor in Broad-ſtr.	33
St Stephen in Coleman-ſtreet	147
St Stephen in Walbrook	16
St Swithin at London-ſtone	27
St Thomas the Apoſtle	18
Trinity Pariſh	23
St Vedaſt, alias Foſter	29

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1790 Buried 2656 Plague 0

St Andrew in Holborn	906
St Bartholomew the Great	41
St Bartholomew the Leſs	22
St Botolph by Alderſgate	188
St Botolph by Aldgate	502
St Botolph by Biſhopſgate	465
Bridewell Precinct	23
St Bridget, vulg. St Bride's	278
St Dunſtan in the Weſt	171
St George in Southwark	342
St Giles by Cripplegate	1192
St Olave in Southwark	581
St Saviour in Southwark	480
St Sepulchre's Pariſh	554
St Thomas in Southwark	55
Trinity in the Minories	12
The Peſt-houſe	—

Chriſtened in the ſixteen Pariſhes without the Walls 4580 Buried 5812 Plague 0

Chriſt Church in Surrey —141	St John at Wapping ——272	St Mary Magd. Bermondſey 376
St Dunſtan at Stepney——1918	St Katherine near the Tower 152	St Mary at Newington ——167
St Giles in the Fields ——1200	Lambeth Pariſh — ——240	St Mary at Rotherhith ——211
St James at Clerkenwell —294	St Leonard in Shoreditch—447	St Mary in Whitechapel —715
St John at Hackney —— 84	St Mary at Iſlington — — 99	St Paul at Shadwell ——331

Chriſtened in the fifteen Out Pariſhes in Middleſex and Surrey 5053 Buried 6647 Pl. o

St Ann in Weſtminſter - —496	St Margaret in Weſtminſter 794	St Mary Savoy in the Strand 104
St Clement Danes — ——403	St Martin in the Fields—1424	St Paul in Covent Garden 180
St James in Weſtminſter —927		

Chriſtened in the ſeven Pariſhes in the City and Liberties of Weſtminſter 3216
Buried 4328 Pl. o

DISEASES and CASUALTIES.

Abortive and Stillborn 546	Grief —— — —— 5	Strangury —— —— 9
Aged and Bedridden 1242	Griping in the Guts — — 1004	Surfeit —— — —— 76
Ague and Fever —— —3676	Head-ach —— —— 1	Swelling in the Neck —— 1
Apoplexy and Suddenly— 104	Headmouldſhot — —— 6	Teeth —— ——1159
Bleeding, Bloody Flux, and Flux — 13	Jaundies —— —— 73	Twiſting of the Guts —— 2
Cancer, Canker and Thruſh 124	Impoſthume — — —— 59	Vapours and Water in the Head — 7
Chicken Pox — —— 1	Lethargy —— —— 5	Vomiting — — —— 15
Childbed —— —— 240	Livergrown —— — — 11	Worms —— —— 53
Chriſomes and Infants —— 78	Looſeneſs —— —— 1	
Colick —— — —— 72	Overlaid —— —— 69	
Conſumption and Tiſſick 2819	Palſy —— —— — 31	
Convulſion —— ——4631	Pleuriſy —— —— 30	
Cough and Chincough — 7	Quinſy —— —— — 10	
Cut of the Stone and Stone 43	Rheumatiſm — —— 16	
Diabetes —— —— 1	Rickets —— —— 393	
Diſtracted and Lunatick— 35	Riſing of the Lights —— 101	
Dropſy and Tympany —— 659	Rupture —— —— 18	
Evil —— —— 83	St Anthony's Fire —— 9	
Executed —— —— 29	Scarlet Fever —— —— 1	
Falling Sickneſs —— — 1	Scurvy —— —— 5	
Flox, Small Pox and Meaſles 1031	Shingles —— —— 1	
French Pox —— —— 69	Sores and Ulcers —— 62	
Gangrene, Fiſtula, and Mortification — 36	Spleen —— — —— 3	
Gout and Cramp —— 15	Spotted Fever and Purples 189	
	Stoppage in the Stomach 320	

CASUALTIES.

Bruiſed —— —— 1
Burnt and Scalded — — 8
Deceaſed (ſo reported in the Coroner's Warrant) 1
Drowned —— — — 48
Found dead in the Streets, &c. 9
Hang'd and made away themſelves — 28
Hanged by Misfortune — 1
Kill'd by ſeveral Accidents 38
Murdered — — —— 11
Smothered and Suffocated 3
Stabbed — — —— 1

CHRISTENED { Males — 7578 / Females 7061 / In all — 14639 } BURIED { Males — 9653 / Females 9790 / In all — 19443 } Pl. o

Decreaſed in the Burials this Year 1352

A General

A General BILL of all the Chriſtenings and Burials,

From the 17th of December 1700, to the 16th of December 1701.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	29
Alhallows Barkin —	86
Alhallows in Bread-ſtreet —	18
Alhallows the Great ——	41
Alhallows in Honey-lane —	4
Alhallows the Leſs ——	14
Alhallows in Lombard-ſtreet	16
Alhallows Staining — ——	34
Alhallows on London Wall	61
St Alphage near Sion College	32
St Andrew Hubbard — —	20
St Andrew Underſhaft ——	41
St Andrew Wardrobe ——	48
St Ann within Alderſgate—	33
St Ann in Black Friars - —	138
St Anthony, vulg. Antholin	8
St Auguſtin, vulg. Auſtin—	12
St Bartholomew by Exchange	18
St Benedict, v. Bennet Fink	28
St Bennet Gracechurch - —	16
St Bennet at Paul's Wharf	39
St Bennet Sherehog - ——	2
St Botolph at Billinſgate —	14
Chriſt Church Pariſh ——	117
St Chriſtopher's Pariſh ——	16
St Clement near Eaſtcheap	13
St Dionis Backchurch ——	27
St Dunſtan in the Eaſt ——	76
St Edmund the King — —	28
St Ethelburga's Pariſh ——	34
St Faith under St Paul's —	42
St Gabriel in Fenchurch-ſtr.	7
St George in Botolph-lane—	13
St Gregory by St Paul's —	81
St Helen near Biſhopſgate—	38
St James in Duke's Place —	11
St James at Garlickhithe —	49
St John Baptiſt by Dowgate	27
St John the Evangeliſt ——	5
St John Zachary —— —	27
St Katherine Coleman ——	63
St Katherine Creechurch —	70
St Laurence Jewry ———	53
St Laurence Pountney ——	15
St Leonard in Eaſtcheap —	12
St Leonard in Foſter-lane—	43
St Magnus by London Bridge	42
St Margaret in Lothbury —	24
St Margaret Moſes ———	3
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattons — —	6
St Martin Ironmonger-lane	9
St Martin at Ludgate ——	40
St Martin Orgars —— —	19
St Martin Outwich ———	13
St Martin Vintrey — ——	20
St Mary Abchurch — —	30
St Mary in Aldermanbury—	30
St Mary Aldermary — —	17
St Mary le Bow in Cheapſide	21
St Mary Bothaw at Dowgate	6
St Mary Colechurch ———	1
St Mary Hill by Billinſgate	29
St Mary Magd. in Milk-ſtr.	0
St Mary Magd. Old Fiſh-ſtr.	29
St Mary Mounthaw — —	5
St Mary Somerſet — ——	44
St Mary Staining —— —	17
St Mary Woolchurch ——	0
St Mary Woolnoth ———	32
St Matthew in Friday-ſtreet	11
St Michael Baſſiſhaw — —	26
St Michael in Cornhill ——	24
St Michael in Crooked-lane	36
St Michael at Queenhithe—	38
St Michael at Quern ——	14
St Michael Royal —— —	26
St Michael in Wood-ſtreet	9
St Mildred in Bread-ſtreet	20
St Mildred in the Poultry	21
St Nicholas Acons —— —	0
St Nicholas Coleabby ——	13
St Nicholas Olave ———	14
St Olave in Hart-ſtreet - —	40
St Olave in the Old Jewry	13
St Olave in Silver-ſtreet —	27
St Pancras in Pancras-lane	5
St Peter in Cheapſide ——	11
St Peter in Cornhill ———	25
St Peter near Paul's Wharf	18
St Peter Poor in Broad-ſtr.	24
St Stephen in Coleman-ſtreet	109
St Stephen in Walbrook —	25
St Swithin at London-ſtone	18
St Thomas the Apoſtle - —	24
Trinity Pariſh —— ——	12
St Vedaſt, alias Foſter ——	32

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1762 Buried 2691 Pl. 0

St Andrew in Holborn ———	904
St Bartholomew the Great--	70
St Bartholomew the Leſs —	33
St Botolph by Alderſgate —	198
St Botolph by Aldgate ———	527
St Botolph by Biſhopſgate—	507
Bridewell Precinct ———	9
St Bridget, vulg. St Bride's	302
St Dunſtan in the Weſt - —	175
St George in Southwark —	347
St Giles by Cripplegate —	1148
St Olave in Southwark - —	711
St Saviour in Southwark —	519
St Sepulchre's Pariſh ———	634
St Thomas in Southwark—	80
Trinity in the Minories —	18
The Peſt-houſe — ——	

Chriſtened in the ſixteen Pariſhes without the Walls 4783 Buried 6182 Pl. 0

1701.

Chriſt Church in Surrey —106	St John at Wapping ——289	St Mary Magd. Bermondſey 410
St Dunſtan at Stepney——2057	St Katherine near the Tower 167	St Mary at Newington ——195
St Giles in the Fields ——1298	Lambeth Pariſh — ——278	St Mary at Rotherhith ——172
St James at Clerkenwell —336	St Leonard in Shoreditch —469	St Mary in Whitechapel —735
St John at Hackney ——117	St Mary at Iſlington — —114	St Paul at Shadwell ——375

Chriſtened in the fifteen Out Pariſhes in Middleſex and Surrey 5440 Buried 7118 Pl. o

St Ann in Weſtminſter - —446	St Margaret in Weſtminſter 831	St Mary Savoy in the Strand 126
St Clement Danes — —434	St Martin in the Fields —1424	St Paul in Covent Garden 212
St James in Weſtminſter—1007		

Chriſtened in the ſeven Pariſhes in the City and Liberties of Weſtminſter 3631
Buried 4480 Pl. o

DISEASES and CASUALTIES.

AGED 1456 Bedridden 5 In all	1456	Gangrene 15 Fiſtula 19 Mortification 8 — 42
Ague 6 Fever 2902 —2908		Gout 16 Cramp 1 Sciatica 2 — — 19
Apoplexy 74 Suddenly 74 —	148	Grief —— — — 5
Aſthma —— ——	1	Griping in the Guts — —1136
Bleeding 6 Bloody Flux 6 Flux 6 —	18	Headmouldſhot — — 6
Burſten 1 Rupture 28—	29	Jaundies —— —— 86
Cancer 56 Canker 11 Thruſh 34 —	101	Impoſthume —— —— 53
Childbed —— — ——	225	Lethargy —— — — 4
Chriſomes 44 Infants 29	73	Livergrown —— —— 8
Colick 91 Wind 1 ——	92	Looſeneſs —— —— 2
Conſumption 2678 Tiſſick 284 —	2962	Megrims —— —— 3
Convulſion —— ——	5532	Pain in the Side — — 1
Cough 3 Chincough 2 Hooping Cough 1	6	Palſy —— — —— 18
Cut of the Stone 1 Stone 39 —	40	Pleuriſy —— —— 37
Diabetes —— ——	4	Quinſy —— —— 7
Diſtracted 1 Lunatick 28	29	Rheumatiſm —— —— 10
Dropſy 708 Tympany 15	723	Rickets —— —— 455
Evil —— ——	55	Riſing of the Lights —— 98
Flox and Small Pox 1095 Meaſles 4 —	1099	St Anthony's Fire —— 1
French Pox —— ——	57	Scald Head —— —— 2
		Scurvy —— —— 8
		Sores and Ulcers —— 60
		Spleen —— —— —— 2
		Spotted Fever 68 Purples 9 — 77
		Stoppage in the Stomach 375
		Strangury —— —— 9
		Surfeit —— —— —— 55
		Teeth —— — —1261
		Vomiting —— —— 21
		Water in the Head —— 3
		Worms —— —— 41

CASUALTIES.

Abortive 101 Stillborn 527 ——	628	
Bruiſed —— — —	2	
Burnt —— ——	8	
Died by Misfortune (ſo reported) —	1	
Drowned —— ——	81	
Exceſſive Drinking ——	1	
Executed —— — ——	15	
Found dead in the Streets, &c.	22	
Frighted —— ——	1	
Hang'd and made away themſelves —	40	
Kill'd by ſeveral Accidents	69	
Murdered —— ——	12	
Overlaid —— ——	83	
Poiſoned —— ——	1	
Wounded —— ——	1	

CHRISTENED	Males — 8102 Females 7514 In all 15616	BURIED	Males — 10270 Females 10201 In all — 20471	Pl. o

Increaſed in the Burials this Year 1028

A General

1702.

A General BILL of all the Chriſtenings and Burials,

From the 16th of December 1701, to the 15th of December 1702.

According to the Report made to the Queen's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	21
Alhallows Barkin	84
Alhallows in Bread-ſtreet	20
Alhallows the Great	33
Alhallows in Honey-lane	2
Alhallows the Leſs	15
Alhallows in Lombard-ſtreet	27
Alhallows Staining	36
Alhallows on London Wall	52
St Alphage near Sion College	31
St Andrew Hubbard	18
St Andrew Underſhaft	46
St Andrew Wardrobe	56
St Ann within Alderſgate	17
St Ann in Black Friars	131
St Anthony, vulg. Antholin	17
St Auguſtin, vulg. Auſtin	15
St Bartholomew by Exchange	28
St Benedict, v. Bennet Fink	32
St Bennet Gracechurch	8
St Bennet at Paul's Wharf	42
St Bennet Sherehog	1
St Botolph at Billinſgate	11
Chriſt Church Pariſh	98
St Chriſtopher's Pariſh	14
St Clement near Eaſtcheap	15
St Dionis Backchurch	30
St Dunſtan in the Eaſt	80
St Edmund the King	22
St Ethelburga's Pariſh	25
St Faith under St Paul's	26
St Gabriel in Fenchurch-ſtr.	9
St George in Botolph-lane	16
St Gregory by St Paul's	68
St Helen near Biſhopſgate	27
St James in Duke's Place	13
St James at Garlickhithe	37
St John Baptiſt by Dowgate	13
St John the Evangeliſt	5
St John Zachary	19
St Katherine Coleman	54
St Katherine Creechurch	53
St Laurence Jewry	43
St Laurence Pountney	12
St Leonard in Eaſtcheap	7
St Leonard in Foſter-lane	21
St Magnus by London Bridge	39
St Margaret in Lothbury	34
St Margaret Moſes	2
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattons	15
St Martin Ironmonger-lane	12
St Martin at Ludgate	35
St Martin Orgars	20
St Martin Outwich	13
St Martin Vintrey	39
St Mary Abchurch	31
St Mary in Aldermanbury	21
St Mary Aldermary	30
St Mary le Bow in Cheapſide	32
St Mary Bothaw at Dowgate	4
St Mary Colechurch	0
St Mary Hill by Billinſgate	24
St Mary Magd. in Milk-ſtr.	0
St Mary Magd. Old Fiſh-ſtr.	46
St Mary Mounthaw	3
St Mary Somerſet	35
St Mary Staining	19
St Mary Woolchurch	0
St Mary Woolnoth	23
St Matthew in Friday-ſtreet	18
St Michael Baſſiſhaw	36
St Michael in Cornhill	17
St Michael in Crooked-lane	27
St Michael at Queenhithe	27
St Michael at Quern	8
St Michael Royal	8
St Michael in Wood-ſtreet	7
St Mildred in Bread-ſtreet	23
St Mildred in the Poultry	16
St Nicholas Acons	0
St Nicholas Coleabby	23
St Nicholas Olave	9
St Olave in Hart-ſtreet	41
St Olave in the Old Jewry	11
St Olave in Silver-ſtreet	19
St Pancras in Pancras-lane	5
St Peter in Cheapſide	14
St Peter in Cornhill	30
St Peter near Paul's Wharf	16
St Peter Poor in Broad-ſtr.	18
St Stephen in Coleman-ſtreet	121
St Stephen in Walbrook	18
St Swithin at London-ſtone	25
St Thomas the Apoſtle	11
Trinity Pariſh	11
St Vedaſt, alias Foſter	26

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1919 Buried 2512 Plague 0

St Andrew in Holborn	899
St Bartholomew the Great	54
St Bartholomew the Leſs	23
St Botolph by Alderſgate	179
St Botolph by Aldgate	483
St Botolph by Biſhopſgate	492
Bridewell Precinct	25
St Bridget, vulg. St Bride's	291
St Dunſtan in the Weſt	169
St George in Southwark	375
St Giles by Cripplegate	1002
St Olave in Southwark	739
St Saviour in Southwark	564
St Sepulchre's Pariſh	527
St Thomas in Southwark	69
Trinity in the Minories	11
The Peſt-houſe	

Chriſtened in the ſixteen Pariſhes without the Walls 4845 Buried 5902 Plague 9

1702.

Chriſt Church in Surrey —121	St John at Wapping———292	St Mary Magd. Bermondſey 382
St Dunſtan at Stepney——1940	St Katherine near the Tower 162	St Mary at Newington ——204
St Giles in the Fields ——1310	St Leonard in Shoreditch —427	St Mary at Rotherhith ——147
St James at Clerkenwell —309	St Mary at Iſlington———105	St Mary in Whitechapel —731
St John at Hackney———100	St Mary at Lambeth — —271	St Paul at Shadwell ———420

Chriſtened in the fifteen Out Pariſhes in Middleſex and Surrey 5300
Buried 6921 Plague 0

St Ann in Weſtminſter —401	St Margaret in Weſtminſt. 736	St Mary Savoy in the Strand 104
St Clement Danes ———432	St Martin in the Fields —1366	St Paul in Covent Garden 179
St James in Weſtminſter—928		

Chriſtened in the ſeven Pariſhes in the City and Liberties of Weſtminſter 3623
Buried 4146 Plague 0

DISEASES and CASUALTIES.

AGED ——— ———1455	Hooping Cough — ——— 1	Surfeit —— — ——— 61
Ague —— — —— 3	Jaundies ——— ——— 62	Swelling —— —— —— 2
Apoplexy —— — —— 74	Impoſthume —— —— 57	Teeth ——— — ———1304
Aſthma ——— ——— 3	Infants —— — ——— 18	Thruſh —— —— —— 36
Bedridden ——— — —— 5	Leproſy ——— ——— 3	Tiſſick ——— ——— 248
Bleeding ——— ——— 5	Lethargy — — — — 6	Twiſting of the Guts — — 2
Bloody Flux —— —— 4	Livergrown —— ——— 4	Tympany ——— ——— 18
Burſten ——— ——— 7	Lunatick —— —— —— 35	Vomiting ——— ——— 20
Calenture —— — —— 1	Meaſles ——— ——— 27	Water in the Head — —— 4
Cancer —— — ——— 56	Megrims —— —— —— 2	Wen ——— — ——— 1
Canker ——— — —— 9	Mortification —— —— 11	Worms ——— ——— 60
Childbed ——— ——— 222	Palſy —— —— ——— 15	
Chincough —— — —— 3	Pleuriſy ——— — —— 16	CASUALTIES.
Choaked with Fat —— — 1	Purples —— — ——— 6	
Chriſomes —— — —— 49	Quinſy ——— — —— 20	Abortive ——— ——— 80
Colick ——— ——— 108	Raſh —— — —— — 1	Bruiſed —— —— —— 1
Conſumption ——— ——2730	Rheumatiſm ——— —— 23	Dead by Misfortune (ſo reported) 1
Convulſion —— ——5639	Rickets —— — — — 443	Died in the Streets — —— 2
Cough ——— — —— 11	Riſing of the Lights — —— 90	Drowned ——— ——— 66
Cramp —— — ——— 1	Rupture ——— ——— 18	Exceſſive Drinking — —— 1
Dropſy ——— ——— 709	St Anthony's Fire — —— 9	Executed ——— ——— 7
Evil —— ——— —— 69	Scald Head ——— ——— 2	Found dead in the Streets, &c. 19
Fever ——— —— ——2682	Scurvy ——— — —— 9	Hanged and made away themſelves —— 23
Fiſtula —— —— ——— 29	Small Pox ——— ——— 311	Killed by ſeveral Accidents—— 47
Flux ——— —— —— 5	Sores and Ulcers — ——— 43	Murdered ——— ——— 10
French Pox —— ——— 55	Spleen ——— — — — 3	Overlaid —— — —— 90
Gangrene ——— —— 12	Spotted Fever —— ——— 53	Scalded — —— ——— 2
Gout —— ——— —— 12	Stone ——— — ——— 33	Smothered —— ——— 2
Grief —— —— ——— 5	Stoppage in the Stomach —— 315	Stifled in Mud —— —— 1
Griping in the Guts — ——1189	Strangury —— ——— 8	Stillborn ——— ——— 513
Head-ach —— ——— 4	Strongullion ——— —— 1	
Headmouldſhot —— —— 12	Suddenly ——— ——— 46	

CHRISTENED	Males — 8031	BURIED	Males — 9781	Of the Plague 0
	Females 7656		Females 9700	
	In all — 15687		In all — 19481	

Decreaſed in the Burials this Year 990

1703.

A General BILL of all the Chriſtenings and Burials,

From the 15th of December 1702, to the 14th of December 1703.

According to the Report made to the Queen's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.		Bur.		Bur.
St ALBAN in Wood-ſtreet	26	St Gregory by St Paul's	77	St Mary Mounthaw	1
Alhallows Barkin	93	St Helen near Biſhopſgate	30	St Mary Somerſet	24
Alhallows in Bread-ſtreet	13	St James in Duke's Place	24	St Mary Staining	17
Alhallows the Great	38	St James at Garlickhithe	45	St Mary Woolchurch	0
Alhallows in Honey-lane	0	St John Baptiſt by Dowgate	12	St Mary Woolnoth	30
Alhallows the Leſs	11	St John the Evangeliſt	3	St Matthew in Friday-ſtreet	15
Alhallows in Lombard-ſtreet	16	St John Zachary	22	St Michael Baſſiſhaw	34
Alhallows Staining	38	St Katherine Coleman	47	St Michael in Cornhill	21
Alhallows on London Wall	70	St Katherine Creechurch	45	St Michael in Crooked-lane	24
St Alphage near Sion College	31	St Laurence Jewry	29	St Michael at Queenhithe	36
St Andrew Hubbard	10	St Laurence Pountney	16	St Michael at Quern	11
St Andrew Underſhaft	45	St Leonard in Eaſtcheap	11	St Michael Royal	30
St Andrew Wardrobe	48	St Leonard in Foſter-lane	37	St Michael in Wood-ſtreet	7
St Ann within Alderſgate	31	St Magnus by London Bridge	39	St Mildred in Bread-ſtreet	14
St Ann in Black Friars	118	St Margaret in Lothbury	35	St Mildred in the Poultry	14
St Anthony, vulg. Antholin	12	St Margaret Moſes	3	St Nicholas Acons	1
St Auguſtin, vulg. Auſtin	20	St Margaret in New Fiſh-ſtr.	0	St Nicholas Coleabby	10
St Bartholomew by Exchange	17	St Margaret Pattons	14	St Nicholas Olave	6
St Benedict, v. Bennet Fink	12	St Martin Ironmonger-lane	6	St Olave in Hart-ſtreet	39
St Bennet Gracechurch	16	St Martin at Ludgate	36	St Olave in the Old Jewry	13
St Bennet at Paul's Wharf	49	St Martin Orgars	24	St Olave in Silver-ſtreet	21
St Bennet Sherehog	3	St Martin Outwich	8	St Pancras in Pancras-lane	7
St Botolph at Billinſgate	9	St Martin Vintrey	34	St Peter in Cheapſide	14
Chriſt Church Pariſh	105	St Mary Abchurch	28	St Peter in Cornhill	39
St Chriſtopher's Pariſh	15	St Mary in Aldermanbury	33	St Peter near Paul's Wharf	14
St Clement near Eaſtcheap	16	St Mary Aldermary	30	St Peter Poor in Broad-ſtr.	23
St Dionis Backchurch	38	St Mary le Bow in Cheapſide	25	St Stephen in Coleman-ſtreet	120
St Dunſtan in the Eaſt	77	St Mary Bothaw at Dowgate	3	St Stephen in Walbrook	25
St Edmund the King	23	St Mary Colechurch	2	St Swithin at London-ſtone	24
St Ethelburga's Pariſh	21	St Mary Hill by Billinſgate	32	St Thomas the Apoſtle	9
St Faith under St Paul's	26	St Mary Magd. in Milk-ſtr.	0	Trinity Pariſh	24
St Gabriel in Fenchurch-ſtr.	9	St Mary Magd. Old Fiſh-ſtr.	33	St Vedaſt, alias Foſter	15
St George in Botolph-lane	18				

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1773 Buried 2550 Plague 0

St Andrew in Holborn	981	Bridewell Precinct	10	St Saviour in Southwark	509
St Bartholomew the Great	70	St Bridget, vulg. St Bride's	268	St Sepulchre's Pariſh	622
St Bartholomew the Leſs	31	St Dunſtan in the Weſt	159	St Thomas in Southwark	66
St Botolph by Alderſgate	186	St George in Southwark	366	Trinity in the Minories	20
St Botolph by Aldgate	530	St Giles by Cripplegate	1197	The Peſt-houſe	
St Botolph by Biſhopſgate	553	St Olave in Southwark	717		

Chriſtened in the ſixteen Pariſhes without the Walls 4781 Buried 6285 Plague 0

Chriſt Church in Surrey —145	St John at Wapping ——244	St Mary Magd. Bermondſey 387
St Dunſtan at Stepney——2150	St Katherine near the Tower 156	St Mary at Newington ——213
St Giles in the Fields ——1333	St Leonard in Shoreditch —490	St Mary at Rotherhith ——161
St James at Clerkenwell —353	St Mary at Iſlington ——115	St Mary in Whitechapel —804
St John at Hackney ——105	St Mary at Lambeth ——250	St Paul at Shadwell ——423

Chriſtened in the fifteen Out Pariſhes in Middleſex and Surrey 5392
Buried 7329 Plague 0

St Ann in Weſtminſter —424	St Margaret in Weſtminſt. 919	St Mary Savoy in the Strand 112
St Clement Danes — ——436	St Martin in the Fields —1400	St Paul in Covent Garden 205
St James in Weſtminſter 1060		

Chriſtened in the ſeven Pariſhes in the City and Liberties of Weſtminſter 3502
Buried 4556 Plague 0

DISEASES and CASUALTIES.

AGED —— —1563	Gangrene —— — 16	Rupture —— —— 23	
Ague — —— 7	Gout —— —— 26	St Anthony's Fire—— 10	CASUALTIES.
Apoplexy —— — 71	Green Sickneſs —— 1	Scald Head —— — 1	
Aſthma —— —— 3	Grief —— ——— 6	Scarlet Fever ——— 7	Abortive — —— 111
Bedridden —— — 3	Griping in the Guts— 985	Scurvy ——— —— 14	Bruiſed — ——— 2
Black Catterick —— 1	Headmouldſhot —— 9	Small Pox — ——— 898	Burnt ——— —— 3
Bleeding — ——— 4	Hectic Fever ——— 1	Sores and Ulcers —— 45	Choaked — ——— 2
Bloody Flux ——— 6	Hiccough — —— 1	Spleen — ——— 3	Dead by Misfortune (ſo reported) 1
Burſten —— —— 3	Hooping Cough —— 5	Spotted Fever ——— 74	Drowned — —— 61
Cancer — ——— 77	Jaundies — ——— 102	Stone ——— —— 39	Executed — ——— 6
Canker —— —— 9	Impoſthume — —— 49	Stoppage in the Stomach 333	Found dead in the Streets, &c. 19
Childbed — ——— 217	Infants — ——— 25	Strangury — —— 9	Frighted — ——— 1
Chriſomes —— — 51	Lethargy —— —— 5	Strongullion — — 3	Hang'd and made away themſelves 21
Colick — ——— 102	Livergrown —— — 6	Suddenly — ——— 68	Killed by ſeveral Accidents 72
Conſumption ——2831	Lunatick — ——— 34	Surfeit ——— — 70	Murdered — —— 12
Convulſion — ——5493	Meaſles —— —— 51	Teeth —— ———1305	Overlaid — ——— 69
Cough — ——— 3	Mortification ——— 14	Thruſh —— —— 41	Scalded ——— — 1
Cut of the Stone —— 1	Pain in the Head —— 1	Tiſſick — ——— 310	Stifled — ——— 3
Diabetes — ——— 4	Palſy —— ——— 20	Twiſting of the Guts 1	Stillborn —— —— 443
Diſtracted —— —— 2	Pleuriſy —— —— 23	Tympany — —— 8	Suffocated with Charcoal 1
Dropſy — ——— 848	Purples — ——— 11	Vomiting —— — 9	
Evil ——— —— 101	Quinſy —— —— 14	Water in the Head — 11	
Fever —— ——3162	Raſh —— ——— 5	Wen ——— —— 1	
Fiſtula —— —— 27	Rheumatiſm — — 26	Wind — ——— 1	
Flux ——— —— 5	Rickets — ——— 381	Wolf —— ——— 1	
French Pox — —— 63	Riſing of the Lights— 86	Worms —— —— 47	

CHRISTENED { Males — 7765 / Females 7683 / In all — 15448 } | BURIED { Males — 10354 / Females 10366 / In all — 20720 } Of the Plague 0

Increaſed in the Burials this Year 1239

1704.

A General BILL of all the Chriſtenings and Burials,

From the 14th of December 1703, to the 19th of December 1704.

According to the Report made to the Queen's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	27
Alhallows Barkin	69
Alhallows in Bread-ſtreet	24
Alhallows the Great	50
Alhallows in Honey-lane	4
Alhallows the Leſs	16
Alhallows in Lombard-ſtreet	22
Alhallows Staining	31
Alhallows on London Wall	70
St Alphage near Sion College	36
St Andrew Hubbard	10
St Andrew Underſhaft	39
St Andrew Wardrobe	47
St Ann within Alderſgate	33
St Ann in Black Friars	137
St Anthony, vulg. Antholin	15
St Auguſtin, vulg. Auſtin	16
St Bartholomew by Exchange	24
St Benedict, v. Bennet Fink	21
St Bennet Gracechurch	13
St Bennet at Paul's Wharf	52
St Bennet Sherehog	2
St Botolph at Billinſgate	4
Chriſt Church Pariſh	115
St Chriſtopher's Pariſh	10
St Clement near Eaſtcheap	13
St Dionis Backchurch	41
St Dunſtan in the Eaſt	69
St Edmund the King	27
St Ethelburga's Pariſh	26
St Faith under St Paul's	43
St Gabriel in Fenchurch-ſtr.	12
St George in Botolph-lane	15
St Gregory by St Paul's	73
St Helen near Biſhopſgate	36
St James in Duke's Place	21
St James at Garlickhithe	45
St John Baptiſt by Dowgate	19
St John the Evangeliſt	4
St John Zachary	15
St Katherine Coleman	69
St Katherine Creechurch	52
St Laurence Jewry	48
St Laurence Pountney	21
St Leonard in Eaſtcheap	7
St Leonard in Foſter-lane	33
St Magnus by London Bridge	45
St Margaret in Lothbury	34
St Margaret Moſes	1
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattons	15
St Martin Ironmonger-lane	9
St Martin at Ludgate	31
St Martin Orgars	24
St Martin Outwich	12
St Martin Vintrey	38
St Mary Abchurch	25
St Mary in Aldermanbury	32
St Mary Aldermary	18
St Mary le Bow in Cheapſide	31
St Mary Bothaw at Dowgate	7
St Mary Colechurch	2
St Mary Hill by Billinſgate	29
St Mary Magd. in Milk-ſtr.	0
St Mary Magd. Old Fiſh-ſtr.	40
St Mary Mounthaw	13
St Mary Somerſet	35
St Mary Staining	16
St Mary Woolchurch	0
St Mary Woolnoth	25
St Matthew in Friday-ſtreet	18
St Michael Baſſiſhaw	36
St Michael in Cornhill	17
St Michael in Crooked-lane	23
St Michael at Queenhithe	34
St Michael at Quern	13
St Michael Royal	20
St Michael in Wood-ſtreet	5
St Mildred in Bread-ſtreet	15
St Mildred in the Poultry	13
St Nicholas Acons	0
St Nicholas Coleabby	28
St Nicholas Olave	11
St Olave in Hart-ſtreet	40
St Olave in the Old Jewry	13
St Olave in Silver-ſtreet	22
St Pancras in Pancras-lane	8
St Peter in Cheapſide	11
St Peter in Cornhill	27
St Peter near Paul's Wharf	19
St Peter Poor in Broad-ſtr.	33
St Stephen in Coleman-ſtreet	144
St Stephen in Walbrook	21
St Swithin at London-ſtone	23
St Thomas the Apoſtle	16
Trinity Pariſh	26
St Vedaſt, alias Foſter	38

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1928 Buried 2732 Plague 0

St Andrew in Holborn	1087	Bridewell Precinct — — 23
St Bartholomew the Great	94	St Bridget, vulg. St Bride's 327
St Bartholomew the Leſs	30	St Dunſtan in the Weſt — 190
St Botolph by Alderſgate	232	St George in Southwark — 376
St Botolph by Aldgate	645	St Giles by Cripplegate — 1160
St Botolph by Biſhopſgate	545	St Olave in Southwark — 747
St Saviour in Southwark	594	
St Sepulchre's Pariſh	658	
St Thomas in Southwark	61	
Trinity in the Minories	26	
The Peſt-houſe	—	

Chriſtened in the ſixteen Pariſhes without the Walls 4868 Buried 6795 Plague 0

1704.

Chriſt Church in Surrey —137	St John at Wapping ——331	St Mary Magd. Bermondſey 408
St Dunſtan at Stepney——2406	St Katherine near the Tower 178	St Mary at Newington ——179
St Giles in the Fields ——1458	St Leonard in Shoreditch—658	St Mary at Rotherhith ——215
St James at Clerkenwell —363	St Mary at Iſlington — —147	St Mary in Whitechapel —853
St John at Hackney ——134	St Mary at Lambeth — —246	St Paul at Shadwell ——498

Chriſtened in the fifteen Out Pariſhes in Middleſex and Surrey 5494 Buried 8251 Pl. o

St Ann in Weſtminſter - —505	St Margaret in Weſtminſt. 1023	St Mary Savoy in the Strand 130
St Clement Danes — ——455	St Martin in the Fields—1489	St Paul in Covent Garden 205
St James in Weſtminſter 1099		

Chriſtened in the ſeven Pariſhes in the City and Liberties of Weſtminſter 3605
Buried 4906 Pl. o

DISEASES and CASUALTIES.

AGED — ——1799	Gravel — —— 1	St Anthony's Fire - — 6	CASUALTIES.
Ague —— — 6	Grief —— —— 5	Scarlet Fever —— 8	
Apoplexy — —— 53	Griping in the Guts—1134	Scurvy —— —— 14	
Aſthma —— — 11	Headmouldſhot — — 18	Small Pox ——— —1501	Abortive — —— 102
Bedridden — —— 8	Hectic Fever —— 1	Sores and Ulcers —— 43	Broken Leg — — 1
Bleeding —— — 3	Horſhoehead — — 1	Spleen — —— 5	Bruiſed — —— 4
Bloody Flux —— 5	Jaundies —— —— 84	Spotted Fever — — 61	Burnt —— —— 42
Burſten —— — 2	Impoſthume —— 57	Stone —— —— 45	Choaked with a Piece of Meat 1
Cancer — —— 62	Infants —— —— 32	Stone Colick —— 1	Drowned — —— 52
Canker —— —— 6	Inflammation —— 1	Stoppage in the Stomach 293	Exceſſive Drinking — 1
Childbed — —— 266	Leproſy —— —— 2	Strangury — —— 3	Executed — —— 9
Chincough — —— 1	Lethargy — —— 4	Strongullion — — 4	Found dead in the Streets, &c. 25
Chriſomes — —— 69	Livergrown — — 8	Suddenly — —— 64	Hanged and made away themſelves 25
Colick —— — 125	Lunatick — —— 46	Surfeit —— — 61	Killed by ſeveral Accidents 63
Conſumption ——3013	Malignant Fever —— 1	Swelling — —— 2	Murdered — —— 8
Convulſion — —5987	Meaſles —— — 12	Teeth —— —1332	Overlaid —— — 71
Cough — —— 1	Megrims — —— 4	Thruſh —— —— 38	Scalded — —— 1
Cut of the Stone —— 1	Mortification —— 22	Tiſſick — —— 295	Smothered — —— 4
Diabetes — —— 4	Palſy —— —— 30	Twiſting of the Guts 8	Stifled in Mud — — 1
Diſtracted — —— 1	Pleuriſy — —— 40	Tympany — —— 15	Stillborn — —— 486
Dropſy — —— 918	Purples —— — 14	Vapours — —— 1	
Evil —— —— 94	Quinſy —— —— 16	Vomiting — —— 18	
Fever —— ——3243	Raſh —— —— 2	Vomiting and Looſneſs 3	
Fiſtula —— — 32	Rheumatiſm — — 42	Water in the Head — 11	
Flux —— —— 7	Rickets — —— 421	Wen —— —— 1	
French Pox — —— 52	Riſing of the Lights— 107	White Swelling — — 3	
Gangrene —— — 16	Rupture — —— 27	Worms — —— 42	
Gout —— —— 23			

CHRISTENED	Males — 8153 Females 7742 In all — 15895	BURIED	Males — 11401 Females 11283 In all — 22684 Pl. o

Increaſed in the Burials this Year 1964

A General

1705.

A General BILL of all the Chriſtenings and Burials,

From the 19th of December 1704, to the 18th of December 1705.

According to the Report made to the Queen's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	32
Alhallows Barkin —	84
Alhallows in Bread-ſtreet —	15
Alhallows the Great ——	49
Alhallows in Honey-lane —	6
Alhallows the Leſs ———	17
Alhallows in Lombard-ſtreet	18
Alhallows Staining — ——	42
Alhallows on London Wall	61
St Alphage near Sion College	27
St Andrew Hubbard — —	8
St Andrew Underſhaft ——	38
St Andrew Wardrobe ——	64
St Ann within Alderſgate —	39
St Ann in Black Friars - —	117
St Anthony, vulg. Antholin	9
St Auguſtin, vulg. Auſtin—	13
St Bartholomew by Exchange	21
St Benedict, v. Bennet Fink	34
St Bennet Gracechurch - —	14
St Bennet at Paul's Wharf	46
St Bennet Sherehog - ——	1
St Botolph at Billinſgate —	13
Chriſt Church Pariſh ——	106
St Chriſtopher's Pariſh ——	19
St Clement near Eaſtcheap	17
St Dionis Backchurch ——	22
St Dunſtan in the Eaſt ——	66
St Edmund the King — —	29
St Ethelburga's Pariſh ——	27
St Faith under St Paul's —	40
St Gabriel in Fenchurch-ſtr.	8
St George in Botolph-lane—	13
St Gregory by St Paul's —	72
St Helen near Biſhopſgate—	30
St James in Duke's Place —	36
St James at Garlickhithe —	29
St John Baptiſt by Dowgate	19
St John the Evangeliſt ——	3
St John Zachary —— —	17
St Katherine Coleman ——	61
St Katherine Creechurch —	54
St Laurence Jewry ———	42
St Laurence Pountney ——	11
St Leonard in Eaſtcheap —	17
St Leonard in Foſter-lane—	40
St Magnus by London Bridge	43
St Margaret in Lothbury—	41
St Margaret Moſes ———	4
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattons — —	19
St Martin Ironmonger-lane	12
St Martin at Ludgate ——	39
St Martin Orgars —— —	11
St Martin Outwich ———	9
St Martin Vintrey — ——	25
St Mary Abchurch — —	26
St Mary in Aldermanbury—	37
St Mary Aldermary — —	20
St Mary le Bow in Cheapſide	23
St Mary Bothaw at Dowgate	6
St Mary Colechurch ——	0
St Mary Hill by Billinſgate	40
St Mary Magd. in Milk-ſtr.	0
St Mary Magd. Old Fiſh-ſtr.	33
St Mary Mounthaw — —	7
St Mary Somerſet — ——	38
St Mary Staining —— —	16
St Mary Woolchurch ——	1
St Mary Woolnoth ———	25
St Matthew in Friday-ſtreet	8
St Michael Baſſiſhaw — —	35
St Michael in Cornhill ——	18
St Michael in Crooked-lane	29
St Michael at Queenhithe—	49
St Michael at Quern ——	16
St Michael Royal —— —	10
St Michael in Wood-ſtreet	9
St Mildred in Bread-ſtreet	14
St Mildred in the Poultry	17
St Nicholas Acons —— —	3
St Nicholas Coleabby ——	28
St Nicholas Olave ———	9
St Olave in Hart-ſtreet - —	33
St Olave in the Old Jewry	13
St Olave in Silver-ſtreet —	28
St Pancras in Pancras-lane	4
St Peter in Cheapſide ——	13
St Peter in Cornhill ———	36
St Peter near Paul's Wharf	12
St Peter Poor in Broad-ſtr.	36
St Stephen in Coleman-ſtreet	122
St Stephen in Walbrook —	20
St Swithin at London-ſtone	23
St Thomas the Apoſtle - —	30
Trinity Pariſh —— ——	26
St Vedaſt, alias Foſter ——	34

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1850 Buried 2696

St Andrew in Holborn ———	942
St Bartholomew the Great--	74
St Bartholomew the Leſs —	29
St Botolph by Alderſgate —	249
St Botolph by Aldgate ——	617
St Botolph by Biſhopſgate—	549
Bridewell Precinct ———	14
St Bridget, vulg. St Bride's	315
St Dunſtan in the Weſt - —	184
St George in Southwark —	373
St Giles by Cripplegate —	1189
St Olave in Southwark -—	799
St Saviour in Southwark —	625
St Sepulchre's Pariſh -——	631
St Thomas in Southwark—	76
Trinity in the Minories -—	26
The Peſt-houſe — ——	

Chriſtened in the ſixteen Pariſhes without the Walls 5013 Buried 6692

1705.

Chriſt Church in Surrey —176	St John at Wapping ——287	St Mary Magd. Bermondſey 403
St Dunſtan at Stepney——2267	St Katherine near the Tower 166	St Mary at Newington ——197
St Giles in the Fields ——1544	St Leonard in Shoreditch —637	St Mary at Rotherhith ——211
St James at Clerkenwell —371	St Mary at Iſlington — —143	St Mary in Whitechapel —812
St John at Hackney ——125	St Mary at Lambeth ——299	St Paul at Shadwell ——419

Chriſtened in the fifteen Out Pariſhes in Middleſex and Surrey 5891 Buried 8057

St Ann in Weſtminſter - —439	St Margaret in Weſtminſter 973	St Mary Savoy in the Strand 120
St Clement Danes — ——493	St Martin in the Fields —1489	St Paul in Covent Garden 204
St James in Weſtminſter —934		

Chriſtened in the ſeven Pariſhes in the City and Liberties of Weſtminſter 3391 Buried 4652

DISEASES and CASUALTIES.

AGED — ——1746	Gangrene —— — 7	Rupture —— —— 16	
Ague — — 3	Gout —— —— 24	St Anthony's Fire—— 9	CASUALTIES.
Apoplexy — —— 66	Grief —— —— 2	Scarlet Fever —— 5	
Aſthma — —— 21	Griping in the Guts—1021	Scurvy —— —— 6	Abortive — —— 79
Bedridden —— — 5	Headmouldſhot —— 20	Small Pox — ——1095	Broken Leg — — 3
Bleeding —— —— 2	Jaundies — —— 78	Sores and Ulcers —— 37	Bruiſed —— —— 6
Bloody Flux —— 10	Impoſthume — —— 50	Spleen —— —— 6	Burnt —— —— 6
Burſten —— —— 6	Infants —— —— 21	Spotted Fever —— 41	Died by Misfortune (ſo reported) 2
Cancer — —— 66	Inflammation — — 1	Stagnation in the Head 1	Died by cutting off a Leg 1
Canker —— —— 11	Lethargy — —— 8	Stone —— —— 50	Drowned — —— 66
Childbed —— — 287	Livergrown — —— 3	Stoppage in the Stomach 244	Executed —— —— 9
Chincough — —— 5	Looſneſs —— —— 2	Strangury —— —— 8	Found dead in the Streets, &c. 14
Chriſomes —— — 44	Lunatick — —— 18	Strongullion —— 3	Hanged and made away themſelves 27
Colick — —— 126	Malignant Fever —— 1	Suddenly —— —— 68	Killed by ſeveral Accidents 54
Conſumption ——2784	Meaſles — —— 319	Surfeit —— —— 56	Murdered — —— 4
Convulſion — ——6248	Megrims —— — 2	Teeth —— —1384	Overlaid —— —— 62
Cough — —— 12	Mortification —— 24	Thruſh —— —— 62	Stabbed — —— 1
Cut of the Stone —— 2	Pain in the Side —— 1	Tiſſick —— —— 356	Stifled in a Houſe of Office 1
Diabetes — —— 2	Palſy —— —— 23	Twiſting of the Guts 6	Stillborn —— —— 490
Diſtracted — —— 1	Pleuriſy —— —— 50	Tympany — —— 14	Suffocated —— — 1
Dropſy —— —— 786	Purples — —— 12	Vapours —— —— 1	
Evil —— —— 78	Quinſy —— —— 26	Vomiting —— — 11	
Fever —— ——3290	Raſh —— —— 2	Vomiting and Looſneſs 1	
Fiſtula —— —— 29	Rheumatiſm — —— 29	Water in the Head — 6	
Flux —— —— 2	Rickets —— —— 272	Wind —— —— 1	
French Pox — —— 29	Riſing of the Lights— 76	Worms —— —— 31	

CHRISTENED	Males — 8366	BURIED	Males — 11011
	Females 7779		Females 11086
	In all 16145		In all — 22097

Decreaſed in the Burials this Year 587

A General

1706.

A General BILL of all the Chriſtenings and Burials,

From the 18th of December 1705, to the 10th of December 1706.

According to the Report made to the Queen's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	20
Alhallows Barkin	78
Alhallows in Bread-ſtreet	12
Alhallows the Great	27
Alhallows in Honey-lane	2
Alhallows the Leſs	15
Alhallows in Lombard-ſtreet	14
Alhallows Staining	29
Alhallows on London Wall	57
St Alphage near Sion College	25
St Andrew Hubbard	11
St Andrew Underſhaft	53
St Andrew Wardrobe	41
St Ann within Alderſgate	28
St Ann in Black Friars	124
St Anthony, vulg. Antholin	15
St Auguſtin, vulg. Auſtin	15
St Bartholomew by Exchange	28
St Benedict, v. Bennet Fink	12
St Bennet Gracechurch	11
St Bennet at Paul's Wharf	32
St Bennet Sherehog	2
St Botolph at Billinſgate	9
Chriſt Church Pariſh	92
St Chriſtopher's Pariſh	9
St Clement near Eaſtcheap	15
St Dionis Backchurch	19
St Dunſtan in the Eaſt	68
St Edmund the King	23
St Ethelburga's Pariſh	25
St Faith under St Paul's	32
St Gabriel in Fenchurch-ſtr.	13
St George in Botolph-lane	15
St Gregory by St Paul's	48
St Helen near Biſhopſgate	24
St James in Duke's Place	17
St James at Garlickhithe	29
St John Baptiſt by Dowgate	14
St John the Evangeliſt	2
St John Zachary	6
St Katherine Coleman	59
St Katherine Creechurch	53
St Laurence Jewry	21
St Laurence Pountney	19
St Leonard in Eaſtcheap	9
St Leonard in Foſter-lane	22
St Magnus by London Bridge	44
St Margaret in Lothbury	27
St Margaret Moſes	1
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattons	11
St Martin Ironmonger-lane	8
St Martin at Ludgate	27
St Martin Orgars	17
St Martin Outwich	10
St Martin Vintrey	42
St Mary Abchurch	29
St Mary in Aldermanbury	22
St Mary Aldermary	19
St Mary le Bow in Cheapſide	25
St Mary Bothaw at Dowgate	2
St Mary Colechurch	1
St Mary Hill by Billinſgate	33
St Mary Magd. in Milk-ſtr.	0
St Mary Magd. Old Fiſh-ſtr.	28
St Mary Mounthaw	4
St Mary Somerſet	39
St Mary Staining	9
St Mary Woolchurch	0
St Mary Woolnoth	22
St Matthew in Friday-ſtreet	9
St Michael Baſſiſhaw	25
St Michael in Cornhill	25
St Michael in Crooked-lane	28
St Michael at Queenhithe	45
St Michael at Quern	7
St Michael Royal	18
St Michael in Wood-ſtreet	15
St Mildred in Bread-ſtreet	20
St Mildred in the Poultry	13
St Nicholas Acons	4
St Nicholas Coleabby	18
St Nicholas Olave	6
St Olave in Hart-ſtreet	25
St Olave in the Old Jewry	12
St Olave in Silver-ſtreet	24
St Pancras in Pancras-lane	7
St Peter in Cheapſide	10
St Peter in Cornhill	20
St Peter near Paul's Wharf	21
St Peter Poor in Broad-ſtr.	30
St Stephen in Coleman-ſtreet	103
St Stephen in Walbrook	16
St Swithin at London-ſtone	28
St Thomas the Apoſtle	8
Trinity Pariſh	12
St Vedaſt, alias Foſter	29

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1796 Buried 2292

St Andrew in Holborn	991	Bridewell Precinct 24
St Bartholomew the Great	48	St Bridget, vulg. St Bride's 305
St Bartholomew the Leſs	21	St Dunſtan in the Weſt 168
St Botolph by Alderſgate	175	St George in Southwark 326
St Botolph by Aldgate	544	St Giles by Cripplegate 1099
St Botolph by Biſhopſgate	474	St Olave in Southwark 665
		St Saviour in Southwark 545
		St Sepulchre's Pariſh 590
		St Thomas in Southwark 90
		Trinity in the Minories 19
		The Peſt-houſe —

Chriſtened in the ſixteen Pariſhes without the Walls 4806 Buried 6084

1706.

Chriſt Church in Surrey —140	St John at Wapping——268	St Mary Magd. Bermondſey 364
St Dunſtan at Stepney——2069	St Katherine near the Tower 159	St Mary at Newington ——174
St Giles in the Fields ——1303	St Leonard in Shoreditch —520	St Mary at Rotherhith ——196
St James at Clerkenwell —377	St Mary at Iſlington ——127	St Mary in Whitechapel —727
St John at Hackney ——111	St Mary at Lambeth ——299	St Paul at Shadwell ——437

Chriſtened in the fifteen Out Pariſhes in Middleſex and Surrey 5444 Buried 7271

St Ann in Weſtminſter —398	St Margaret in Weſtminſt. 804	St Mary Savoy in the Strand 141
St Clement Danes — ——436	St Martin in the Fields —1294	St Paul in Covent Garden 151
St James in Weſtminſter —976		

Chriſtened in the ſeven Pariſhes in the City and Liberties of Weſtminſter 3323 Buried 4200

DISEASES and CASUALTIES.

AGED —— —1563	Gangrene —— — 6	Rheumatiſm — — 29	Vomiting and Looſneſs 1
Ague — —— 2	Gout —— —— 17	Rickets — ——— 206	Water in the Head — 4
Apoplexy —— — 64	Great Cold — —— 2	Riſing of the Lights— 56	Wen —— —— 1
Aſthma —— —— 22	Grief —— —— 7	Rupture —— —— 7	Worms —— —— 12
Bedridden —— — 1	Griping in the Guts— 948	St Anthony's Fire—— 8	
Bleeding — ——— 4	Head-ach — ——— 1	Scald Head —— — 1	CASUALTIES.
Bloody Flux ——— 6	Headmouldſhot —— 10	Scarlet Fever ——— 4	
Burſten —— —— 4	Hooping Cough —— 2	Sciatica — ——— 2	Abortive — —— 90
Calenture — —— 2	Jaundies — ——— 87	Scurvy ——— —— 5	Bruiſed — ——— 4
Cancer — ——— 73	Impoſthume — —— 54	Shingles — ——— 1	Burnt ——— —— 5
Canker —— —— 6	Infants — ——— 25	Small Pox — ——— 721	Drowned — —— 74
Childbed — ——— 238	Leproſy — ——— 1	Sores and Ulcers —— 48	Executed — ——— 2
Chincough —— — 2	Lethargy —— —— 6	Spleen — ——— 5	Found dead in the Streets, &c. 16
Chriſomes —— — 38	Livergrown —— — 6	Spotted Fever ——— 54	Frighted — ——— 1
Colick — ——— 101	Looſneſs — ——— 6	Stone ——— —— 43	Hang'd and made away themſelves 40
Conſumption ———2716	Lunatick — ——— 26	Stoppage in the Stomach 188	Killed by ſeveral Accidents 54
Convulſion — ——5961	Malignant Fever —— 2	Strangury — —— 7	Murdered — —— 5
Cough — ——— 5	Meaſles —— —— 361	Strongullion — — 3	Overlaid — ——— 40
Cut of the Stone—— 1	Megrims ——— — 2	Suddenly — ——— 68	Scalded ——— — 4
Diabetes — ——— 6	Mortification ——— 28	Surfeit ——— — 52	Stillborn —— —— 459
Dropſy — ——— 742	Pain in the Side —— 1	Teeth —— ———1185	Suffocated — —— 3
Evil ——— —— 60	Palſy —— —— 23	Thruſh —— —— 38	Wounded at Sea —— 1
Fever —— ———2662	Pleuriſy —— —— 26	Tiſſick — ——— 251	
Fiſtula —— —— 22	Purples — ——— 9	Twiſting of the Guts 7	
Flux ——— —— 11	Quinſy —— —— 8	Tympany — —— 11	
French Pox — —— 47	Raſh —— ——— 3	Vomiting —— — 5	

CHRISTENED	Males — 7952	BURIED	Males — 9988
	Females 7417		Females 9859
	In all — 15369		In all — 19847

Decreaſed in the Burials this Year 2250

1707.

A General BILL of all the Chriſtenings and Burials,

From the 10th of December 1706, to the 16th of December 1707.

According to the Report made to the Queen's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	25
Alhallows Barkin	91
Alhallows in Bread-ſtreet	13
Alhallows the Great	48
Alhallows in Honey-lane	1
Alhallows the Leſs	18
Alhallows in Lombard-ſtreet	17
Alhallows Staining	30
Alhallows on London Wall	72
St Alphage near Sion College	36
St Andrew Hubbard	8
St Andrew Underſhaft	46
St Andrew Wardrobe	55
St Ann within Alderſgate	36
St Ann in Black Friars	135
St Anthony, vulg. Antholin	18
St Auguſtin, vulg. Auſtin	10
St Bartholomew by Exchange	14
St Benedict, v. Bennet Fink	21
St Bennet Gracechurch	13
St Bennet at Paul's Wharf	48
St Bennet Sherehog	2
St Botolph at Billinſgate	4
Chriſt Church Pariſh	103
St Chriſtopher's Pariſh	14
St Clement near Eaſtcheap	16
St Dionis Backchurch	28
St Dunſtan in the Eaſt	60
St Edmund the King	12
St Ethelburga's Pariſh	21
St Faith under St Paul's	32
St Gabriel in Fenchurch-ſtr.	7
St George in Botolph-lane	8
St Gregory by St Paul's	66
St Helen near Biſhopſgate	28
St James in Duke's Place	14
St James at Garlickhithe	38
St John Baptiſt by Dowgate	18
St John the Evangeliſt	3
St John Zachary	19
St Katherine Coleman	51
St Katherine Creechurch	65
St Laurence Jewry	33
St Laurence Pountney	20
St Leonard in Eaſtcheap	11
St Leonard in Foſter-lane	38
St Magnus by London Bridge	36
St Margaret in Lothbury	29
St Margaret Moſes	0
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattons	10
St Martin Ironmonger-lane	9
St Martin at Ludgate	29
St Martin Orgars	20
St Martin Outwich	6
St Martin Vintrey	31
St Mary Abchurch	32
St Mary in Aldermanbury	34
St Mary Aldermary	22
St Mary le Bow in Cheapſide	29
St Mary Bothaw at Dowgate	4
St Mary Colechurch	2
St Mary Hill by Billinſgate	36
St Mary Magd. in Milk-ſtr.	0
St Mary Magd. Old Fiſh-ſtr.	23
St Mary Mounthaw	7
St Mary Somerſet	34
St Mary Staining	11
St Mary Woolchurch	0
St Mary Woolnoth	34
St Matthew in Friday-ſtreet	12
St Michael Baſſiſhaw	25
St Michael in Cornhill	22
St Michael in Crooked-lane	23
St Michael at Queenhithe	36
St Michael at Quern	9
St Michael Royal	16
St Michael in Wood-ſtreet	23
St Mildred in Bread-ſtreet	17
St Mildred in the Poultry	21
St Nicholas Acons	6
St Nicholas Coleabby	15
St Nicholas Olave	12
St Olave in Hart-ſtreet	26
St Olave in the Old Jewry	12
St Olave in Silver-ſtreet	41
St Pancras in Pancras-lane	8
St Peter in Cheapſide	8
St Peter in Cornhill	25
St Peter near Paul's Wharf	11
St Peter Poor in Broad-ſtr.	28
St Stephen in Coleman-ſtreet	104
St Stephen in Walbrook	24
St Swithin at London-ſtone	24
St Thomas the Apoſtle	8
Trinity Pariſh	15
St Vedaſt, alias Foſter	35

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1879 Buried 2513

St Andrew in Holborn	986
St Bartholomew the Great	60
St Bartholomew the Leſs	31
St Botolph by Alderſgate	182
St Botolph by Aldgate	621
St Botolph by Biſhopſgate	524
Bridewell Precinct	30
St Bridget, vulg. St Bride's	285
St Dunſtan in the Weſt	178
St George in Southwark	386
St Giles by Cripplegate	1307
St Olave in Southwark	730
St Saviour in Southwark	599
St Sepulchre's Pariſh	658
St Thomas in Southwark	139
Trinity in the Minories	25
The Peſt-houſe	—

Chriſtened in the ſixteen Pariſhes without the Walls 5071 Buried 6741

1707.

Chriſt Church in Surrey — 118	St John at Wapping — 360	St Mary Magd. Bermondſey 395
St Dunſtan at Stepney — 2127	St Katherine near the Tower 147	St Mary at Newington — 195
St Giles in the Fields — 1425	St Leonard in Shoreditch — 540	St Mary at Rotherhith — 220
St James at Clerkenwell — 419	St Mary at Iſlington — 132	St Mary in Whitechapel — 787
St John at Hackney — 139	St Mary at Lambeth — 315	St Paul at Shadwell — 424

Chriſtened in the fifteen Out Pariſhes in Middleſex and Surrey 5703 Buried 7743

St Ann in Weſtminſter — 445	St Margaret in Weſtminſt. 890	St Mary Savoy in the Strand 132
St Clement Danes — 429	St Martin in the Fields — 1485	St Paul in Covent Garden 192
St James in Weſtminſter 1030		

Chriſtened in the ſeven Pariſhes in the City and Liberties of Weſtminſter 3413 Buried 4603

DISEASES and CASUALTIES.

AGED — 1965	Headmouldſhot — 27	Strangury — 10
Ague — 2	Hectic Fever — 3	Strongullion — 1
Apoplexy — 71	Hooping Cough — 3	Suddenly — 68
Aſthma — 26	Jaundies — 81	Surfeit — 33
Bedridden — 6	Impoſthume — 64	Teeth — 1343
Bleeding — 8	Infants — 30	Thruſh — 54
Bloody Flux — 4	Leproſy — 1	Tiſſick — 387
Burſten — 3	Lethargy — 9	Twiſting of the Guts — 6
Cancer — 82	Livergrown — 5	Tympany — 16
Canker — 11	Looſneſs — 3	Vomiting — 18
Childbed — 258	Lunatick — 14	Vomiting and Looſneſs — 3
Chincough — 2	Malignant Fever — 2	Water in the Head — 9
Chriſomes — 55	Meaſles — 37	Wen — 1
Colick — 97	Mortification — 39	Worms — 35
Conſumption — 3049	Palſy — 17	
Convulſion — 5948	Pleuriſy — 28	CASUALTIES.
Cough — 5	Purples — 5	Abortive — 108
Cut of the Stone — 1	Putrification — 1	Bruiſed — 3
Diabetes — 1	Quinſy — 8	Burnt — 3
Diſtracted — 1	Raſh — 7	Drowned — 72
Dropſy — 903	Rheumatiſm — 32	Executed — 5
Evil — 94	Rickets — 226	Found dead in the Streets, &c. 21
Fever — 2947	Riſing of the Lights — 76	Frighted — 1
Fiſtula — 16	Rupture — 21	Hanged and made away themſelves — 38
Flux — 6	St Anthony's Fire — 10	Killed by ſeveral Accidents — 52
French Pox — 53	Scurvy — 2	Murdered — 6
Gangrene — 8	Small Pox — 1078	Overlaid — 68
Gout — 25	Sores and Ulcers — 58	Scalded — 1
Gravel — 1	Spleen — 3	Shot in a Mutiny — 2
Grief — 3	Spotted Fever — 42	Stillborn — 439
Griping in the Guts — 883	Stone and Stone Colick — 48	Strangled accidentally — 3
Head-ach — 1	Stoppage in the Stomach — 266	

CHRISTENED		BURIED	
Males —	8379	Males —	10785
Females	7687	Females	10815
In all —	16066	In all —	21600

Increaſed in the Burials this Year 1753

1708.

A General BILL of all the Chriſtenings and Burials,

From the 16th of December 1707, to the 14th of December 1708.

According to the Report made to the Queen's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	28
Alhallows Barkin	91
Alhallows in Bread-ſtreet	14
Alhallows the Great	42
Alhallows in Honey-lane	6
Alhallows the Leſs	10
Alhallows in Lombard-ſtreet	10
Alhallows Staining	16
Alhallows on London Wall	61
St Alphage near Sion College	32
St Andrew Hubbard	12
St Andrew Underſhaft	52
St Andrew Wardrobe	57
St Ann within Alderſgate	37
St Ann in Black Friars	134
St Anthony, vulg. Antholin	11
St Auguſtin, vulg. Auſtin	18
St Bartholomew by Exchange	21
St Benedict, v. Bennet Fink	22
St Bennet Gracechurch	9
St Bennet at Paul's Wharf	60
St Bennet Sherehog	0
St Botolph at Billinſgate	9
Chriſt Church Pariſh	99
St Chriſtopher's Pariſh	17
St Clement near Eaſtcheap	13
St Dionis Backchurch	21
St Dunſtan in the Eaſt	62
St Edmund the King	19
St Ethelburga's Pariſh	33
St Faith under St Paul's	36
St Gabriel in Fenchurch-ſtr.	11
St George in Botolph-lane	10
St Gregory by St Paul's	76
St Helen near Biſhopſgate	41
St James in Duke's Place	20
St James at Garlickhithe	36
St John Baptiſt by Dowgate	23
St John the Evangeliſt	5
St John Zachary	14
St Katherine Coleman	55
St Katherine Creechurch	59
St Laurence Jewry	37
St Laurence Pountney	13
St Leonard in Eaſtcheap	7
St Leonard in Foſter-lane	31
St Magnus by London Bridge	44
St Margaret in Lothbury	39
St Margaret Moſes	4
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattons	15
St Martin Ironmonger-lane	17
St Martin at Ludgate	34
St Martin Orgars	15
St Martin Outwich	10
St Martin Vintrey	40
St Mary Abchurch	21
St Mary in Aldermanbury	31
St Mary Aldermary	28
St Mary le Bow in Cheapſide	26
St Mary Bothaw at Dowgate	4
St Mary Colechurch	1
St Mary Hill by Billinſgate	32
St Mary Magd. in Milk-ſtr.	0
St Mary Magd. Old Fiſh-ſtr.	37
St Mary Mounthaw	18
St Mary Somerſet	32
St Mary Staining	11
St Mary Woolchurch	1
St Mary Woolnoth	28
St Matthew in Friday-ſtreet	8
St Michael Baſſiſhaw	21
St Michael in Cornhill	27
St Michael in Crooked-lane	27
St Michael at Queenhithe	42
St Michael at Quern	11
St Michael Royal	10
St Michael in Wood-ſtreet	15
St Mildred in Bread-ſtreet	15
St Mildred in the Poultry	10
St Nicholas Acons	5
St Nicholas Coleabby	10
St Nicholas Olave	5
St Olave in Hart-ſtreet	37
St Olave in the Old Jewry	9
St Olave in Silver-ſtreet	29
St Pancras in Pancras-lane	8
St Peter in Cheapſide	13
St Peter in Cornhill	25
St Peter near Paul's Wharf	9
St Peter Poor in Broad-ſtr.	25
St Stephen in Coleman-ſtreet	109
St Stephen in Walbrook	17
St Swithin at London-ſtone	18
St Thomas the Apoſtle	6
Trinity Pariſh	18
St Vedaſt, alias Foſter	27
Chriſtened in the ninety-ſeven Pariſhes within the Walls	1897
Buried	2534

St Andrew in Holborn	1017	Bridewell Precinct	29	St Saviour in Southwark	582
St Bartholomew the Great	74	St Bridget, vulg. St Bride's	344	St Sepulchre's Pariſh	606
St Bartholomew the Leſs	34	St Dunſtan in the Weſt	206	St Thomas in Southwark	111
St Botolph by Alderſgate	196	St George in Southwark	448	Trinity in the Minories	22
St Botolph by Aldgate	569	St Giles by Cripplegate	1204	The Peſt-houſe	—
St Botolph by Biſhopſgate	496	St Olave in Southwark	703		
Chriſtened in the ſixteen Pariſhes without the Walls			4890	Buried	6641

1708.

Chriſt Church in Surrey —150	St John at Wapping ——310	St Mary Magd. Bermondſey 463
St Dunſtan at Stepney——2084	St Katherine near the Tower 152	St Mary at Newington ——212
St Giles in the Fields ——1370	St Leonard in Shoreditch —543	St Mary at Rotherhith ——201
St James at Clerkenwell —412	St Mary at Iſlington — —294	St Mary in Whitechapel —647
St John at Hackney ——125	St Mary at Lambeth ——114	St Paul at Shadwell ——413

Chriſtened in the fifteen Out Pariſhes in Middleſex and Surrey 5661 Buried 7490

St Ann in Weſtminſter - —444	St Margaret in Weſtminſter 834	St Mary Savoy in the Strand 124
St Clement Danes — ——485	St Martin in the Fields —1487	St Paul in Covent Garden 194
St James in Weſtminſter—1058		

Chriſtened in the ſeven Pariſhes in the City and Liberties of Weſtminſter 3414 Buried 4626

DISEASES and CASUALTIES.

AGED — ——1728	French Pox — —— 39	Raſh —— —— 7	Vomiting —— — 28
Ague — — 4	Gangrene —— — 4	Rheumatiſm — —— 28	Vomiting and Looſneſs 1
Apoplexy — —— 76	Gout —— —— 17	Rickets —— —— 211	Water in the Head — 13
Aſthma — —— 15	Grief —— —— 9	Riſing of the Lights— 72	Wind —— —— 1
Bleeding —— —— 11	Griping in the Guts— 768	Rupture —— —— 11	Worms —— —— 42
Bloody Flux —— 6	Headmouldſhot —— 13	St Anthony's Fire—— 5	
Burſten —— —— 5	Hectic Fever —— 1	Scarlet Fever —— 1	CASUALTIES.
Calenture — —— 1	Hooping Cough —— 3	Scurvy —— —— 8	
Cancer — —— 77	Jaundies — —— 85	Small Pox — ——1687	Abortive — —— 120
Canker —— —— 10	Impoſthume — —— 61	Sores and Ulcers —— 36	Bruiſed —— —— 5
Chicken Pox —— 1	Infants —— —— 35	Spleen —— —— 4	Burnt —— —— 3
Childbed —— — 247	Inflammation — — 1	Spotted Fever —— 62	Dead by Misfortune— 1
Chincough — —— 3	Leproſy —— — 1	Stone —— —— 43	Drowned — —— 63
Chriſomes —— — 57	Lethargy — —— 9	Stone Colick —— 1	Executed —— —— 6
Colick — —— 93	Livergrown — —— 4	Stoppage in the Stomach 272	Extremity of Cold — 1
Conſumption ——2796	Looſneſs —— —— 10	Strangury —— —— 5	Found dead — — 27
Convulſion — ——5902	Lunatick — —— 22	Strongullion —— 3	Frighted — —— 1
Cough — —— 3	Malignant Fever —— 2	Suddenly —— —— 73	Killed accidentally — 50
Cramp — —— 1	Meaſles — —— 126	Suffocation of the Blood 1	Murdered — —— 15
Cut of the Stone —— 2	Mortification —— 46	Surfeit —— —— 36	Overlaid —— —— 53
Diabetes — —— 1	Pain in the Side —— 1	Teeth —— —1282	Planet-ſtruck —— 1
Diſtracted — —— 1	Palſy —— —— 23	Thruſh —— —— 59	Self-Murder —— 28
Dropſy —— —— 783	Plague in the Guts — 1	Tiſſick —— —— 324	Smothered — —— 1
Evil —— —— 68	Pleuriſy —— —— 47	Twiſting of the Guts 8	Stabbed — —— 1
Fever —— ——2738	Purples — —— 16	Tympany — —— 21	Stillborn —— —— 539
Fiſtula —— —— 30	Quinſy —— —— 14	Vapours —— —— 4	Suffocated —— — 1
Flux —— —— 9			

CHRISTENED	Males — 8239	BURIED	Males — 10604
	Females 7623		Females 10687
	In all 15862		In all — 21291

Decreaſed in the Burials this Year 309

A General

1709.

A General BILL of all the Chriſtenings and Burials,

From the 14th of December 1708, to the 13th of December 1709.

According to the Report made to the Queen's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	38
Alhallows Barkin	104
Alhallows in Bread-ſtreet	12
Alhallows the Great	49
Alhallows in Honey-lane	3
Alhallows the Leſs	22
Alhallows in Lombard-ſtreet	10
Alhallows Staining	29
Alhallows on London Wall	38
St Alphage near Sion College	46
St Andrew Hubbard	9
St Andrew Underſhaft	42
St Andrew Wardrobe	66
St Ann within Alderſgate	35
St Ann in Black Friars	129
St Anthony, vulg. Antholin	14
St Auguſtin, vulg. Auſtin	15
St Bartholomew by Exchange	16
St Benedict, v. Bennet Fink	20
St Bennet Gracechurch	9
St Bennet at Paul's Wharf	41
St Bennet Sherehog	2
St Botolph at Billinſgate	11
Chriſt Church Pariſh	101
St Chriſtopher's Pariſh	19
St Clement near Eaſtcheap	12
St Dionis Backchurch	28
St Dunſtan in the Eaſt	70
St Edmund the King	26
St Ethelburga's Pariſh	16
St Faith under St Paul's	27
St Gabriel in Fenchurch-ſtr.	7
St George in Botolph-lane	10
St Gregory by St Paul's	55
St Helen near Biſhopſgate	32
St James in Duke's Place	21
St James at Garlickhithe	39
St John Baptiſt by Dowgate	22
St John the Evangeliſt	10
St John Zachary	21
St Katherine Coleman	56
St Katherine Creechurch	53
St Laurence Jewry	49
St Laurence Pountney	18
St Leonard in Eaſtcheap	9
St Leonard in Foſter-lane	24
St Magnus by London Bridge	33
St Margaret in Lothbury	26
St Margaret Moſes	1
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattons	11
St Martin Ironmonger-lane	6
St Martin at Ludgate	35
St Martin Orgars	16
St Martin Outwich	18
St Martin Vintrey	37
St Mary Abchurch	26
St Mary in Aldermanbury	32
St Mary Aldermary	22
St Mary le Bow in Cheapſide	29
St Mary Bothaw at Dowgate	4
St Mary Colechurch	0
St Mary Hill by Billinſgate	35
St Mary Magd. in Milk-ſtr.	0
St Mary Magd. Old Fiſh-ſtr.	34
St Mary Mounthaw	14
St Mary Somerſet	19
St Mary Staining	25
St Mary Woolchurch	0
St Mary Woolnoth	32
St Matthew in Friday-ſtreet	17
St Michael Baſſiſhaw	23
St Michael in Cornhill	16
St Michael in Crooked-lane	29
St Michael at Queenhithe	40
St Michael at Quern	13
St Michael Royal	17
St Michael in Wood-ſtreet	14
St Mildred in Bread-ſtreet	11
St Mildred in the Poultry	21
St Nicholas Acons	3
St Nicholas Coleabby	10
St Nicholas Olave	11
St Olave in Hart-ſtreet	33
St Olave in the Old Jewry	9
St Olave in Silver-ſtreet	24
St Pancras in Pancras-lane	7
St Peter in Cheapſide	12
St Peter in Cornhill	26
St Peter near Paul's Wharf	10
St Peter Poor in Broad-ſtr.	40
St Stephen in Coleman-ſtreet	109
St Stephen in Walbrook	20
St Swithin at London-ſtone	21
St Thomas the Apoſtle	13
Trinity Pariſh	12
St Vedaſt, alias Foſter	22

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1852 Buried 2539

St Andrew in Holborn	1103
St Bartholomew the Great	55
St Bartholomew the Leſs	38
St Botolph by Alderſgate	222
St Botolph by Aldgate	616
St Botolph by Biſhopſgate	522
Bridewell Precinct	20
St Bridget, vulg. St Bride's	379
St Dunſtan in the Weſt	210
St George in Southwark	452
St Giles by Cripplegate	1349
St Olave in Southwark	771
St Saviour in Southwark	641
St Sepulchre's Pariſh	671
St Thomas in Southwark	195
Trinity in the Minories	18
The Peſt-houſe	

Chriſtened in the ſixteen Pariſhes without the Walls 4593 Buried 7262

1709.

Chriſt Church in Surrey —148	St John at Wapping ——347	St Mary Magd. Bermondſey 396
St Dunſtan at Stepney——2100	St Katherine near the Tower 169	St Mary at Newington ——237
St Giles in the Fields ——1296	St Leonard in Shoreditch —531	St Mary at Rotherhith —— 219
St James at Clerkenwell —364	St Mary at Iſlington — —124	St Mary in Whitechapel —707
St John at Hackney ——120	St Mary at Lambeth — —287	St Paul at Shadwell ——448

Chriſtened in the fifteen Out Pariſhes in Middleſex and Surrey 5288 Buried 7493

St Ann in Weſtminſter - —418	St Margaret in Weſtminſt. 860	St Mary Savoy in the Strand 157
St Clement Danes — ——475	St Martin in the Fields —1456	St Paul in Covent Garden 195
St James in Weſtminſter —945		

Chriſtened in the ſeven Pariſhes in the City and Liberties of Weſtminſter 3487 Buried 4506

DISEASES and CASUALTIES.

AGED — ——2056	French Pox — —— 61	Putrefaction —— 1	Twiſting of the Guts 11
Ague —— — 15	Gangrene —— — 6	Quinſy —— —— 20	Tympany — —— 17
Apoplexy — —— 64	Gout —— —— 19	Raſh —— —— 6	Vapours — —— 1
Aſthma —— — 27	Gravel — —— 2	Rheumatiſm — — 27	Vomiting — —— 22
Bleeding —— — 7	Green Sickneſs —— 1	Rickets — —— 295	Vomiting and Looſneſs 3
Bloody Flux —— 20	Grief —— —— 7	Riſing of the Lights — 89	Water in the Head — 11
Burſten —— — 5	Griping in the Guts— 812	Rupture — —— 14	Worms — —— 61
Calenture — — — 1	Head-ach — —— 1	St Anthony's Fire - — 3	
Cancer — —— 77	Headmouldſhot — — 12	Scarlet Fever —— 16	CASUALTIES.
Canker —— —— 11	Hooping Cough —— 1	Sciatica —— — 1	
Carbuncle —— — 1	Jaundies —— —— 98	Scurvy —— —— 6	Abortive — —— 86
Childbed — —— 215	Impoſthume —— 56	Small Pox —— —1024	Bruiſed — —— 5
Chincough — —— 1	Infants —— —— 29	Sores and Ulcers —— 39	Burnt —— —— 4
Chriſomes — —— 54	Leproſy —— —— 4	Spleen — —— 4	Died by Misfortune — 3
Colick —— — 96	Lethargy — —— 11	Spotted Fever — — 118	Drowned — —— 57
Conſumption ——3040	Livergrown — — 1	Stone —— —— 48	Exceſſive Drinking — 1
Convulſion — —5892	Looſneſs — —— 23	Stoppage in the Stomach 322	Executed — —— 3
Cough —— — 2	Lunatick — —— 34	Stoppage of the Urine 1	Found dead — —— 36
Diabetes — —— 1	Meaſles —— — 89	Strangury — —— 5	Frighted — —— 2
Diſtracted — —— 2	Megrims — —— 1	Strongullion — — 4	Killed accidentally — 45
Dropſy — —— 788	Miſcarriage — — — 1	Suddenly — —— 70	Murdered — —— 11
Evil —— —— 78	Mortification —— 50	Surfeit —— — 41	Overlaid —— — 41
Falling Sickneſs —— 1	Palſy —— —— 29	Swelling — —— 1	Self-Murder —— 36
Fever —— ——3140	Pleuriſy — —— 31	Teeth —— —1117	Smothered — —— 6
Fiſtula —— — 39	Polypus — —— 2	Thruſh —— —— 69	Stifled — —— 1
Flux —— —— 4	Purples —— — 24	Tiſſick — —— 421	Stillborn — —— 533

CHRISTENED	Males — 7840	BURIED	Males — 10907
	Females 7380		Females 10893
	In all — 15220		In all — 21800

Increaſed in the Burials this Year 509

A General

1710.

A General BILL of all the Chriſtenings and Burials,

From the 13th of December 1709, to the 12th of December 1710.

According to the Report made to the Queen's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	32
Alhallows Barkin	105
Alhallows in Bread-ſtreet	13
Alhallows the Great	63
Alhallows in Honey-lane	3
Alhallows the Leſs	33
Alhallows in Lombard-ſtreet	17
Alhallows Staining	38
Alhallows on London Wall	63
St Alphage near Sion College	50
St Andrew Hubbard	16
St Andrew Underſhaft	40
St Andrew Wardrobe	73
St Ann within Alderſgate	38
St Ann in Black Friars	126
St Anthony, vulg. Antholin	17
St Auguſtin, vulg. Auſtin	19
St Bartholomew by Exchange	21
St Benedict, v. Bennet Fink	27
St Bennet Gracechurch	14
St Bennet at Paul's Wharf	63
St Bennet Sherehog	0
St Botolph at Billinſgate	12
Chriſt Church Pariſh	154
St Chriſtopher's Pariſh	15
St Clement near Eaſtcheap	22
St Dionis Backchurch	32
St Dunſtan in the Eaſt	92
St Edmund the King	24
St Ethelburga's Pariſh	28
St Faith under St Paul's	28
St Gabriel in Fenchurch-ſtr.	11
St George in Botolph-lane	12
St Gregory by St Paul's	52
St Helen near Biſhopſgate	38
St James in Duke's Place	17
St James at Garlickhithe	39
St John Baptiſt by Dowgate	34
St John the Evangeliſt	2
St John Zachary	17
St Katherine Coleman	85
St Katherine Creechurch	68
St Laurence Jewry	51
St Laurence Pountney	11
St Leonard in Eaſtcheap	11
St Leonard in Foſter-lane	40
St Magnus by London Bridge	35
St Margaret in Lothbury	27
St Margaret Moſes	4
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattons	19
St Martin Ironmonger-lane	12
St Martin at Ludgate	33
St Martin Orgars	16
St Martin Outwich	10
St Martin Vintrey	54
St Mary Abchurch	33
St Mary in Aldermanbury	29
St Mary Aldermary	26
St Mary le Bow in Cheapſide	32
St Mary Bothaw at Dowgate	9
St Mary Colechurch	2
St Mary Hill by Billinſgate	35
St Mary Magd. in Milk-ſtr.	0
St Mary Magd. Old Fiſh-ſtr.	31
St Mary Mounthaw	14
St Mary Somerſet	42
St Mary Staining	16
St Mary Woolchurch	0
St Mary Woolnoth	31
St Matthew in Friday-ſtreet	15
St Michael Baſſiſhaw	32
St Michael in Cornhill	29
St Michael in Crooked-lane	28
St Michael at Queenhithe	45
St Michael at Quern	10
St Michael Royal	19
St Michael in Wood-ſtreet	13
St Mildred in Bread-ſtreet	12
St Mildred in the Poultry	16
St Nicholas Acons	5
St Nicholas Coleabby	18
St Nicholas Olave	9
St Olave in Hart-ſtreet	40
St Olave in the Old Jewry	5
St Olave in Silver-ſtreet	38
St Pancras in Pancras-lane	6
St Peter in Cheapſide	2
St Peter in Cornhill	42
St Peter near Paul's Wharf	20
St Peter Poor in Broad-ſtr.	29
St Stephen in Coleman-ſtreet	100
St Stephen in Walbrook	18
St Swithin at London-ſtone	23
St Thomas the Apoſtle	31
Trinity Pariſh	20
St Vedaſt, alias Foſter	26

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1815 Buried 2927

St Andrew in Holborn	1213
St Bartholomew the Great	74
St Bartholomew the Leſs	40
St Botolph by Alderſgate	211
St Botolph by Aldgate	641
St Botolph by Biſhopſgate	632
Bridewell Precinct	21
St Bridget, vulg. St Bride's	362
St Dunſtan in the Weſt	190
St George in Southwark	542
St Giles by Cripplegate	1637
St Olave in Southwark	811
St Saviour in Southwark	729
St Sepulchre's Pariſh	698
St Thomas in Southwark	162
Trinity in the Minories	16
The Peſt-houſe	—

Chriſtened in the ſixteen Pariſhes without the Walls 4751 Buried 7979

1710.

Chriſt Church in Surrey —163	St John at Wapping——289	St Mary Magd. Bermondſey 447
St Dunſtan at Stepney——2473	St Katherine near the Tower 200	St Mary at Newington ——186
St Giles in the Fields ——1653	St Leonard in Shoreditch —675	St Mary at Rotherhith ——174
St James at Clerkenwell —482	St Mary at Iſlington ———111	St Mary in Whitechapel —777
St John at Hackney———142	St Mary at Lambeth — —301	St Paul at Shadwell ———470

Chriſtened in the fifteen Out Pariſhes in Middleſex and Surrey 5134 Buried 8543

St Ann in Weſtminſter —458	St Margaret in Weſtminſt. 977	St Mary Savoy in the Strand 156
St Clement Danes ———528	St Martin in the Fields —1684	St Paul in Covent Garden 229
St James in Weſtminſter 1139		

Chriſtened in the ſeven Pariſhes in the City and Liberties of Weſtminſter 3228 Buried 5171

DISEASES and CASUALTIES.

ABORTIVE — — 112	Horſhoehead — — — — 3	Stoppage in the Stomach —— 232
Aged ——— ———1851	Jaundies ——— ——— 78	Strangury —— ——— 17
Ague ——— — ——— 10	Impoſthume ——— ——— 59	Strongullion ——— —— 1
Apoplexy —— — —— 76	Infants —— — ——— 39	Suddenly ——— ——— 65
Aſthma ——— ——— 25	Lethargy — — — — 3	Surfeit —— ——— — 60
Bedridden —— — —— 2	Livergrown ——— —— 8	Swelling —— —— —— 1
Bleeding ——— ——— 12	Looſneſs ——— ——— 13	Teeth ——— — ———1197
Bloody Flux —— —— 13	Lunatick —— —— —— 26	Thruſh —— —— —— 69
Burſten ——— ——— 4	Malignant Fever —— — 5	Tiſſick ——— ——— 241
Cancer ——— — —— 70	Meaſles ——— ——— 181	Twiſting of the Guts — — 12
Canker —— ——— — 14	Mortification —— —— 99	Tympany ——— ——— 11
Childbed ——— ——— 217	Pain in the Head ——— — 2	Vomiting ——— ——— 6
Chriſomes —— — —— 73	Palſy —— —— ——— 22	Water in the Head — —— 9
Colick ——— ——— 83	Piles —— ——— —— 1	Worms ——— ——— 75
Conſumption ——— ——2706	Plague in the Guts ——— 1	
Convulſion —— ———6046	Pleuriſy ——— — —— 24	CASUALTIES.
Cough ——— — —— 4	Purples —— — ——— 56	
Diabetes ——— ——— 1	Quinſy ——— — —— 8	Bruiſed —— —— —— 2
Died with Fat ——— — 1	Raſh —— — —— — 4	Burnt ——— — ——— 2
Dropſy ——— ——— 598	Rheumatiſm ——— —— 24	Dead by Misfortune ——— 1
Evil —— ——— —— 65	Rickets —— — — — 343	Drowned ——— ——— 49
Fever —— —— ———4397	Riſing of the Lights — —— 98	Exceſſive Drinking — —— 1
Fiſtula ——— —— —— 14	Rupture ——— ——— 21	Executed ——— ——— 3
Flux —— —— ——— 6	St Anthony's Fire — —— 1	Found dead ——— —— 28
French Pox ——— —— 55	Scald Head ——— ——— 1	Killed accidentally —— — 44
Gangrene —— ——— 14	Scarlet Fever ——— —— 15	Murdered ——— ——— 9
Gout ——— —— —— 18	Small Pox ——— ———3138	Overlaid —— — —— 51
Grief —— —— ——— 7	Sores and Ulcers ——— — 34	Poiſoned ——— ——— 1
Griping in the Guts — —— 707	Spleen — — — ——— 1	Scalded ——— — —— 1
Head-ach —— ——— 9	Spotted Fever ——— —— 343	Self-Murder —— ——— 33
Headmouldſhot —— —— 15	Stillborn ——— ——— 464	Stabbed ——— — —— 3
Hooping Cough — ——— 5	Stone ——— — ——— 51	

CHRISTENED		BURIED	
Males — 7640		Males — 11972	
Females 7288		Females 12648	
In all — 14928		In all — 24620	

Increaſed in the Burials this Year 2820

1711.

A General BILL of all the Chriſtenings and Burials,

From the 12th of December 1710, to the 11th of December 1711.

According to the Report made to the Queen's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	21
Alhallows Barkin	100
Alhallows in Bread-ſtreet	13
Alhallows the Great	47
Alhallows in Honey-lane	1
Alhallows the Leſs	12
Alhallows in Lombard-ſtreet	15
Alhallows Staining	31
Alhallows on London Wall	45
St Alphage near Sion College	30
St Andrew Hubbard	6
St Andrew Underſhaft	33
St Andrew Wardrobe	52
St Ann within Alderſgate	34
St Ann in Black Friars	166
St Anthony, vulg. Antholin	13
St Auguſtin, vulg. Auſtin	19
St Bartholomew by Exchange	19
St Benedict, v. Bennet Fink	18
St Bennet Gracechurch	5
St Bennet at Paul's Wharf	38
St Bennet Sherehog	1
St Botolph at Billinſgate	9
Chriſt Church Pariſh	108
St Chriſtopher's Pariſh	10
St Clement near Eaſtcheap	10
St Dionis Backchurch	29
St Dunſtan in the Eaſt	57
St Edmund the King	20
St Ethelburga's Pariſh	22
St Faith under St Paul's	27
St Gabriel in Fenchurch-ſtr.	6
St George in Botolph-lane	13
St Gregory by St Paul's	66
St Helen near Biſhopſgate	34
St James in Duke's Place	21
St James at Garlickhithe	40
St John Baptiſt by Dowgate	17
St John the Evangeliſt	4
St John Zachary	17
St Katherine Coleman	40
St Katherine Creechurch	64
St Laurence Jewry	44
St Laurence Pountney	22
St Leonard in Eaſtcheap	8
St Leonard in Foſter-lane	30
St Magnus by London Bridge	31
St Margaret in Lothbury	29
St Margaret Moſes	6
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattons	15
St Martin Ironmonger-lane	9
St Martin at Ludgate	23
St Martin Orgars	12
St Martin Outwich	20
St Martin Vintrey	34
St Mary Abchurch	23
St Mary in Aldermanbury	22
St Mary Aldermary	16
St Mary le Bow in Cheapſide	19
St Mary Bothaw at Dowgate	3
St Mary Colechurch	1
St Mary Hill by Billinſgate	23
St Mary Magd. in Milk-ſtr.	0
St Mary Magd. Old Fiſh-ſtr.	21
St Mary Mounthaw	8
St Mary Somerſet	32
St Mary Staining	22
St Mary Woolchurch	0
St Mary Woolnoth	16
St Matthew in Friday-ſtreet	13
St Michael Baſſiſhaw	23
St Michael in Cornhill	13
St Michael in Crooked-lane	19
St Michael at Queenhithe	29
St Michael at Quern	9
St Michael Royal	25
St Michael in Wood-ſtreet	11
St Mildred in Bread-ſtreet	12
St Mildred in the Poultry	17
St Nicholas Acons	4
St Nicholas Coleabby	8
St Nicholas Olave	3
St Olave in Hart-ſtreet	36
St Olave in the Old Jewry	5
St Olave in Silver-ſtreet	26
St Pancras in Pancras-lane	7
St Peter in Cheapſide	8
St Peter in Cornhill	36
St Peter near Paul's Wharf	12
St Peter Poor in Broad-ſtr.	31
St Stephen in Coleman-ſtreet	92
St Stephen in Walbrook	27
St Swithin at London-ſtone	24
St Thomas the Apoſtle	10
Trinity Pariſh	20
St Vedaſt, alias Foſter	29

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1719 Buried 2371

St Andrew in Holborn	977
St Bartholomew the Great	64
St Bartholomew the Leſs	36
St Botolph by Alderſgate	162
St Botolph by Aldgate	536
St Botolph by Biſhopſgate	465
Bridewell Precinct	21
St Bridget, vulg. St Bride's	339
St Dunſtan in the Weſt	180
St George in Southwark	363
St Giles by Cripplegate	1169
St Olave in Southwark	712
St Saviour in Southwark	571
St Sepulchre's Pariſh	611
St Thomas in Southwark	133
Trinity in the Minories	16
The Peſt-houſe	—

Chriſtened in the ſixteen Pariſhes without the Walls 4683 Buried 6355

1711.

Chriſt Church in Surrey —123	St John at Wapping——294	St Mary Magd. Bermondſey 376
St Dunſtan at Stepney——1893	St Katherine near the Tower 138	St Mary at Newington——174
St Giles in the Fields——1205	St Leonard in Shoreditch—465	St Mary at Rotherhith——154
St James at Clerkenwell —342	St Mary at Iſlington——146	St Mary in Whitechapel —645
St John at Hackney——120	St Mary at Lambeth——268	St Paul at Shadwell——337

Chriſtened in the fifteen Out Pariſhes in Middleſex and Surrey 5042 Buried 6680

St Ann in Weſtminſter —397	St Margaret in Weſtminſt. 874	St Mary Savoy in the Strand 168
St Clement Danes——468	St Martin in the Fields —1378	St Paul in Covent Garden 211
St James in Weſtminſter—931		

Chriſtened in the ſeven Pariſhes in the City and Liberties of Weſtminſter 3262 Buried 4427

DISEASES and CASUALTIES.

ABORTIVE—— 76	French Pox —— 70	Purples —— 13	Twiſting of the Guts 9
Aged ——1722	Gangrene —— 13	Quinſy —— 18	Tympany —— 9
Ague —— 1	Gout —— 21	Raſh —— 7	Vomiting —— 28
Apoplexy —— 78	Gravel —— 2	Rheumatiſm —— 9	Water in the Head — 6
Aſthma —— 23	Grief —— 9	Rickets —— 196	White Swelling —— 2
Bedridden —— 1	Griping in the Guts— 614	Riſing of the Lights— 92	Worms —— 61
Bleeding —— 8	Head-ach —— 2	Rupture —— 12	
Bloody Flux —— 9	Headmouldſhot —— 30	St Anthony's Fire—— 3	CASUALTIES.
Burſten —— 8	Hectic Fever —— 2	Scarlet Fever —— 4	
Cancer —— 75	Hooping Cough —— 7	Sciatica —— 1	Blown up —— 2
Canker —— 8	Horſhoehead —— 4	Scurvy —— 2	Bruiſed —— 5
Carbuncle —— 1	Jaundies —— 59	Small Pox —— 915	Burnt —— 3
Childbed —— 195	Impoſthume —— 37	Sores and Ulcers —— 42	Died by a Fall —— 1
Chincough —— 1	Infants —— 13	Spleen —— 1	Died by a broken Leg 1
Choaked with Fat — 1	Inflammation —— 1	Spotted Fever —— 142	Died of a Wound —— 1
Chriſomes —— 64	Leproſy —— 2	Stillborn —— 497	Drowned —— 63
Colick —— 90	Lethargy —— 7	Stone —— 41	Exceſſive Drinking — 1
Conſumption ——2520	Livergrown —— 6	Stone Colick —— 1	Executed —— 7
Convulſion —— 5516	Looſneſs —— 20	Stoppage in the Stomach 255	Found dead —— 25
Cough —— 1	Lunatick —— 35	Strangury —— 9	Killed accidentally —— 43
Cut of the Stone—— 1	Malignant Fever —— 5	Strongullion —— 5	Killed in a Duel —— 1
Diabetes —— 1	Meaſles —— 97	Suddenly —— 77	Murdered —— 8
Dropſy —— 625	Megrims —— 1	Surfeit —— 61	Overlaid —— 37
Evil —— 54	Melancholy —— 1	Teeth ——1013	Planet-ſtruck —— 1
Fever ——3461	Mortification —— 82	Thruſh —— 64	Scalded —— 1
Fiſtula —— 34	Palſy —— 25	Tiſſick —— 256	Self-Murder —— 26
Flux —— 1	Pleuriſy —— 16		

CHRISTENED	Males — 7482	BURIED	Males — 9841
	Females 7224		Females 9992
	In all — 14706		In all — 19833

Decreaſed in the Burials this Year 4787

1712.

A General BILL of all the Chriſtenings and Burials,

From the 11th of December 1711, to the 16th of December 1712.

According to the Report made to the Queen's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	27
Alhallows Barkin	91
Alhallows in Bread-ſtreet	15
Alhallows the Great	37
Alhallows in Honey-lane	7
Alhallows the Leſs	15
Alhallows in Lombard-ſtreet	17
Alhallows Staining	33
Alhallows on London Wall	58
St Alphage near Sion College	30
St Andrew Hubbard	1
St Andrew Underſhaft	29
St Andrew Wardrobe	42
St Ann within Alderſgate	28
St Ann in Black Friars	128
St Anthony, vulg. Antholin	16
St Auguſtin, vulg. Auſtin	11
St Bartholomew by Exchange	19
St Benedict, v. Bennet Fink	13
St Bennet Gracechurch	8
St Bennet at Paul's Wharf	41
St Bennet Sherehog	2
St Botolph at Billinſgate	12
Chriſt Church Pariſh	130
St Chriſtopher's Pariſh	9
St Clement near Eaſtcheap	18
St Dionis Backchurch	27
St Dunſtan in the Eaſt	74
St Edmund the King	21
St Ethelburga's Pariſh	33
St Faith under St Paul's	25
St Gabriel in Fenchurch-ſtr.	3
St George in Botolph-lane	14
St Gregory by St Paul's	45
St Helen near Biſhopſgate	24
St James in Duke's Place	23
St James at Garlickhithe	32
St John Baptiſt by Dowgate	29
St John the Evangeliſt	5
St John Zachary	25
St Katherine Coleman	41
St Katherine Creechurch	49
St Laurence Jewry	41
St Laurence Pountney	15
St Leonard in Eaſtcheap	7
St Leonard in Foſter-lane	29
St Magnus by London Bridge	33
St Margaret in Lothbury	31
St Margaret Moſes	2
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattons	13
St Martin Ironmonger-lane	8
St Martin at Ludgate	26
St Martin Orgars	11
St Martin Outwich	10
St Martin Vintrey	32
St Mary Abchurch	26
St Mary in Aldermanbury	25
St Mary Aldermary	28
St Mary le Bow in Cheapſide	24
St Mary Bothaw at Dowgate	2
St Mary Colechurch	2
St Mary Hill by Billinſgate	48
St Mary Magd. in Milk-ſtr.	0
St Mary Magd. Old Fiſh-ſtr.	22
St Mary Mounthaw	11
St Mary Somerſet	52
St Mary Staining	20
St Mary Woolchurch	0
St Mary Woolnoth	27
St Matthew in Friday-ſtreet	9
St Michael Baſſiſhaw	27
St Michael in Cornhill	33
St Michael in Crooked-lane	19
St Michael at Queenhithe	46
St Michael at Quern	11
St Michael Royal	15
St Michael in Wood-ſtreet	8
St Mildred in Bread-ſtreet	11
St Mildred in the Poultry	18
St Nicholas Acons	5
St Nicholas Coleabby	20
St Nicholas Olave	9
St Olave in Hart-ſtreet	31
St Olave in the Old Jewry	11
St Olave in Silver-ſtreet	31
St Pancras in Pancras-lane	4
St Peter in Cheapſide	4
St Peter in Cornhill	28
St Peter near Paul's Wharf	15
St Peter Poor in Broad-ſtr.	29
St Stephen in Coleman-ſtreet	110
St Stephen in Walbrook	16
St Swithin at London-ſtone	23
St Thomas the Apoſtle	10
Trinity Pariſh	19
St Vedaſt, alias Foſter	34

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1859 Buried 2438

St Andrew in Holborn	975
St Bartholomew the Great	64
St Bartholomew the Leſs	26
St Botolph by Alderſgate	193
St Botolph by Aldgate	550
St Botolph by Biſhopſgate	493
Bridewell Precinct	30
St Bridget, vulg. St Bride's	325
St Dunſtan in the Weſt	189
St George in Southwark	442
St Giles by Cripplegate	1276
St Olave in Southwark	784
St Saviour in Southwark	634
St Sepulchre's Pariſh	555
St Thomas in Southwark	134
Trinity in the Minories	25
The Peſt-houſe	

Chriſtened in the ſixteen Pariſhes without the Walls 5045 Buried 6695

1712.

Chriſt Church in Surrey —158	St John at Wapping ——322	St Mary Magd. Bermondſey 416
St Dunſtan at Stepney——2153	St Katherine near the Tower 164	St Mary at Newington ——180
St Giles in the Fields ——1303	St Leonard in Shoreditch—531	St Mary at Rotherhith ——197
St James at Clerkenwell —371	St Mary at Iſlington — —125	St Mary in Whitechapel —705
St John at Hackney ——118	St Mary at Lambeth — —304	St Paul at Shadwell ——427

Chriſtened in the fifteen Out Pariſhes in Middleſex and Surrey 5327 Buried 7474

St Ann in Weſtminſter - —403	St Margaret in Weſtminſt. 891	St Mary Savoy in the Strand 125
St Clement Danes — ——526	St Martin in the Fields—1413	St Paul in Covent Garden 222
St James in Weſtminſter 1011		

Chriſtened in the ſeven Pariſhes in the City and Liberties of Weſtminſter 3429 Buried 4591

DISEASES and CASUALTIES.

ABORTIVE —— 88	Gangrene —— — 13	Purples —— — 23	Tiſſick — —— 271
Aged -——1918	Gout —— —— 13	Quinſy —— —— 18	Twiſting of the Guts 8
Ague —— —— 8	Gravel — —— 1	Raſh —— —— 2	Tympany — —— 14
Apoplexy —— — 76	Grief —— —— 8	Rheumatiſm — — 20	Vapours — —— 2
Aſthma — —— 27	Griping in the Guts— 575	Rickets — —— 214	Vomiting — —— 19
Bedridden — —— 2	Head-ach — —— 2	Riſing of the Lights— 64	Water in the Head — 15
Bleeding —— — 9	Headmouldſhot — — 21	Rupture — —— 19	White Swelling — — 1
Bloody Flux —— 5	Hooping Cough —— 3	St Anthony's Fire -— 2	Worms — —— 70
Burſten —— — 3	Horſhoehead — — 2	Scald Head -—— 1	
Cancer — —— 69	Jaundies —— —— 82	Scarlet Fever —— 4	CASUALTIES.
Canker —— —— 9	Impoſthume —— 54	Scurvy —— —— 11	
Childbed —— — 207	Infants —— —— 16	Small Pox — ——1943	Bruiſed — —— 1
Chriſomes — —— 69	Inflammation —— 1	Sores and Ulcers —— 48	Burnt —— —— 4
Colick —— — 66	Leproſy —— —— 1	Spleen — —— 1	Died by a Hurt —— 1
Conſumption ——2551	Lethargy — —— 10	Spotted Fever — — 96	Dropt down dead —— 1
Convulſion — ——6156	Livergrown — — 9	Stillborn — —— 422	Drowned — —— 64
Cough —— — 2	Looſneſs — —— 24	Stone —— —— 42	Exceſſive Drinking — 4
Diabetes — —— 8	Lunatick —— — 29	Stoppage in the Stomach 311	Found dead — —— 15
Died by Misfortune — 2	Malignant Fever —— 6	Strangury — —— 6	Frozen to Death —— 1
Dropſy — —— 572	Meaſles —— — 77	Strongullion — — 3	Killed accidentally — 37
Evil —— —— 43	Mortification —— 77	Suddenly — —— 60	Murdered — —— 8
Fever —— ——3131	Pain in the Head —— 4	Surfeit —— — 35	Overlaid —— — 41
Fiſtula —— — 19	Palſy —— —— 21	Teeth — ——1000	Scalded — —— 3
Flux —— —— 4	Pleuriſy — —— 25	Thruſh —— —— 80	Self-Murder —— 24
French Pox — —— 56			

CHRISTENED	Males — 8029	BURIED	Males — 10376
	Females 7631		Females 10822
	In all — 15660		In all — 21198

Increaſed in the Burials this Year 1365

A General

1713.

A General BILL of all the Chriſtenings and Burials,

From the 16th of December 1712, to the 15th of December 1713.

According to the Report made to the Queen's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	17
Alhallows Barkin	97
Alhallows in Bread-ſtreet	18
Alhallows the Great	55
Alhallows in Honey-lane	3
Alhallows the Leſs	7
Alhallows in Lombard-ſtreet	11
Alhallows Staining	24
Alhallows on London Wall	45
St Alphage near Sion College	36
St Andrew Hubbard	6
St Andrew Underſhaft	35
St Andrew Wardrobe	50
St Ann within Alderſgate	41
St Ann in Black Friars	110
St Anthony, vulg. Antholin	15
St Auguſtin, vulg. Auſtin	14
St Bartholomew by Exchange	19
St Benedict, v. Bennet Fink	15
St Bennet Gracechurch	5
St Bennet at Paul's Wharf	31
St Bennet Sherehog	2
St Botolph at Billinſgate	7
Chriſt Church Pariſh	135
St Chriſtopher's Pariſh	14
St Clement near Eaſtcheap	15
St Dionis Backchurch	17
St Dunſtan in the Eaſt	85
St Edmund the King	21
St Ethelburga's Pariſh	29
St Faith under St Paul's	38
St Gabriel in Fenchurch-ſtr.	6
St George in Botolph-lane	13
St Gregory by St Paul's	52
St Helen near Biſhopſgate	34
St James in Duke's Place	21
St James at Garlickhithe	50
St John Baptiſt by Dowgate	11
St John the Evangeliſt	1
St John Zachary	13
St Katherine Coleman	57
St Katherine Creechurch	54
St Laurence Jewry	57
St Laurence Pountney	15
St Leonard in Eaſtcheap	7
St Leonard in Foſter-lane	35
St Magnus by London Bridge	36
St Margaret in Lothbury	22
St Margaret Moſes	4
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattons	10
St Martin Ironmonger-lane	11
St Martin at Ludgate	38
St Martin Orgars	13
St Martin Outwich	15
St Martin Vintrey	40
St Mary Abchurch	24
St Mary in Aldermanbury	32
St Mary Aldermary	25
St Mary le Bow in Cheapſide	32
St Mary Bothaw at Dowgate	10
St Mary Colechurch	2
St Mary Hill by Billinſgate	37
St Mary Magd. in Milk-ſtr.	0
St Mary Magd. Old Fiſh-ſtr.	27
St Mary Mounthaw	14
St Mary Somerſet	42
St Mary Staining	18
St Mary Woolchurch	0
St Mary Woolnoth	20
St Matthew in Friday-ſtreet	6
St Michael Baſſiſhaw	33
St Michael in Cornhill	26
St Michael in Crooked-lane	29
St Michael at Queenhithe	37
St Michael at Quern	6
St Michael Royal	17
St Michael in Wood-ſtreet	9
St Mildred in Bread-ſtreet	3
St Mildred in the Poultry	19
St Nicholas Acons	2
St Nicholas Coleabby	13
St Nicholas Olave	7
St Olave in Hart-ſtreet	42
St Olave in the Old Jewry	12
St Olave in Silver-ſtreet	20
St Pancras in Pancras-lane	8
St Peter in Cheapſide	12
St Peter in Cornhill	38
St Peter near Paul's Wharf	20
St Peter Poor in Broad-ſtr.	30
St Stephen in Coleman-ſtreet	84
St Stephen in Walbrook	13
St Swithin at London-ſtone	24
St Thomas the Apoſtle	15
Trinity Pariſh	20
St Vedaſt, alias Foſter	21

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1783 Buried 2481

St Andrew in Holborn	988
St Bartholomew the Great	59
St Bartholomew the Leſs	42
St Botolph by Alderſgate	196
St Botolph by Aldgate	611
St Botolph by Biſhopſgate	424
Bridewell Precinct	19
St Bridget, vulg. St Bride's	298
St Dunſtan in the Weſt	185
St George in Southwark	445
St Giles by Cripplegate	1218
St Olave in Southwark	779
St Saviour in Southwark	618
St Sepulchre's Pariſh	577
St Thomas in Southwark	156
Trinity in the Minories	22
The Peſt-houſe	—

Chriſtened in the ſixteen Pariſhes without the Walls 5251 Buried 6637

1713.

Chriſt Church in Surrey —139	St John at Wapping ——298	St Mary Magd. Bermondſey 413
St Dunſtan at Stepney——1890	St Katherine near the Tower 197	St Mary at Newington ——202
St Giles in the Fields ——1424	St Leonard in Shoreditch —499	St Mary at Rotherhith ——202
St James at Clerkenwell —405	St Mary at Iſlington — —136	St Mary in Whitechapel —706
St John at Hackney ——130	St Mary at Lambeth ——327	St Paul at Shadwell ——391

Chriſtened in the fifteen Out Pariſhes in Middleſex and Surrey 5549 Buried 7359

St Ann in Weſtminſter - —371	St Margaret in Weſtminſter 838	St Mary Savoy in the Strand 113
St Clement Danes — ——525	St Martin in the Fields —1495	St Paul in Covent Garden 171
St James in Weſtminſter—1067		

Chriſtened in the ſeven Pariſhes in the City and Liberties of Weſtminſter 3344 Buried 4580

DISEASES and CASUALTIES.

ABORTIVE —— 80	Gangrene —— — 8	Purples — —— 31	Twiſting of the Guts 11
Aged ——1939	Gout —— —— 18	Quinſy —— —— 8	Tympany — —— 12
Ague —— —— 11	Gravel —— — 1	Raſh —— —— 3	Vomiting —— — 28
Apoplexy — —— 85	Grief —— —— 8	Rheumatiſm —— — 20	Water in the Head — 26
Aſthma — —— 47	Griping in the Guts— 581	Rickets —— —— 171	White Flux —— 1
Bedridden —— — 2	Headmouldſhot —— 16	Riſing of the Lights— 52	Worms —— —— 41
Bleeding —— —— 3	Hooping Cough —— 6	Rupture —— —— 20	
Bloody Flux —— 7	Horſhoehead —— 3	St Anthony's Fire—— 5	CASUALTIES.
Burſten —— —— 10	Hyſtericks — —— 1	Scarlet Fever —— 4	
Cancer — —— 59	Jaundies — —— 94	Scurvy —— —— 6	Broken Leg —— 1
Canker —— —— 13	Impoſthume — —— 56	Shortneſs of Breath — 2	Bruiſed —— —— 2
Childbed —— — 178	Infants —— —— 17	Small Pox — ——1614	Burnt —— —— 2
Chincough — —— 2	Itch —— —— 1	Sores and Ulcers —— 31	Dropt down dead — 1
Chriſomes —— — 71	Leproſy —— — 2	Spleen —— —— 1	Drowned — —— 63
Colick — —— 71	Lethargy — —— 7	Spotted Fever —— 102	Exceſſive Drinking — 2
Conſumption ——2745	Livergrown — —— 3	Stillborn —— —— 487	Executed —— —— 12
Convulſion — ——5779	Looſneſs —— —— 24	Stone —— —— 49	Found dead — — 32
Cramp — —— 2	Lunatick — —— 21	Stoppage in the Stomach 335	Killed accidentally — 29
Diabetes —— — 2	Malignant Fever —— 4	Strangury —— —— 1	Killed with a Razor— 1
Dropſy —— —— 745	Meaſles — —— 61	Strongullion —— 7	Killed by a Sword — 1
Evil —— —— 55	Megrims — —— 1	Suddenly —— —— 81	Murdered — —— 12
Fever —— ——3039	Mortification —— 81	Surfeit —— —— 39	Overlaid —— —— 44
Fiſtula —— —— 19	Overflowing of the Gall 1	Teeth —— —1099	Self-Murder —— 34
Flux —— —— 4	Palſy —— —— 30	Thruſh —— —— 64	Shot with a Piſtol — 1
French Pox — —— 87	Pleuriſy —— —— 35	Tiſſick —— —— 333	Wounded — —— 1

CHRISTENED	Males — 8262	BURIED	Males — 10412
	Females 7665		Females 10645
	In all 15927		In all — 21057

Decreaſed in the Burials this Year 141

A General

1714.

A General BILL of all the Chriſtenings and Burials,

From the 15th of December 1713, to the 14th of December 1714.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	31
Alhallows Barkin	94
Alhallows in Bread-ſtreet	22
Alhallows the Great	63
Alhallows in Honey-lane	0
Alhallows the Leſs	18
Alhallows in Lombard-ſtreet	15
Alhallows Staining	22
Alhallows on London Wall	41
St Alphage near Sion College	36
St Andrew Hubbard	0
St Andrew Underſhaft	61
St Andrew Wardrobe	66
St Ann within Alderſgate	50
St Ann in Black Friars	155
St Anthony, vulg. Antholin	17
St Auguſtin, vulg. Auſtin	15
St Bartholomew by Exchange	14
St Benedict, v. Bennet Fink	21
St Bennet Gracechurch	12
St Bennet at Paul's Wharf	52
St Bennet Sherehog	1
St Botolph at Billinſgate	10
Chriſt Church Pariſh	158
St Chriſtopher's Pariſh	23
St Clement near Eaſtcheap	17
St Dionis Backchurch	33
St Dunſtan in the Eaſt	80
St Edmund the King	16
St Ethelburga's Pariſh	27
St Faith under St Paul's	24
St Gabriel in Fenchurch-ſtr.	9
St George in Botolph-lane	10
St Gregory by St Paul's	75
St Helen near Biſhopſgate	43
St James in Duke's Place	41
St James at Garlickhithe	44
St John Baptiſt by Dowgate	28
St John the Evangeliſt	2
St John Zachary	21
St Katherine Coleman	76
St Katherine Creechurch	35
St Laurence Jewry	67
St Laurence Pountney	19
St Leonard in Eaſtcheap	13
St Leonard in Foſter-lane	33
St Magnus by London Bridge	36
St Margaret in Lothbury	36
St Margaret Moſes	4
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattons	19
St Martin Ironmonger-lane	13
St Martin at Ludgate	35
St Martin Orgars	13
St Martin Outwich	19
St Martin Vintrey	56
St Mary Abchurch	33
St Mary in Aldermanbury	28
St Mary Aldermary	27
St Mary le Bow in Cheapſide	37
St Mary Bothaw at Dowgate	7
St Mary Colechurch	0
St Mary Hill by Billinſgate	57
St Mary Magd. in Milk-ſtr.	0
St Mary Magd. Old Fiſh-ſtr.	39
St Mary Mounthaw	18
St Mary Somerſet	35
St Mary Staining	45
St Mary Woolchurch	1
St Mary Woolnoth	22
St Matthew in Friday-ſtreet	12
St Michael Baſſiſhaw	22
St Michael in Cornhill	25
St Michael in Crooked-lane	25
St Michael at Queenhithe	32
St Michael at Quern	19
St Michael Royal	21
St Michael in Wood-ſtreet	6
St Mildred in Bread-ſtreet	15
St Mildred in the Poultry	42
St Nicholas Acons	1
St Nicholas Coleabby	12
St Nicholas Olave	15
St Olave in Hart-ſtreet	60
St Olave in the Old Jewry	4
St Olave in Silver-ſtreet	38
St Pancras in Pancras-lane	2
St Peter in Cheapſide	15
St Peter in Cornhill	28
St Peter near Paul's Wharf	22
St Peter Poor in Broad-ſtr.	34
St Stephen in Coleman-ſtreet	105
St Stephen in Walbrook	17
St Swithin at London-ſtone	17
St Thomas the Apoſtle	30
Trinity Pariſh	26
St Vedaſt, alias Foſter	28

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1810. Buried 2961.

St Andrew in Holborn	1274
St Bartholomew the Great	74
St Bartholomew the Leſs	31
St Botolph by Alderſgate	234
St Botolph by Aldgate	796
St Botolph by Biſhopſgate	607
Bridewell Precinct	13
St Bridget, vulg. St Bride's	420
St Dunſtan in the Weſt	216
St George in Southwark	564
St Giles by Cripplegate	1491
St Olave in Southwark	863
St Saviour in Southwark	714
St Sepulchre's Pariſh	718
St Thomas in Southwark	161
Trinity in the Minories	24
The Peſt-houſe	

Chriſtened in the ſixteen Pariſhes without the Walls 5691 Buried 8200.

1714.

Chriſt Church in Surrey —190	St John at Wapping ——346	St Mary Magd. Bermondſey 504
St Dunſtan at Stepney——2646	St Katherine near the Tower 208	St Mary at Newington ——242
St Giles in the Fields ——1743	St Leonard in Shoreditch —662	St Mary at Rotherhith ——239
St James at Clerkenwell —502	St Mary at Iſlington — —194	St Mary in Whitechapel —952
St John at Hackney ——179	St Mary at Lambeth ——336	St Paul at Shadwell ——486

Chriſtened in the fifteen Out Pariſhes in Middleſex and Surrey 6123 Buried 9429

St Ann in Weſtminſter - —490	St Margaret in Weſtminſt. 1193	St Mary Savoy in the Strand 145
St Clement Danes — ——576	St Martin in the Fields —1787	St Paul in Covent Garden 242
St James in Weſtminſter—1546		

Chriſtened in the ſeven Pariſhes in the City and Liberties of Weſtminſter 3871 Buried 5979

DISEASES and CASUALTIES.

ABORTIVE —— 103	Gangrene —— — 3	Rheumatiſm —— — 12	
Aged ——2146	Gout —— —— 20	Rickets —— —— 205	CASUALTIES.
Ague —— —— 4	Gravel —— — 2	Riſing of the Lights— 52	
Apoplexy — —— 82	Grief —— —— 5	Rupture —— —— 13	Broken Leg —— 3
Aſthma — —— 71	Griping in the Guts— 670	St Anthony's Fire—— 5	Burnt —— —— 11
Bedridden —— — 3	Head-ach — —— 1	Small Pox — ——2810	Died by Misfortune — 1
Bleeding —— —— 5	Headmouldſhot —— 14	Sores and Ulcers —— 25	Drowned — —— 51
Bloody Flux —— 13	Hooping Cough —— 6	Spleen —— —— 2	Exceſſive Drinking — 1
Burſten —— —— 6	Horſhoehead —— 2	Spotted Fever —— 150	Executed —— —— 16
Cancer — —— 71	Jaundies —— — 100	Stillborn —— —— 537	Found dead — — 32
Canker —— —— 10	Impoſthume — —— 49	Stone —— —— 67	Frighted — —— 1
Carbuncle — —— 1	Infants —— —— 5	Stoppage in the Stomach 348	Killed by ſeveral Acci- 65
Childbed —— — 309	Inflammation — — 1	Strangury —— —— 3	dents
Chriſomes — —— 68	Leproſy —— — 1	Strongullion —— 9	Made away themſelves 34
Colick — —— 61	Lethargy — —— 8	Suddenly —— —— 92	Murdered — —— 11
Conſumption ——3029	Livergrown —— — 9	Surfeit —— —— 20	Overlaid —— —— 46
Convulſion — ——7161	Looſneſs —— —— 19	Swelling in the Throat 1	Planet-ſtruck —— 2
Cough — —— 1	Lunatick — —— 24	Teeth —— —1328	Scalded —— — 2
Cramp — —— 3	Meaſles —— — 139	Thruſh —— —— 50	Smothered — —— 1
Diabetes —— — 3	Mortification —— 119	Tiſſick —— —— 281	Stabbed — —— 1
Dropſy —— —— 848	Pain in the Head —— 1	Twiſting of the Guts 14	Starved — —— 2
Evil —— —— 48	Palſy —— —— 25	Tympany — —— 18	Suffocated —— — 1
Fever —— ——4631	Pleuriſy —— —— 56	Vomiting —— — 20	Wounded — —— 1
Fiſtula —— —— 22	Purples — —— 29	Water in the Head — 32	
Flux —— —— 7	Quinſy —— —— 21	Wind —— —— 1	
French Pox — —— 105	Raſh —— —— 6	Worms —— —— 45	

CHRISTENED	Males — 8950	BURIED	Males — 13139
	Females 8545		Females 13430
	In all 17495		In all — 26569

Increaſed in the Burials this Year 5512.

1715.

A General BILL of all the Chriſtenings and Burials,

From the 14th of December 1714, to the 13th of December 1715.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	16
Alhallows Barkin	92
Alhallows in Bread-ſtreet	17
Alhallows the Great	54
Alhallows in Honey-lane	0
Alhallows the Leſs	20
Alhallows in Lombard-ſtreet	24
Alhallows Staining	29
Alhallows on London Wall	40
St Alphage near Sion College	32
St Andrew Hubbard	2
St Andrew Underſhaft	52
St Andrew Wardrobe	44
St Ann within Alderſgate	37
St Ann in Black Friars	110
St Anthony, vulg. Antholin	10
St Auguſtin, vulg. Auſtin	15
St Bartholomew by Exchange	15
St Benedict, v. Bennet Fink	20
St Bennet Gracechurch	21
St Bennet at Paul's Wharf	30
St Bennet Sherehog	1
St Botolph at Billinſgate	13
Chriſt Church Pariſh	117
St Chriſtopher's Pariſh	18
St Clement near Eaſtcheap	11
St Dionis Backchurch	31
St Dunſtan in the Eaſt	61
St Edmund the King	17
St Ethelburga's Pariſh	28
St Faith under St Paul's	44
St Gabriel in Fenchurch-ſtr.	6
St George in Botolph-lane	8
St Gregory by St Paul's	75
St Helen near Biſhopſgate	30
St James in Duke's Place	19
St James at Garlickhithe	39
St John Baptiſt by Dowgate	24
St John the Evangeliſt	2
St John Zachary	21
St Katherine Coleman	44
St Katherine Creechurch	34
St Laurence Jewry	43
St Laurence Pountney	13
St Leonard in Eaſtcheap	8
St Leonard in Foſter-lane	35
St Magnus by London Bridge	33
St Margaret in Lothbury	30
St Margaret Moſes	4
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattons	15
St Martin Ironmonger-lane	10
St Martin at Ludgate	20
St Martin Orgars	15
St Martin Outwich	23
St Martin Vintrey	46
St Mary Abchurch	32
St Mary in Aldermanbury	32
St Mary Aldermary	29
St Mary le Bow in Cheapſide	32
St Mary Bothaw at Dowgate	5
St Mary Colechurch	0
St Mary Hill by Billinſgate	34
St Mary Magd. in Milk-ſtr.	0
St Mary Magd. Old Fiſh-ſtr.	34
St Mary Mounthaw	17
St Mary Somerſet	27
St Mary Staining	35
St Mary Woolchurch	0
St Mary Woolnoth	10
St Matthew in Friday-ſtreet	10
St Michael Baſſiſhaw	22
St Michael in Cornhill	18
St Michael in Crooked-lane	46
St Michael at Queenhithe	38
St Michael at Quern	7
St Michael Royal	8
St Michael in Wood-ſtreet	14
St Mildred in Bread-ſtreet	12
St Mildred in the Poultry	23
St Nicholas Acons	1
St Nicholas Coleabby	20
St Nicholas Olave	11
St Olave in Hart-ſtreet	32
St Olave in the Old Jewry	8
St Olave in Silver-ſtreet	26
St Pancras in Pancras-lane	0
St Peter in Cheapſide	13
St Peter in Cornhill	34
St Peter near Paul's Wharf	23
St Peter Poor in Broad-ſtr.	26
St Stephen in Coleman-ſtreet	89
St Stephen in Walbrook	14
St Swithin at London-ſtone	24
St Thomas the Apoſtle	32
Trinity Pariſh	12
St Vedaſt, alias Foſter	25

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1828 Buried 2493

	Bur.
St Andrew in Holborn	1077
St Bartholomew the Great	61
St Bartholomew the Leſs	30
St Botolph by Alderſgate	227
St Botolph by Aldgate	674
St Botolph by Biſhopſgate	573
Bridewell Precinct	18
St Bridget, vulg. St Bride's	326
St Dunſtan in the Weſt	193
St George in Southwark	503
St Giles by Cripplegate	1339
St Olave in Southwark	696
St Saviour in Southwark	677
St Sepulchre's Pariſh	670
St Thomas in Southwark	170
Trinity in the Minories	25
The Peſt-houſe	—

Chriſtened in the ſixteen Pariſhes without the Walls 5704 Buried 7259

1715.

Chriſt Church in Surrey —165	St John at Wapping———251	St Mary Magd. Bermondſey 415
St Dunſtan at Stepney——2110	St Katherine near the Tower 168	St Mary at Newington ——279
St Giles in the Fields ——1452	St Leonard in Shoreditch —575	St Mary at Rotherhith ——214
St James at Clerkenwell —419	St Mary at Iſlington ———160	St Mary in Whitechapel —794
St John at Hackney———136	St Mary at Lambeth — —284	St Paul at Shadwell ———358

Chriſtened in the fifteen Out Pariſhes in Middleſex and Surrey 5862 Buried 7780

St Ann in Weſtminſter —420	St Margaret in Weſtminſt. 941	St Mary Savoy in the Strand 113
St Clement Danes ———464	St Martin in the Fields —1415	St Paul in Covent Garden 183
St James in Weſtminſter 1165		

Chriſtened in the ſeven Pariſhes in the City and Liberties of Weſtminſter 3840 Buried 4700

DISEASES and CASUALTIES.

Abortive —— 68	Gravel —— —— 3	Rupture — ——— 10					
Aged -———1931	Grief —— ——— 5	St Anthony's Fire — 1		Casualties.			
Ague ——— — 8	Griping in the Guts— 589	Salivation — —— 1					
Apoplexy — —— 73	Headmouldſhot —— 38	Scald Head —— — 1		Broken Leg — —	3		
Aſthma — ——— 46	Hooping Cough —— 7	Small Pox — ——1057		Bruiſed — ——	2		
Bedridden — —— 5	Horſhoehead ——— 3	Sores and Ulcers —— 31		Drowned — ———	59		
Bleeding — ——— 5	Jaundies —— —— 80	Spleen — ——— 1		Exceſſive Drinking —	4		
Bloody Flux -——— 19	Impoſthume ——— 48	Spotted Fever ——— 161		Executed — ———	17		
Burſten —— —— 5	Infants —— —— 6	Stillborn —— —— 463		Found dead — ——	39		
Cancer — ——— 65	Inflammation ——— 1	Stone — ——— 35		Frighted — ———	1		
Canker —— —— 6	Leproſy ——— —— 1	Stoppage in the Stomach 186		Killed by ſeveral Accidents	55		
Childbed — ——— 275	Lethargy —— — 5	Strangury — —— 2		Killed by a Sword ——	3		
Chriſomes — —— 46	Livergrown ——— 3	Strongullion ——— 1		Made away themſelves	28		
Colick ——— — 63	Looſneſs —— —— 12	Suddenly — —— 85		Murdered — ——	11		
Conſumption ———2842	Lunatick ——— — 21	Surfeit — ——— 13		Overlaid — ———	47		
Convulſion -———6818	Meaſles — ——— 30	Teeth —— ——1276		Planet-ſtruck ———	1		
Cough —— —— 5	Mortification ——— 117	Thruſh — ——— 67		Wounded — ——	5		
Diabetes —, ——— 2	Palſy ——— —— 27	Tiſſick —— —— 271					
Dropſy —— —— 789	Pleuriſy — ——— 41	'Twiſting of the Guts 10		Total	275		
Evil —— ——— 52	Purples —— —— 27	Tympany — —— 15					
Fever —— ——3588	Quinſy — ——— 9	Vapours — ——— 1					
Fiſtula —— ——— 15	Raſh ——— —— 12	Vomiting — —— 25					
Flux ——— —— 4	Rheumatiſm ——— 22	Water in the Head — 25					
French Pox -——— 82	Rickets —— —— 161	Wind —— —— 1					
Gangrene — —— 6	Riſing of the Lights— 51	Worms — ——— 44					
Gout —— —— 25							

Christened	Males — 8788	Buried	Males — 11083
	Females 8446		Females 11149
	In all — 17234		In all — 22232

Decreaſed in the Burials this Year 4337

1716.

A General BILL of all the Chriſtenings and Burials,

From the 13th of December 1715, to the 11th of December 1716.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	27
Alhallows Barkin	115
Alhallows in Bread-ſtreet	15
Alhallows the Great	76
Alhallows in Honey-lane	0
Alhallows the Leſs	8
Alhallows in Lombard-ſtreet	9
Alhallows Staining	19
Alhallows on London Wall	65
St Alphage near Sion College	40
St Andrew Hubbard	5
St Andrew Underſhaft	54
St Andrew Wardrobe	83
St Ann within Alderſgate	50
St Ann in Black Friars	169
St Anthony, vulg. Antholin	11
St Auguſtin, vulg. Auſtin	16
St Bartholomew by Exchange	20
St Benedict, v. Bennet Fink	18
St Bennet Gracechurch	14
St Bennet at Paul's Wharf	50
St Bennet Sherehog	0
St Botolph at Billinſgate	10
Chriſt Church Pariſh	124
St Chriſtopher's Pariſh	27
St Clement near Eaſtcheap	14
St Dionis Backchurch	31
St Dunſtan in the Eaſt	57
St Edmund the King	25
St Ethelburga's Pariſh	28
St Faith under St Paul's	28
St Gabriel in Fenchurch-ſtr.	4
St George in Botolph-lane	14
St Gregory by St Paul's	66
St Helen near Biſhopſgate	25
St James in Duke's Place	21
St James at Garlickhithe	28
St John Baptiſt by Dowgate	19
St John the Evangeliſt	4
St John Zachary	26
St Katherine Coleman	49
St Katherine Creechurch	59
St Laurence Jewry	45
St Laurence Pountney	14
St Leonard in Eaſtcheap	9
St Leonard in Foſter-lane	35
St Magnus by London Bridge	34
St Margaret in Lothbury	23
St Margaret Moſes	17
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattons	15
St Martin Ironmonger-lane	7
St Martin at Ludgate	46
St Martin Orgars	6
St Martin Outwich	24
St Martin Vintrey	38
St Mary Abchurch	20
St Mary in Aldermanbury	19
St Mary Aldermary	33
St Mary le Bow in Cheapſide	29
St Mary Bothaw at Dowgate	6
St Mary Colechurch	0
St Mary Hill by Billinſgate	41
St Mary Magd. in Milk-ſtr.	0
St Mary Magd. Old Fiſh-ſtr.	43
St Mary Mounthaw	11
St Mary Somerſet	40
St Mary Staining	23
St Mary Woolchurch	0
St Mary Woolnoth	11
St Matthew in Friday-ſtreet	13
St Michael Baſſiſhaw	25
St Michael in Cornhill	25
St Michael in Crooked-lane	24
St Michael at Queenhithe	35
St Michael at Quern	17
St Michael Royal	15
St Michael in Wood-ſtreet	19
St Mildred in Bread-ſtreet	18
St Mildred in the Poultry	26
St Nicholas Acons	0
St Nicholas Coleabby	22
St Nicholas Olave	7
St Olave in Hart-ſtreet	41
St Olave in the Old Jewry	7
St Olave in Silver-ſtreet	34
St Pancras in Pancras-lane	2
St Peter in Cheapſide	7
St Peter in Cornhill	33
St Peter near Paul's Wharf	28
St Peter Poor in Broad-ſtr.	26
St Stephen in Coleman-ſtreet	90
St Stephen in Walbrook	13
St Swithin at London-ſtone	19
St Thomas the Apoſtle	23
Trinity Pariſh	20
St Vedaſt, alias Foſter	24

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1884 Buried 2725

St Andrew in Holborn	1398
St Bartholomew the Great	66
St Bartholomew the Leſs	39
St Botolph by Alderſgate	216
St Botolph by Aldgate	756
St Botolph by Biſhopſgate	503
Bridewell Precinct	23
St Bridget, vulg. St Bride's	365
St Dunſtan in the Weſt	193
St George in Southwark	497
St Giles by Cripplegate	1343
St Olave in Southwark	762
St Saviour in Southwark	793
St Sepulchre's Pariſh	723
St Thomas in Southwark	169
Trinity in the Minories	14
The Peſt-houſe	

Chriſtened in the ſixteen Pariſhes without the Walls 5742 Buried 7860

1716.

Chriſt Church in Surrey —194	St John at Wapping —284	St Mary Magd. Bermondſey 411
St Dunſtan at Stepney——2259	St Katherine near the Tower 181	St Mary at Newington——304
St Giles in the Fields——1606	St Leonard in Shoreditch—578	St Mary at Rotherhith——209
St James at Clerkenwell —562	St Mary at Iſlington — —159	St Mary in Whitechapel —809
St John at Hackney ——141	St Mary at Lambeth — —327	St Paul at Shadwell ——405

Chriſtened in the fifteen Out Pariſhes in Middleſex and Surrey 5956 Buried 8429

St Ann in Weſtminſter - —502	St Margaret in Weſtminſt. 1126	St Mary Savoy in the Strand 118
St Clement Danes — ——501	St Martin in the Fields —1626	St Paul in Covent Garden 241
St James in Weſtminſter 1308		

Chriſtened in the ſeven Pariſhes in the City and Liberties of Weſtminſter 3839 Buried 5422

DISEASES and CASUALTIES.

ABORTIVE —— 133	Gout —— —— 35	Rupture — —— 14	
Aged -——1959	Gravel — —— 2	St Anthony's Fire -— 2	CASUALTIES.
Ague —— —— 2	Grief —— —— 4	Scarlet Fever —— 1	
Apoplexy —— — 65	Griping in the Guts— 709	Small Pox — ——2427	BRoken Leg — — 2
Aſthma — —— 57	Head-ach — —— 3	Sores and Ulcers —— 36	Bruiſed -—— 2
Bedridden — —— 8	Headmouldſhot — — 46	Spleen — —— 2	Burnt —— —— 2
Bleeding —— — 1	Hooping Cough —— 11	Spotted Fever — — 100	Died by Misfortune — 1
Bloody Flux —— 6	Horſhoehead — — 6	Stillborn — —— 542	Died by untimely Births 2
Burſten —— — 4	Jaundies —— —— 95	Stone —— —— 44	Drowned — —— 45
Cancer — —— 68	Impoſthume —— 39	Stoppage in the Stomach 239	Exceſſive Drinking — 3
Canker —— —— 5	Infants —— —— 4	Stoppage in the Throat 1	Executed — —— 30
Childbed —— — 229	Lethargy — —— 7	Strangury — —— 2	Found dead — —— 38
Chriſomes — —— 42	Livergrown — — 1	Strongullion — — 10	Frighted — —— 3
Colick —— — 78	Looſneſs — —— 13	Suddenly — —— 94	Killed accidentally — 52
Conſumption ——3189	Lunatick —— — 27	Surfeit —— — 17	Killed with a Sword— 5
Convulſion — ——7114	Malignant Fever —— 1	Teeth — ——1313	Made away themſelves 28
Cough —— — 4	Meaſles —— — 270	Thruſh —— —— 48	Murdered — —— 5
Diabetes — —— 1	Mortification —— 128	Tiſſick — —— 421	Overlaid —— — 59
Diſtracted — —— 3	Palſy —— —— 25	Twiſting of the Guts 12	Scalded — —— 3
Dropſy — —— 766	Pleuriſy — —— 24	Tympany — —— 7	Shot —— —— 3
Evil —— —— 61	Purples —— — 40	Vapours — —— 1	Suffocated — —— 1
Fever —— ——3078	Quinſy —— —— 12	Vomiting — —— 23	Wounded — —— 1
Fiſtula —— — 13	Raſh —— —— 10	Water in the Head — 41	
Flux —— —— 3	Rheumatiſm — — 25	White Swelling— — 3	Total 285
French Pox — —— 63	Rickets — —— 169	Worms — —— 31	
Gangrene —— — 4	Riſing of the Lights— 58		

CHRISTENED	Males — 9076	BURIED	Males — 12356
	Females 8345		Females 12080
	In all — 17421		In all — 24436

Increaſed in the Burials this Year 2204

A General

1717.

A General BILL of all the Chriſtenings and Burials,

From the 11th of December 1716, to the 17th of December 1717.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	27
Alhallows Barkin	110
Alhallows in Bread-ſtreet	19
Alhallows the Great	56
Alhallows in Honey-lane	0
Alhallows the Leſs	28
Alhallows in Lombard-ſtreet	16
Alhallows Staining	31
Alhallows on London Wall	57
St Alphage near Sion College	33
St Andrew Hubbard	3
St Andrew Underſhaft	57
St Andrew Wardrobe	48
St Ann within Alderſgate	45
St Ann in Black Friars	131
St Anthony, vulg. Antholin	13
St Auguſtin, vulg. Auſtin	14
St Bartholomew by Exchange	17
St Benedict, v. Bennet Fink	23
St Bennet Gracechurch	9
St Bennet at Paul's Wharf	41
St Bennet Sherehog	0
St Botolph at Billinſgate	15
Chriſt Church Pariſh	123
St Chriſtopher's Pariſh	25
St Clement near Eaſtcheap	15
St Dionis Backchurch	34
St Dunſtan in the Eaſt	57
St Edmund the King	15
St Ethelburga's Pariſh	22
St Faith under St Paul's	30
St Gabriel in Fenchurch-ſtr.	10
St George in Botolph-lane	11
St Gregory by St Paul's	53
St Helen near Biſhopſgate	41
St James in Duke's Place	26
St James at Garlickhithe	40
St John Baptiſt by Dowgate	22
St John the Evangeliſt	2
St John Zachary	21
St Katherine Coleman	52
St Katherine Creechurch	31
St Laurence Jewry	53
St Laurence Pountney	17
St Leonard in Eaſtcheap	7
St Leonard in Foſter-lane	20
St Magnus by London Bridge	35
St Margaret in Lothbury	28
St Margaret Moſes	6
St Margaret in New Fiſh-ſtr.	3
St Margaret Pattons	16
St Martin Ironmonger-lane	15
St Martin at Ludgate	50
St Martin Orgars	14
St Martin Outwich	15
St Martin Vintrey	41
St Mary Abchurch	28
St Mary in Aldermanbury	33
St Mary Aldermary	22
St Mary le Bow in Cheapſide	37
St Mary Bothaw at Dowgate	6
St Mary Colechurch	0
St Mary Hill by Billinſgate	36
St Mary Magd. in Milk-ſtr.	0
St Mary Magd. Old Fiſh-ſtr.	22
St Mary Mounthaw	11
St Mary Somerſet	44
St Mary Staining	27
St Mary Woolchurch	0
St Mary Woolnoth	12
St Matthew in Friday-ſtreet	15
St Michael Baſſiſhaw	22
St Michael in Cornhill	13
St Michael in Crooked-lane	18
St Michael at Queenhithe	25
St Michael at Quern	5
St Michael Royal	13
St Michael in Wood-ſtreet	9
St Mildred in Bread-ſtreet	16
St Mildred in the Poultry	36
St Nicholas Acons	1
St Nicholas Coleabby	24
St Nicholas Olave	10
St Olave in Hart-ſtreet	50
St Olave in the Old Jewry	8
St Olave in Silver-ſtreet	29
St Pancras in Pancras-lane	0
St Peter in Cheapſide	8
St Peter in Cornhill	32
St Peter near Paul's Wharf	21
St Peter Poor in Broad-ſtr.	26
St Stephen in Coleman-ſtreet	86
St Stephen in Walbrook	17
St Swithin at London-ſtone	21
St Thomas the Apoſtle	22
Trinity Pariſh	16
St Vedaſt, alias Foſter	28

Chriſtened in the ninety-ſeven Pariſhes within the Walls 2031 Buried 2592

St Andrew in Holborn	1165	Bridewell Precinct 23
St Bartholomew the Great	57	St Bridget, vulg. St Bride's 309
St Bartholomew the Leſs	33	St Dunſtan in the Weſt 208
St Botolph by Alderſgate	200	St George in Southwark 485
St Botolph by Aldgate	817	St Giles by Cripplegate 1367
St Botolph by Biſhopſgate	521	St Olave in Southwark 817
St Saviour in Southwark	628	
St Sepulchre's Pariſh	647	
St Thomas in Southwark	181	
Trinity in the Minories	21	
The Peſt-houſe	—	

Chriſtened in the ſixteen Pariſhes without the Walls 6211 Buried 7479

1717.

Chriſt Church in Surrey —202	St John at Wapping——327	St Mary Magd. Bermondſey 458
St Dunſtan at Stepney——2369	St Katherine near the Tower 206	St Mary at Newington——175
St Giles in the Fields——1347	St Leonard in Shoreditch —643	St Mary at Rotherhith——214
St James at Clerkenwell —422	St Mary at Iſlington ——178	St Mary in Whitechapel —889
St John at Hackney——165	St Mary at Lambeth ——325	St Paul at Shadwell ——450

Chriſtened in the fifteen Out Pariſhes in Middleſex and Surrey 6172 Buried 8370

St Ann in Weſtminſter —447	St Margaret in Weſtminſt. 1006	St Mary Savoy in the Strand 113
St Clement Danes— ——419	St Martin in the Fields —1605	St Paul in Covent Garden 256
St James in Weſtminſter 1159		

Chriſtened in the ſeven Pariſhes in the City and Liberties of Weſtminſter 4061 Buried 5005

DISEASES and CASUALTIES.

ABORTIVE —— 89	Grief —— —— 8	Riſing of the Lights— 47	
Aged ——2011	Griping in the Guts— 653	Rupture —— —— 18	CASUALTIES.
Ague —— —— 4	Head-ach — —— 4	St Anthony's Fire—— 4	
Apoplexy —— — 88	Headmouldſhot —— 52	Scald Head —— — 2	BRoken Arm — — 1
Aſthma —— —— 39	Hooping Cough —— 15	Scarlet Fever —— 2	Broken Leg —— 2
Bedridden —— — 3	Horſhoehead —— 9	Sciatica — —— 2	Bruiſed — —— 6
Bleeding — —— 1	Jaundies —— — 96	Scurvy —— —— 3	Burnt —— —— 2
Bloody Flux —— 12	Impoſthume — —— 56	Small Pox — ——2211	Choaked — —— 1
Burſten —— —— 9	Infants — —— 8	Sores and Ulcers —— 30	Dropt down dead — 1
Cancer — —— 75	Inflammation —— 3	Spleen —— — 4	Drowned — —— 62
Canker —— —— 9	Leproſy —— — 2	Spotted Fever —— 137	Exceſſive Drinking — 5
Chicken Pox —— 1	Lethargy —— —— 8	Stillborn —— —— 596	Executed — —— 19
Childbed — —— 243	Livergrown —— — 1	Stone —— —— 47	Found dead - —— 36
Chriſomes — —— 46	Looſneſs — —— 55	Stoppage in the Stomach 233	Frighted — —— 2
Colick —— — 92	Lunatick — —— 38	Strangury — —— 1	Hang'd itſelf accidentally — } 1
Conſumption ——2764	Malignant Fever - — 1	Strongullion — — 8	Killed by ſeveral Accidents } 61
Convulſion — ——7147	Meaſles —— —— 35	Suddenly — —— 122	Made away themſelves 37
Cough — —— 4	Megrims —— — 1	Surfeit —— — 18	Murdered — —— 9
Diabetes —— — 6	Mortification —— 125	Swelling in the Throat 1	Overlaid — —— 70
Dropſy — —— 740	Pain in the Head —— 1	Teeth —— ——1250	Scorched and burnt — 2
Evil —— —— 37	Palſy —— —— 32	Thruſh —— —— 64	Starved —— —— 1
Fever —— ——2940	Pleuriſy —— —— 32	Tiſſick — —— 289	Wounded — —— 2
Fiſtula —— —— 14	Purples — —— 16	Twiſting of the Guts 17	
Flux —— —— 10	Quinſy —— —— 13	Tympany — —— 8	Total 320
French Pox — —— 109	Raſh —— —— 8	Vomiting —— — 24	
Gangrene —— — 1	Rheumatiſm — — 29	Water in the Head — 26	
Gout —— —— 30	Rickets — —— 96	Worms —— —— 39	
Gravel — —— 2			

CHRISTENED	Males — 9630	BURIED	Males — 11934
	Females 8845		Females 11512
	In all — 18475		In all — 23446

Decreaſed in the Burials this Year 990

A General

1718.

A General BILL of all the Chriſtenings and Burials,

From the 17th of December 1717, to the 16th of December 1718.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	31
Alhallows Barkin —	95
Alhallows in Bread-ſtreet —	10
Alhallows the Great ——	62
Alhallows in Honey-lane —	0
Alhallows the Leſs ——	16
Alhallows in Lombard-ſtreet	16
Alhallows Staining ——	34
Alhallows on London Wall	79
St Alphage near Sion College	37
St Andrew Hubbard ——	5
St Andrew Underſhaft ——	48
St Andrew Wardrobe ——	59
St Ann within Alderſgate —	54
St Ann in Black Friars ——	169
St Anthony, vulg. Antholin	12
St Auguſtin, vulg. Auſtin—	13
St Bartholomew by Exchange	27
St Benedict, v. Bennet Fink	23
St Bennet Gracechurch——	19
St Bennet at Paul's Wharf—	37
St Bennet Sherehog ——	4
St Botolph at Billinſgate —	12
Chriſt Church Pariſh ——	151
St Chriſtopher's Pariſh——	19
St Clement near Eaſtcheap	10
St Dionis Backchurch ——	30
St Dunſtan in the Eaſt ——	63
St Edmund the King ——	20
St Ethelburga's Pariſh ——	24
St Faith under St Paul's —	29
St Gabriel in Fenchurch-ſtr.	8
St George in Botolph-lane—	7
St Gregory by St Paul's —	70
St Helen near Biſhopſgate—	31
St James in Duke's Place —	24
St James at Garlickhithe —	40
St John Baptiſt by Dowgate	17
St John the Evangeliſt ——	1
St John Zachary —— —	27
St Katherine Coleman ——	46
St Katherine Creechurch —	57
St Laurence Jewry ——	58
St Laurence Pountney ——	21
St Leonard in Eaſtcheap —	6
St Leonard in Foſter-lane—	25
St Magnus by London Bridge	51
St Margaret in Lothbury —	27
St Margaret Moſes ——	14
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattons ——	17
St Martin Ironmonger-lane	10
St Martin at Ludgate ——	50
St Martin Orgars —— —	11
St Martin Outwich ——	15
St Martin Vintrey —— —	49
St Mary Abchurch ——	33
St Mary in Aldermanbury—	29
St Mary Aldermary ——	33
St Mary le Bow in Cheapſide	30
St Mary Bothaw at Dowgate	7
St Mary Colechurch ——	1
St Mary Hill by Billinſgate	37
St Mary Magd. in Milk-ſtr.	0
St Mary Magd. Old Fiſh-ſtr.	30
St Mary Mounthaw ——	9
St Mary Somerſet — ——	22
St Mary Staining —— —	24
St Mary Woolchurch ——	0
St Mary Woolnoth — —	14
St Matthew in Friday-ſtreet	9
St Michael Baſſiſhaw ——	29
St Michael in Cornhill ——	28
St Michael in Crooked-lane	32
St Michael at Queenhithe—	34
St Michael at Quern ——	7
St Michael Royal —— —	17
St Michael in Wood-ſtreet	16
St Mildred in Bread-ſtreet—	10
St Mildred in the Poultry—	34
St Nicholas Acons — ——	2
St Nicholas Coleabby — —	24
St Nicholas Olave — ——	6
St Olave in Hart-ſtreet ——	42
St Olave in the Old Jewry	7
St Olave in Silver-ſtreet —	36
St Pancras in Pancras-lane	0
St Peter in Cheapſide ——	6
St Peter in Cornhill ——	39
St Peter near Paul's Wharf	18
St Peter Poor in Broad-ſtr.	20
St Stephen in Coleman-ſtreet	99
St Stephen in Walbrook —	18
St Swithin at London-ſtone	19
St Thomas the Apoſtle ——	13
Trinity Pariſh — ——	12
St Vedaſt, alias Foſter ——	23

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1899 Buried 2759

St Andrew in Holborn —	1348
St Bartholomew the Great--	66
St Bartholomew the Leſs —	35
St Botolph by Alderſgate—	258
St Botolph by Aldgate——	871
St Botolph by Biſhopſgate—	586
Bridewell Precinct ——	26
St Bridget, vulg. St Bride's	345
St Dunſtan in the Weſt ——	242
St George in Southwark —	585
St Giles by Cripplegate —	1559
St Olave in Southwark——	819
St Saviour in Southwark —	765
St Sepulchre's Pariſh ——	751
St Thomas in Southwark —	169
Trinity in the Minories ——	12
The Peſt-houſe — ——	

Chriſtened in the ſixteen Pariſhes without the Walls 6166 Buried 8437

1718.

Chriſt Church in Surrey —229	St John at Wapping——314	St Mary Magd. Bermondſey 477
St Dunſtan at Stepney——2458	St Katherine near the Tower 196	St Mary at Newington ——305
St Giles in the Fields ——1789	St Leonard in Shoreditch —728	St Mary at Rotherhith ——215
St James at Clerkenwell —535	St Mary at Iſlington ——219	St Mary in Whitechapel —891
St John at Hackney ——202	St Mary at Lambeth ——484	St Paul at Shadwell ——443

Chriſtened in the fifteen Out Pariſhes in Middleſex and Surrey 6333 Buried 9485

St Ann in Weſtminſter —524	St Margaret in Weſtminſt. 1245	St Mary Savoy in the Strand 162
St Clement Danes — ——464	St Martin in the Fields —1860	St Paul in Covent Garden 251
St James in Weſtminſter 1336		

Chriſtened in the ſeven Pariſhes in the City and Liberties of Weſtminſter 3909 Buried 5842

DISEASES and CASUALTIES.

ABORTIVE —— 86	Gangrene —— — 2	Raſh —— —— 13	
Aged ——2221	Gout —— —— 38	Rheumatiſm — — 41	CASUALTIES.
Ague —— —— 10	Gravel — —— 3	Rickets — —— 81	
Apoplexy —— — 92	Green Sickneſs —— 1	Riſing of the Lights— 64	BRoken Leg —— 4
Aſthma —— —— 107	Grief —— —— 10	Rupture —— —— 4	Bruiſed — —— 5
Bedridden —— — 9	Griping in the Guts— 801	St Anthony's Fire—— 2	Burnt —— —— 5
Bleeding — —— 1	Head-ach — —— 2	Scarlet Fever —— 7	Died by Accident—— 1
Bloody Flux —— 27	Headmouldſhot —— 57	Small Pox ——1884	Drowned — —— 81
Burſten —— —— 6	Hooping Cough —— 24	Sores and Ulcers —— 40	Exceſſive Drinking — 11
Cancer — —— 73	Horſhoehead —— 10	Spleen —— — 3	Executed — —— 15
Canker —— —— 8	Jaundies —— — 129	Spotted Fever —— 132	Found dead —— 36
Chicken Pox —— 2	Impoſthume — —— 47	Stillborn —— —— 609	Frighted —— — 1
Childbed — —— 263	Infants —— — 19	Stone —— —— 45	Killed by ſeveral Acci- 56
Chincough —— — 8	Inflammation —— 1	Stoppage in the Stomach 152	Made away themſelves 31
Chriſomes — —— 53	Leproſy —— — 4	Strangury — —— 11	Murdered — —— 7
Colick —— — 84	Lethargy —— —— 12	Suddenly — —— 98	Overlaid — —— 76
Conſumption ——3106	Livergrown —— — 2	Surfeit —— — 15	Poiſoned —— — 4
Convulſion — ——8055	Looſneſs — —— 62	Swelling — —— 2	Scalded —— —— 3
Cough —— — 14	Lunatick — —— 29	Teeth —— ——1487	Stifled — —— 1
Cramp — —— 1	Malignant Fever —— 1	Thruſh —— —— 72	Wounded — —— 3
Diabetes —— — 4	Meaſles —— —— 492	Tiſſick — —— 387	
Dropſy — ——1014	Mortification —— 124	Twiſting of the Guts 53	Total 340
Evil —— —— 45	Overflowing of the Gall 1	Tympany —— — 16	
Falling Sickneſs —— 1	Palſy —— —— 36	Vapours —— —— 1	
Fever —— ——3475	Pleuriſy —— —— 32	Vomiting —— — 40	
Fiſtula —— —— 17	Purples — —— 26	Water in the Head — 29	
Flux —— —— 10	Quinſy —— —— 19	Worms —— —— 28	
French Pox — —— 91			

CHRISTENED	Males — 9444	BURIED	Males — 13339
	Females 8863		Females 13184
	In all — 18307		In all — 26523

Increaſed in the Burials this Year 3077

1719.

A General BILL of all the Chriſtenings and Burials,

From the 16th of December 1718, to the 15th of December 1719.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	28
Alhallows Barkin	101
Alhallows in Bread-ſtreet	16
Alhallows the Great	74
Alhallows in Honey-lane	1
Alhallows the Leſs	13
Alhallows in Lombard-ſtreet	21
Alhallows Staining	38
Alhallows on London Wall	70
St Alphage near Sion College	38
St Andrew Hubbard	10
St Andrew Underſhaft	38
St Andrew Wardrobe	61
St Ann within Alderſgate	51
St Ann in Black Friars	145
St Anthony, vulg. Antholin	16
St Auguſtin, vulg. Auſtin	13
St Bartholomew by Exchange	23
St Benedict, v. Bennet Fink	26
St Bennet Gracechurch	7
St Bennet at Paul's Wharf	50
St Bennet Sherehog	1
St Botolph at Billinſgate	12
Chriſt Church Pariſh	165
St Chriſtopher's Pariſh	21
St Clement near Eaſtcheap	14
St Dionis Backchurch	32
St Dunſtan in the Eaſt	58
St Edmund the King	24
St Ethelburga's Pariſh	22
St Faith under St Paul's	36
St Gabriel in Fenchurch-ſtr.	9
St George in Botolph-lane	12
St Gregory by St Paul's	67
St Helen near Biſhopſgate	31
St James in Duke's Place	21
St James at Garlickhithe	41
St John Baptiſt by Dowgate	23
St John the Evangeliſt	4
St John Zachary	27
St Katherine Coleman	60
St Katherine Creechurch	49
St Laurence Jewry	51
St Laurence Pountney	20
St Leonard in Eaſtcheap	16
St Leonard in Foſter-lane	19
St Magnus by London Bridge	43
St Margaret in Lothbury	37
St Margaret Moſes	8
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattons	16
St Martin Ironmonger-lane	14
St Martin at Ludgate	34
St Martin Orgars	25
St Martin Outwich	13
St Martin Vintrey	52
St Mary Abchurch	23
St Mary in Aldermanbury	34
St Mary Aldermary	28
St Mary le Bow in Cheapſide	30
St Mary Bothaw at Dowgate	7
St Mary Colechurch	0
St Mary Hill by Billinſgate	40
St Mary Magd. in Milk-ſtr.	0
St Mary Magd. Old Fiſh-ſtr.	34
St Mary Mounthaw	17
St Mary Somerſet	41
St Mary Staining	23
St Mary Woolchurch	0
St Mary Woolnoth	18
St Matthew in Friday-ſtreet	6
St Michael Baſſiſhaw	35
St Michael in Cornhill	10
St Michael in Crooked-lane	24
St Michael at Queenhithe	39
St Michael at Quern	15
St Michael Royal	23
St Michael in Wood-ſtreet	7
St Mildred in Bread-ſtreet	14
St Mildred in the Poultry	24
St Nicholas Acons	4
St Nicholas Coleabby	17
St Nicholas Olave	16
St Olave in Hart-ſtreet	44
St Olave in the Old Jewry	14
St Olave in Silver-ſtreet	37
St Pancras in Pancras-lane	1
St Peter in Cheapſide	6
St Peter in Cornhill	40
St Peter near Paul's Wharf	14
St Peter Poor in Broad-ſtr.	37
St Stephen in Coleman-ſtreet	120
St Stephen in Walbrook	17
St Swithin at London-ſtone	21
St Thomas the Apoſtle	20
Trinity Pariſh	24
St Vedaſt, alias Foſter	28

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1917 Buried 2870

St Andrew in Holborn	1357
St Bartholomew the Great	72
St Bartholomew the Leſs	36
St Botolph by Alderſgate	247
St Botolph by Aldgate	964
St Botolph by Biſhopſgate	601
Bridewell Precinct	30
St Bridget, vulg. St Bride's	348
St Dunſtan in the Weſt	237
St George in Southwark	647
St Giles by Cripplegate	1589
St Olave in Southwark	1002
St Saviour in Southwark	881
St Sepulchre's Pariſh	746
St Thomas in Southwark	216
Trinity in the Minories	26
The Peſt-houſe	—

Chriſtened in the ſixteen Pariſhes without the Walls 6188 Buried 8999

1719.

Chriſt Church in Surrey —213	St John at Wapping ——400	St Mary Magd. Bermondſey 638
St Dunſtan at Stepney——2750	St Katherine near the Tower 259	St Mary at Newington ——377
St Giles in the Fields ——1737	St Leonard in Shoreditch —849	St Mary at Rotherhith ——343
St James at Clerkenwell —510	St Mary at Iſlington — —209	St Mary in Whitechapel—1016
St John at Hackney ——177	St Mary at Lambeth ——515	St Paul at Shadwell ——508

Chriſtened in the fifteen Out Pariſhes in Middleſex and Surrey 6421 Buried 10501

St Ann in Weſtminſter - —491	St Margaret in Weſtminſt. 1319	St Mary Savoy in the Strand110
St Clement Danes — ——523	St Martin in the Fields —1956	St Paul in Covent Garden 229
St James in Weſtminſter—1349		

Chriſtened in the ſeven Pariſhes in the City and Liberties of Weſtminſter 3887 Buried 5977

DISEASES and CASUALTIES.

ABORTIVE —— 84	Gangrene — —— 1	Rheumatiſm —— — 32	
Aged ——2384	Gout —— —— 44	Rickets —— —— 91	CASUALTIES.
Ague —— —— 15	Gravel —— — 5	Riſing of the Lights— 76	
Apoplexy — —— 92	Grief —— —— 12	Rupture —— —— 17	BRoken Leg — — 3
Aſthma — —— 124	Griping in the Guts— 826	St Anthony's Fire—— 2	Broken Skull—— 1
Bedridden —— — 14	Headmouldſhot —— 60	Scarlet Fever —— 3	Bruiſed — —— 7
Bleeding —— —— 6	Hooping Cough —— 17	Small Pox — ——3229	Burnt —— —— 1
Bloody Flux —— 18	Horſhoehead —— 24	Sores and Ulcers —— 41	Died by Accident —— 1
Burſten —— —— 9	Jaundies —— — 123	Spleen —— —— 2	Died of a Wound —— 1
Cancer — —— 99	Impoſthume — —— 53	Spotted Fever —— 124	Drowned — —— 81
Canker —— —— 13	Infants —— —— 18	Stillborn —— —— 586	Exceſſive Drinking — 16
Chicken Pox —— 1	Inflammation — — 5	Stone —— —— 50	Executed —— —— 18
Childbed —— — 292	Leproſy —— — 5	Stoppage in the Stomach 150	Found dead — — 29
Chincough — —— 12	Lethargy — —— 7	Strangury —— —— 4	Killed by ſeveral Ac- } 44
Chriſomes — —— 50	Livergrown —— — 4	Suddenly —— —— 118	cidents }
Colick — —— 120	Looſneſs —— —— 90	Surfeit —— —— 17	Killed by a Fall —— 23
Conſumption ——3206	Lunatick — —— 42	Swelling in the Knee 1	Killed with a Sword— 1
Convulſion — ——7690	Meaſles —— — 243	Teeth —— —1734	Murdered — —— 6
Cough — —— 13	Megrims — —— 1	Thruſh —— —— 72	Overlaid —— —— 67
Diabetes —— — 4	Mortification —— 153	Tiſſick —— —— 337	Scalded —— — 4
Diſtracted — —— 1	Overflowing of the Gall 1	Twiſting of the Guts 54	Self-Murder —— 26
Dropſy —— ——1109	Pain in the Head —— 1	Tympany — —— 19	Starved — —— 1
Evil —— —— 31	Palſy —— —— 33	Vomiting —— — 27	Suffocated —— — 1
Fever —— ——3803	Pleuriſy —— —— 44	Water in the Head — 31	
Fiſtula —— —— 12	Purples — —— 42	White Swelling —— 2	Total 331
Flux —— —— 21	Quinſy —— —— 11	Worms —— —— 27	
French Pox — —— 70	Raſh —— —— 12		

CHRISTENED	Males — 9516	BURIED	Males — 14157
	Females 8897		Females 14190
	In all 18413		In all — 28347

Increaſed in the Burials this Year 1824

1720.

A General BILL of all the Chriſtenings and Burials,

From the 15th of December 1719, to the 13th of December 1720.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	34
Alhallows Barkin	104
Alhallows in Bread-ſtreet	11
Alhallows the Great	53
Alhallows in Honey-lane	0
Alhallows the Leſs	17
Alhallows in Lombard-ſtreet	13
Alhallows Staining	32
Alhallows on London Wall	69
St Alphage near Sion College	36
St Andrew Hubbard	17
St Andrew Underſhaft	51
St Andrew Wardrobe	56
St Ann within Alderſgate	29
St Ann in Black Friars	126
St Anthony, vulg. Antholin	9
St Auguſtin, vulg. Auſtin	16
St Bartholomew by Exchange	24
St Benedict, v. Bennet Fink	17
St Bennet Gracechurch	11
St Bennet at Paul's Wharf	36
St Bennet Sherehog	3
St Botolph at Billinſgate	10
Chriſt Church Pariſh	186
St Chriſtopher's Pariſh	15
St Clement near Eaſtcheap	11
St Dionis Backchurch	31
St Dunſtan in the Eaſt	72
St Edmund the King	17
St Ethelburga's Pariſh	26
St Faith under St Paul's	35
St Gabriel in Fenchurch-ſtr.	9
St George in Botolph-lane	14
St Gregory by St Paul's	69
St Helen near Biſhopſgate	31
St James in Duke's Place	23
St James at Garlickhithe	34
St John Baptiſt by Dowgate	18
St John the Evangeliſt	2
St John Zachary	16
St Katherine Coleman	51
St Katherine Creechurch	59
St Laurence Jewry	42
St Laurence Pountney	12
St Leonard in Eaſtcheap	5
St Leonard in Foſter-lane	37
St Magnus by London Bridge	43
St Margaret in Lothbury	23
St Margaret Moſes	5
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattons	20
St Martin Ironmonger-lane	10
St Martin at Ludgate	46
St Martin Orgars	8
St Martin Outwich	11
St Martin Vintrey	29
St Mary Abchurch	17
St Mary in Aldermanbury	41
St Mary Aldermary	31
St Mary le Bow in Cheapſide	24
St Mary Bothaw at Dowgate	2
St Mary Colechurch	0
St Mary Hill by Billinſgate	29
St Mary Magd. in Milk-ſtr.	0
St Mary Magd. Old Fiſh-ſtr.	31
St Mary Mounthaw	4
St Mary Somerſet	37
St Mary Staining	17
St Mary Woolchurch	0
St Mary Woolnoth	5
St Matthew in Friday-ſtreet	8
St Michael Baſſiſhaw	31
St Michael in Cornhill	19
St Michael in Crooked-lane	30
St Michael at Queenhithe	35
St Michael at Quern	11
St Michael Royal	17
St Michael in Wood-ſtreet	16
St Mildred in Bread-ſtreet	16
St Mildred in the Poultry	34
St Nicholas Acons	1
St Nicholas Coleabby	22
St Nicholas Olave	15
St Olave in Hart-ſtreet	47
St Olave in the Old Jewry	11
St Olave in Silver-ſtreet	33
St Pancras in Pancras-lane	1
St Peter in Cheapſide	5
St Peter in Cornhill	38
St Peter near Paul's Wharf	30
St Peter Poor in Broad-ſtr.	28
St Stephen in Coleman-ſtreet	99
St Stephen in Walbrook	17
St Swithin at London-ſtone	25
St Thomas the Apoſtle	24
Trinity Pariſh	13
St Vedaſt, alias Foſter	35

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1898 Buried 2686

St Andrew in Holborn	1296
St Bartholomew the Great	60
St Bartholomew the Leſs	24
St Botolph by Alderſgate	208
St Botolph by Aldgate	819
St Botolph by Biſhopſgate	516
Bridewell Precinct	17
St Bridget, vulg. St Bride's	357
St Dunſtan in the Weſt	230
St George in Southwark	499
St Giles by Cripplegate	1481
St Olave in Southwark	786
St Saviour in Southwark	771
St Sepulchre's Pariſh	728
St Thomas in Southwark	250
Trinity in the Minories	27
The Peſt-houſe	—

Chriſtened in the ſixteen Pariſhes without the Walls 5931 Buried 8069

Chriſt Church in Surrey —263	St John at Wapping——313	St Mary Magd. Bermondſey 484
St Dunſtan at Stepney——2257	St Katherine near the Tower 169	St Mary at Newington——322
St Giles in the Fields——1747	St Leonard in Shoreditch —664	St Mary at Rotherhith——229
St James at Clerkenwell —413	St Mary at Iſlington——207	St Mary in Whitechapel —884
St John at Hackney——173	St Mary at Lambeth — —454	St Paul at Shadwell——442

Chriſtened in the fifteen Out Pariſhes in Middleſex and Surrey 5901 Buried 9021

St Ann in Weſtminſter —434	St Margaret in Weſtminſt. 1210	St Mary Savoy in the Strand 146
St Clement Danes——522	St Martin in the Fields —1927	St Paul in Covent Garden 243
St James in Weſtminſter 1196		

Chriſtened in the ſeven Pariſhes in the City and Liberties of Weſtminſter 3749 Buried 5678

DISEASES and CASUALTIES.

ABORTIVE—132	Gravel——5	Riſing of the Lights—122	
Aged——2317	Grief——12	Rupture——20	CASUALTIES.
Ague——15	Griping in the Guts—731	St Anthony's Fire—8	
Apoplexy——82	Headmouldſhot——66	Scald Head——2	BRoken Leg——2
Aſthma——86	Hooping Cough——33	Scarlet Fever——3	Bruiſed——3
Bedridden——3	Horſhoehead——46	Scurvy——1	Burnt——3
Bleeding——4	Jaundies——107	Small Pox——1440	Died for Want——2
Bloody Flux——11	Impoſthume——47	Sores and Ulcers——32	Drowned——66
Burſten——6	Infants——14	Spleen——6	Exceſſive Drinking—18
Cancer——64	Inflammation——6	Spotted Fever——66	Executed——20
Canker——20	Lethargy——6	Stillborn——562	Found dead——21
Childbed——260	Livergrown——1	Stone——59	Frighted——1
Chincough——10	Looſneſs——45	Stoppage in the Stomach 125	Killed by ſeveral Accidents 47
Chriſomes——56	Lunatick——44	Strangury——10	Killed by Falls——13
Colick——98	Meaſles——213	Suddenly——119	Killed with a Sword—3
Conſumption——3054	Mortification——184	Surfeit——8	Killed themſelves——27
Convulſion——6787	Pain in the Head——3	Swine Pox——1	Murdered——4
Cough——8	Pain in the Limbs——1	Teeth——1817	Overlaid——69
Diabetes——5	Pain in the Stomach—1	Thruſh——80	Scalded——1
Dropſy——1021	Planet-ſtruck——1	Tiſſick——455	Shot——1
Evil——24	Palſy——40	Twiſting of the Guts 77	Smothered——4
Fever——3910	Pleuriſy——32	Tympany——9	Stabbed——1
Fiſtula——12	Purples——16	Vomiting——21	Suffocated——3
Flux——11	Quinſy——7	Water in the Head—110	
French Pox——108	Raſh——10	White Swelling——1	Total 309
Gangrene——5	Rheumatiſm——22	Worms——75	
Gout——30	Rickets——84		

CHRISTENED	Males — 8877	BURIED	Males — 12713
	Females 8602		Females 12741
	In all — 17479		In all — 25454

Decreaſed in the Burials this Year 2893

A General

1721.

A General BILL of all the Chriſtenings and Burials,

From the 13th of December 1720, to the 12th of December 1721.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	31
Alhallows Barkin	76
Alhallows in Bread-ſtreet	14
Alhallows the Great	57
Alhallows in Honey-lane	0
Alhallows the Leſs	20
Alhallows in Lombard-ſtreet	12
Alhallows Staining	26
Alhallows on London Wall	64
St Alphage near Sion College	23
St Andrew Hubbard	15
St Andrew Underſhaft	43
St Andrew Wardrobe	47
St Ann within Alderſgate	40
St Ann in Black Friars	122
St Anthony, vulg. Antholin	14
St Auguſtin, vulg. Auſtin	24
St Bartholomew by Exchange	19
St Benedict, v. Bennet Fink	24
St Bennet Gracechurch	16
St Bennet at Paul's Wharf	36
St Bennet Sherehog	1
St Botolph at Billinſgate	12
Chriſt Church Pariſh	149
St Chriſtopher's Pariſh	22
St Clement near Eaſtcheap	18
St Dionis Backchurch	25
St Dunſtan in the Eaſt	84
St Edmund the King	14
St Ethelburga's Pariſh	21
St Faith under St Paul's	38
St Gabriel in Fenchurch-ſtr.	7
St George in Botolph-lane	16
St Gregory by St Paul's	57
St Helen near Biſhopſgate	35
St James in Duke's Place	25
St James at Garlickhithe	39
St John Baptiſt by Dowgate	15
St John the Evangeliſt	5
St John Zachary	25
St Katherine Coleman	49
St Katherine Creechurch	63
St Laurence Jewry	43
St Laurence Pountney	14
St Leonard in Eaſtcheap	7
St Leonard in Foſter-lane	21
St Magnus by London Bridge	42
St Margaret in Lothbury	30
St Margaret Moſes	11
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattons	9
St Martin Ironmonger-lane	10
St Martin at Ludgate	29
St Martin Orgars	18
St Martin Outwich	15
St Martin Vintrey	34
St Mary Abchurch	25
St Mary in Aldermanbury	31
St Mary Aldermary	41
St Mary le Bow in Cheapſide	20
St Mary Bothaw at Dowgate	5
St Mary Colechurch	0
St Mary Hill by Billinſgate	33
St Mary Magd. in Milk-ſtr.	0
St Mary Magd. Old Fiſh-ſtr.	30
St Mary Mounthaw	12
St Mary Somerſet	22
St Mary Staining	16
St Mary Woolchurch	0
St Mary Woolnoth	12
St Matthew in Friday-ſtreet	10
St Michael Baſſiſhaw	30
St Michael in Cornhill	26
St Michael in Crooked-lane	32
St Michael at Queenhithe	42
St Michael at Quern	5
St Michael Royal	14
St Michael in Wood-ſtreet	13
St Mildred in Bread-ſtreet	7
St Mildred in the Poultry	17
St Nicholas Acons	5
St Nicholas Coleabby	14
St Nicholas Olave	14
St Olave in Hart-ſtreet	45
St Olave in the Old Jewry	5
St Olave in Silver-ſtreet	48
St Pancras in Pancras-lane	3
St Peter in Cheapſide	7
St Peter in Cornhill	38
St Peter near Paul's Wharf	35
St Peter Poor in Broad-ſtr.	15
St Stephen in Coleman-ſtreet	96
St Stephen in Walbrook	17
St Swithin at London-ſtone	20
St Thomas the Apoſtle	11
Trinity Pariſh	19
St Vedaſt, alias Foſter	27

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1871 Buried 2588

St Andrew in Holborn	1221
St Bartholomew the Great	52
St Bartholomew the Leſs	30
St Botolph by Alderſgate	191
St Botolph by Aldgate	816
St Botolph by Biſhopſgate	544
Bridewell Precinct	18
St Bridget, vulg. St Bride's	306
St Dunſtan in the Weſt	201
St George in Southwark	552
St Giles by Cripplegate	1419
St Olave in Southwark	929
St Saviour in Southwark	775
St Sepulchre's Pariſh	681
St Thomas in Southwark	240
Trinity in the Minories	25
The Peſt-houſe	

Chriſtened in the ſixteen Pariſhes without the Walls 5944 Buried 8000

Chriſt Church in Surrey —222	St John at Wapping ——348	St Mary Magd. Bermondſey 458
St Dunſtan at Stepney——2543	St Katherine near the Tower 194	St Mary at Newington ——350
St Giles in the Fields ——1698	St Leonard in Shoreditch —697	St Mary at Rotherhith ——278
St James at Clerkenwell —458	St Mary at Iſlington — —201	St Mary in Whitechapel —937
St John at Hackney ——172	St Mary at Lambeth — —482	St Paul at Shadwell ——526

Chriſtened in the fifteen Out Pariſhes in Middleſex and Surrey 6462 Buried 9564

St Ann in Weſtminſter - —409	St Margaret in Weſtminſt. 1278	St Mary Savoy in the Strand 141
St Clement Danes — ——561	St Martin in the Fields —1969	St Paul in Covent Garden 253
St James in Weſtminſter 1379		

Chriſtened in the ſeven Pariſhes in the City and Liberties of Weſtminſter 4093 Buried 5990.

DISEASES and CASUALTIES.

ABORTIVE —— 111	Gravel — —— 5	Rickets — —— 119	
Aged - ——2309	Grief —— —— 12	Riſing of the Lights— 133	CASUALTIES.
Ague —— —— 18	Griping in the Guts— 697	Rupture — —— 19	
Apoplexy —— — 88	Headmouldſhot — — 65	St Anthony's Fire - — 10	BRoken Leg — — 3
Aſthma — —— 167	Hooping Cough —— 20	Scald Head -—— 1	Bruiſed -—— 3
Bedridden — —— 5	Horſhoehead — — 63	Scarlet Fever —— 2	Burnt —— —— 5
Bleeding —— — 2	Jaundies —— —— 114	Scurvy —— —— 3	Concuſſion in the Brain 1
Bloody Flux —— 10	Impoſthume —— 65	Small Pox — ——2375	Drowned — —— 86
Burſten —— — 12	Infants —— —— 30	Sores and Ulcers —— 30	Exceſſive Drinking — 17
Cancer — —— 71	Inflammation —— 4	Spleen — —— 4	Executed — —— 13
Canker —— —— 17	Leproſy —— —— 1	Spotted Fever — — 84	Found dead — —— 33
Childbed —— — 299	Lethargy — —— 8	Stillborn — —— 617	Killed accidentally — 34
Chincough — —— 3	Livergrown — — 5	Stone —— —— 67	Killed by Falls -—— 25
Chriſomes — —— 43	Looſneſs — —— 42	Stoppage in the Stomach 176	Killed with a Sword— 4
Colick —— — 71	Lunatick —— — 44	Strangury — —— 9	Made away themſelves 52
Conſumption ——3188	Malignant Fever —— 1	Suddenly — —— 119	Murdered —— — 11
Convulſion — ——6879	Meaſles —— — 238	Surfeit —— — 11	Overlaid — —— 67
Cough —— — 10	Mortification —— 182	Swelling — —— 1	Scalded — —— 4
Diabetes — —— 5	Pain in the Head —— 1	Teeth — ——1595	Shot —— —— 3
Dropſy —— — 903	Pain in the Limbs —— 1	Thruſh —— —— 79	Smothered —— — 3
Evil —— —— 36	Palſy —— —— 43	Tiſſick — —— 511	Strangled — —— 1
Fever —— ——3331	Planet-ſtruck — —— 4	Twiſting of the Guts 46	
Fiſtula —— — 18	Pleuriſy — —— 31	Tympany — —— 12	Total 365
Flux —— —— 12	Purples —— — 39	Vomiting — —— 16	
French Pox — —— 66	Quinſy —— —— 12	Water in the Head — 128	
Gangrene —— — 1	Raſh —— —— 18	Worms — —— 91	
Gout —— —— 56	Rheumatiſm — — 43		

CHRISTENED	Males — 9430	BURIED	Males — 13146
	Females 8940		Females 12996
	In all — 18370		In all — 26142

Increaſed in the Burials this Year 688

A General

1721.

A General BILL of all the Chriſtenings and Burials,

From the 13th of December 1720, to the 12th of December 1721.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	31
Alhallows Barkin	76
Alhallows in Bread-ſtreet	14
Alhallows the Great	57
Alhallows in Honey-lane	0
Alhallows the Leſs	20
Alhallows in Lombard-ſtreet	12
Alhallows Staining	26
Alhallows on London Wall	64
St Alphage near Sion College	23
St Andrew Hubbard	15
St Andrew Underſhaft	43
St Andrew Wardrobe	47
St Ann within Alderſgate	40
St Ann in Black Friars	122
St Anthony, vulg. Antholin	14
St Auguſtin, vulg. Auſtin	24
St Bartholomew by Exchange	19
St Benedict, v. Bennet Fink	24
St Bennet Gracechurch	16
St Bennet at Paul's Wharf	36
St Bennet Sherehog	1
St Botolph at Billinſgate	12
Chriſt Church Pariſh	149
St Chriſtopher's Pariſh	22
St Clement near Eaſtcheap	18
St Dionis Backchurch	25
St Dunſtan in the Eaſt	84
St Edmund the King	14
St Ethelburga's Pariſh	21
St Faith under St Paul's	38
St Gabriel in Fenchurch-ſtr.	7
St George in Botolph-lane	16
St Gregory by St Paul's	57
St Helen near Biſhopſgate	35
St James in Duke's Place	25
St James at Garlickhithe	39
St John Baptiſt by Dowgate	15
St John the Evangeliſt	5
St John Zachary	25
St Katherine Coleman	49
St Katherine Creechurch	63
St Laurence Jewry	43
St Laurence Pountney	14
St Leonard in Eaſtcheap	7
St Leonard in Foſter-lane	21
St Magnus by London Bridge	42
St Margaret in Lothbury	30
St Margaret Moſes	11
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattons	9
St Martin Ironmonger-lane	10
St Martin at Ludgate	29
St Martin Orgars	18
St Martin Outwich	15
St Martin Vintrey	34
St Mary Abchurch	25
St Mary in Aldermanbury	31
St Mary Aldermary	41
St Mary le Bow in Cheapſide	20
St Mary Bothaw at Dowgate	5
St Mary Colechurch	0
St Mary Hill by Billinſgate	33
St Mary Magd. in Milk-ſtr.	0
St Mary Magd. Old Fiſh-ſtr.	30
St Mary Mounthaw	12
St Mary Somerſet	22
St Mary Staining	16
St Mary Woolchurch	0
St Mary Woolnoth	12
St Matthew in Friday-ſtreet	10
St Michael Baſſiſhaw	30
St Michael in Cornhill	26
St Michael in Crooked-lane	32
St Michael at Queenhithe	42
St Michael at Quern	5
St Michael Royal	14
St Michael in Wood-ſtreet	13
St Mildred in Bread-ſtreet	7
St Mildred in the Poultry	17
St Nicholas Acons	5
St Nicholas Coleabby	14
St Nicholas Olave	14
St Olave in Hart-ſtreet	45
St Olave in the Old Jewry	5
St Olave in Silver-ſtreet	48
St Pancras in Pancras-lane	3
St Peter in Cheapſide	7
St Peter in Cornhill	38
St Peter near Paul's Wharf	35
St Peter Poor in Broad-ſtr.	15
St Stephen in Coleman-ſtreet	96
St Stephen in Walbrook	17
St Swithin at London-ſtone	20
St Thomas the Apoſtle	11
Trinity Pariſh	19
St Vedaſt, alias Foſter	27

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1871 Buried 2588

St Andrew in Holborn	1221
St Bartholomew the Great	52
St Bartholomew the Leſs	30
St Botolph by Alderſgate	191
St Botolph by Aldgate	816
St Botolph by Biſhopſgate	544
Bridewell Precinct	18
St Bridget, vulg. St Bride's	306
St Dunſtan in the Weſt	201
St George in Southwark	552
St Giles by Cripplegate	1419
St Olave in Southwark	929
St Saviour in Southwark	775
St Sepulchre's Pariſh	681
St Thomas in Southwark	240
Trinity in the Minories	25
The Peſt-houſe	

Chriſtened in the ſixteen Pariſhes without the Walls 5944 Buried 8000

1722.

A General BILL of all the Chriſtenings and Burials,

From the 12th of December 1721, to the 11th of December 1722.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	26
Alhallows Barkin —	82
Alhallows in Bread-ſtreet —	12
Alhallows the Great ——	42
Alhallows in Honey-lane —	0
Alhallows the Leſs ——	17
Alhallows in Lombard-ſtreet	20
Alhallows Staining — ——	24
Alhallows on London Wall	39
St Alphage near Sion College	39
St Andrew Hubbard — —	9
St Andrew Underſhaft ——	48
St Andrew Wardrobe ——	46
St Ann within Alderſgate—	48
St Ann in Black Friars - —	158
St Anthony, vulg. Antholin	8
St Auguſtin, vulg. Auſtin—	14
St Bartholomew by Exchange	18
St Benedict, v. Bennet Fink	14
St Bennet Gracechurch - —	14
St Bennet at Paul's Wharf	56
St Bennet Sherehog - ——	0
St Botolph at Billinſgate —	6
Chriſt Church Pariſh ——	130
St Chriſtopher's Pariſh ——	17
St Clement near Eaſtcheap	16
St Dionis Backchurch ——	30
St Dunſtan in the Eaſt ——	62
St Edmund the King — —	24
St Ethelburga's Pariſh ——	24
St Faith under St Paul's —	38
St Gabriel in Fenchurch-ſtr.	7
St George in Botolph-lane—	17
St Gregory by St Paul's —	65
St Helen near Biſhopſgate—	33
St James in Duke's Place —	34
St James at Garlickhithe —	39
St John Baptiſt by Dowgate	29
St John the Evangeliſt ——	7
St John Zachary —— —	20
St Katherine Coleman ——	41
St Katherine Creechurch —	43
St Laurence Jewry ———	52
St Laurence Pountney ——	27
St Leonard in Eaſtcheap —	8
St Leonard in Foſter-lane—	28
St Magnus by London Bridge	52
St Margaret in Lothbury—	33
St Margaret Moſes ———	8
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattons — —	16
St Martin Ironmonger-lane	9
St Martin at Ludgate ——	31
St Martin Orgars —— —	11
St Martin Outwich ———	8
St Martin Vintrey — ——	36
St Mary Abchurch — —	27
St Mary in Aldermanbury—	26
St Mary Aldermary — —	18
St Mary le Bow in Cheapſide	25
St Mary Bothaw at Dowgate	9
St Mary Colechurch ———	0
St Mary Hill by Billinſgate	23
St Mary Magd. in Milk-ſtr.	0
St Mary Magd. Old Fiſh-ſtr.	36
St Mary Mounthaw — —	11
St Mary Somerſet — ——	34
St Mary Staining —— —	24
St Mary Woolchurch ——	0
St Mary Woolnoth ———	16
St Matthew in Friday-ſtreet	12
St Michael Baſſiſhaw — —	27
St Michael in Cornhill ——	25
St Michael in Crooked-lane	34
St Michael at Queenhithe—	29
St Michael at Quern ——	10
St Michael Royal —— —	16
St Michael in Wood-ſtreet	11
St Mildred in Bread-ſtreet	12
St Mildred in the Poultry	35
St Nicholas Acons —— —	1
St Nicholas Coleabby ——	18
St Nicholas Olave ———	11
St Olave in Hart-ſtreet - —	34
St Olave in the Old Jewry	6
St Olave in Silver-ſtreet —	32
St Pancras in Pancras-lane	6
St Peter in Cheapſide ——	3
St Peter in Cornhill ———	33
St Peter near Paul's Wharf	28
St Peter Poor in Broad-ſtr.	17
St Stephen in Coleman-ſtreet	94
St Stephen in Walbrook —	13
St Swithin at London-ſtone	15
St Thomas the Apoſtle - —	15
Trinity Pariſh —— ——	12
St Vedaſt, alias Foſter ——	22

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1802 Buried 2555

St Andrew in Holborn ——	1219
St Bartholomew the Great--	70
St Bartholomew the Leſs —	43
St Botolph by Alderſgate —	235
St Botolph by Aldgate ——	847
St Botolph by Biſhopſgate—	648
Bridewell Precinct ———	29
St Bridget, vulg. St Bride's	331
St Dunſtan in the Weſt - —	213
St George in Southwark —	536
St Giles by Cripplegate —	1571
St Olave in Southwark - —	904
St Saviour in Southwark —	788
St Sepulchre's Pariſh - ——	786
St Thomas in Southwark—	156
Trinity in the Minories ——	30
The Peſt-houſe — ——	

Chriſtened in the ſixteen Pariſhes without the Walls 6280 Buried 8406

1722.

Chriſt Church in Surrey —242	St John at Wapping——275	St Mary Magd. Bermondſey 483
St Dunſtan at Stepney——2491	St Katherine near the Tower 209	St Mary at Newington ——277
St Giles in the Fields ——1528	St Leonard in Shoreditch —757	St Mary at Rotherhith ——286
St James at Clerkenwell —510	St Mary at Iſlington ——171	St Mary in Whitechapel —943
St John at Hackney ——163	St Mary at Lambeth ——404	St Paul at Shadwell ——412

Chriſtened in the fifteen Out Pariſhes in Middleſex and Surrey 6352 Buried 9151

St Ann in Weſtminſter —354	St Margaret in Weſtminſt. 1158	St Mary Savoy in the Strand 171
St Clement Danes — ——509	St Martin in the Fields —1910	St Paul in Covent Garden 255
St James in Weſtminſter 1281		

Chriſtened in the ſeven Pariſhes in the City and Liberties of Weſtminſter 3905 Buried 5638

DISEASES and CASUALTIES.

ABORTIVE —— 100	Gravel — —— 2	Rickets — —— 145	
Aged ——2253	Grief —— —— 9	Riſing of the Lights— 148	CASUALTIES.
Ague —— —— 9	Griping in the Guts— 663	Rupture —— —— 19	
Apoplexy —— — 100	Headmouldſhot —— 32	St Anthony's Fire—— 17	BRoken Leg —— 1
Aſthma —— —— 125	Hooping Cough —— 21	Scald Head —— — 1	Bruiſed — —— 4
Bedridden —— — 6	Horſhoehead —— 75	Shingles — —— 1	Burnt —— —— 3
Bleeding — —— 10	Jaundies —— — 109	Small Pox —— —2167	Drowned — —— 50
Bloody Flux —— 16	Impoſthume — —— 40	Sores and Ulcers —— 37	Exceſſive Drinking — 7
Burſten —— —— 7	Infants —— — 25	Spleen —— — 1	Executed — —— 23
Cancer — —— 83	Inflammation —— 3	Spotted Fever —— 22	Found dead - —— 24
Canker —— —— 13	Leproſy —— — 4	Stillborn —— —— 684	Frighted —— — 2
Chicken Pox —— 3	Lethargy —— —— 5	Stone —— —— 44	Killed by ſeveral Acci- dents 49
Childbed — —— 293	Livergrown —— — 16	Stoppage in the Stomach 138	
Chincough —— — 3	Looſneſs — —— 15	Strangury — —— 4	Killed with a Sword— 3
Chriſomes — —— 45	Lunatick — —— 32	Suddenly — —— 84	Killed with a hot Iron 1
Colick —— — 131	Malignant Fever - — 2	Surfeit —— — 5	Made away themſelves 41
Conſumption ——3107	Meaſles —— —— 114	Swelling — —— 5	Murdered — —— 9
Convulſion — ——7152	Megrims — —— 1	Teeth —— ——1955	Overlaid — —— 76
Cough —— — 2	Mortification —— 184	Thruſh —— —— 93	Poiſoned —— — 1
Diabetes —— — 3	Pain in the Head —— 2	Tiſſick — —— 399	Scalded —— —— 1
Dropſy — —— 988	Palſy —— —— 37	Twiſting of the Guts 15	Shot —— —— 3
Evil —— —— 31	Pleuriſy —— —— 26	Tympany —— — 9	Stabbed — —— 1
Fever —— ——3088	Purples — —— 23	Vapours —— —— 1	
Fiſtula —— —— 11	Quinſy —— —— 14	Vomiting —— — 15	Total 299
Flux —— —— 5	Raſh —— —— 9	Water in the Head — 139	
French Pox — —— 78	Rheumatiſm — — 33	Worms —— —— 90	
Gout —— —— 55			

CHRISTENED	Males — 9325	BURIED	Males — 12956
	Females 9014		Females 12794
	In all — 18339		In all — 25750

Decreaſed in the Burials this Year 392

1723.

A General BILL of all the Chriſtenings and Burials,

From the 11th of December 1722, to the 10th of December 1723.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	36
Alhallows Barkin	97
Alhallows in Bread-ſtreet	12
Alhallows the Great	71
Alhallows in Honey-lane	0
Alhallows the Leſs	19
Alhallows in Lombard-ſtreet	20
Alhallows Staining	20
Alhallows on London Wall	60
St Alphage near Sion College	42
St Andrew Hubbard	19
St Andrew Underſhaft	50
St Andrew Wardrobe	67
St Ann within Alderſgate	43
St Ann in Black Friars	138
St Anthony, vulg. Antholin	9
St Auguſtin, vulg. Auſtin	18
St Bartholomew by Exchange	17
St Benedict, v. Bennet Fink	15
St Bennet Gracechurch	19
St Bennet at Paul's Wharf	46
St Bennet Sherehog	1
St Botolph at Billinſgate	5
Chriſt Church Pariſh	177
St Chriſtopher's Pariſh	14
St Clement near Eaſtcheap	16
St Dionis Backchurch	23
St Dunſtan in the Eaſt	92
St Edmund the King	28
St Ethelburga's Pariſh	25
St Faith under St Paul's	36
St Gabriel in Fenchurch-ſtr.	9
St George in Botolph-lane	17
St Gregory by St Paul's	56
St Helen near Biſhopſgate	31
St James in Duke's Place	37
St James at Garlickhithe	39
St John Baptiſt by Dowgate	27
St John the Evangeliſt	11
St John Zachary	23
St Katherine Coleman	59
St Katherine Creechurch	73
St Laurence Jewry	50
St Laurence Pountney	26
St Leonard in Eaſtcheap	8
St Leonard in Foſter-lane	29
St Magnus by London Bridge	35
St Margaret in Lothbury	33
St Margaret Moſes	8
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattons	14
St Martin Ironmonger-lane	10
St Martin at Ludgate	33
St Martin Orgars	14
St Martin Outwich	22
St Martin Vintrey	42
St Mary Abchurch	25
St Mary in Aldermanbury	21
St Mary Aldermary	21
St Mary le Bow in Cheapſide	26
St Mary Bothaw at Dowgate	5
St Mary Colechurch	0
St Mary Hill by Billinſgate	43
St Mary Magd. in Milk-ſtr.	1
St Mary Magd. Old Fiſh-ſtr.	30
St Mary Mounthaw	13
St Mary Somerſet	51
St Mary Staining	20
St Mary Woolchurch	1
St Mary Woolnoth	17
St Matthew in Friday-ſtreet	1
St Michael Baſſiſhaw	32
St Michael in Cornhill	29
St Michael in Crooked-lane	39
St Michael at Queenhithe	35
St Michael at Quern	17
St Michael Royal	25
St Michael in Wood-ſtreet	21
St Mildred in Bread-ſtreet	12
St Mildred in the Poultry	28
St Nicholas Acons	4
St Nicholas Coleabby	18
St Nicholas Olave	13
St Olave in Hart-ſtreet	55
St Olave in the Old Jewry	11
St Olave in Silver-ſtreet	36
St Pancras in Pancras-lane	1
St Peter in Cheapſide	9
St Peter in Cornhill	41
St Peter near Paul's Wharf	26
St Peter Poor in Broad-ſtr.	19
St Stephen in Coleman-ſtreet	110
St Stephen in Walbrook	15
St Swithin at London-ſtone	20
St Thomas the Apoſtle	22
Trinity Pariſh	15
St Vedaſt, alias Foſter	27

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1868 Buried 2896

St Andrew in Holborn	1315
St Bartholomew the Great	56
St Bartholomew the Leſs	33
St Botolph by Alderſgate	218
St Botolph by Aldgate	988
St Botolph by Biſhopſgate	621
Bridewell Precinct	34
St Bridget, vulg. St Bride's	290
St Dunſtan in the Weſt	236
St George in Southwark	574
St Giles by Cripplegate	1865
St Olave in Southwark	1016
St Saviour in Southwark	971
St Sepulchre's Pariſh	887
St Thomas in Southwark	228
Trinity in the Minories	46
The Peſt-houſe	

Chriſtened in the ſixteen Pariſhes without the Walls 6643 Buried 9378

1723.

Chriſt Church in Surrey —248	St John at Wapping ——356	St Mary Magd. Bermondſey 583
St Dunſtan at Stepney——2965	St Katherine near the Tower 234	St Mary at Newington ——322
St Giles in the Fields ——1710	St Leonard in Shoreditch —824	St Mary at Rotherhith ——284
St James at Clerkenwell —555	St Mary at Iſlington — —234	St Mary in Whitechapel—1083
St John at Hackney ——204	St Mary at Lambeth ——515	St Paul at Shadwell ——553

Chriſtened in the fifteen Out Pariſhes in Middleſex and Surrey 6778 Buried 10670

St Ann in Weſtminſter - —402	St Margaret in Weſtminſt. 1356	St Mary Savoy in the Strand 177
St Clement Danes — ——549	St Martin in the Fields —2074	St Paul in Covent Garden 280
St James in Weſtminſter—1415		

Chriſtened in the ſeven Pariſhes in the City and Liberties of Weſtminſter 3914 Buried 6253

DISEASES and CASUALTIES.

ABORTIVE —— 86	Gravel —— — 2	Rickets —— —— 121	
Aged ——2225	Grief —— —— 18	Riſing of the Lights— 129	CASUALTIES.
Ague —— —— 5	Griping in the Guts— 910	Rupture —— —— 18	
Apoplexy — —— 109	Headmouldſhot —— 60	St Anthony's Fire—— 6	BRoken Limbs —— 4
Aſthma — —— 134	Hooping Cough —— 38	Scald Head —— — 1	Bruiſed - —— 5
Bedridden —— — 3	Horſhoehead —— 53	Scarlet Fever —— 2	Burnt —— —— 7
Bleeding —— —— 13	Jaundies —— — 133	Scurvy —— —— 3	Died for Want (in Newgate) 2
Bloody Flux —— 9	Impoſthume — —— 53	Small Pox — ——3271	Drowned — —— 62
Burſten —— —— 6	Inflammation — — 1	Sores and Ulcers —— 27	Exceſſive Drinking — 15
Cancer — —— 72	Leproſy —— — 5	Spleen —— —— 2	Executed —— —— 16
Canker —— —— 8	Lethargy — —— 6	Spotted Fever —— 51	Found dead — — 26
Chicken Pox —— 2	Livergrown —— — 8	Stillborn —— —— 692	Killed by ſeveral Accidents 48
Childbed —— — 291	Looſneſs —— —— 114	Stone —— —— 53	Made away themſelves 45
Chincough — —— 3	Lunatick — —— 30	Stoppage in the Stomach 163	Murdered — —— 7
Chriſtmes — —— 86	Malignant Fever —— 2	Strangury —— —— 12	Overlaid —— —— 88
Colick — —— 110	Meaſles —— — 231	Suddenly —— —— 83	Scalded —— — 2
Conſumption ——3352	Miſcarriage — — — 4	Surfeit —— —— 5	Shot —— —— 5
Convulſion — ——8244	Mortification —— 211	Swelling — —— 2	Smothered — —— 2
Cough — —— 15	Pain in the Head —— 4	Teeth —— —2006	Strangled in the Pillory 1
Diabetes —— — 4	Palſy —— —— 46	Thruſh —— —— 98	Suffocated —— — 3
Dropſy —— ——1120	Planet-ſtruck —— 1	Tiſſick —— —— 408	Total 338
Evil —— —— 28	Pleuriſy —— —— 30	Twiſting of the Guts 20	
Fever —— ——3321	Purples — —— 24	Tympany — —— 7	
Fiſtula —— —— 8	Quinſy —— —— 16	Vomiting —— — 29	
Flux —— —— 5	Raſh —— —— 11	Water in the Head — 132	
French Pox — —— 84	Rheumatiſm —— — 43	Worms —— —— 75	
Gout —— —— 46			

CHRISTENED	Males — 9811	BURIED	Males — 14738
	Females 9392		Females 14459
	In all 19203		In all — 29197

Increaſed in the Burials this Year 3447

1724.

A General BILL of all the Chriſtenings and Burials,

From the 10th of December 1723, to the 15th of December 1724.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	25
Alhallows Barkin	76
Alhallows in Bread-ſtreet	11
Alhallows the Great	45
Alhallows in Honey-lane	0
Alhallows the Leſs	16
Alhallows in Lombard-ſtreet	18
Alhallows Staining	6
Alhallows on London Wall	65
St Alphage near Sion College	29
St Andrew Hubbard	6
St Andrew Underſhaft	39
St Andrew Wardrobe	53
St Ann within Alderſgate	36
St Ann in Black Friars	132
St Anthony, vulg. Antholin	16
St Auguſtin, vulg. Auſtin	22
St Bartholomew by Exchange	22
St Benedict, v. Bennet Fink	14
St Bennet Gracechurch	15
St Bennet at Paul's Wharf	35
St Bennet Sherehog	2
St Botolph at Billinſgate	10
Chriſt Church Pariſh	186
St Chriſtopher's Pariſh	20
St Clement near Eaſtcheap	12
St Dionis Backchurch	28
St Dunſtan in the Eaſt	57
St Edmund the King	24
St Ethelburga's Pariſh	24
St Faith under St Paul's	35
St Gabriel in Fenchurch-ſtr.	8
St George in Botolph-lane	18
St Gregory by St Paul's	50
St Helen near Biſhopſgate	37
St James in Duke's Place	37
St James at Garlickhithe	39
St John Baptiſt by Dowgate	24
St John the Evangeliſt	2
St John Zachary	25
St Katherine Coleman	57
St Katherine Creechurch	53
St Laurence Jewry	55
St Laurence Pountney	14
St Leonard in Eaſtcheap	5
St Leonard in Foſter-lane	20
St Magnus by London Bridge	35
St Margaret in Lothbury	39
St Margaret Moſes	6
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattons	16
St Martin Ironmonger-lane	12
St Martin at Ludgate	35
St Martin Orgars	9
St Martin Outwich	15
St Martin Vintrey	42
St Mary Abchurch	29
St Mary in Aldermanbury	19
St Mary Aldermary	31
St Mary le Bow in Cheapſide	25
St Mary Bothaw at Dowgate	4
St Mary Colechurch	0
St Mary Hill by Billinſgate	32
St Mary Magd. in Milk-ſtr.	0
St Mary Magd. Old Fiſh-ſtr.	21
St Mary Mounthaw	5
St Mary Somerſet	50
St Mary Staining	15
St Mary Woolchurch	0
St Mary Woolnoth	15
St Matthew in Friday-ſtreet	17
St Michael Baſſiſhaw	32
St Michael in Cornhill	20
St Michael in Crooked-lane	34
St Michael at Queenhithe	32
St Michael at Quern	21
St Michael Royal	15
St Michael in Wood-ſtreet	19
St Mildred in Bread-ſtreet	14
St Mildred in the Poultry	34
St Nicholas Acons	5
St Nicholas Coleabby	9
St Nicholas Olave	7
St Olave in Hart-ſtreet	63
St Olave in the Old Jewry	9
St Olave in Silver-ſtreet	35
St Pancras in Pancras-lane	4
St Peter in Cheapſide	7
St Peter in Cornhill	33
St Peter near Paul's Wharf	19
St Peter Poor in Broad-ſtr.	34
St Stephen in Coleman-ſtreet	91
St Stephen in Walbrook	19
St Swithin at London-ſtone	26
St Thomas the Apoſtle	7
Trinity Pariſh	14
St Vedaſt, alias Foſter	20

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1927 Buried 2618

St Andrew in Holborn	1090
St Bartholomew the Great	62
St Bartholomew the Leſs	33
St Botolph by Alderſgate	198
St Botolph by Aldgate	874
St Botolph by Biſhopſgate	593
Bridewell Precinct	35
St Bridget, vulg. St Bride's	352
St Dunſtan in the Weſt	223
St George in Southwark	516
St Giles by Cripplegate	1609
St Olave in Southwark	907
St Saviour in Southwark	804
St Sepulchre's Pariſh	731
St Thomas in Southwark	250
Trinity in the Minories	26
The Peſt-houſe	

Chriſtened in the ſixteen Pariſhes without the Walls 6499 Buried 8303

1724.

Chriſt Church in Surrey —234	St John at Wapping——314	St Mary Magd. Bermondſey 524
St Dunſtan at Stepney——2585	St Katherine near the Tower 200	St Mary at Newington——319
St Giles in the Fields——1505	St Leonard in Shoreditch —765	St Mary at Rotherhith——249
St James at Clerkenwell —444	St Mary at Iſlington——218	St Mary in Whitechapel —935
St John at Hackney——174	St Mary at Lambeth — —370	St Paul at Shadwell——492

Chriſtened in the fifteen Out Pariſhes in Middleſex and Surrey 6973 Buried 9328

St Ann in Weſtminſter —364	St Margaret in Weſtminſt. 1190	St Mary Savoy in the Strand 161
St Clement Danes——523	St Martin in the Fields —1962	St Paul in Covent Garden 259
St James in Weſtminſter 1244		

Chriſtened in the ſeven Pariſhes in the City and Liberties of Weſtminſter 3971 Buried 5703

DISEASES and CASUALTIES.

ABORTIVE—104	Gout——43	Raſh——15	
Aged——2516	Gravel——8	Rheumatiſm——39	CASUALTIES.
Ague——4	Grief——19	Rickets——65	
Apoplexy——100	Griping in the Guts—710	Riſing of the Lights—132	BRoken Leg——2
Aſthma——153	Headmouldſhot——42	Rupture——16	Broken Skull——1
Bedridden——9	Hooping Cough——25	St Anthony's Fire——3	Bruiſed——3
Bleeding——5	Horſhoehead——86	Scurvy——2	Burnt——5
Bloody Flux——12	Jaundies——121	Small Pox——1227	Died for Want (in Newgate)——1
Burſten——9	Impoſthume——42	Sores and Ulcers——38	Drowned——83
Cancer——87	Inflammation——4	Spleen——2	Exceſſive Drinking —23
Canker——11	Itch——1	Spotted Fever——84	Executed——17
Chicken Pox——2	Leproſy——5	Stillborn——663	Found dead——15
Childbed——247	Lethargy——14	Stone——55	Killed by ſeveral Accidents——54
Chincough——2	Livergrown——7	Stoppage in the Stomach 148	Made away themſelves 38
Chriſomes——55	Looſneſs——31	Strangury——16	Murdered——9
Colick——147	Lunatick——25	Suddenly——105	Overlaid——89
Conſumption——3371	Malignant Fever——3	Surfeit——13	Scalded——3
Convulſion——7357	Meaſles——118	Teeth——1896	Shot——1
Cough——14	Megrims——2	Thruſh——89	Smothered——4
Diſtracted——1	Miſcarriage——1	Tiſſick——428	Starved to Death (being ſhipwreck'd)——1
Dropſy——1134	Mortification——187	Twiſting of the Guts 12	
Evil——40	Pain in the Limbs——1	Tympany——7	Total 349
Fever——3262	Palſy——45	Vomiting——24	
Fiſtula——13	Planet-ſtruck——1	Water in the Head —128	
Flux——7	Pleuriſy——34	White Swelling——1	
French Pox——98	Purples——24	Worms——28	
Gangrene——1	Quinſy——7		

CHRISTENED	Males — 9902	BURIED	Males — 13252
	Females 9468		Females 12700
	In all — 19370		In all — 25952

Decreaſed in the Burials this Year 3245

A General

1725.

A General BILL of all the Chriſtenings and Burials,

From the 15th of December 1724, to the 14th of December 1725.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	38
Alhallows Barkin	95
Alhallows in Bread-ſtreet	11
Alhallows the Great	55
Alhallows in Honey-lane	0
Alhallows the Leſs	24
Alhallows in Lombard-ſtreet	21
Alhallows Staining	26
Alhallows on London Wall	50
St Alphage near Sion College	48
St Andrew Hubbard	11
St Andrew Underſhaft	41
St Andrew Wardrobe	54
St Ann within Alderſgate	45
St Ann in Black Friars	145
St Anthony, vulg. Antholin	15
St Auguſtin, vulg. Auſtin	15
St Bartholomew by Exchange	17
St Benedict, v. Bennet Fink	28
St Bennet Gracechurch	10
St Bennet at Paul's Wharf	39
St Bennet Sherehog	4
St Botolph at Billinſgate	11
Chriſt Church Pariſh	170
St Chriſtopher's Pariſh	9
St Clement near Eaſtcheap	12
St Dionis Backchurch	28
St Dunſtan in the Eaſt	87
St Edmund the King	17
St Ethelburga's Pariſh	27
St Faith under St Paul's	30
St Gabriel in Fenchurch-ſtr.	1
St George in Botolph-lane	17
St Gregory by St Paul's	59
St Helen near Biſhopſgate	35
St James in Duke's Place	28
St James at Garlickhithe	42
St John Baptiſt by Dowgate	23
St John the Evangeliſt	4
St John Zachary	18
St Katherine Coleman	48
St Katherine Creechurch	76
St Laurence Jewry	44
St Laurence Pountney	12
St Leonard in Eaſtcheap	5
St Leonard in Foſter-lane	39
St Magnus by London Bridge	34
St Margaret in Lothbury	18
St Margaret Moſes	2
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattons	14
St Martin Ironmonger-lane	15
St Martin at Ludgate	28
St Martin Orgars	10
St Martin Outwich	6
St Martin Vintrey	47
St Mary Abchurch	21
St Mary in Aldermanbury	18
St Mary Aldermary	22
St Mary le Bow in Cheapſide	30
St Mary Bothaw at Dowgate	4
St Mary Colechurch	0
St Mary Hill by Billinſgate	25
St Mary Magd. in Milk-ſtr.	0
St Mary Magd. Old Fiſh-ſtr.	31
St Mary Mounthaw	16
St Mary Somerſet	44
St Mary Staining	9
St Mary Woolchurch	0
St Mary Woolnoth	16
St Matthew in Friday-ſtreet	10
St Michael Baſſiſhaw	23
St Michael in Cornhill	18
St Michael in Crooked-lane	38
St Michael at Queenhithe	23
St Michael at Quern	7
St Michael Royal	9
St Michael in Wood-ſtreet	25
St Mildred in Bread-ſtreet	9
St Mildred in the Poultry	27
St Nicholas Acons	7
St Nicholas Coleabby	14
St Nicholas Olave	8
St Olave in Hart-ſtreet	39
St Olave in the Old Jewry	4
St Olave in Silver-ſtreet	34
St Pancras in Pancras-lane	2
St Peter in Cheapſide	7
St Peter in Cornhill	39
St Peter near Paul's Wharf	19
St Peter Poor in Broad-ſtr.	23
St Stephen in Coleman-ſtreet	74
St Stephen in Walbrook	21
St Swithin at London-ſtone	27
St Thomas the Apoſtle	17
Trinity Pariſh	17
St Vedaſt, alias Foſter	22

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1822 Buried 2607

St Andrew in Holborn	1166	Bridewell Precinct 36
St Bartholomew the Great	48	St Bridget, vulg. St Bride's 350
St Bartholomew the Leſs	30	St Dunſtan in the Weſt 230
St Botolph by Alderſgate	236	St George in Southwark 492
St Botolph by Aldgate	843	St Giles by Cripplegate 1631
St Botolph by Biſhopſgate	504	St Olave in Southwark 848
St Saviour in Southwark	681	
St Sepulchre's Pariſh	740	
St Thomas in Southwark	268	
Trinity in the Minories	20	
The Peſt-houſe		

Chriſtened in the ſixteen Pariſhes without the Walls 6320 Buried 8123

1725.

Chriſt Church in Surrey —257	St John at Wapping ——357	St Mary Magd. Bermondſey 473
St Dunſtan at Stepney——2511	St Katherine near the Tower 209	St Mary at Newington ——274
St Giles in the Fields ——1554	St Leonard in Shoreditch—761	St Mary at Rotherhith ——244
St James at Clerkenwell —477	St Mary at Iſlington — —140	St Mary in Whitechapel —905
St John at Hackney ——171	St Mary at Lambeth — —384	St Paul at Shadwell ——445

Chriſtened in the fifteen Out Pariſhes in Middleſex and Surrey 6890 Buried 9162

St Ann in Weſtminſter - —414	St Margaret in Weſtminſt. 1220	St Mary Savoy in the Strand 130
St Clement Danes — ——577	St Martin in the Fields —1643	St Paul in Covent Garden 257
St James in Weſtminſter 1390		

Chriſtened in the ſeven Pariſhes in the City and Liberties of Weſtminſter 3827 Buried 5631

DISEASES and CASUALTIES.

ABORTIVE —— 81	Gravel — —— 3	Rickets — —— 76	CASUALTIES.
Aged - ——2194	Grief —— —— 17	Riſing of the Lights— 122	BRoken Leg — — 2
Ague —— —— 3	Griping in the Guts— 563	Rupture — —— 15	Broken Skull—— 1
Apoplexy —— — 108	Headmouldſhot — — 38	St Anthony's Fire - — 1	Bruiſed —— — 5
Aſthma — —— 118	Hooping Cough —— 53	Scurvy —— —— 3	Burnt —— —— 2
Bedridden — —— 9	Horſhoehead — — 43	Small Pox — ——3188	Died for Want —— 1
Bleeding —— — 3	Jaundies —— —— 114	Sores and Ulcers —— 22	Drowned — —— 74
Bloody Flux —— 6	Impoſthume —— 33	Spleen — —— 3	Exceſſive Drinking — 17
Burſten —— — 4	Inflammation —— 1	Spotted Fever — — 59	Exceſſive Fat —— 1
Cancer — —— 80	Itch —— —— 3	Stillborn — —— 630	Executed — —— 19
Canker —— —— 6	Leproſy —— —— 5	Stone —— —— 46	Found dead —— — 43
Childbed —— — 263	Lethargy — —— 11	Stoppage in the Stomach 130	Frighted — —— 1
Chriſomes — —— 55	Livergrown — — 4	Strangury — —— 9	Killed by Falls and other Accidents } 58
Colick —— — 89	Looſneſs — —— 23	Suddenly — —— 83	Killed with a Sword— 1
Conſumption ——3240	Lunatick —— — 40	Surfeit —— — 12	Made away themſelves 59
Convulſion — ——6583	Meaſles —— — 70	Swelling in the Throat 1	Murdered —— — 6
Cough —— — 8	Megrims — —— 1	Teeth — ——1497	Overlaid — —— 71
Diabetes — —— 2	Miſcarriage — —— 3	Thruſh —— —— 89	Preſs'd to Death in a Crowd } 1
Dropſy —— —1017	Mortification —— 192	Tiſſick — —— 398	Scalded — —— 1
Evil —— —— 27	Palſy —— —— 32	Twiſting of the Guts 8	Stabbed —— — 2
Fever —— ——3277	Pleuriſy — —— 29	Tympany — —— 8	Strangled — —— 1
Fiſtula —— — 13	Purples —— — 12	Vomiting — —— 16	Total 366
Flux —— —— 8	Quinſy —— —— 12	Water in the Head — 64	
French Pox — —— 85	Raſh —— —— 9	Worms — —— 34	
Gout —— —— 27	Rheumatiſm — — 26		

CHRISTENED	Males — 9661	BURIED	Males — 12847
	Females 9198		Females 12676
	In all — 18859		In all — 25523

Decreaſed in the Burials this Year 429

A General

1726.

A General BILL of all the Chriſtenings and Burials,

From the 14th of December 1725, to the 13th of December 1726.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	32
Alhallows Barkin	111
Alhallows in Bread-ſtreet	10
Alhallows the Great	51
Alhallows in Honey-lane	0
Alhallows the Leſs	25
Alhallows in Lombard-ſtreet	11
Alhallows Staining	31
Alhallows on London Wall	60
St Alphage near Sion College	38
St Andrew Hubbard	21
St Andrew Underſhaft	64
St Andrew Wardrobe	71
St Ann within Alderſgate	36
St Ann in Black Friars	175
St Anthony, vulg. Antholin	13
St Auguſtin, vulg. Auſtin	19
St Bartholomew by Exchange	21
St Benedict, v. Bennet Fink	19
St Bennet Gracechurch	15
St Bennet at Paul's Wharf	56
St Bennet Sherehog	3
St Botolph at Billinſgate	6
Chriſt Church Pariſh	198
St Chriſtopher's Pariſh	22
St Clement near Eaſtcheap	19
St Dionis Backchurch	36
St Dunſtan in the Eaſt	84
St Edmund the King	30
St Ethelburga's Pariſh	24
St Faith under St Paul's	46
St Gabriel in Fenchurch-ſtr.	8
St George in Botolph-lane	17
St Gregory by St Paul's	54
St Helen near Biſhopſgate	42
St James in Duke's Place	32
St James at Garlickhithe	44
St John Baptiſt by Dowgate	20
St John the Evangeliſt	4
St John Zachary	18
St Katherine Coleman	57
St Katherine Creechurch	79
St Laurence Jewry	63
St Laurence Pountney	18
St Leonard in Eaſtcheap	11
St Leonard in Foſter-lane	38
St Magnus by London Bridge	28
St Margaret in Lothbury	26
St Margaret Moſes	13
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattons	15
St Martin Ironmonger-lane	18
St Martin at Ludgate	16
St Martin Orgars	21
St Martin Outwich	6
St Martin Vintrey	38
St Mary Abchurch	31
St Mary in Aldermanbury	32
St Mary Aldermary	30
St Mary le Bow in Cheapſide	30
St Mary Bothaw at Dowgate	5
St Mary Colechurch	0
St Mary Hill by Billinſgate	49
St Mary Magd. in Milk-ſtr.	0
St Mary Magd. Old Fiſh-ſtr.	48
St Mary Mounthaw	10
St Mary Somerſet	56
St Mary Staining	2
St Mary Woolchurch	0
St Mary Woolnoth	18
St Matthew in Friday-ſtreet	7
St Michael Baſſiſhaw	38
St Michael in Cornhill	39
St Michael in Crooked-lane	42
St Michael at Queenhithe	46
St Michael at Quern	6
St Michael Royal	14
St Michael in Wood-ſtreet	45
St Mildred in Bread-ſtreet	16
St Mildred in the Poultry	35
St Nicholas Acons	6
St Nicholas Coleabby	20
St Nicholas Olave	12
St Olave in Hart-ſtreet	37
St Olave in the Old Jewry	5
St Olave in Silver-ſtreet	40
St Pancras in Pancras-lane	1
St Peter in Cheapſide	11
St Peter in Cornhill	36
St Peter near Paul's Wharf	24
St Peter Poor in Broad-ſtr.	22
St Stephen in Coleman-ſtreet	82
St Stephen in Walbrook	26
St Swithin at London-ſtone	15
St Thomas the Apoſtle	26
Trinity Pariſh	19
St Vedaſt, alias Foſter	29

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1982 Buried 3043

	Bur.
St Andrew in Holborn	1271
St Bartholomew the Great	73
St Bartholomew the Leſs	55
St Botolph by Alderſgate	280
St Botolph by Aldgate	965
St Botolph by Biſhopſgate	659
Bridewell Precinct	39
St Bridget, vulg. St Bride's	352
St Dunſtan in the Weſt	272
St George in Southwark	615
St Giles by Cripplegate	1779
St Olave in Southwark	1070
St Saviour in Southwark	983
St Sepulchre's Pariſh	850
St Thomas in Southwark	248
Trinity in the Minories	25
The Peſt-houſe	—

Chriſtened in the ſixteen Pariſhes without the Walls 6157 Buried 9536.

1726.

Chriſt Church in Surrey —275	St John at Wapping ——343	St Mary Magd. Bermondſey 483
St Dunſtan at Stepney——2978	St Katherine near the Tower 221	St Mary at Newington ——354
St Giles in the Fields ——1669	St Leonard in Shoreditch —884	St Mary at Rotherhith ——273
St James at Clerkenwell —643	St Mary at Iſlington ——228	St Mary in Whitechapel—1209
St John at Hackney ——229	St Mary at Lambeth ——484	St Paul at Shadwell ——573

Chriſtened in the fifteen Out Pariſhes in Middleſex and Surrey 6919 Buried 10846

St Ann in Weſtminſter —558	St Margaret in Weſtminſt. 1223	St Mary Savoy in the Strand 102
St Clement Danes — ——661	St Martin in the Fields —1822	St Paul in Covent Garden 296
St James in Weſtminſter 1498	St Mary le Strand —— 62	

Chriſtened in the ſeven Pariſhes in the City and Liberties of Weſtminſter 3750 Buried 6222

DISEASES and CASUALTIES.

ABORTIVE —— 73	Gout —— —— 32	Rheumatiſm — — 40	
Aged ——2667	Gravel — —— 2	Rickets — —— 187	CASUALTIES.
Ague —— —— 6	Grief —— —— 18	Riſing of the Lights— 72	
Apoplexy —— — 93	Griping in the Guts— 583	Rupture —— —— 18	BRoken Leg — — 3
Aſthma —— —— 144	Headmouldſhot —— 58	St Anthony's Fire—— 5	Broken Skull —— 1
Bedridden —— — 3	Hooping Cough —— 37	Scald Head —— — 1	Bruiſed —— — 3
Bleeding — —— 5	Horſhoehead —— 37	Scurvy — —— 2	Burnt —— —— 2
Bloody Flux —— 23	Jaundies —— — 140	Small Pox ——— —1569	Drowned — —— 98
Burſten —— —— 2	Impoſthume — —— 37	Sores and Ulcers —— 17	Exceſſive Drinking — 25
Cancer — —— 56	Itch —— —— 3	Spleen —— — 7	Executed — —— 21
Canker —— —— 15	Leproſy —— — 3	Spotted Fever —— 84	Found dead - —— 36
Childbed — —— 245	Lethargy —— —— 7	Stillborn —— —— 609	Frighted —— — 1
Chriſomes — —— 3	Livergrown —— — 13	Stone —— —— 51	Killed by ſeveral Accidents 46
Colick —— — 116	Looſneſs — —— 58	Stoppage in the Stomach 183	Killed by phyſically taking the Powder of a poiſonous Herb 1
Conſumption ——3764	Lunatick — —— 35	Strangury — —— 2	
Convulſion — —8708	Malignant Fever — — 1	Suddenly — —— 111	
Cough —— — 15	Meaſles —— —— 256	Surfeit —— — 9	Made away themſelves 59
Cramp — —— 1	Miſcarriage — —— 1	Swelling — —— 1	Murdered — —— 9
Diabetes —— — 1	Mortification —— 216	Teeth —— ——2058	Overlaid — —— 67
Dropſy — ——1072	Pain in the Head —— 2	Thruſh —— —— 112	Scalded —— —— 2
Evil —— —— 43	Palſy —— —— 34	Tiſſick — —— 476	Shot —— —— 1
Falling Sickneſs —— 1	Planet-ſtruck — —— 1	Twiſting of the Guts 21	Stabbed — —— 1
Fever —— ——4666	Pleuriſy —— —— 53	Tympany —— — 10	
Fiſtula —— —— 15	Purples — —— 12	Vomiting —— — 19	Total 376
Flux —— —— 11	Quinſy —— —— 4	Water in the Head — 77	
French Pox — —— 82	Raſh —— —— 5	Worms —— —— 52	

CHRISTENED	Males — 9605	BURIED	Males — 15030
	Females 9203		Females 14617
	In all — 18808		In all — 29647

Increaſed in the Burials this Year 4124

1727.

A General BILL of all the Chriſtenings and Burials,

From the 14th of December 1726, to the 12th of December 1727.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	31
Alhallows Barkin	97
Alhallows in Bread-ſtreet	9
Alhallows the Great	62
Alhallows in Honey-lane	0
Alhallows the Leſs	30
Alhallows in Lombard-ſtreet	30
Alhallows Staining	28
Alhallows on London Wall	46
St Alphage near Sion College	39
St Andrew Hubbard	15
St Andrew Underſhaft	54
St Andrew Wardrobe	66
St Ann within Alderſgate	54
St Ann in Black Friars	149
St Anthony, vulg. Antholin	9
St Auguſtin, vulg. Auſtin	19
St Bartholomew by Exchange	23
St Benedict, v. Bennet Fink	17
St Bennet Gracechurch	8
St Bennet at Paul's Wharf	47
St Bennet Sherehog	3
St Botolph at Billinſgate	4
Chriſt Church Pariſh	203
St Chriſtopher's Pariſh	15
St Clement near Eaſtcheap	19
St Dionis Backchurch	23
St Dunſtan in the Eaſt	79
St Edmund the King	21
St Ethelburga's Pariſh	26
St Faith under St Paul's	42
St Gabriel in Fenchurch-ſtr.	8
St George in Botolph-lane	21
St Gregory by St Paul's	52
St Helen near Biſhopſgate	37
St James in Duke's Place	29
St James at Garlickhithe	43
St John Baptiſt by Dowgate	32
St John the Evangeliſt	3
St John Zachary	23
St Katherine Coleman	49
St Katherine Creechurch	70
St Laurence Jewry	29
St Laurence Pountney	18
St Leonard in Eaſtcheap	8
St Leonard in Foſter-lane	30
St Magnus by London Bridge	29
St Margaret in Lothbury	39
St Margaret Moſes	7
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattons	19
St Martin Ironmonger-lane	14
St Martin at Ludgate	34
St Martin Orgars	11
St Martin Outwich	14
St Martin Vintrey	38
St Mary Abchurch	21
St Mary in Aldermanbury	28
St Mary Aldermary	27
St Mary le Bow in Cheapſide	24
St Mary Bothaw at Dowgate	4
St Mary Colechurch	0
St Mary Hill by Billinſgate	26
St Mary Magd. in Milk-ſtr.	0
St Mary Magd. Old Fiſh-ſtr.	26
St Mary Mounthaw	9
St Mary Somerſet	48
St Mary Staining	11
St Mary Woolchurch	0
St Mary Woolnoth	29
St Matthew in Friday-ſtreet	14
St Michael Baſſiſhaw	33
St Michael in Cornhill	17
St Michael in Crooked-lane	33
St Michael at Queenhithe	26
St Michael at Quern	9
St Michael Royal	18
St Michael in Wood-ſtreet	11
St Mildred in Bread-ſtreet	14
St Mildred in the Poultry	38
St Nicholas Acons	4
St Nicholas Coleabby	8
St Nicholas Olave	12
St Olave in Hart-ſtreet	43
St Olave in the Old Jewry	4
St Olave in Silver-ſtreet	34
St Pancras in Pancras-lane	7
St Peter in Cheapſide	5
St Peter in Cornhill	41
St Peter near Paul's Wharf	25
St Peter Poor in Broad-ſtr.	15
St Stephen in Coleman-ſtreet	61
St Stephen in Walbrook	19
St Swithin at London-ſtone	16
St Thomas the Apoſtle	13
Trinity Pariſh	20
St Vedaſt, alias Foſter	36

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1843 Buried 2754

St Andrew in Holborn	1219
St Bartholomew the Great	64
St Bartholomew the Leſs	26
St Botolph by Alderſgate	268
St Botolph by Aldgate	960
St Botolph by Biſhopſgate	620
Bridewell Precinct	40
St Bridget, vulg. St Bride's	333
St Dunſtan in the Weſt	199
St George in Southwark	459
St Giles by Cripplegate	1796
St Olave in Southwark	921
St Saviour in Southwark	748
St Sepulchre's Pariſh	788
St Thomas in Southwark	270
Trinity in the Minories	22
The Peſt-houſe	—

Chriſtened in the ſixteen Pariſhes without the Walls 5933 Buried 8733

Chriſt Church in Surrey —225	St John at Wapping ——370	St Mary Magd. Bermondſey 501
St Dunſtan at Stepney——3150	St Katherine near the Tower 216	St Mary at Newington ——341
St Giles in the Fields ——1623	St Leonard in Shoreditch —962	St Mary at Rotherhith ——325
St James at Clerkenwell —578	St Mary at Iſlington — —246	St Mary in Whitechapel—1161
St John at Hackney ——237	St Mary at Lambeth ——487	St Paul at Shadwell ——731

Chriſtened in the fifteen Out Pariſhes in Middleſex and Surrey 6763 Buried 11153

St Ann in Weſtminſter - —512	St Margaret in Weſtminſt. 1265	St Mary Savoy in the Strand 117
St Clement Danes — ——601	St Martin in the Fields —1560	St Paul in Covent Garden 257
St James in Weſtminſter—1421	St Mary le Strand —— 45	

Chriſtened in the eight Pariſhes in the City and Liberties of Weſtminſter 3713 Buried 5778

DISEASES and CASUALTIES.

ABORTIVE —— 62	Gravel —— — 1	Rickets —— —— 114	
Aged -——2516	Grief —— —— 12	Riſing of the Lights— 53	CASUALTIES.
Ague —— —— 11	Griping in the Guts— 517	Rupture —— —— 15	
Apoplexy — —— 82	Headmouldſhot —— 35	Scald Head —— — 1	BRoken Leg — — 1
Aſthma — —— 136	Hooping Cough —— 67	Scurvy —— —— 1	Bruiſed -—— 5
Bedridden —— — 7	Horſhoehead —— 15	Small Pox — ——2379	Burnt —— —— 2
Bleeding —— —— 4	Jaundies —— — 133	Sores and Ulcers —— 32	Drowned — —— 89
Bloody Flux —— 24	Impoſthume — —— 34	Spleen —— —— 5	Exceſſive Drinking — 16
Burſten —— —— 1	Inflammation — — 12	Spotted Fever —— 102	Executed —— —— 11
Cancer — —— 49	Leproſy —— — 2	Stillborn —— —— 528	Found dead — — 43
Canker —— —— 7	Lethargy — —— 9	Stone —— —— 47	Frighted — —— 2
Childbed —— — 221	Livergrown —— — 5	Stoppage in the Stomach 132	Killed by the Fall of old Houſes 6
Colick — —— 117	Looſneſs —— —— 87	Strangury —— —— 5	Killed by ſeveral other Accidents 55
Conſumption ——3340	Lunatick — —— 37	Suddenly —— —— 106	Made away themſelves 47
Convulſion — ——8231	Malignant Fever —— 5	Surfeit —— —— 4	Murdered — —— 6
Cough — —— 15	Meaſles —— — 72	Swelling — —— 3	Overlaid —— —— 86
Diabetes —— — 2	Miſcarriage — — — 4	Teeth ——1772	Preſs'd to Death in a Crowd — 1
Diſtracted — —— 3	Mortification —— 202	Thruſh —— —— 106	Scalded —— — 1
Dropſy —— ——1003	Pain in the Head —— 2	Tiſſick —— —— 376	Stabbed — —— 2
Evil —— —— 29	Palſy —— —— 39	Twiſting of the Guts 17	Suffocated —— — 2
Falling Sickneſs —— 2	Planet-ſtruck —— 1	Tympany — —— 8	Total 375
Fever —— ——4728	Pleuriſy —— —— 40	Vapours — —— 1	
Fiſtula —— —— 9	Purples — —— 12	Vomiting —— — 30	
Flux —— —— 16	Quinſy —— —— 9	Water in the Head — 68	
French Pox — —— 77	Raſh —— —— 6	Worms —— —— 26	
Gout —— —— 31	Rheumatiſm —— — 31		

CHRISTENED	Males — 9241	BURIED	Males — 14104
	Females 9011		Females 14314
	In all 18252		In all — 28418

Decreaſed in the Burials this Year 1229

1728.

A General BILL of all the Chriſtenings and Burials,

From the 11th of December 1727, to the 10th of December 1728.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.		Bur.		Bur.
St ALBAN in Wood-ſtreet	27	St Gregory by St Paul's —	60	St Mary Mounthaw ——	9
Alhallows Barkin —	70	St Helen near Biſhopſgate—	25	St Mary Somerſet — ——	41
Alhallows in Bread-ſtreet —	13	St James in Duke's Place —	31	St Mary Staining —— —	17
Alhallows the Great ——	61	St James at Garlickhithe —	25	St Mary Woolchurch ——	0
Alhallows in Honey-lane —	0	St John Baptiſt by Dowgate	31	St Mary Woolnoth ——	25
Alhallows the Leſs ——	25	St John the Evangeliſt ——	6	St Matthew in Friday-ſtreet	3
Alhallows in Lombard-ſtreet	21	St John Zachary —— —	21	St Michael Baſſiſhaw ——	52
Alhallows Staining ——	19	St Katherine Coleman ——	69	St Michael in Cornhill ——	14
Alhallows on London Wall	40	St Katherine Creechurch —	79	St Michael in Crooked-lane	41
St Alphage near Sion College	39	St Laurence Jewry ——	42	St Michael at Queenhithe—	30
St Andrew Hubbard - ——	14	St Laurence Pountney ——	14	St Michael at Quern ——	17
St Andrew Underſhaft ——	39	St Leonard in Eaſtcheap —	12	St Michael Royal —— —	23
St Andrew Wardrobe ——	67	St Leonard in Foſter-lane—	31	St Michael in Wood-ſtreet	13
St Ann within Alderſgate—	36	St Magnus by London Bridge	48	St Mildred in Bread-ſtreet--	19
St Ann in Black Friars ——	167	St Margaret in Lothbury —	19	St Mildred in the Poultry—	35
St Anthony, vulg. Antholin	5	St Margaret Moſes ——	6	St Nicholas Acons — ——	3
St Auguſtin, vulg. Auſtin—	22	St Margaret in New Fiſh-ſtr.	0	St Nicholas Coleabby ——	24
St Bartholomew by Exchange	21	St Margaret Pattons ——	16	St Nicholas Olave — ——	6
St Benedict, v. Bennet Fink	17	St Martin Ironmonger-lane	14	St Olave in Hart-ſtreet ——	54
St Bennet Gracechurch ——	17	St Martin at Ludgate ——	30	St Olave in the Old Jewry	4
St Bennet at Paul's Wharf—	38	St Martin Orgars —— —	22	St Olave in Silver-ſtreet -—	50
St Bennet Sherehog ——	1	St Martin Outwich ——	20	St Pancras in Pancras-lane	1
St Botolph at Billinſgate —	5	St Martin Vintrey — ——	35	St Peter in Cheapſide ——	4
Chriſt Church Pariſh -——	185	St Mary Abchurch ——	24	St Peter in Cornhill ——	49
St Chriſtopher's Pariſh ——	21	St Mary in Aldermanbury—	37	St Peter near Paul's Wharf	15
St Clement near Eaſtcheap	20	St Mary Aldermary ——	18	St Peter Poor in Broad-ſtr.	24
St Dionis Backchurch ——	30	St Mary le Bow in Cheapſide	31	St Stephen in Coleman-ſtreet	48
St Dunſtan in the Eaſt ——	80	St Mary Bothaw at Dowgate	5	St Stephen in Walbrook —	16
St Edmund the King — —	21	St Mary Colechurch ——	0	St Swithin at London-ſtone	23
St Ethelburga's Pariſh ——	30	St Mary Hill by Billinſgate	37	St Thomas the Apoſtle ——	11
St Faith under St Paul's —	39	St Mary Magd. in Milk-ſtr.	0	Trinity Pariſh — ——	31
St Gabriel in Fenchurch-ſtr.	20	St Mary Magd. Old Fiſh-ſtr.	29	St Vedaſt, alias Foſter ——	28
St George in Botolph-lane—	16				

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1574 Buried 2793

St Andrew in Holborn ——	1245	Bridewell Precinct — ——	35	St Saviour in Southwark ——	888
St Bartholomew the Great --	45	St Bridget, vulg. St Bride's	387	St Sepulchre's Pariſh -——	784
St Bartholomew the Leſs —	35	St Dunſtan in the Weſt -—	262	St Thomas in Southwark —	371
St Botolph by Alderſgate —	248	St George in Southwark —	592	Trinity in the Minories -—	34
St Botolph by Aldgate ——	833	St Giles by Cripplegate —	1694	The Peſt-houſe — ——	
St Botolph by Biſhopſgate—	564	St Olave in Southwark ——	877		

Chriſtened in the ſixteen Pariſhes without the Walls 5570 Buried 8894

Chriſt Church in Surrey — 213	St John at Wapping — 324	St Mary Magd. Bermondſey 516
St Dunſtan at Stepney — 2812	St Katherine near the Tower 198	St Mary at Newington — 382
St Giles in the Fields — 1481	St Leonard in Shoreditch — 858	St Mary at Rotherhith — 310
St James at Clerkenwell — 621	St Mary at Iſlington — 269	St Mary in Whitechapel — 1085
St John at Hackney — 217	St Mary at Lambeth — 553	St Paul at Shadwell — 623

Chriſtened in the fifteen Out Pariſhes in Middleſex and Surrey 6027 Buried 10462

St Ann in Weſtminſter — 463	St Margaret in Weſtminſt. 1145	The Precinct of the Savoy 73
St Clement Danes — 582	St Martin in the Fields — 1600	St Paul in Covent Garden 283
St James in Weſtminſter 1409	St Mary le Strand — 106	

Chriſtened in the eight Pariſhes in the City and Liberties of Weſtminſter 3481 Buried 5661

DISEASES and CASUALTIES.

ABORTIVE — 55	Gravel — 4	Rickets — 103
Aged — 2768	Grief — 13	Riſing of the Lights — 41
Ague — 44	Griping in the Guts — 433	Rupture — 12
Apoplexy — 73	Headmouldſhot — 40	St Anthony's Fire — 6
Aſthma — 156	Hooping Cough — 21	Scald Head — 5
Bedridden — 14	Horſhoehead — 28	Scurvy — 3
Bleeding — 3	Jaundies — 132	Small Pox — 2105
Bloody Flux — 23	Impoſthume — 28	Sores and Ulcers — 36
Cancer — 49	Inflammation — 4	Spleen — 3
Canker — 16	Itch — 3	Spotted Fever — 94
Chicken Pox — 1	Leproſy — 8	Stillborn — 533
Childbed — 216	Lethargy — 13	Stone — 43
Colick — 78	Livergrown — 10	Stoppage in the Stomach 147
Concuſſion of the Brain 1	Looſneſs — 33	Strangury — 4
Conſumption — 3491	Lunatick — 26	Suddenly — 101
Convulſion — 7517	Malignant Fever — 2	Surfeit — 8
Cough — 5	Meaſles — 82	Swelling — 1
Diabetes — 3	Miſcarriage — 1	Teeth — 1676
Dropſy — 1125	Mortification — 238	Thruſh — 84
Evil — 35	Palſy — 28	Tiſſick — 456
Fever — 4716	Pleuriſy — 48	Twiſting of the Guts 16
Fiſtula — 10	Purples — 10	Tympany — 18
Flux — 14	Quinſy — 11	Vomiting — 6
French Pox — 113	Raſh — 2	Water in the Head — 73
Gout — 39	Rheumatiſm — 25	Worms — 31

CASUALTIES.

BRoken Limbs — 2	
Bruiſed — 3	
Burnt — 2	
Died for Want — 6	
Died by the Bite of a mad Dog	1
Drowned — 80	
Exceſſive Drinking — 22	
Executed — 37	
Found dead — 44	
Frighted — 2	
Killed by Falls and other Accidents	47
Made away themſelves 59	
Murdered — 6	
Overlaid — 71	
Poiſoned — 1	
Scalded — 4	
Stabbed — 1	
Total	397

CHRISTENED	Males — 8498	BURIED	Males — 13538
	Females 8155		Females 14272
	In all — 16652		In all — 27810

Decreaſed in the Burials this Year 608

Whereof have died,

Under Two Years of Age 9851	Twenty and Thirty — 2254	Sixty and Seventy — 1863
Between Two and Five — 2407	Thirty and Forty — 2490	Seventy and Eighty — 1290
Five and Ten — 1038	Forty and Fifty — 2624	Eighty and Ninety — 785
Ten and Twenty — 950	Fifty and Sixty — 2123	Ninety and upwards — 135

A General

1729.

A General BILL of all the Chriſtenings and Burials,

From the 10th of December 1728, to the 9th of December 1729.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	32
Alhallows Barkin	66
Alhallows in Bread-ſtreet	11
Alhallows the Great	64
Alhallows in Honey-lane	0
Alhallows the Leſs	28
Alhallows in Lombard-ſtreet	23
Alhallows Staining	26
Alhallows on London Wall	37
St Alphage near Sion College	44
St Andrew Hubbard	13
St Andrew Underſhaft	45
St Andrew Wardrobe	43
St Ann within Alderſgate	50
St Ann in Black Friars	171
St Anthony, vulg. Antholin	11
St Auguſtin, vulg. Auſtin	17
St Bartholomew by Exchange	26
St Benedict, v. Bennet Fink	26
St Bennet Gracechurch	7
St Bennet at Paul's Wharf	40
St Bennet Sherehog	1
St Botolph at Billinſgate	9
Chriſt Church Pariſh	217
St Chriſtopher's Pariſh	20
St Clement near Eaſtcheap	17
St Dionis Backchurch	30
St Dunſtan in the Eaſt	79
St Edmund the King	27
St Ethelburga's Pariſh	28
St Faith under St Paul's	36
St Gabriel in Fenchurch-ſtr.	14
St George in Botolph-lane	9
St Gregory by St Paul's	78
St Helen near Biſhopſgate	15
St James in Duke's Place	40
St James at Garlickhithe	37
St John Baptiſt by Dowgate	17
St John the Evangeliſt	4
St John Zachary	20
St Katherine Coleman	47
St Katherine Creechurch	85
St Laurence Jewry	48
St Laurence Pountney	12
St Leonard in Eaſtcheap	10
St Leonard in Foſter-lane	29
St Magnus by London Bridge	50
St Margaret in Lothbury	28
St Margaret Moſes	7
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattons	16
St Martin Ironmonger-lane	8
St Martin at Ludgate	22
St Martin Orgars	22
St Martin Outwich	8
St Martin Vintrey	34
St Mary Abchurch	20
St Mary in Aldermanbury	46
St Mary Aldermary	28
St Mary le Bow in Cheapſide	26
St Mary Bothaw at Dowgate	3
St Mary Colechurch	0
St Mary Hill by Billinſgate	46
St Mary Magd. in Milk-ſtr.	0
St Mary Magd. Old Fiſh-ſtr.	33
St Mary Mounthaw	17
St Mary Somerſet	36
St Mary Staining	21
St Mary Woolchurch	0
St Mary Woolnoth	19
St Matthew in Friday-ſtreet	10
St Michael Baſſiſhaw	36
St Michael in Cornhill	22
St Michael in Crooked-lane	34
St Michael at Queenhithe	35
St Michael at Quern	14
St Michael Royal	11
St Michael in Wood-ſtreet	9
St Mildred in Bread-ſtreet	7
St Mildred in the Poultry	25
St Nicholas Acons	4
St Nicholas Coleabby	19
St Nicholas Olave	9
St Olave in Hart-ſtreet	49
St Olave in the Old Jewry	4
St Olave in Silver-ſtreet	52
St Pancras in Pancras-lane	3
St Peter in Cheapſide	4
St Peter in Cornhill	41
St Peter near Paul's Wharf	20
St Peter Poor in Broad-ſtr.	12
St Peter ad Vincula	14
St Stephen in Coleman-ſtreet	101
St Stephen in Walbrook	14
St Swithin at London-ſtone	20
St Thomas the Apoſtle	17
Trinity Pariſh	18
St Vedaſt, alias Foſter	26

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1703 Buried 2826

St Andrew in Holborn	1447
St Bartholomew the Great	67
St Bartholomew the Leſs	35
St Botolph by Alderſgate	245
St Botolph by Aldgate	906
St Botolph by Biſhopſgate	585
Bridewell Precinct	36
St Bridget, vulg. St Bride's	339
St Dunſtan in the Weſt	243
St George in Southwark	536
St Giles by Cripplegate	1771
St Olave in Southwark	936
St Saviour in Southwark	883
St Sepulchre's Pariſh	866
St Thomas in Southwark	352
Trinity in the Minories	37
The Peſt-houſe	

Chriſtened in the ſixteen Pariſhes without the Walls 5504 Buried 9284

Chriſt Church in Surrey —226	St James at Clerkenwell —611	St Mary at Lambeth — —478
Chriſt Church in Spital-fields 355	St John at Hackney ——200	St Mary Magd. Bermondſey 582
St Dunſtan at Stepney——2327	St John at Wapping ——365	St Mary at Newington——353
St Giles in the Fields——1650	St Katherine near the Tower 249	St Mary at Rotherhith——300
St George in the Eaſt ——374	St Leonard in Shoreditch—814	St Mary in Whitechapel—1307
St George by Hanover-ſqu. 78	St Mary at Iſlington — —211	St Paul at Shadwell ——538
St George by Queen's ſquare 227		

Chriſtened in the nineteen Out Pariſhes in Middleſex and Surrey 6405 Buried 11247

St Ann in Weſtminſter - —527	St Margaret in Weſtminſt. 1276	The Precinct of the Savoy 99
St Clement Danes — ——695	St Martin in the Fields—1283	St Paul in Covent Garden 257
St James in Weſtminſter 1580	St Mary le Strand —— 107	

Chriſtened in the eight Pariſhes in the City and Liberties of Weſtminſter 3448 Buried 6367

DISEASES and CASUALTIES.

ABORTIVE —— 55	Fever, Malignant Fever, Spotted Fever, and Purples — 5235	Pain in the Head —— 7
Aged ——2681	Fiſtula —— —— 10	Palſy —— —— 38
Ague —— —— 27	Flux —— —— 17	Pleuriſy — —— 77
Apoplexy, Planet-ſtruck, and Suddenly —— 182	French Pox — —— 105	Quinſy —— —— 14
Aſthma and Tiſſick — 657	Gout —— —— 43	Raſh —— —— 5
Bedridden — —— 8	Gravel, Stone, and Strangury — 42	Rheumatiſm — — 17
Bleeding —— — 3	Grief —— —— 19	Rickets — —— 102
Bloody Flux —— 21	Griping in the Guts— 446	Riſing of the Lights— 36
Burſten and Rupture-- 26	Headmoldſhot, Horſhoehead, and Water in the Head 107	St Anthony's Fire -— 4
Cancer — —— 55	Jaundies —— —— 119	Scurvy —— —— 2
Canker —— —— 20	Impoſthume —— 27	Small Pox — ——2849
Childbed —— — 244	Inflammation — —— 4	Sores and Ulcers —— 36
Cold —— —— 2	Itch —— —— 5	Spleen — —— 4
Colick and Twiſting of the Guts — 91	Lethargy — —— 5	Stillborn —— — 497
Conſumption ——3544	Livergrown — — 11	Stoppage in the Stomach 258
Convulſion — —8359	Looſneſs — —— 27	Surfeit —— — 4
Cough, Chincough, and Hooping Cough — 35	Lunatick —— — 41	Swelling —— —— 2
Diabetes — —— 2	Meaſles —— — 41	Swine Pox — —— 1
Dropſy —— —1049	Miſcarriage — —— 6	Teeth — ——1629
Evil —— —— 36	Mortification —— 227	Thruſh —— —— 54
		Tympany — —— 11
		Vomiting — —— 9
		Vomiting and Looſneſs 3
		Worms — —— 24

CASUALTIES.

BRoken Limbs —— 4	
Bruiſed —— — 3	
Burnt —— —— 3	
Died for Want —— 9	
Died by the cutting off their Limbs 2	
Drowned — —— 77	
Exceſſive Drinking — 24	
Executed — —— 11	
Found dead —— — 68	
Killed by Falls and ſeveral other Accidents — 51	
Killed with a Sword— 1	
Made away themſelves 50	
Murdered —— — 4	
Overlaid — —— 87	
Scalded — —— 5	
Smothered —— — 4	
Stabbed —— — 1	
Strangled — —— 1	
Total 405	

CHRISTENED	Males — 8736 Females 8324 In all — 17060	BURIED	Males — 14898 Females 14824 In all — 29722

Increaſed in the Burials this Year 1712

Whereof have died,

Under Two Years of Age 10735	Twenty and Thirty —— 2371	Sixty and Seventy—— 1938
Between Two and Five— 2516	Thirty and Forty —— 2784	Seventy and Eighty —— 1375
Five and Ten —— —— 1056	Forty and Fifty — —— 2698	Eighty and Ninety — — 769
Ten and Twenty —— 999	Fifty and Sixty —— — 2338	Ninety and upwards—— 143

A General

1730.

A General BILL of all the Chriſtenings and Burials,

From the 9th of December 1729, to the 15th of December 1730.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	26
Alhallows Barkin	92
Alhallows in Bread-ſtreet	13
Alhallows the Great	59
Alhallows in Honey-lane	0
Alhallows the Leſs	17
Alhallows in Lombard-ſtreet	17
Alhallows Staining	21
Alhallows on London Wall	56
St Alphage near Sion College	37
St Andrew Hubbard	21
St Andrew Underſhaft	43
St Andrew Wardrobe	46
St Ann within Alderſgate	47
St Ann in Black Friars	161
St Anthony, vulg. Antholin	8
St Auguſtin, vulg. Auſtin	18
St Bartholomew by Exchange	26
St Benedict, v. Bennet Fink	20
St Bennet Gracechurch	13
St Bennet at Paul's Wharf	44
St Bennet Sherehog	1
St Botolph at Billinſgate	7
Chriſt Church Pariſh	168
St Chriſtopher's Pariſh	19
St Clement near Eaſtcheap	18
St Dionis Backchurch	33
St Dunſtan in the Eaſt	76
St Edmund the King	21
St Ethelburga's Pariſh	21
St Faith under St Paul's	38
St Gabriel in Fenchurch-ſtr.	11
St George in Botolph-lane	20
St Gregory by St Paul's	72
St Helen near Biſhopſgate	33
St James in Duke's Place	27
St James at Garlickhithe	23
St John Baptiſt by Dowgate	27
St John the Evangeliſt	1
St John Zachary	26
St Katherine Coleman	50
St Katherine Creechurch	59
St Laurence Jewry	38
St Laurence Pountney	19
St Leonard in Eaſtcheap	10
St Leonard in Foſter-lane	22
St Magnus by London Bridge	42
St Margaret in Lothbury	21
St Margaret Moſes	3
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattons	23
St Martin Ironmonger-lane	10
St Martin at Ludgate	23
St Martin Orgars	12
St Martin Outwich	9
St Martin Vintrey	35
St Mary Abchurch	21
St Mary in Aldermanbury	33
St Mary Aldermary	26
St Mary le Bow in Cheapſide	32
St Mary Bothaw at Dowgate	7
St Mary Colechurch	0
St Mary Hill by Billinſgate	29
St Mary Magd. in Milk-ſtr.	0
St Mary Magd. Old Fiſh-ſtr.	31
St Mary Mounthaw	11
St Mary Somerſet	58
St Mary Staining	27
St Mary Woolchurch	0
St Mary Woolnoth	16
St Matthew in Friday-ſtreet	10
St Michael Baſſiſhaw	25
St Michael in Cornhill	18
St Michael in Crooked-lane	28
St Michael at Queenhithe	35
St Michael at Quern	16
St Michael Royal	18
St Michael in Wood-ſtreet	15
St Mildred in Bread-ſtreet	13
St Mildred in the Poultry	15
St Nicholas Acons	2
St Nicholas Coleabby	15
St Nicholas Olave	7
St Olave in Hart-ſtreet	52
St Olave in the Old Jewry	8
St Olave in Silver-ſtreet	29
St Pancras in Pancras-lane	5
St Peter in Cheapſide	13
St Peter in Cornhill	36
St Peter near Paul's Wharf	24
St Peter Poor in Broad-ſtr.	12
St Peter ad Vincula	14
St Stephen in Coleman-ſtreet	65
St Stephen in Walbrook	14
St Swithin at London-ſtone	23
St Thomas the Apoſtle	18
Trinity Pariſh	10
St Vedaſt, alias Foſter	20

Chriſtened in the ninety-eight Pariſhes within the Walls 1564 Buried 2654

St Andrew in Holborn	1142
St Bartholomew the Great	52
St Bartholomew the Leſs	36
St Botolph by Alderſgate	248
St Botolph by Aldgate	827
St Botolph by Biſhopſgate	638
Bridewell Precinct	33
St Bridget, vulg. St Bride's	321
St Dunſtan in the Weſt	183
St George in Southwark	377
St Giles by Cripplegate	1562
St Olave in Southwark	829
St Saviour in Southwark	772
St Sepulchre's Pariſh	740
St Thomas in Southwark	271
Trinity in the Minories	25
The Peſt-houſe	—

Chriſtened in the ſixteen Pariſhes without the Walls 5585 Buried 8056

St Ann at Limehouſe —— 49	St James at Clerkenwell —529	St Mary at Lambeth ——436
Chriſt Church in Surrey —261	St John at Hackney ——209	St Mary Magd. Bermondſey 532
Chriſt Church in Spital-fields 683	St John at Wapping ——330	St Mary at Newington ——295
St Dunſtan at Stepney——1160	St Katherine near the Tower 206	St Mary at Rotherhith ——321
St Giles in the Fields ——1403	St Leonard in Shoreditch —810	St Mary in Whitechapel—1184
St George in the Eaſt ——792	St Mary at Iſlington ——193	St Paul at Shadwell ——487
St George by Queen's ſquare 196		

Chriſtened in the nineteen Out Pariſhes in Middleſex and Surrey 6082 Buried 10076

St Ann in Weſtminſter ——479	St James in Weſtminſter 1300	St Mary le Strand —— 117
St Clement Danes — ——545	St Margaret in Weſtminſt. 1197	The Precinct of the Savoy 83
St George by Hanover-ſqu. 521	St Martin in the Fields —1495	St Paul in Covent Garden 238

Chriſtened in the nine Pariſhes in the City and Liberties of Weſtminſter 3687 Buried 5975

DISEASES and CASUALTIES.

ABORTIVE —— 52	Flux —— —— 28	Raſh —— —— 8	CASUALTIES.
Aged ——1971	French Pox — —— 108	Rheumatiſm — — 30	
Ague —— —— 16	Gout —— —— 45	Rickets — —— 85	BRoken Leg — — 3
Apoplexy and Suddenly 238	Gravel, Stone, and Strangury — 49	Riſing of the Lights— 27	Bruiſed — —— 2
Aſthma and Tiſſick — 403		St Anthony's Fire—— 3	Burnt —— —— 9
Bedridden —— — 9	Grief —— —— 17	Scald Head —— — 1	Died by the Bite of a mad Dog — 1
Bleeding — —— 3	Griping in the Guts— 382	Scurvy — —— 3	Died by drawing a Tooth 1
Bloody Flux —— 19	Headmoldſhot, Horſhoehead, and Water in the Head 104	Small Pox —— —1914	Died by the Bite of a Cat 1
Burſten and Rupture-- 13		Sores and Ulcers —— 35	Drowned — —— 83
Cancer — —— 71		Spleen —— — 3	Exceſſive Drinking — 29
Canker —— —— 10	Jaundies —— — 122	Stillborn —— —— 582	Executed — —— 13
Childbed — —— 266	Impoſthume — —— 33	Stoppage in the Stomach 229	Found dead - —— 52
Colick and Twiſting of the Guts — 65	Inflammation —— 7	Surfeit —— — 5	Frighted —— — 1
	Lameneſs — —— 1	Swelling — —— 2	Killed by Falls and ſeveral other Accidents —— 62
Conſumption ——3728	Leproſy —— — 7	Teeth —— ——1585	
Convulſion — ——8023	Lethargy —— —— 11	Thruſh —— —— 51	
Cough, Chincough, and Hooping Cough 152	Livergrown —— — 3	Tympany —— — 9	Made away themſelves 49
	Lunatick — —— 29	Vomiting and Looſneſs 49	Murdered — —— 8
Diabetes —— — 3	Meaſles —— —— 311	Worms —— —— 15	Overlaid — —— 86
Dropſy — —— 934	Miſcarriage — —— 7		Poiſoned —— — 1
Evil —— —— 30	Mortification —— 232		Scalded —— —— 2
Falling Sickneſs —— 1	Overflowing of the Gall 1		Smothered — —— 3
Fever, Malignant Fever, Spotted Fever, and Purples 4011	Pain in the Head —— 1		Starved —— —— 1
	Palſy —— —— 29		Total 407
Fiſtula —— —— 17	Pleuriſy —— —— 44		
	Quinſy —— —— 12		

CHRISTENED	Males — 8606	BURIED	Males — 13306
	Females 8512		Females 13455
	In all — 17118		In all — 26761

Decreaſed in the Burials this Year 2961

Whereof have died,

Under Two Years of Age 10368	Thirty and Forty — 2471	Seventy and Eighty—1001	A Hundred and Two — 1
Between Two and Five— 2448	Forty and Fifty — 2373	Eighty and Ninety — 622	A Hundred and Three-- 2
Five and Ten — —— 1092	Fifty and Sixty —— 1713	Ninety and a Hundred 138	A Hundred and Four — 3
Ten and Twenty —— 901	Sixty and Seventy— 1577	A Hundred and One— 2	A Hundred and Five — 1
Twenty and Thirty —— 2048			

1731.

A General BILL of all the Chriſtenings and Burials,

From the 15th of December 1730, to the 14th of December 1731.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	21
Alhallows Barkin	65
Alhallows in Bread-ſtreet	15
Alhallows the Great	52
Alhallows in Honey-lane	0
Alhallows the Leſs	20
Alhallows in Lombard-ſtreet	15
Alhallows Staining	24
Alhallows on London Wall	39
St Alphage near Sion College	39
St Andrew Hubbard	11
St Andrew Underſhaft	38
St Andrew Wardrobe	64
St Ann within Alderſgate	36
St Ann in Black Friars	141
St Anthony, vulg. Antholin	12
St Auguſtin, vulg. Auſtin	14
St Bartholomew by Exchange	21
St Benedict, v. Bennet Fink	22
St Bennet Gracechurch	10
St Bennet at Paul's Wharf	31
St Bennet Sherehog	6
St Botolph at Billinſgate	6
Chriſt Church Pariſh	117
St Chriſtopher's Pariſh	16
St Clement near Eaſtcheap	14
St Dionis Backchurch	28
St Dunſtan in the Eaſt	48
St Edmund the King	16
St Ethelburga's Pariſh	23
St Faith under St Paul's	34
St Gabriel in Fenchurch-ſtr.	12
St George in Botolph-lane	14
St Gregory by St Paul's	48
St Helen near Biſhopſgate	26
St James in Duke's Place	24
St James at Garlickhithe	18
St John Baptiſt by Dowgate	31
St John the Evangeliſt	1
St John Zachary	14
St Katherine Coleman	39
St Katherine Creechurch	69
St Laurence Jewry	29
St Laurence Pountney	15
St Leonard in Eaſtcheap	9
St Leonard in Foſter-lane	29
St Magnus by London Bridge	42
St Margaret in Lothbury	21
St Margaret Moſes	3
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattons	12
St Martin Ironmonger-lane	10
St Martin at Ludgate	22
St Martin Orgars	14
St Martin Outwich	10
St Martin Vintrey	38
St Mary Abchurch	29
St Mary in Aldermanbury	36
St Mary Aldermary	19
St Mary le Bow in Cheapſide	23
St Mary Bothaw at Dowgate	10
St Mary Colechurch	0
St Mary Hill by Billinſgate	36
St Mary Magd. in Milk-ſtr.	0
St Mary Magd. Old Fiſh-ſtr.	27
St Mary Mounthaw	12
St Mary Somerſet	43
St Mary Staining	18
St Mary Woolchurch	0
St Mary Woolnoth	22
St Matthew in Friday-ſtreet	11
St Michael Baſſiſhaw	32
St Michael in Cornhill	24
St Michael in Crooked-lane	34
St Michael at Queenhithe	26
St Michael at Quern	11
St Michael Royal	14
St Michael in Wood-ſtreet	13
St Mildred in Bread-ſtreet	11
St Mildred in the Poultry	29
St Nicholas Acons	4
St Nicholas Coleabby	9
St Nicholas Olave	7
St Olave in Hart-ſtreet	37
St Olave in the Old Jewry	6
St Olave in Silver-ſtreet	37
St Pancras in Pancras-lane	5
St Peter in Cheapſide	8
St Peter in Cornhill	24
St Peter near Paul's Wharf	19
St Peter Poor in Broad-ſtr.	16
St Stephen in Coleman-ſtreet	58
St Stephen in Walbrook	23
St Swithin at London-ſtone	13
St Thomas the Apoſtle	7
Trinity Pariſh	17
St Vedaſt, alias Foſter	28

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1593 Buried 2346

St Andrew in Holborn	1233
St Bartholomew the Great	57
St Bartholomew the Leſs	34
St Botolph by Alderſgate	229
St Botolph by Aldgate	850
St Botolph by Biſhopſgate	525
Bridewell Precinct	27
St Bridget, vulg. St Bride's	298
St Dunſtan in the Weſt	188
St George in Southwark	368
St Giles by Cripplegate	1585
St Olave in Southwark	937
St Saviour in Southwark	761
St Sepulchre's Pariſh	663
St Thomas in Southwark	261
Trinity in the Minories	20
The Peſt-houſe	

Chriſtened in the ſixteen Pariſhes without the Walls 5809 Buried 8036

St Ann at Limehouſe —184	St George by Queen's ſquare 206	St Mary at Lambeth —417
Chriſt Church in Surrey —209	St James at Clerkenwell —608	St Mary Magd. Bermondſey 487
Chriſt Church in Spital-fields 576	St John at Hackney —188	St Mary at Newington —359
St Dunſtan at Stepney—1009	St John at Wapping —317	St Mary at Rotherhith —268
St Giles in the Fields —945	St Katherine near the Tower 190	St Mary in Whitechapel—1133
St George in Bloomſbury —255	St Leonard in Shoreditch —754	St Paul at Shadwell —505
St George in the Eaſt —631	St Mary at Iſlington — —200	

Chriſtened in the twenty Out Pariſhes in Middleſex and Surrey 6470 Buried 9441

St Ann in Weſtminſter - —480	St James in Weſtminſter—1173	St Mary le Strand — 99
St Clement Danes — —519	St Margaret in Weſtminſt. 1054	The Precinct of the Savoy 66
St George by Hanover-ſqu. 369	St Martin in the Fields —1389	St Paul in Covent Garden 210
St John the Evangeliſt - — 80		

Chriſtened in the ten Pariſhes in the City and Liberties of Weſtminſter 3958 Buried 5439

DISEASES and CASUALTIES.

Abortive — 60	Fiſtula — — 23	Rheumatiſm — — 24	
Aged -—1675	Flux — — 25	Rickets — — 54	CASUALTIES.
Ague — — 11	French Pox — — 98	Riſing of the Lights— 37	
Apoplexy and Suddenly 237	Gout — — 66	St Anthony's Fire— 2	Broken Limbs — 3
Aſthma and Tiſſick — 469	Gravel, Stone, and Strangury — 41	Scurvy — — 3	Bruiſed -— 3
Bedridden — — 2	Grief — — 14	Small Pox — —2640	Burnt — — 3
Bleeding — — 6	Griping in the Guts— 288	Sores and Ulcers — 32	Choaked in Eating — 1
Bloody Flux — 17	Head-ach — — 2	Spleen — — 3	Drowned — — 112
Burſten and Rupture-- 8	Headmoldſhot, Horſhoehead, and Water in the Head 64	Stillborn — — 613	Exceſſive Drinking — 22
Cancer — — 75		Stoppage in the Stomach 193	Executed — — 29
Canker — — 8		Surfeit — — 1	Found dead — — 51
Childbed — — 251	Jaundies — — 106	Swelling — — 1	Frighted — — 1
Cold — — 1	Impoſthume — — 29	Teeth — —1242	Killed by Falls and ſeveral other Accidents — 52
Colick and Twiſting of the Guts — 64	Inflammation — — 12	Thruſh — — 48	
Conſumption —3425	Leproſy — — 2	Tympany — — 3	Made away themſelves 47
Convulſion — —7986	Lethargy — — 4	Vapours — — 1	Murdered — — 8
Cough and Hooping Cough — 33	Livergrown — — 5	Vomiting and Looſneſs 38	Overlaid — — 110
	Lunatick — — 21	Worms — — 27	Poiſoned — — 1
Diabetes — — 3	Meaſles — — 102		Scalded — — 1
Dropſy — —1047	Miſcarriage — — — 6		Stabbed — — 1
Exil — — 47	Mortification — 189		Starved — — 2
Falling Sickneſs — 2	Palſy — — 38		Suffocated — — 2
Fever, Malignant Fever, Scarlet Fever, Spotted Fever, and Purples — 3225	Pleuriſy — — 50		Total 449
	Quinſy — — 8		
	Raſh — — 6		

CHRISTENED	Males — 9177	BURIED	Males — 12608
	Females 8653		Females 12654
	In all 17830		In all — 25262

Decreaſed in the Burials this Year 1499

Whereof have died,

Under Two Years of Age 9907	Twenty and Thirty 1916	Sixty and Seventy— 1500	A Hundred and Two— 2
Between Two and Five— 2096	Thirty and Forty — 2351	Seventy and Eighty 913	A Hundred and Three-- 2
Five and Ten — — 932	Forty and Fifty — 2261	Eighty and Ninety— 628	A Hundred and Seven— 1
Ten and Twenty — 806	Fifty and Sixty — 1839	Ninety and a Hundred 108	

1732.

A General BILL of all the Chriſtenings and Burials,

From the 14th of December 1731, to the 12th of December 1732.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.		Bur.		Bur.
St ALBAN in Wood-ſtreet	27	St Gregory by St Paul's	45	St Mary Mounthaw	11
Alhallows Barkin	62	St Helen near Biſhopſgate	26	St Mary Somerſet	36
Alhallows in Bread-ſtreet	22	St James in Duke's Place	29	St Mary Staining	17
Alhallows the Great	56	St James at Garlickhithe	11	St Mary Woolchurch	0
Alhallows in Honey-lane	0	St John Baptiſt by Dowgate	20	St Mary Woolnoth	5
Alhallows the Leſs	19	St John the Evangeliſt	5	St Matthew in Friday-ſtreet	2
Alhallows in Lombard-ſtreet	19	St John Zachary	15	St Michael Baſſiſhaw	28
Alhallows Staining	17	St Katherine Coleman	52	St Michael in Cornhill	19
Alhallows on London Wall	34	St Katherine Creechurch	59	St Michael in Crooked-lane	33
St Alphage near Sion College	37	St Laurence Jewry	42	St Michael at Queenhithe	31
St Andrew Hubbard	13	St Laurence Pountney	7	St Michael at Quern	6
St Andrew Underſhaft	30	St Leonard in Eaſtcheap	11	St Michael Royal	14
St Andrew Wardrobe	48	St Leonard in Foſter-lane	32	St Michael in Wood-ſtreet	9
St Ann within Alderſgate	30	St Magnus by London Bridge	31	St Mildred in Bread-ſtreet	9
St Ann in Black Friars	117	St Margaret in Lothbury	23	St Mildred in the Poultry	29
St Anthony, vulg. Antholin	16	St Margaret Moſes	11	St Nicholas Acons	3
St Auguſtin, vulg. Auſtin	16	St Margaret in New Fiſh-ſtr.	0	St Nicholas Coleabby	9
St Bartholomew by Exchange	16	St Margaret Pattons	11	St Nicholas Olave	5
St Benedict, v. Bennet Fink	19	St Martin Ironmonger-lane	9	St Olave in Hart-ſtreet	51
St Bennet Gracechurch	11	St Martin at Ludgate	21	St Olave in the Old Jewry	5
St Bennet at Paul's Wharf	39	St Martin Orgars	17	St Olave in Silver-ſtreet	35
St Bennet Sherehog	1	St Martin Outwich	9	St Pancras in Pancras-lane	2
St Botolph at Billinſgate	4	St Martin Vintrey	42	St Peter in Cheapſide	3
Chriſt Church Pariſh	121	St Mary Abchurch	18	St Peter in Cornhill	30
St Chriſtopher's Pariſh	15	St Mary in Aldermanbury	26	St Peter near Paul's Wharf	10
St Clement near Eaſtcheap	13	St Mary Aldermary	11	St Peter Poor in Broad-ſtr.	10
St Dionis Backchurch	17	St Mary le Bow in Cheapſide	32	St Stephen in Coleman-ſtreet	64
St Dunſtan in the Eaſt	60	St Mary Bothaw at Dowgate	6	St Stephen in Walbrook	16
St Edmund the King	9	St Mary Colechurch	0	St Swithin at London-ſtone	19
St Ethelburga's Pariſh	26	St Mary Hill by Billinſgate	33	St Thomas the Apoſtle	6
St Faith under St Paul's	44	St Mary Magd. in Milk-ſtr.	1	Trinity Pariſh	21
St Gabriel in Fenchurch-ſtr.	11	St Mary Magd. Old Fiſh-ſtr.	29	St Vedaſt, alias Foſter	22
St George in Botolph-lane	11				

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1551 Buried 2224

St Andrew in Holborn	978	Bridewell Precinct	32	St Saviour in Southwark	685
St Bartholomew the Great	50	St Bridget, vulg. St Bride's	287	St Sepulchre's Pariſh	612
St Bartholomew the Leſs	24	St Dunſtan in the Weſt	184	St Thomas in Southwark	199
St Botolph by Alderſgate	173	St George in Southwark	349	Trinity in the Minories	14
St Botolph by Aldgate	826	St Giles by Cripplegate	1305	The Peſt-houſe	
St Botolph by Biſhopſgate	503	St Olave in Southwark	773		

Chriſtened in the fixteen Pariſhes without the Walls 5874 Buried 6994

St Ann at Limehouſe —145	St George by Queen's ſquare 212	St Mary at Lambeth — —459
Chriſt Church in Surrey —177	St James at Clerkenwell —404	St Mary Magd. Bermondſey 464
Chriſt Church in Spital-fields 557	St John at Hackney——164	St Mary at Newington——283
St Dunſtan at Stepney ——910	St John at Wapping——320	St Mary at Rotherhith——258
St Giles in the Fields ——786	St Katherine near the Tower 199	St Mary in Whitechapel—1050
St George in Bloomſbury—407	St Leonard in Shoreditch —688	St Paul at Shadwell ——442
St George in the Eaſt ——631	St Mary at Iſlington——186	

Chriſtened in the twenty Out Pariſhes in Middleſex and Surrey 6345 Buried 8742

St Ann in Weſtminſter —455	St James in Weſtminſter 1114	St Mary le Strand —— 101
St Clement Danes ——480	St Margaret in Weſtminſt. 978	The Precinct of the Savoy 76
St George by Hanover-ſqu. 363	St Martin in the Fields —1350	St Paul in Covent Garden 260
St John the Evangeliſt —221		

Chriſtened in the ten Pariſhes in the City and Liberties of Weſtminſter 4018 Buried 5398

DISEASES and CASUALTIES.

Abortive and Stilborn 637	Fiſtula —— —— 17	Raſh —— —— 2	CASUALTIES.
Aged — ——1781	Flux —— —— 32	Rheumatiſm —— 29	
Ague —— — 10	French Pox —— 90	Rickets —— —— 74	Broken Leg —— 3
Apoplexy and Suddenly 237	Gout —— —— 38	Riſing of the Lights— 34	Burnt —— —— 3
Aſthma and Tiſſick — 573	Gravel, Stone, and Strangury — 52	St Anthony's Fire — 2	Choaked with a Cherry 1
Bedridden — —— 3	Grief —— —— 14	Scald Head —— 2	Drowned — —— 98
Bleeding — —— 5	Griping in the Guts— 273	Small Pox —— —1197	Exceſſive Drinking — 38
Bloody Flux —— 13	Headmoldſhot, Horſhoehead, and Water in the Head 81	Sores and Ulcers —— 45	Executed — —— 25
Burſten and Rupture-- 22		Spleen — —— 5	Found dead — —— 37
Cancer — —— 50		Stoppage in the Stomach 197	Fractured Skull — — 1
Canker —— —— 14		Surfeit — —— 4	Killed by Falls and ſeveral other Accidents — 55
Childbed — —— 219	Jaundies —— —— 117	Swelling —— —— 1	
Cold —— —— 1	Impoſthume —— 31	Teeth —— ——1361	
Colick and Twiſting of the Guts — 52	Inflammation —— 19	Thruſh — —— 65	
	Itch —— —— 2	Tympany —— — 6	Killed by the Bite of a mad Dog — 2
Conſumption ——3719	Leproſy —— —— 2	Vapours — —— 1	
Convulſion ——7428	Lethargy —— — 13	Vomiting and Looſneſs 26	Made away themſelves 52
Cough and Hooping Cough —— 65	Livergrown —— 9	Worms — —— 11	Murdered — —— 11
	Lunatick —— — 25		Murdered in the Pillory 1
Diabetes — —— 5	Meaſles — —— 30		Overlaid — —— 133
Dropſy —— —— 945	Miſcarriage —— 3		Scalded — —— 2
Evil —— —— 19	Mortification —— 149		Smothered, Strangled or Suffocated — 3
Fever, Malignant Fever, Scarlet Fever, and Purples — 2939	Palſy —— —— 30		Starved — —— 1
	Pleuriſy — —— 55		
	Quinſy — —— 11		Total 466

CHRISTENED	Males — 9144	BURIED	Males — 11655
	Females 8644		Females 11703
	In all — 17788		In all — 23358

Decreaſed in the Burials this Year 1904

Whereof have died,

Under Two Years of Age 9502	Twenty and Thirty 1627	Sixty and Seventy— 1581	A Hundred —— —— 3
Between Two and Five— 1517	Thirty and Forty — 2175	Seventy and Eighty 974	A Hundred and One — 3
Five and Ten —— 716	Forty and Fifty —— 2121	Eighty and Ninety-- 660	A Hundred and Two — 4
Ten and Twenty —— 611	Fifty and Sixty —— 1741	Ninety and a Hundred 121	A Hundred and Five— 2

A General

1733.

A General BILL of all the Chriſtenings and Burials,

From the 12th of December 1732, to the 11th of December 17 3.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	37
Alhallows Barkin —	79
Alhallows in Bread-ſtreet —	13
Alhallows the Great ——	68
Alhallows in Honey-lane —	1
Alhallows the Leſs ——	20
Alhallows in Lombard-ſtreet	23
Alhallows Staining ——	27
Alhallows on London Wall	44
St Alphage near Sion College	40
St Andrew Hubbard ——	21
St Andrew Underſhaft ——	45
St Andrew Wardrobe — —	87
St Ann within Alderſgate —	46
St Ann in Black Friars - —	189
St Anthony, vulg. Antholin	9
St Auguſtin, vulg. Auſtin—	15
St Bartholomew by Exchange	21
St Benedict, v. Bennet Fink	19
St Bennet Gracechurch ——	12
St Bennet at Paul's Wharf—	25
St Bennet Sherehog ——	2
St Botolph at Billinſgate —	9
Chriſt Church Pariſh ——	127
St Chriſtopher's Pariſh ——	20
St Clement near Eaſtcheap	14
St Dionis Backchurch ——	24
St Dunſtan in the Eaſt ——	74
St Edmund the King ——	11
St Ethelburga's Pariſh - —	21
St Faith under St Paul's —	52
St Gabriel in Fenchurch-ſtr.	13
St George in Botolph-lane—	16
St Gregory by St Paul's —	44
St Helen near Biſhopſgate—	19
St James in Duke's Place —	32
St James at Garlickhithe —	19
St John Baptiſt by Dowgate	22
St John the Evangeliſt ——	3
St John Zachary —— —	16
St Katherine Coleman ——	46
St Katherine Creechurch —	58
St Laurence Jewry ——	38
St Laurence Pountney ——	21
St Leonard in Eaſtcheap —	8
St Leonard in Foſter-lane—	33
St Magnus by London Bridge	26
St Margaret in Lothbury —	36
St Margaret Moſes ——	4
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattons — —	12
St Martin Ironmonger-lane	12
St Martin at Ludgate ——	19
St Martin Orgars —— —	16
St Martin Outwich ——	15
St Martin Vintrey —— —	33
St Mary Abchurch ——	18
St Mary in Aldermanbury—	42
St Mary Aldermary ——	28
St Mary le Bow in Cheapſide	27
St Mary Bothaw at Dowgate	9
St Mary Colechurch ——	0
St Mary Hill by Billinſgate	34
St Mary Magd. in Milk-ſtr.	3
St Mary Magd. Old Fiſh-ſtr.	30
St Mary Mounthaw ——	9
St Mary Somerſet — ——	41
St Mary Staining —— —	24
St Mary Woolchurch ——	0
St Mary Woolnoth — —	15
St Matthew in Friday-ſtreet	7
St Michael Baſſiſhaw -——	18
St Michael in Cornhill ——	19
St Michael in Crooked-lane	39
St Michael at Queenhithe—	45
St Michael at Quern ——	16
St Michael Royal —— —	15
St Michael in Wood-ſtreet	18
St Mildred in Bread-ſtreet—	2
St Mildred in the Poultry—	21
St Nicholas Acons — ——	2
St Nicholas Coleabby — —	16
St Nicholas Olave — ——	7
St Olave in Hart-ſtreet - —	44
St Olave in the Old Jewry	8
St Olave in Silver-ſtreet —	45
St Pancras in Pancras-lane	2
St Peter in Cheapſide ——	6
St Peter in Cornhill ——	27
St Peter near Paul's Wharf	23
St Peter Poor in Broad-ſtr.	18
St Stephen in Coleman-ſtreet	63
St Stephen in Walbrook —	23
St Swithin at London-ſtone	23
St Thomas the Apoſtle ——	18
Trinity Pariſh — ——	20
St Vedaſt, alias Foſter ——	39

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1480 Buried 2610

	Bur.
St Andrew in Holborn —	1235
St Bartholomew the Great--	63
St Bartholomew the Leſs —	36
St Botolph by Alderſgate ——	272
St Botolph by Aldgate ——	963
St Botolph by Biſhopſgate—	642
Bridewell Precinct — ——	33
St Bridget, vulg. St Bride's	331
St Dunſtan in the Weſt ——	214
St George in Southwark ——	405
St Giles by Cripplegate ——	1733
St John in Southwark ——	201
St Olave in Southwark ——	845
St Saviour in Southwark —	810
St Sepulchre's Pariſh ——	853
St Thomas in Southwark —	214
Trinity in the Minories ——	17
The Peſt-houſe — ——	

Chriſtened in the ſeventeen Pariſhes without the Walls 5768 Buried 8867

St Ann at Limehouſe —— 187	St George by Queen's ſquare 262	St Mary at Iſlington — — 252
Chriſt Church in Surrey — 260	St James at Clerkenwell — 605	St Mary at Lambeth — — 503
Chriſt Church in Spital-fields 753	St John at Hackney —— 201	St Mary Magd. Bermondſey 569
St Dunſtan at Stepney —— 1230	St John at Wapping —— 432	St Mary at Newington —— 336
St Giles in the Fields —— 1032	St Katherine near the Tower 265	St Mary at Rotherhith —— 319
St George in Bloomſbury — 567	St Leonard in Shoreditch — 912	St Mary in Whitechapel — 1363
St George in Middleſex — 773	St Luke in Middleſex —— 69	St Paul at Shadwell —— 534

Chriſtened in the twenty-one Out Pariſhes in Middleſex and Surrey 6355 Buried 11424

St Ann in Weſtminſter — 657	St James in Weſtminſter 1230	St Mary le Strand —— 114
St Clement Danes — —— 534	St Margaret in Weſtminſt. 1082	The Precinct of the Savoy 118
St George by Hanover-ſqu. 468	St Martin in the Fields — 1577	St Paul in Covent Garden 267
St John the Evangeliſt — 285		

Chriſtened in the ten Pariſhes in the City and Liberties of Weſtminſter 3862 Buried 6332

DISEASES and CASUALTIES.

Abortive and Stilborn 656	Fiſtula —— —— 22	Pleuriſy — —— 63	CASUALTIES.
Aged —— —— 2207	Flux —— —— 12	Quinſy —— —— 10	
Ague —— —— 3	French Pox — —— 125	Raſh —— —— 1	Broken Limbs —— 7
Apoplexy and Suddenly 227	Gout —— —— 54	Rheumatiſm — — 18	Bruiſed —— — 1
Aſthma and Tiſſick — 896	Gravel, Stone, and Strangury — 70	Rickets — —— 83	Burnt —— —— 6
Bedridden — —— 10	Grief —— —— 13	Riſing of the Lights — 26	Drowned — —— 81
Bleeding —— — 3	Griping in the Guts — 258	St Anthony's Fire - — 4	Exceſſive Drinking — 62
Bloody Flux —— 10	Headmoldſhot, Horſhoehead, and Water in the Head 71	Scurvy —— —— 2	Executed — —— 22
Burſten and Rupture-- 24		Small Pox — ——1370	Found dead —— — 44
Cancer — —— 48		Sores and Ulcers —— 34	Killed by Falls and ſeveral other Accidents — 49
Canker —— —— 17		Spleen — —— 2	
Chicken Pox —— 1	Jaundies —— —— 158	Stoppage in the Stomach 188	Killed by Lightning — 2
Childbed —— — 292	Impoſthume —— 28	Surfeit —— — 4	Made away themſelves 48
Colick and Twiſting of the Guts — 74	Infants —— — 1	Swelling —— —— 1	Murdered —— — 15
Conſumption ——4601	Inflammation — —— 62	Teeth — ——1623	Overlaid — —— 112
Convulſion — ——9336	Itch —— —— 4	Thruſh —— —— 87	Scalded — —— 1
Cough and Hooping Cough — 97	Leproſy —— —— 2	Tympany — —— 10	Shot —— —— 3
Dropſy —— —1124	Lethargy — —— 10	Vapours —— —— 2	Starved —— — 2
Evil —— —— 28	Livergrown — — 3	Vomiting and Looſneſs 26	Strangled — —— 1
Falling Sickneſs —— 2	Lunatick —— — 19	Worms — —— 4	Suffocated — —— 3
Fever, Malignant Fever, Spotted Fever, and Purples — 3831	Meaſles —— — 605		Total 459
	Miſcarriage — —— 7		
	Mortification —— 169		
	Palſy —— —— 36		

CHRISTENED	Males — 8811	BURIED	Males — 14372
	Females 8654		Females 14861
	In all — 17465		In all — 29233

Increaſed in the Burials this Year 5875

Whereof have died,

Under Two Years of Age 11738	Thirty and Forty — 2564	Eighty and Ninety — 804	A Hundred and Three 5
Between Two and Five — 2409	Forty and Fifty — 2685	Ninety and a Hundred 198	A Hundred and Five — 1
Five and Ten —— 957	Fifty and Sixty — 2196	A Hundred —— 3	A Hundred and Six — 3
Ten and Twenty —— 794	Sixty and Seventy — 1871	A Hundred and One 1	A Hundred and Twelve 1
Twenty and Thirty — 1857	Seventy and Eighty 1188		

A General

1734.

A General BILL of all the Chriſtenings and Burials,

From the 12th of December 1733, to the 10th of December 1734.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	29
Alhallows Barkin —	74
Alhallows in Bread-ſtreet —	8
Alhallows the Great ——	46
Alhallows in Honey-lane —	0
Alhallows the Leſs ———	17
Alhallows in Lombard-ſtreet	12
Alhallows Staining — ——	30
Alhallows on London Wall	23
St Alphage near Sion College	30
St Andrew Hubbard — —	20
St Andrew Underſhaft ——	40
St Andrew Wardrobe ——	41
St Ann within Alderſgate —	40
St Ann in Black Friars - —	135
St Anthony, vulg. Antholin	7
St Auguſtin, vulg. Auſtin—	21
St Bartholomew by Exchange	11
St Benedict, v. Bennet Fink	15
St Bennet Gracechurch - —	14
St Bennet at Paul's Wharf	30
St Bennet Sherehog - ——	2
St Botolph at Billinſgate —	7
Chriſt Church Pariſh ——	113
St Chriſtopher's Pariſh ——	24
St Clement near Eaſtcheap	13
St Dionis Backchurch ——	33
St Dunſtan in the Eaſt ——	58
St Edmund the King — —	14
St Ethelburga's Pariſh ——	21
St Faith under St Paul's —	35
St Gabriel in Fenchurch-ſtr.	18
St George in Botolph-lane—	16
St Gregory by St Paul's —	83
St Helen near Biſhopſgate—	30
St James in Duke's Place —	30
St James at Garlickhithe —	24
St John Baptiſt by Dowgate	21
St John the Evangeliſt ——	3
St John Zachary —— —	11
St Katherine Coleman ——	56
St Katherine Creechurch —	62
St Laurence Jewry ———	40
St Laurence Pountney ——	12
St Leonard in Eaſtcheap —	18
St Leonard in Foſter-lane—	23
St Magnus by London Bridge	35
St Margaret in Lothbury—	28
St Margaret Moſes ———	2
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattons — —	16
St Martin Ironmonger-lane	6
St Martin at Ludgate ——	8
St Martin Orgars —— —	19
St Martin Outwich ———	4
St Martin Vintrey — ——	36
St Mary Abchurch — —	20
St Mary in Aldermanbury—	33
St Mary Aldermary — —	22
St Mary le Bow in Cheapſide	21
St Mary Bothaw at Dowgate	3
St Mary Colechurch ———	0
St Mary Hill by Billinſgate	34
St Mary Magd. in Milk-ſtr.	0
St Mary Magd. Old Fiſh-ſtr.	25
St Mary Mounthaw — —	15
St Mary Somerſet — ——	49
St Mary Staining —— —	9
St Mary Woolchurch ——	0
St Mary Woolnoth ———	11
St Matthew in Friday-ſtreet	11
St Michael Baſſiſhaw — —	8
St Michael in Cornhill ——	26
St Michael in Crooked-lane	26
St Michael at Queenhithe—	29
St Michael at Quern ——	12
St Michael Royal —— —	16
St Michael in Wood-ſtreet	7
St Mildred in Bread-ſtreet	8
St Mildred in the Poultry	25
St Nicholas Acons —— —	4
St Nicholas Coleabby ——	16
St Nicholas Olave ———	11
St Olave in Hart-ſtreet - —	54
St Olave in the Old Jewry	5
St Olave in Silver-ſtreet —	31
St Pancras in Pancras-lane	1
St Peter in Cheapſide ——	8
St Peter in Cornhill ———	33
St Peter near Paul's Wharf	11
St Peter Poor in Broad-ſtr.	13
St Stephen in Coleman-ſtreet	71
St Stephen in Walbrook —	11
St Swithin at London-ſtone	18
St Thomas the Apoſtle - —	20
Trinity Pariſh —— ——	24
St Vedaſt, alias Foſter ——	41

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1441 Buried 2346

St Andrew in Holborn ——	1002
St Bartholomew the Great--	47
St Bartholomew the Leſs —	29
St Botolph by Alderſgate —	226
St Botolph by Aldgate ——	838
St Botolph by Biſhopſgate—	659
Bridewell Precinct ———	34
St Bridget, vulg. St Bride's	296
St Dunſtan in the Weſt - —	186
St George in Southwark —	384
St Giles by Cripplegate ——	583
St John in Southwark ——	387
St Olave in Southwark —	552
St Saviour in Southwark —	755
St Sepulchre's Pariſh - ——	715
St Thomas in Southwark —	210
Trinity in the Minories —	26
The Peſt-houſe — ——	

Chriſtened in the ſeventeen Pariſhes without the Walls 4909 Buried 6929

St Ann at Limehouſe ——217	St George by Queen's ſquare 222	St Mary at Iſlington ——256
Chriſt Church in Surrey —236	St James at Clerkenwell —480	St Mary at Lambeth ——481
Chriſt Church in Middleſex 807	St John at Hackney ——199	St Mary Magd. Bermondſey 506
St Dunſtan at Stepney——1150	St John at Wapping——268	St Mary at Newington ——347
St Giles in the Fields — —955	St Katherine near the Tower 191	St Mary at Rotherhith ——286
St George in Bloomſbury —436	St Leonard in Shoreditch —842	St Mary in Whitechapel—1191
St George in Middleſex —715	St Luke in Middleſex ——920	St Paul at Shadwell ——480

Chriſtened in the twenty-one Out Pariſhes in Middleſex and Surrey 7171 Buried 11185

St Ann in Weſtminſter —511	St James in Weſtminſter 1133	St Mary le Strand —— 104
St Clement Danes — ——426	St Margaret in Weſtminſt. 1074	The Precinct of the Savoy 90
St George by Hanover-ſqu. 518	St Martin in the Fields —1297	St Paul in Covent Garden 204
St John the Evangeliſt——245		

Chriſtened in the ten Pariſhes in the City and Liberties of Weſtminſter 4109 Buried 5602

DISEASES and CASUALTIES.

Abortive and Stilborn 661	Fiſtula —— —— 14	Rheumatiſm — — 21	
Aged — ——1459	Flux —— —— 24	Rickets — —— 82	CASUALTIES.
Ague —— —— 6	French Pox — —— 105	Riſing of the Lights— 18	
Apoplexy and Suddenly 182	Gout —— —— 44	St Anthony's Fire—— 4	Broken Limbs —— 4
Aſthma and Tiſſick — 466	Gravel, Stone, and Strangury — 56	Sciatica —— — 2	Burnt — —— 4
Bedridden —— — 5	Grief —— —— 12	Scurvy — —— 3	Drowned — —— 78
Bleeding — —— 8	Headmoldſhot, Horſhoehead, and Water in the Head 116	Small Pox ——— —2688	Exceſſive Drinking — 57
Bloody Flux —— 13		Sores and Ulcers —— 34	Executed — —— 15
Burſten and Rupture-- 21		Spleen —— — 4	Found dead - —— 38
Cancer — —— 48		Stoppage in the Stomach 138	Frighted —— — 1
Canker —— —— 12	Jaundies —— — 126	Surfeit —— — 2	Killed by Falls and ſeveral other Accidents —— 60
Childbed — —— 271	Impoſthume — —— 36	Swelling — —— 4	
Colick, Gripes, and Twiſting of the Guts —— 351	Inflammation —— 31	Teeth —— ——1316	Made away themſelves 62
	Itch —— —— 2	Thruſh —— —— 90	Murdered — —— 10
Conſumption ——4139	Leproſy —— — 6	Tympany —— — 3	Overlaid — —— 107
Convulſion — —8295	Lethargy —— —— 9	Vapours — —— 1	Scalded —— —— 2
Cough and Hooping Cough —— 139	Livergrown —— — 8	Vomiting and Looſneſs 20	Starved —— —— 4
	Lunatick — —— 22	Worms —— —— 10	Strangled — —— 1
Diabetes —— — 2	Meaſles —— —— 20		
Dropſy — —— 998	Miſcarriage — —— 2		Total 443
Evil —— —— 30	Mortification —— 193		
Falling Sickneſs —— 1	Palſy —— —— 37		
Fever, Malignant Fever, Scarlet Fever, Spotted Fever, and Purples —— 3116	Planet-ſtruck — —— 1		
	Pleuriſy —— —— 58		
	Quinſy —— —— 31		
	Raſh —— —— 3		

CHRISTENED	Males — 8955	BURIED	Males — 13016
	Females 8675		Females 13046
	In all — 17630		In all — 26062

Decreaſed in the Burials this Year 3171

Whereof have died,

Under Two Years of Age 10752	Twenty and Thirty 1718	Sixty and Seventy — 1324	A Hundred and One — 1
Between Two and Five— 2830	Thirty and Forty — 2212	Seventy and Eighty 793	A Hundred and Four — 1
Five and Ten —— —— 1228	Forty and Fifty—— 2154	Eighty and Ninety— 484	A Hundred and Five — 1
Ten and Twenty —— 829	Fifty and Sixty —— 1668	Ninety and a Hundred 66	A Hundred and Six —— 1

1736.

A General BILL of all the Chriſtenings and Burials,

From the 9th of December 1735, to the 7th of December 1736.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	35
Alhallows Barkin	80
Alhallows in Bread-ſtreet	8
Alhallows the Great	50
Alhallows in Honey-lane	1
Alhallows the Leſs	18
Alhallows in Lombard-ſtreet	16
Alhallows Staining	22
Alhallows on London Wall	50
St Alphage near Sion College	19
St Andrew Hubbard	20
St Andrew Underſhaft	40
St Andrew Wardrobe	57
St Ann within Alderſgate	46
St Ann in Black Friars	155
St Anthony, vulg. Antholin	7
St Auguſtin, vulg. Auſtin	20
St Bartholomew by Exchange	19
St Benedict, v. Bennet Fink	23
St Bennet Gracechurch	11
St Bennet at Paul's Wharf	41
St Bennet Sherehog	1
St Botolph at Billinſgate	6
Chriſt Church Pariſh	120
St Chriſtopher's Pariſh	12
St Clement near Eaſtcheap	17
St Dionis Backchurch	20
St Dunſtan in the Eaſt	63
St Edmund the King	3
St Ethelburga's Pariſh	22
St Faith under St Paul's	54
St Gabriel in Fenchurch-ſtr.	8
St George in Botolph-lane	13
St Gregory by St Paul's	70
St Helen near Biſhopſgate	20
St James in Duke's Place	17
St James at Garlickhithe	22
St John Baptiſt by Dowgate	32
St John the Evangeliſt	5
St John Zachary	12
St Katherine Coleman	42
St Katherine Creechurch	48
St Laurence Jewry	45
St Laurence Pountney	20
St Leonard in Eaſtcheap	10
St Leonard in Foſter-lane	24
St Magnus by London Bridge	33
St Margaret in Lothbury	26
St Margaret Moſes	7
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattons	5
St Martin Ironmonger-lane	11
St Martin at Ludgate	25
St Martin Orgars	6
St Martin Outwich	4
St Martin Vintrey	42
St Mary Abchurch	21
St Mary in Aldermanbury	39
St Mary Aldermary	24
St Mary le Bow in Cheapſide	24
St Mary Bothaw at Dowgate	6
St Mary Colechurch	0
St Mary Hill by Billinſgate	39
St Mary Magd. in Milk-ſtr.	2
St Mary Magd. Old Fiſh-ſtr.	39
St Mary Mounthaw	11
St Mary Somerſet	46
St Mary Staining	24
St Mary Woolchurch	0
St Mary Woolnoth	21
St Matthew in Friday-ſtreet	5
St Michael Baſſiſhaw	28
St Michael in Cornhill	28
St Michael in Crooked-lane	30
St Michael at Queenhithe	27
St Michael at Quern	14
St Michael Royal	13
St Michael in Wood-ſtreet	3
St Mildred in Bread-ſtreet	10
St Mildred in the Poultry	19
St Nicholas Acons	6
St Nicholas Coleabby	17
St Nicholas Olave	13
St Olave in Hart-ſtreet	48
St Olave in the Old Jewry	7
St Olave in Silver-ſtreet	25
St Pancras in Pancras-lane	2
St Peter in Cheapſide	3
St Peter in Cornhill	32
St Peter near Paul's Wharf	13
St Peter Poor in Broad-ſtr.	7
St Stephen in Coleman-ſtreet	66
St Stephen in Walbrook	19
St Swithin at London-ſtone	20
St Thomas the Apoſtle	14
Trinity Pariſh	7
St Vedaſt, alias Foſter	23

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1452 Buried 2398

St Andrew in Holborn	1217
St Bartholomew the Great	45
St Bartholomew the Leſs	23
St Botolph by Alderſgate	250
St Botolph by Aldgate	909
St Botolph by Biſhopſgate	584
Bridewell Precinct	33
St Bridget, vulg. St Bride's	274
St Dunſtan in the Weſt	174
St George in Southwark	389
St Giles by Cripplegate	640
St John in Southwark	391
St Olave in Southwark	523
St Saviour in Southwark	760
St Sepulchre's Pariſh	775
St Thomas in Southwark	235
Trinity in the Minories	22
The Peſt-houſe	

Chriſtened in the ſeventeen Pariſhes without the Walls 4475 Buried 7244

St Ann at Limehouſe —113	St George by Queen's ſquare 208	St Mary at Iſlington — —239
Chriſt Church in Surrey —188	St James at Clerkenwell —488	St Mary at Lambeth —383
Chriſt Church in Middleſex 712	St John at Hackney —191	St Mary Magd. Bermondſey 393
St Dunſtan at Stepney —911	St John at Wapping —298	St Mary at Newington —287
St Giles in the Fields —1024	St Katherine near the Tower 194	St Mary at Rotherhith —294
St George in Bloomſbury —370	St Leonard in Shoreditch —755	St Mary in Whitechapel—1014
St George in Middleſex - —695	St Luke in Middleſex —769	St Paul at Shadwell —475

Chriſtened in the twenty-one Out Pariſhes in Middleſex and Surrey 6742 Buried 10001

St Ann in Weſtminſter - —440	St James in Weſtminſter—1149	St Mary le Strand — 97
St Clement Danes — —406	St Margaret in Weſtminſt. 994	The Precinct of the Savoy 92
St George by Hanover-ſqu. 527	St Martin in the Fields —1252	St Paul in Covent Garden 254
St John the Evangeliſt - —250		

Chriſtened in the ten Pariſhes in the City and Liberties of Weſtminſter 3937 Buried 5461

DISEASES and CASUALTIES.

Abortive and Stilborn 590	Fiſtula — — 8	Raſh — — 1	CASUALTIES.
Aged — —1595	Flux — — 17	Rheumatiſm — — 12	
Ague — — 6	French Pox — — 102	Rickets — — 107	Broken Limbs — 4
Apoplexy and Suddenly 196	Gout — — 38	Riſing of the Lights— 21	Bruiſed - — 1
Aſthma and Tiſſick — 477	Gravel, Stone, and Strangury — 38	Scald Head — — 2	Burnt — — 6
Bedridden — — 10	Grief — — 14	Scurvy — — 2	Choaked in eating his Dinner — 1
Bleeding — — 3	Head-ach — — 1	Small Pox — —1594	Drowned — — 99
Bloody Flux — 13	Headmoldſhot, Horſhoehead, and Water in the Head 143	Sores and Ulcers — 34	Exceſſive Drinking — 69
Burſten and Rupture-- 19		Stoppage in the Stomach 162	Executed — — 19
Cancer — — 58		Surfeit — — 3	Found dead — — 19
Canker — — 11		Swelling — — 1	Fractured Skull — — 2
Childbed — — 192	Jaundies — — 154	Teeth —1342	Killed by Falls and ſeveral other Accidents — 54
Colick, Gripes, and Twiſting of the Guts — 317	Impoſthume — — 16	Thruſh — — 55	
	Inflammation — — 22	Tympany — — 1	
Conſumption —4064	Itch — — 1	Vomiting and Looſneſs 19	Killed by a Boar — 1
Convulſion — —7572	Leproſy — — 9	Worms — — 9	Made away themſelves 49
Cough and Hooping Cough — 81	Lethargy — — 8		Murdered — — 15
	Livergrown — — 10		Overlaid — — 97
Dropſy — —1050	Lunatick — — 29		Scalded — — 2
Evil — — 26	Meaſles — — 10		Smothered — — 2
Fever, Malignant Fever, Scarlet Fever, Spotted Fever, and Purples — 2544	Miſcarriage — — — 4		Stabbed — — 1
	Mortification — 167		Starved — — 3
	Palſy — — 39		Strangled — — 1
	Pleuriſy — — 55		
	Quinſy — — 19		Total 445

CHRISTENED	Males — 8658	BURIED	Males — 11699
	Females 8215		Females 11839
	In all 16873		In all — 23538

Decreaſed in the Burials this Year 2524.

Whereof have died,

Under Two Years of Age 9672	Thirty and Forty — 2158	Eighty and Ninety — 565	A Hundred and Three 1
Between Two and Five— 1963	Forty and Fifty — 2138	Ninety and a Hundred 84	A Hundred and Four — 1
Five and Ten — 755	Fifty and Sixty — 1684	A Hundred — 3	A Hundred and Five — 1
Ten and Twenty — 691	Sixty and Seventy — 1339	A Hundred and One 1	A Hundred and Six — 3
Twenty and Thirty — 1605	Seventy and Eighty 872	A Hundred and Two 2	

1736.

A General BILL of all the Chriſtenings and Burials,

From the 9th of December 1735, to the 7th of December 1736.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	35
Alhallows Barkin	80
Alhallows in Bread-ſtreet	8
Alhallows the Great	50
Alhallows in Honey-lane	1
Alhallows the Leſs	18
Alhallows in Lombard-ſtreet	16
Alhallows Staining	22
Alhallows on London Wall	50
St Alphage near Sion College	19
St Andrew Hubbard	20
St Andrew Underſhaft	40
St Andrew Wardrobe	57
St Ann within Alderſgate	46
St Ann in Black Friars	155
St Anthony, vulg. Antholin	7
St Auguſtin, vulg. Auſtin	20
St Bartholomew by Exchange	19
St Benedict, v. Bennet Fink	23
St Bennet Gracechurch	11
St Bennet at Paul's Wharf	41
St Bennet Sherehog	1
St Botolph at Billinſgate	6
Chriſt Church Pariſh	120
St Chriſtopher's Pariſh	12
St Clement near Eaſtcheap	17
St Dionis Backchurch	20
St Dunſtan in the Eaſt	63
St Edmund the King	3
St Ethelburga's Pariſh	22
St Faith under St Paul's	54
St Gabriel in Fenchurch-ſtr.	8
St George in Botolph-lane	13
St Gregory by St Paul's	70
St Helen near Biſhopſgate	20
St James in Duke's Place	17
St James at Garlickhithe	22
St John Baptiſt by Dowgate	32
St John the Evangeliſt	5
St John Zachary	12
St Katherine Coleman	42
St Katherine Creechurch	48
St Laurence Jewry	45
St Laurence Pountney	20
St Leonard in Eaſtcheap	10
St Leonard in Foſter-lane	24
St Magnus by London Bridge	33
St Margaret in Lothbury	26
St Margaret Moſes	7
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattons	5
St Martin Ironmonger-lane	11
St Martin at Ludgate	25
St Martin Orgars	6
St Martin Outwich	4
St Martin Vintrey	42
St Mary Abchurch	21
St Mary in Aldermanbury	39
St Mary Aldermary	24
St Mary le Bow in Cheapſide	24
St Mary Bothaw at Dowgate	6
St Mary Colechurch	0
St Mary Hill by Billinſgate	39
St Mary Magd. in Milk-ſtr.	2
St Mary Magd. Old Fiſh-ſtr.	39
St Mary Mounthaw	11
St Mary Somerſet	46
St Mary Staining	24
St Mary Woolchurch	0
St Mary Woolnoth	21
St Matthew in Friday-ſtreet	5
St Michael Baſſiſhaw	28
St Michael in Cornhill	28
St Michael in Crooked-lane	30
St Michael at Queenhithe	27
St Michael at Quern	14
St Michael Royal	13
St Michael in Wood-ſtreet	3
St Mildred in Bread-ſtreet	10
St Mildred in the Poultry	19
St Nicholas Acons	6
St Nicholas Coleabby	17
St Nicholas Olave	13
St Olave in Hart-ſtreet	48
St Olave in the Old Jewry	7
St Olave in Silver-ſtreet	25
St Pancras in Pancras-lane	2
St Peter in Cheapſide	3
St Peter in Cornhill	32
St Peter near Paul's Wharf	13
St Peter Poor in Broad-ſtr.	7
St Stephen in Coleman-ſtreet	66
St Stephen in Walbrook	19
St Swithin at London-ſtone	20
St Thomas the Apoſtle	14
Trinity Pariſh	7
St Vedaſt, alias Foſter	23

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1452 Buried 2398

St Andrew in Holborn	1217
St Bartholomew the Great	45
St Bartholomew the Leſs	23
St Botolph by Alderſgate	250
St Botolph by Aldgate	909
St Botolph by Biſhopſgate	584
Bridewell Precinct	33
St Bridget, vulg. St Bride's	274
St Dunſtan in the Weſt	174
St George in Southwark	389
St Giles by Cripplegate	640
St John in Southwark	391
St Olave in Southwark	523
St Saviour in Southwark	760
St Sepulchre's Pariſh	775
St Thomas in Southwark	235
Trinity in the Minories	22
The Peſt-houſe	

Chriſtened in the ſeventeen Pariſhes without the Walls 4475 Buried 7244

1736.

St Ann at Limehouſe —169	St George by Queen's ſquare 278	St Mary at Iſlington —261
Chriſt Church in Surrey —208	St James at Clerkenwell —604	St Mary at Lambeth —493
Chriſt Church in Middleſex 766	St John at Hackney—186	St Mary Magd. Bermondſey 481
St Dunſtan at Stepney—1093	St John at Wapping—290	St Mary at Newington —340
St Giles in the Fields —1215	St Katherine near the Tower 231	St Mary at Rotherhith —271
St George in Bloomſbury—509	St Leonard in Shoreditch —859	St Mary in Whitechapel—1252
St George in Middleſex —810	St Luke in Middleſex—1061	St Paul at Shadwell —447

Chriſtened in the twenty-one Out Pariſhes in Middleſex and Surrey 6780 Buried 11824

St Ann in Weſtminſter —615	St James in Weſtminſter 1243	St Mary le Strand — 127
St Clement Danes —477	St Margaret in Weſtminſt. 1006	The Precinct of the Savoy 96
St George by Hanover-ſqu. 521	St Martin in the Fields —1478	St Paul in Covent Garden 305
St John the Evangeliſt —247		

Chriſtened in the ten Pariſhes in the City and Liberties of Weſtminſter 3784 Buried 6115

DISEASES and CASUALTIES.

Abortive and Stilborn 592	Fiſtula — 16	Rheumatiſm — 19	Casualties.
Aged — 1918	Flux — 24	Rickets — 70	Broken Limbs — 3
Ague — 1	French Pox — 111	Riſing of the Lights— 24	Burnt — 3
Apoplexy and Suddenly 208	Gout — 47	Small Pox — 3014	Drowned — 120
Aſthma and Tiſſick — 582	Gravel, Stone, and Strangury — 47	Sores and Ulcers — 23	Exceſſive Drinking — 64
Bedridden — 13	Grief — 10	Sore Throat — 2	Executed — 8
Bleeding — 5	Headmoldſhot, Horſhoehead, and Water in the Head 117	Stoppage in the Stomach 173	Found dead — 35
Bloody Flux — 7	Jaundies — 142	Surfeit — 2	Fractured Skull — 1
Burſten and Rupture— 15	Impoſthume — 24	Swelling — 2	Killed by Falls and ſeveral other Accidents — 38
Cancer — 54	Inflammation — 25	Teeth — 1447	Made away themſelves 65
Canker — 10	Itch — 1	Thruſh — 71	Murdered — 9
Childbed — 202	Leproſy — 6	Tympany — 5	Overlaid — 104
Colick, Gripes, and Twiſting of the Guts — 362	Lethargy — 9	Vomiting and Looſneſs 15	Scalded — 1
Conſumption — 4554	Livergrown — 13	Worms — 10	Starved — 3
Convulſion — 7924	Lunatick — 30		Suffocated — 1
Cough and Hooping Cough — 130	Meaſles — 169		Total 455
Diabetes — 3	Miſcarriage — 2		
Dropſy — 1140	Mortification — 232		
Evil — 33	Palſy — 43		
Fever, Malignant Fever, Scarlet Fever, Spotted Fever, and Purples — 3361	Pleuriſy — 51		
	Quinſy — 14		
	Raſh — 2		

CHRISTENED	Males — 8471	BURIED	Males — 13695
	Females 8020		Females 13886
	In all — 16491		In all — 27581

Increaſed in the Burials this Year 4043

Whereof have died,

Under Two Years of Age 10580	Twenty and Thirty 2139	Sixty and Seventy— 1666	A Hundred — 1
Between Two and Five— 2706	Thirty and Forty — 2445	Seventy and Eighty 1114	A Hundred and Five— 1
Five and Ten — 993	Forty and Fifty — 2357	Eighty and Ninety-- 557	A Hundred and Eight— 1
Ten and Twenty — 816	Fifty and Sixty — 2121	Ninety and a Hundred 83	A Hundred and Sixteen 1

A General

1737.

A General BILL of all the Chriſtenings and Burials,

From the 7th of December 1736, to the 13th of December 1737.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	32
Alhallows Barkin	61
Alhallows in Bread-ſtreet	13
Alhallows the Great	51
Alhallows in Honey-lane	1
Alhallows the Leſs	18
Alhallows in Lombard-ſtreet	15
Alhallows Staining	30
Alhallows on London Wall	33
St Alphage near Sion College	30
St Andrew Hubbard	12
St Andrew Underſhaft	43
St Andrew Wardrobe	47
St Ann within Alderſgate	38
St Ann in Black Friars	132
St Anthony, vulg. Antholin	5
St Auguſtin, vulg. Auſtin	16
St Bartholomew by Exchange	24
St Benedict, v. Bennet Fink	20
St Bennet Gracechurch	16
St Bennet at Paul's Wharf	47
St Bennet Sherehog	0
St Botolph at Billinſgate	13
Chriſt Church Pariſh	146
St Chriſtopher's Pariſh	12
St Clement near Eaſtcheap	13
St Dionis Backchurch	33
St Dunſtan in the Eaſt	66
St Edmund the King	17
St Ethelburga's Pariſh	20
St Faith under St Paul's	32
St Gabriel in Fenchurch-ſtr.	11
St George in Botolph-lane	8
St Gregory by St Paul's	73
St Helen near Biſhopſgate	19
St James in Duke's Place	21
St James at Garlickhithe	19
St John Baptiſt by Dowgate	17
St John the Evangeliſt	5
St John Zachary	15
St Katherine Coleman	61
St Katherine Creechurch	48
St Laurence Jewry	24
St Laurence Pountney	14
St Leonard in Eaſtcheap	18
St Leonard in Foſter-lane	19
St Magnus by London Bridge	33
St Margaret in Lothbury	38
St Margaret Moſes	3
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattons	15
St Martin Ironmonger-lane	6
St Martin at Ludgate	9
St Martin Orgars	11
St Martin Outwich	13
St Martin Vintrey	41
St Mary Abchurch	25
St Mary in Aldermanbury	34
St Mary Aldermary	26
St Mary le Bow in Cheapſide	17
St Mary Bothaw at Dowgate	0
St Mary Colechurch	0
St Mary Hill by Billinſgate	30
St Mary Magd. in Milk-ſtr.	1
St Mary Magd. Old Fiſh-ſtr.	41
St Mary Mounthaw	10
St Mary Somerſet	42
St Mary Staining	8
St Mary Woolchurch	0
St Mary Woolnoth	23
St Matthew in Friday-ſtreet	7
St Michael Baſſiſhaw	34
St Michael in Cornhill	20
St Michael in Crooked-lane	34
St Michael at Queenhithe	30
St Michael at Quern	10
St Michael Royal	17
St Michael in Wood-ſtreet	9
St Mildred in Bread-ſtreet	11
St Mildred in the Poultry	23
St Nicholas Acons	0
St Nicholas Coleabby	16
St Nicholas Olave	10
St Olave in Hart-ſtreet	38
St Olave in the Old Jewry	1
St Olave in Silver-ſtreet	16
St Pancras in Pancras-lane	4
St Peter in Cheapſide	5
St Peter in Cornhill	23
St Peter near Paul's Wharf	12
St Peter Poor in Broad-ſtr.	14
St Stephen in Coleman-ſtreet	62
St Stephen in Walbrook	4
St Swithin at London-ſtone	18
St Thomas the Apoſtle	18
Trinity Pariſh	10
St Vedaſt, alias Foſter	23

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1430 Buried 2303

St Andrew in Holborn	1089	Bridewell Precinct	31	St Olave in Southwark	493
St Bartholomew the Great	49	St Bridget, vulg. St Bride's	280	St Saviour in Southwark	739
St Bartholomew the Leſs	32	St Dunſtan in the Weſt	187	St Sepulchre's Pariſh	743
St Botolph by Alderſgate	270	St George in Southwark	459	St Thomas in Southwark	209
St Botolph by Aldgate	984	St Giles by Cripplegate	567	Trinity in the Minories	24
St Botolph by Biſhopſgate	606	St John in Southwark	404	The Peſt-houſe	

Chriſtened in the ſeventeen Pariſhes without the Walls 4670 Buried 7166

St Ann at Limehouſe —174	St George by Queen's ſquare 276	St Mary at Iſlington — —258
Chriſt Church in Surrey —210	St James at Clerkenwell —472	St Mary at Lambeth — —469
Chriſt Church in Middleſex 897	St John at Hackney —200	St Mary Magd. Bermondſey 571
St Dunſtan at Stepney—1215	St John at Wapping —322	St Mary at Newington —434
St Giles in the Fields —1203	St Katherine near the Tower 234	St Mary at Rotherhith —290
St George in Bloomſbury—547	St Leonard in Shoreditch—921	St Mary in Whitechapel—1311
St George in Middleſex —774	St Luke in Middleſex —995	St Paul at Shadwell —601

Chriſtened in the twenty-one Out Pariſhes in Middleſex and Surrey 6735 Buried 12374

St Ann in Weſtminſter —535	St James in Weſtminſter 1225	St Mary le Strand — 122
St Clement Danes — —508	St Margaret in Weſtminſt. 951	The Precinct of the Savoy 116
St George by Hanover-ſqu.530	St Martin in the Fields—1467	St Paul in Covent Garden 277
St John the Evangeliſt —249		

Chriſtened in the ten Pariſhes in the City and Liberties of Weſtminſter 3925 Buried 5980

DISEASES and CASUALTIES.

Abortive and Stilborn 641	Fiſtula — — 16	Rheumatiſm — — 19	CASUALTIES.
Aged — —1984	Flux — — 19	Rickets — — 80	
Ague — — 3	French Pox — — 159	Riſing of the Lights— 8	Broken Limbs — 2
Apoplexy and Suddenly 243	Gout — — 55	St Anthony's Fire — 1	Bruiſed — — 1
Aſthma and Tiſſick — 620	Gravel, Stone, and Strangury — 66	Scurvy — — 2	Burnt — — 7
Bedridden — — 12	Grief — — 10	Small Pox — —2084	Drowned — — 103
Bleeding — — 2	Headmoldſhot, Horſhoehead, and Water in the Head 153	Sores and Ulcers — 27	Exceſſive Drinking — 29
Bloody Flux — 7	Jaundies — — 158	Spleen — — 1	Executed — — 7
Burſten and Rupture-- 15	Impoſthume — 33	Stoppage in the Stomach 173	Found dead — — 42
Cancer — — 51	Inflammation — — 56	Surfeit — — 5	Killed by the Bite of a mad Dog — 1
Canker — — 7	Leproſy — — 5	Swelling — — 2	Killed by Falls and ſeveral other Accidents — 35
Childbed — — 284	Lethargy — — 7	Teeth — —1423	Made away themſelves 42
Colick, Gripes, and Twiſting of the Guts — 338	Livergrown — — 10	Thruſh — — 69	Murdered — — 17
Conſumption —4441	Lunatick — — 34	Tympany — — 3	Overlaid — — 80
Convulſion — —7811	Meaſles — — 127	Vapours — — 1	Scalded — — 1
Cough and Hooping Cough — 160	Miſcarriage — — 1	Vomiting and Looſneſs 11	Shot accidentally — 1
Dropſy — —1035	Mortification — 209	Worms — — 12	Smothered — — 1
Evil — — 35	Palſy — — 35		Starved — — 1
Fever, Malignant Fever, Scarlet Fever, Spotted Fever, and Purples — 4580	Pleuriſy — — 71		Suffocated — — 3
	Quinſy — — 31		Total 373
	Raſh — — 5		

CHRISTENED	Males — 8482	BURIED	Males — 13690
	Females 8278		Females 14133
	In all — 16760		In all — 27823

Increaſed in the Burials this Year 242

Whereof have died,

Under Two Years of Age 10054	Thirty and Forty — 2652	Seventy and Eighty—1164	A Hundred and Three-- 1
Between Two and Five— 2613	Forty and Fifty — 2578	Eighty and Ninety — 576	A Hundred and Five — 1
Five and Ten — — 1008	Fifty and Sixty — 2270	Ninety and a Hundred 127	A Hundred and Six — 1
Ten and Twenty — 885	Sixty and Seventy— 1650	A Hundred and One— 1	A Hundred and Sixteen 1
Twenty and Thirty — 2241			

A General

1738.

A General BILL of all the Chriſtenings and Burials,

From the 13th of December 1737, to the 12th of December 1738.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	26
Alhallows Barkin —	75
Alhallows in Bread-ſtreet —	11
Alhallows the Great ——	54
Alhallows in Honey-lane —	3
Alhallows the Leſs ——	25
Alhallows in Lombard-ſtreet	11
Alhallows Staining — ——	28
Alhallows on London Wall	20
St Alphage near Sion College	18
St Andrew Hubbard — —	11
St Andrew Underſhaft ——	34
St Andrew Wardrobe ——	61
St Ann within Alderſgate —	33
St Ann in Black Friars - —	123
St Anthony, vulg. Antholin	7
St Auguſtin, vulg. Auſtin—	9
St Bartholomew by Exchange	17
St Benedict, v. Bennet Fink	13
St Bennet Gracechurch - —	6
St Bennet at Paul's Wharf	41
St Bennet Sherehog - ——	0
St Botolph at Billinſgate —	7
Chriſt Church Pariſh ——	95
St Chriſtopher's Pariſh——	12
St Clement near Eaſtcheap	10
St Dionis Backchurch ——	24
St Dunſtan in the Eaſt ——	70
St Edmund the King — —	25
St Ethelburga's Pariſh ——	30
St Faith under St Paul's —	27
St Gabriel in Fenchurch-ſtr.	14
St George in Botolph-lane—	14
St Gregory by St Paul's —	91
St Helen near Biſhopſgate—	14
St James in Duke's Place —	24
St James at Garlickhithe —	26
St John Baptiſt by Dowgate	20
St John the Evangeliſt ——	3
St John Zachary —— —	26
St Katherine Coleman ——	29
St Katherine Creechurch —	41
St Laurence Jewry ——	38
St Laurence Pountney ——	17
St Leonard in Eaſtcheap —	11
St Leonard in Foſter-lane—	17
St Magnus by London Bridge	37
St Margaret in Lothbury—	38
St Margaret Moſes ——	0
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattons — —	13
St Martin Ironmonger-lane	11
St Martin at Ludgate ——	13
St Martin Orgars —— —	9
St Martin Outwich ——	7
St Martin Vintrey — ——	33
St Mary Abchurch — —	21
St Mary in Aldermanbury—	20
St Mary Aldermary — —	20
St Mary le Bow in Cheapſide	20
St Mary Bothaw at Dowgate	2
St Mary Colechurch ——	0
St Mary Hill by Billinſgate	37
St Mary Magd. in Milk-ſtr.	4
St Mary Magd. Old Fiſh-ſtr.	31
St Mary Mounthaw — —	8
St Mary Somerſet — ——	29
St Mary Staining —— —	10
St Mary Woolchurch ——	1
St Mary Woolnoth ——	14
St Matthew in Friday-ſtreet	4
St Michael Baſſiſhaw — —	32
St Michael in Cornhill ——	18
St Michael in Crooked-lane	28
St Michael at Queenhithe—	31
St Michael at Quern ——	6
St Michael Royal —— —	9
St Michael in Wood-ſtreet	10
St Mildred in Bread-ſtreet	5
St Mildred in the Poultry	14
St Nicholas Acons —— —	4
St Nicholas Coleabby ——	10
St Nicholas Olave ——	7
St Olave in Hart-ſtreet - —	53
St Olave in the Old Jewry	2
St Olave in Silver-ſtreet —	21
St Pancras in Pancras-lane	9
St Peter in Cheapſide ——	5
St Peter in Cornhill ——	26
St Peter near Paul's Wharf	17
St Peter Poor in Broad-ſtr.	11
St Stephen in Coleman-ſtreet	37
St Stephen in Walbrook —	16
St Swithin at London-ſtone	12
St Thomas the Apoſtle - —	14
Trinity Pariſh —— ——	12
St Vedaſt, alias Foſter ——	27

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1283 Buried 2129

St Andrew in Holborn —	1030
St Bartholomew the Great--	62
St Bartholomew the Leſs —	26
St Botolph by Alderſgate —	224
St Botolph by Aldgate -—	730
St Botolph by Biſhopſgate—	538
Bridewell Precinct ——	32
St Bridget, vulg. St Bride's	244
St Dunſtan in the Weſt - —	155
St George in Southwark —	374
St Giles by Cripplegate——	549
St John in Southwark ——	350
St Olave in Southwark —	456
St Saviour in Southwark —	706
St Sepulchre's Pariſh -——	708
St Thomas in Southwark—	188
Trinity in the Minories —	27
The Peſt-houſe — ——	

Chriſtened in the ſeventeen Pariſhes without the Walls 4325 Buried 6399

St Ann at Limehouſe —— 158	St George by Queen's ſquare 241	St Mary at Iſlington — — 289
Chriſt Church in Surrey — 184	St James at Clerkenwell — 548	St Mary at Lambeth —— 441
Chriſt Church in Middleſex 691	St John at Hackney —— 223	St Mary Magd. Bermondſey 437
St Dunſtan at Stepney —— 1119	St John at Wapping —— 296	St Mary at Newington —— 331
St Giles in the Fields —— 1067	St Katherine near the Tower 199	St Mary at Rotherhith —— 286
St George in Bloomſbury — 525	St Leonard in Shoreditch — 796	St Mary in Whitechapel — 1187
St George in Middleſex - — 736	St Luke in Middleſex —— 994	St Paul at Shadwell —— 443

Chriſtened in the twenty-one Out Pariſhes in Middleſex and Surrey 6412 Buried 11191

St Ann in Weſtminſter - — 575	St James in Weſtminſter — 1141	St Mary le Strand —— 113
St Clement Danes — —— 428	St Margaret in Weſtminſt. 947	The Precinct of the Savoy 121
St George by Hanover-ſqu. 952	St Martin in the Fields — 1315	St Paul in Covent Garden 293
St John the Evangeliſt - — 221		

Chriſtened in the ten Pariſhes in the City and Liberties of Weſtminſter 4040 Buried 6106

DISEASES and CASUALTIES.

Abortive and Stilborn 608	Fiſtula —— —— 17	Rheumatiſm —— — 21	CASUALTIES.
Aged —— —— 1841	Flux —— —— 11	Rickets —— —— 73	
Ague —— —— 1	French Pox — —— 117	Riſing of the Lights— 6	Broken Limbs —— 3
Apoplexy and Suddenly 201	Gout —— —— 66	St Anthony's Fire — 2	Broken Jaw — — 1
Aſthma and Tiſſick — 656	Gravel, Stone, and Strangury — 74	Scald Head — —— 2	Bruiſed —— — 4
Bedridden — —— 5	Grief —— —— 10	Small Pox — ——— 1590	Burnt —— —— 5
Bleeding —— —— 3	Headmoldſhot, Horſhoehead, and Water in the Head 175	Sores and Ulcers —— 19	Died by the Bite of a mad Dog — 1
Bloody Flux —— 5	Jaundies —— — 130	Stoppage in the Stomach 188	Drowned — —— 82
Burſten and Rupture-- 25	Impoſthume — —— 13	Surfeit —— —— 2	Exceſſive Drinking — 31
Cancer — —— 54	Inflammation — — 52	Swelling — —— 1	Executed —— —— 17
Canker —— —— 8	Itch —— —— 6	Teeth —— —1376	Found dead — — 19
Childbed —— — 261	Leproſy —— — 4	Thruſh —— —— 94	Fractured Skull — — 2
Colick, Gripes, and Twiſting of the Guts —— 295	Lethargy — —— 7	Tympany —— — 4	Frighted — —— 1
Conſumption ——4326	Livergrown —— — 6	Vomiting and Looſneſs 12	Killed by Falls and ſeveral other Accidents — 49
Convulſion — —7524	Lunatick — —— 39	Worms —— —— 16	Made away themſelves 42
Cough and Hooping Cough — 69	Meaſles —— — 216		Murdered — —— 13
Dropſy —— —— 969	Miſcarriage — — — 1		Overlaid —— —— 82
Evil —— —— 38	Mortification —— 222		Scalded —— — 3
Fever, Malignant Fever, Scarlet Fever, Spotted Fever, and Purples — 3890	Palſy —— —— 30		Shot himſelf accidentally 1
	Pleuriſy —— —— 51		Starved —— —— 7
	Quinſy —— —— 23		Suffocated — —— 4
	Raſh —— —— 3		Total 367

CHRISTENED	Males — 8212	BURIED	Males — 12750
	Females 7848		Females 13075
	In all 16060		In all — 25825

Decreaſed in the Burials this Year 1998

Whereof have died,

Under Two Years of Age 9600	Thirty and Forty — 2439	Seventy and Eighty 1121	A Hundred and Two — 4
Between Two and Five— 2366	Forty and Fifty —— 2363	Eighty and Ninety-- 529	A Hundred and Three— 2
Five and Ten —— 784	Fifty and Sixty —— 2106	Ninety and a Hundred 101	A Hundred and Five— 1
Ten and Twenty —— 783	Sixty and Seventy— 1551	A Hundred — — 2	A Hundred and Eleven— 1
Twenty and Thirty— 2072			

1739.

A General BILL of all the Chriſtenings and Burials,

From the 12th of December 1738, to the 11th of December 1739.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	29
Alhallows Barkin	55
Alhallows in Bread-ſtreet	11
Alhallows the Great	50
Alhallows in Honey-lane	2
Alhallows the Leſs	24
Alhallows in Lombard-ſtreet	17
Alhallows Staining	16
Alhallows on London Wall	61
St Alphage near Sion College	17
St Andrew Hubbard	9
St Andrew Underſhaft	41
St Andrew Wardrobe	66
St Ann within Alderſgate	49
St Ann in Black Friars	127
St Anthony, vulg. Antholin	8
St Auguſtin, vulg. Auſtin	16
St Bartholomew by Exchange	22
St Benedict, v. Bennet Fink	7
St Bennet Gracechurch	9
St Bennet at Paul's Wharf	26
St Bennet Sherehog	1
St Botolph at Billinſgate	4
Chriſt Church Pariſh	101
St Chriſtopher's Pariſh	13
St Clement near Eaſtcheap	10
St Dionis Backchurch	28
St Dunſtan in the Eaſt	58
St Edmund the King	17
St Ethelburga's Pariſh	26
St Faith under St Paul's	29
St Gabriel in Fenchurch-ſtr.	6
St George in Botolph-lane	8
St Gregory by St Paul's	96
St Helen near Biſhopſgate	28
St James in Duke's Place	15
St James at Garlickhithe	30
St John Baptiſt by Dowgate	21
St John the Evangeliſt	3
St John Zachary	8
St Katherine Coleman	35
St Katherine Creechurch	50
St Laurence Jewry	33
St Laurence Pountney	12
St Leonard in Eaſtcheap	15
St Leonard in Foſter-lane	10
St Magnus by London Bridge	28
St Margaret in Lothbury	34
St Margaret Moſes	3
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattons	10
St Martin Ironmonger-lane	14
St Martin at Ludgate	13
St Martin Orgars	10
St Martin Outwich	8
St Martin Vintrey	35
St Mary Abchurch	14
St Mary in Aldermanbury	31
St Mary Aldermary	20
St Mary le Bow in Cheapſide	12
St Mary Bothaw at Dowgate	3
St Mary Colechurch	1
St Mary Hill by Billinſgate	36
St Mary Magd. in Milk-ſtr.	1
St Mary Magd. Old Fiſh-ſtr.	35
St Mary Mounthaw	9
St Mary Somerſet	39
St Mary Staining	20
St Mary Woolchurch	0
St Mary Woolnoth	12
St Matthew in Friday-ſtreet	6
St Michael Baſſiſhaw	23
St Michael in Cornhill	18
St Michael in Crooked-lane	22
St Michael at Queenhithe	24
St Michael at Quern	8
St Michael Royal	11
St Michael in Wood-ſtreet	3
St Mildred in Bread-ſtreet	6
St Mildred in the Poultry	13
St Nicholas Acons	1
St Nicholas Coleabby	21
St Nicholas Olave	8
St Olave in Hart-ſtreet	40
St Olave in the Old Jewry	1
St Olave in Silver-ſtreet	19
St Pancras in Pancras-lane	2
St Peter in Cheapſide	6
St Peter in Cornhill	21
St Peter near Paul's Wharf	17
St Peter Poor in Broad-ſtr.	5
St Stephen in Coleman-ſtreet	60
St Stephen in Walbrook	7
St Swithin at London-ſtone	12
St Thomas the Apoſtle	11
Trinity Pariſh	19
St Vedaſt, alias Foſter	24

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1331 Buried 2115

St Andrew in Holborn	1107
St Bartholomew the Great	68
St Bartholomew the Leſs	23
St Botolph by Alderſgate	255
St Botolph by Aldgate	782
St Botolph by Biſhopſgate	614
Bridewell Precinct	28
St Bridget, vulg. St Bride's	240
St Dunſtan in the Weſt	168
St George in Southwark	367
St Giles by Cripplegate	724
St John in Southwark	375
St Olave in Southwark	443
St Saviour in Southwark	736
St Sepulchre's Pariſh	681
St Thomas in Southwark	161
Trinity in the Minories	26
The Peſt-houſe	

Chriſtened in the ſeventeen Pariſhes without the Walls 4450 Buried 6798

St Ann at Limehouſe —150	St George by Queen's ſquare 259	St Mary at Iſlington —218
Chriſt Church in Surrey —197	St James at Clerkenwell —510	St Mary at Lambeth —539
Chriſt Church in Middleſex 763	St John at Hackney—184	St Mary Magd. Bermondſey 448
St Dunſtan at Stepney —995	St John at Wapping—260	St Mary at Newington —364
St Giles in the Fields —985	St Katherine near the Tower 196	St Mary at Rotherhith —240
St George in Bloomſbury—520	St Leonard in Shoreditch —850	St Mary in Whitechapel—1114
St George in Middleſex —618	St Luke in Middleſex —959	St Paul at Shadwell —404

Chriſtened in the twenty-one Out Pariſhes in Middleſex and Surrey 6585 Buried 10773

St Ann in Weſtminſter —520	St James in Weſtminſter 1181	St Mary le Strand — 101
St Clement Danes —375	St Margaret in Weſtminſt. 1022	The Precinct of the Savoy 83
St George by Hanover-ſqu. 730	St Martin in the Fields —1266	St Paul in Covent Garden 297
St John the Evangeliſt —171		

Chriſtened in the ten Pariſhes in the City and Liberties of Weſtminſter 3815 Buried 5746

DISEASES and CASUALTIES.

Abortive and Stilborn 602	Fiſtula — 9	Rheumatiſm — 23	CASUALTIES.
Aged — —1770	Flux — 10	Rickets — 80	
Ague — 3	French Pox — 116	Riſing of the Lights— 11	Broken Limbs — 12
Apoplexy and Suddenly 194	Gout — 48	St Anthony's Fire— 6	Burnt — 3
Aſthma and Tiſſick — 638	Gravel, Stone, and Strangury — 47	Scald Head — 1	Drowned — 91
Bedridden — 8	Grief — 10	Small Pox —1690	Exceſſive Drinking — 47
Bleeding — 3	Headmoldſhot, Horſhoehead, and Water in the Head 155	Sores and Ulcers — 37	Executed — 12
Bloody Flux — 9		Sore Throat — 2	Found dead — 43
Burſten and Rupture-- 20		Spleen — 1	Fractured Skull — 7
Cancer — 50		Stoppage in the Stomach 206	Killed by the Bite of a Cat — 1
Canker — 8	Jaundies — 121	Surfeit — 6	Killed by a Dog — 1
Childbed — 260	Impoſthume — 22	Swelling — 2	Killed by Falls and ſeveral other Accidents — 55
Colick, Gripes, and Twiſting of the Guts — 280	Inflammation — 39	Teeth — —1372	
	Itch — 4	Thruſh — 104	
Conſumption —4429	Leproſy — 4	Tympany — 2	Made away themſelves 45
Convulſion —7371	Lethargy — 5	Vomiting and Looſneſs 5	Murdered — 7
Cough and Hooping Cough — 72	Livergrown — 10	Worms — 10	Overlaid — 102
	Lunatick — 34	White Ives — 4	Poiſoned — 2
Diabetes — 1	Meaſles — 326		Scalded — 4
Dropſy — —1007	Miſcarriage — 3		Stabbed — 1
Evil — 32	Mortification — 258		Starv'd by Hunger or Cold 9
Fever, Malignant Fever, Scarlet Fever, Spotted Fever, and Purples —3334	Palſy — 37		Suffocated — 3
	Pleuriſy — 53		Total 445
	Quinſy — 19		
	Raſh — 4		

CHRISTENED	Males — 8228	BURIED	Males — 12416
	Females 7953		Females 13016
	In all — 16181		In all — 25432

Decreaſed in the Burials this Year 393

Whereof have died,

Under Two Years of Age 9687	Thirty and Forty — 2218	Eighty and Ninety — 547	A Hundred and Four — 1
Between Two and Five— 2302	Forty and Fifty — 2378	Ninety and a Hundred 76	A Hundred and Five — 1
Five and Ten — 844	Fifty and Sixty — 2039	A Hundred — 3	A Hundred and Eight— 1
Ten and Twenty — 875	Sixty and Seventy — 1421	A Hundred and Two 4	A Hundred and Ten— 1
Twenty and Thirty — 1866	Seventy and Eighty 1166	A Hundred and Three 1	A Hund. and Thirty-eight 1

1740.

A General BILL of all the Chriſtenings and Burials,

From the 11th of December 1739, to the 16th of December 1740.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	31
Alhallows Barkin	71
Alhallows in Bread-ſtreet	12
Alhallows the Great	51
Alhallows in Honey-lane	3
Alhallows the Leſs	15
Alhallows in Lombard-ſtreet	19
Alhallows Staining	19
Alhallows on London Wall	53
St Alphage near Sion College	30
St Andrew Hubbard	24
St Andrew Underſhaft	44
St Andrew Wardrobe	97
St Ann within Alderſgate	77
St Ann in Black Friars	195
St Anthony, vulg. Antholin	10
St Auguſtin, vulg. Auſtin	15
St Bartholomew by Exchange	19
St Benedict, v. Bennet Fink	16
St Bennet Gracechurch	14
St Bennet at Paul's Wharf	42
St Bennet Sherehog	0
St Botolph at Billinſgate	4
Chriſt Church Pariſh	135
St Chriſtopher's Pariſh	13
St Clement near Eaſtcheap	13
St Dionis Backchurch	36
St Dunſtan in the Eaſt	56
St Edmund the King	10
St Ethelburga's Pariſh	24
St Faith under St Paul's	39
St Gabriel in Fenchurch-ſtr.	11
St George in Botolph-lane	14
St Gregory by St Paul's	96
St Helen near Biſhopſgate	34
St James in Duke's Place	23
St James at Garlickhithe	29
St John Baptiſt by Dowgate	24
St John the Evangeliſt	3
St John Zachary	0
St Katherine Coleman	48
St Katherine Creechurch	51
St Laurence Jewry	22
St Laurence Pountney	9
St Leonard in Eaſtcheap	10
St Leonard in Foſter-lane	24
St Magnus by London Bridge	20
St Margaret in Lothbury	24
St Margaret Moſes	5
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattons	15
St Martin Ironmonger-lane	10
St Martin at Ludgate	9
St Martin Orgars	10
St Martin Outwich	11
St Martin Vintrey	33
St Mary Abchurch	11
St Mary in Aldermanbury	42
St Mary Aldermary	22
St Mary le Bow in Cheapſide	25
St Mary Bothaw at Dowgate	0
St Mary Colechurch	0
St Mary Hill by Billinſgate	44
St Mary Magd. in Milk-ſtr.	1
St Mary Magd. Old Fiſh-ſtr.	43
St Mary Mounthaw	12
St Mary Somerſet	40
St Mary Staining	25
St Mary Woolchurch	0
St Mary Woolnoth	11
St Matthew in Friday-ſtreet	11
St Michael Baſſiſhaw	27
St Michael in Cornhill	17
St Michael in Crooked-lane	29
St Michael at Queenhithe	50
St Michael at Quern	7
St Michael Royal	13
St Michael in Wood-ſtreet	3
St Mildred in Bread-ſtreet	11
St Mildred in the Poultry	16
St Nicholas Acons	2
St Nicholas Coleabby	15
St Nicholas Olave	10
St Olave in Hart-ſtreet	73
St Olave in the Old Jewry	4
St Olave in Silver-ſtreet	27
St Pancras in Pancras-lane	4
St Peter in Cheapſide	13
St Peter in Cornhill	39
St Peter near Paul's Wharf	20
St Peter Poor in Broad-ſtr.	16
St Stephen in Coleman-ſtreet	62
St Stephen in Walbrook	16
St Swithin at London-ſtone	17
St Thomas the Apoſtle	22
Trinity Pariſh	24
St Vedaſt, alias Foſter	34

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1279 Buried 2580

St Andrew in Holborn	1315
St Bartholomew the Great	75
St Bartholomew the Leſs	25
St Botolph by Alderſgate	278
St Botolph by Aldgate	953
St Botolph by Biſhopſgate	693
Bridewell Precinct	29
St Bridget, vulg. St Bride's	353
St Dunſtan in the Weſt	218
St George in Southwark	342
St Giles by Cripplegate	943
St John in Southwark	448
St Olave in Southwark	514
St Saviour in Southwark	749
St Sepulchre's Pariſh	827
St Thomas in Southwark	205
Trinity in the Minories	34
The Peſt-houſe	

Chriſtened in the ſeventeen Pariſhes without the Walls 3852 Buried 8001

St Ann at Limehouſe —203	St George by Queen's ſquare 322	St Mary at Iſlington — —267
Chriſt Church in Surrey —208	St James at Clerkenwell —613	St Mary at Lambeth — —511
Chriſt Church in Middleſex 940	St John at Hackney —221	St Mary Magd. Bermondſey 557
St Dunſtan at Stepney—1217	St John at Wapping —291	St Mary at Newington —410
St Giles in the Fields —1274	St Katherine near the Tower 353	St Mary at Rotherhith —331
St George in Bloomſbury—606	St Leonard in Shoreditch 1058	St Mary in Whitechapel—1272
St George in Middleſex —873	St Luke in Middleſex —1257	St Paul at Shadwell —566

Chriſtened in the twenty-one Out Pariſhes in Middleſex and Surrey 6141 Buried 13250

St Ann in Weſtminſter —629	St James in Weſtminſter 1462	St Mary le Strand — 132
St Clement Danes — —573	St Margaret in Weſtminſt. 1268	The Precinct of the Savoy 156
St George by Hanover-ſqu. 636	St Martin in the Fields —1498	St Paul in Covent Garden 361
St John the Evangeliſt —265		

Chriſtened in the ten Pariſhes in the City and Liberties of Weſtminſter 3955 Buried 6980

DISEASES and CASUALTIES.

Abortive and Stilborn 554	Fiſtula — — 8	Rheumatiſm — — 38	Casualties.		
Aged — —2591	Flux — — 16	Rickets — — 81	Broken Limbs — 10		
Ague — — 6	French Pox — — 162	Riſing of the Lights — 12	Bruiſed — — 5		
Apoplexy and Suddenly 228	Gout — — 60	St Anthony's Fire — 4	Burnt — — 11		
Aſthma and Tiſſick —1153	Gravel, Stone, and Strangury — 43	Scald Head — 2	Choaked — — 1		
Bedridden — — 23	Grief — — 12	Scurvy — — 2	Died by the cutting off a Leg — 1		
Bleeding — — 8	Head-ach — — 1	Small Pox — —2725	Drowned — — 97		
Bloody Flux — 6	Headmoldſhot, Horſhoehead, and Water in the Head 165	Sores and Ulcers — 30	Exceſſive Drinking — 52		
Burſten and Rupture-- 28		Spleen — — 1	Executed — — 13		
Cancer — — 56		Stoppage in the Stomach 185	Found dead — — 55		
Canker — — 6		Surfeit — — 5	Fractured Skull — — 8		
Childbed — — 227	Jaundies — — 108	Swelling — — 8	Frighted — — 1		
Colick, Gripes, and Twiſting of the Guts — 296	Impoſthume — 28	Teeth — —1708	Frozen to Death — 2		
	Inflammation — — 35	Thruſh — — 136	Killed by Falls and ſeveral other Accidents — 40		
	Itch — — 1	Tympany — — 6			
Conſumption —4919	Leproſy — — 4	Vomiting and Looſneſs 7			
Convulſion — —8479	Lethargy — — 8	Worms — — 13	Made away themſelves 55		
Cough and Hooping Cough — 280	Livergrown — — 7		Murdered — — 8		
	Lunatick — — 90		Overlaid — — 78		
Diabetes — — 1	Meaſles — — 46		Scalded — — 4		
Dropſy — —1219	Miſcarriage — — 5		Shot — — 1		
Evil — — 50	Mortification — 318		Smothered — — 2		
Falling Sickneſs — 1	Palſy — — 43		Starved — — 15		
Fever, Malignant Fever, Scarlet Fever, Spotted Fever, and Purples — 4003	Pleuriſy — — 70		Suffocated — — 3		
	Quinſy — — 18		Total 462		
	Raſh — — 3				

CHRISTENED	Males — 7833	BURIED	Males — 14985
	Females 7398		Females 15826
	In all — 15231		In all — 30811

Increaſed in the Burials this Year 5379

Whereof have died,

Under Two Years of Age 10765	Thirty and Forty — 2783	Eighty and Ninety — 758	A Hundred and Three-- 1
Between Two and Five— 2862	Forty and Fifty — 2866	Ninety and a Hundred 100	A Hundred and Four — 1
Five and Ten — — 1235	Fifty and Sixty — 2585	A Hundred — — 2	A Hundred and Five — 1
Ten and Twenty — 947	Sixty and Seventy— 1977	A Hundred and One— 2	A Hundred and Six — 1
Twenty and Thirty — 2205	Seventy and Eighty—1716	A Hundred and Two— 2	A Hundred and Seven— 2

A General

1741.

A General BILL of all the Chriſtenings and Burials,

From the 16th of December 1740, to the 15th of December 1741.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	31
Alhallows Barkin	79
Alhallows in Bread-ſtreet	5
Alhallows the Great	76
Alhallows in Honey-lane	1
Alhallows the Leſs	29
Alhallows in Lombard-ſtreet	17
Alhallows Staining	31
Alhallows on London Wall	45
St Alphage near Sion College	14
St Andrew Hubbard	16
St Andrew Underſhaft	36
St Andrew Wardrobe	98
St Ann within Alderſgate	57
St Ann in Black Friars	184
St Anthony, vulg. Antholin	12
St Auguſtin, vulg. Auſtin	19
St Bartholomew by Exchange	23
St Benedict, v. Bennet Fink	20
St Bennet Gracechurch	16
St Bennet at Paul's Wharf	53
St Bennet Sherehog	0
St Botolph at Billinſgate	4
Chriſt Church Pariſh	176
St Chriſtopher's Pariſh	21
St Clement near Eaſtcheap	12
St Dionis Backchurch	31
St Dunſtan in the Eaſt	56
St Edmund the King	14
St Ethelburga's Pariſh	35
St Faith under St Paul's	34
St Gabriel in Fenchurch-ſtr.	12
St George in Botolph-lane	14
St Gregory by St Paul's	94
St Helen near Biſhopſgate	39
St James in Duke's Place	29
St James at Garlickhithe	41
St John Baptiſt by Dowgate	21
St John the Evangeliſt	4
St John Zachary	34
St Katherine Coleman	44
St Katherine Creechurch	56
St Laurence Jewry	39
St Laurence Pountney	9
St Leonard in Eaſtcheap	17
St Leonard in Foſter-lane	19
St Magnus by London Bridge	42
St Margaret in Lothbury	27
St Margaret Moſes	5
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattons	12
St Martin Ironmonger-lane	15
St Martin at Ludgate	15
St Martin Orgars	22
St Martin Outwich	2
St Martin Vintrey	49
St Mary Abchurch	21
St Mary in Aldermanbury	44
St Mary Aldermary	24
St Mary le Bow in Cheapſide	32
St Mary Bothaw at Dowgate	1
St Mary Colechurch	0
St Mary Hill by Billinſgate	41
St Mary Magd. in Milk-ſtr.	2
St Mary Magd. Old Fiſh-ſtr.	46
St Mary Mounthaw	16
St Mary Somerſet	45
St Mary Staining	20
St Mary Woolchurch	0
St Mary Woolnoth	7
St Matthew in Friday-ſtreet	8
St Michael Baſſiſhaw	31
St Michael in Cornhill	28
St Michael in Crooked-lane	34
St Michael at Queenhithe	43
St Michael at Quern	9
St Michael Royal	13
St Michael in Wood-ſtreet	9
St Mildred in Bread-ſtreet	11
St Mildred in the Poultry	13
St Nicholas Acons	2
St Nicholas Coleabby	12
St Nicholas Olave	8
St Olave in Hart-ſtreet	57
St Olave in the Old Jewry	5
St Olave in Silver-ſtreet	23
St Pancras in Pancras-lane	4
St Peter in Cheapſide	13
St Peter in Cornhill	31
St Peter near Paul's Wharf	15
St Peter Poor in Broad-ſtr.	14
St Stephen in Coleman-ſtreet	59
St Stephen in Walbrook	13
St Swithin at London-ſtone	12
St Thomas the Apoſtle	16
Trinity Pariſh	20
St Vedaſt, alias Foſter	30

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1262 Buried 2738

St Andrew in Holborn	1399
St Bartholomew the Great	94
St Bartholomew the Leſs	14
St Botolph by Alderſgate	283
St Botolph by Aldgate	1000
St Botolph by Biſhopſgate	755
Bridewell Precinct	40
St Bridget, vulg. St Bride's	307
St Dunſtan in the Weſt	170
St George in Southwark	466
St Giles by Cripplegate	947
St John in Southwark	460
St Olave in Southwark	665
St Saviour in Southwark	866
St Sepulchre's Pariſh	864
St Thomas in Southwark	216
Trinity in the Minories	45
The Peſt-houſe	

Chriſtened in the ſeventeen Pariſhes without the Walls 3851 Buried 8501

1741.

St Ann at Limehouſe —257	St George by Queen's ſquare 329	St Mary at Iſlington —274
Chriſt Church in Surrey —257	St James at Clerkenwell —665	St Mary at Lambeth —606
Chriſt Church in Middleſex 942	St John at Hackney —247	St Mary Magd. Bermondſey 582
St Dunſtan at Stepney—1296	St John at Wapping —355	St Mary at Newington —469
St Giles in the Fields —1186	St Katherine near the Tower 243	St Mary at Rotherhith —398
St George in Bloomſbury —574	St Leonard in Shoreditch 1081	St Mary in Whitechapel—1496
St George in Middleſex —842	St Luke in Middleſex —1369	St Paul at Shadwell —542

Chriſtened in the twenty-one Out Pariſhes in Middleſex and Surrey 6080 Buried 14010

St Ann in Weſtminſter —525	St James in Weſtminſter 1342	St Mary le Strand — 133
St Clement Danes — —487	St Margaret in Weſtminſt. 1372	The Precinct of the Savoy 185
St George by Hanover-ſqu. 779	St Martin in the Fields —1506	St Paul in Covent Garden 335
St John the Evangeliſt—256		

Chriſtened in the ten Pariſhes in the City and Liberties of Weſtminſter 3764 Buried 6920

DISEASES and CASUALTIES.

Abortive and Stilborn 548	Fiſtula — — 16	Rickets — — 50	Died of a Wound — 1
Aged — —2512	Flux — — 31	Riſing of the Lights— 13	Died in the Street— 1
Ague — — 3	French Pox — — 128	St Anthony's Fire— 5	Died by the Bite of a mad Dog — 1
Apoplexy and Suddenly 230	Gout — — 46	Scald Head — — 2	Drowned — — 116
Aſthma and Tiſſick — 646	Gravel, Stone, and Strangury — 53	Small Pox — —1977	Exceſſive Drinking — 56
Bedridden — — 17	Grief — — 10	Sores and Ulcers — 19	Executed — — 7
Bleeding — — 5	Head-ach — — 1	Sore Throat — — — 3	Found dead — — 71
Bloody Flux — 20	Headmoldſhot, Horſhoehead, and Water in the Head 129	Stoppage in the Stomach 197	Found hang'd — 1
Burſten and Rupture-- 16		Surfeit — — 8	Fractured Skull— 5
Cancer — — 62		Swelling — — 3	Frighted — — 1
Canker — — 5		Teeth — —1501	Killed by the Kick of a Horſe — 1
Childbed — — 256	Jaundies — — 161	Thruſh — — 158	
Colick, Gripes, and Twiſting of the Guts — 258	Impoſthume — — 25	Tympany — — 2	Killed by Falls and ſeveral other Accidents — 43
	Inflammation — 33	Vomiting and Looſneſs 20	
Conſumption —4981	Itch — — 5	Worms — — 16	Made away themſelves 51
Convulſion — —8250	Leproſy — — 9		Murdered — — 8
Cough and Hooping Cough — 109	Lethargy — — 6		Overlaid — — 70
	Lunatick — — 71		Scalded — — 2
Diabetes — — 3	Meaſles — — 42		Shot by Accident — 2
Dropſy — —1058	Miſcarriage — — 5		Stabbed — — 1
Evil — — 31	Mortification — 282		Starved — — 13
Falling Sickneſs — 1	Palſy — — 48		Suffocated — — 1
Fever, Malignant Fever, Scarlet Fever, Spotted Fever, and Purples 7528	Pleuriſy — — 44		
	Quinſy — — 13		Total 466
	Raſh — — 6		
	Rheumatiſm — — 26		

CASUALTIES.

Broken Limbs — 7	
Bruiſed — 3	
Burnt — 2	
Choaked — 1	
Died by cutting off her Breaſt — 1	

CHRISTENED	Males — 7667	BURIED	Males — 15465
	Females 7290		Females 16704
	In all — 14957		In all — 32169

Increaſed in the Burials this Year 1358

Whereof have died,

Under Two Years of Age 10456	Thirty and Forty — 3476	Eighty and Ninety— 734	A Hundred and Two — 5
Between Two and Five— 2368	Forty and Fifty — 3731	Ninety and a Hundred 130	A Hundred and Three— 1
Five and Ten — — 1072	Fifty and Sixty — 2851	A Hundred — — 5	A Hundred and Four — 1
Ten and Twenty — 1048	Sixty and Seventy — 1933	A Hundred and One 1	A Hundred and Six — 1
Twenty and Thirty— 2816	Seventy and Eighty 1540		

N. B. By the Neglect of the Pariſh Clerk of St George Hanover-ſquare, there are 245 omitted to be reported by him this Year, which are not included in this Account.

1743.

A General BILL of all the Chriſtenings and Burials,

From the 14th of December 1742, to the 13th of December 1743.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	33
Alhallows Barkin	64
Alhallows in Bread-ſtreet	11
Alhallows the Great	49
Alhallows in Honey-lane	0
Alhallows the Leſs	14
Alhallows in Lombard-ſtreet	23
Alhallows Staining	20
Alhallows on London Wall	38
St Alphage near Sion College	19
St Andrew Hubbard	14
St Andrew Underſhaft	41
St Andrew Wardrobe	54
St Ann within Alderſgate	39
St Ann in Black Friars	135
St Anthony, vulg. Antholin	6
St Auguſtin, vulg. Auſtin	5
St Bartholomew by Exchange	19
St Benedict, v. Bennet Fink	14
St Bennet Gracechurch	7
St Bennet at Paul's Wharf	49
St Bennet Sherehog	1
St Botolph at Billinſgate	6
Chriſt Church Pariſh	100
St Chriſtopher's Pariſh	10
St Clement near Eaſtcheap	8
St Dionis Backchurch	30
St Dunſtan in the Eaſt	57
St Edmund the King	14
St Ethelburga's Pariſh	24
St Faith under St Paul's	23
St Gabriel in Fenchurch-ſtr.	19
St George in Botolph-lane	7
St Gregory by St Paul's	54
St Helen near Biſhopſgate	28
St James in Duke's Place	30
St James at Garlickhithe	29
St John Baptiſt by Dowgate	20
St John the Evangeliſt	1
St John Zachary	20
St Katherine Coleman	49
St Katherine Creechurch	52
St Laurence Jewry	43
St Laurence Pountney	16
St Leonard in Eaſtcheap	11
St Leonard in Foſter-lane	13
St Magnus by London Bridge	31
St Margaret in Lothbury	25
St Margaret Moſes	4
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattons	10
St Martin Ironmonger-lane	13
St Martin at Ludgate	12
St Martin Orgars	21
St Martin Outwich	6
St Martin Vintrey	27
St Mary Abchurch	23
St Mary in Aldermanbury	29
St Mary Aldermary	25
St Mary le Bow in Cheapſide	12
St Mary Bothaw at Dowgate	4
St Mary Colechurch	0
St Mary Hill by Billinſgate	32
St Mary Magd. in Milk-ſtr.	0
St Mary Magd. Old Fiſh-ſtr.	23
St Mary Mounthaw	8
St Mary Somerſet	27
St Mary Staining	16
St Mary Woolchurch	0
St Mary Woolnoth	18
St Matthew in Friday-ſtreet	12
St Michael Baſſiſhaw	26
St Michael in Cornhill	16
St Michael in Crooked-lane	25
St Michael at Queenhithe	25
St Michael at Quern	17
St Michael Royal	19
St Michael in Wood-ſtreet	1
St Mildred in Bread-ſtreet	7
St Mildred in the Poultry	11
St Nicholas Acons	8
St Nicholas Coleabby	12
St Nicholas Olave	5
St Olave in Hart-ſtreet	37
St Olave in the Old Jewry	1
St Olave in Silver-ſtreet	22
St Pancras in Pancras-lane	3
St Peter in Cheapſide	7
St Peter in Cornhill	30
St Peter near Paul's Wharf	9
St Peter Poor in Broad-ſtr.	12
St Stephen in Coleman-ſtreet	79
St Stephen in Walbrook	14
St Swithin at London-ſtone	11
St Thomas the Apoſtle	14
Trinity Pariſh	13
St Vedaſt, alias Foſter	17

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1135 Buried 2138

St Andrew in Holborn	1156
St Bartholomew the Great	91
St Bartholomew the Leſs	13
St Botolph by Alderſgate	238
St Botolph by Aldgate	740
St Botolph by Biſhopſgate	437
Bridewell Precinct	8
St Bridget, vulg. St Bride's	227
St Dunſtan in the Weſt	181
St George in Southwark	301
St Giles by Cripplegate	690
St John in Southwark	357
St Olave in Southwark	407
St Saviour in Southwark	614
St Sepulchre's Pariſh	577
St Thomas in Southwark	180
Trinity in the Minories	33
The Peſt-houſe	

Chriſtened in the ſeventeen Pariſhes without the Walls 4163 Buried 6250

St Ann at Limehouſe ——208	St George by Queen's ſquare 295	St Mary at Iſlington ——302
Chriſt Church in Surrey —149	St James at Clerkenwell —611	St Mary at Lambeth — —468
Chriſt Church in Middleſex 701	St John at Hackney——201	St Mary Magd. Bermondſey 549
St Dunſtan at Stepney——1049	St John at Wapping——292	St Mary at Newington ——348
St Giles in the Fields ——1021	St Katherine near the Tower 222	St Mary at Rotherhith ——277
St George in Bloomſbury—576	St Leonard in Shoreditch —873	St Mary in Whitechapel—1208
St George in Middleſex - —704	St Luke in Middleſex——1245	St Paul at Shadwell ——425

Chriſtened in the twenty-one Out Pariſhes in Middleſex and Surrey 5489 Buried 11724

St Ann in Weſtminſter - —533	St James in Weſtminſter 1114	St Mary le Strand —— 98
St Clement Danes ——455	St Margaret in Weſtminſt. 1065	The Precinct of the Savoy 83
St George by Hanover-ſqu. 966	St Martin in the Fields —1411	St Paul in Covent Garden 340
St John the Evangeliſt - —142		

Chriſtened in the ten Pariſhes in the City and Liberties of Weſtminſter 3645 Buried 6207

DISEASES and CASUALTIES.

Abortive and Stilborn 530	Fiſtula —— —— 17	Riſing of the Lights— 6	Died by the Bite of a mad Dog — } 1
Aged — ——2131	Flux —— —— 27	St Anthony's Fire—— 1	Drowned — —— 104
Ague —— — 8	French Pox -—— 104	Scald Head — —— 5	Exceſſive Drinking — 36
Apoplexy and Suddenly 235	Gout —— —— 54	Scurvy — —— 2	Executed — —— 17
Aſthma and Tiſſick — 585	Gravel, Stone, and Strangury — } 41	Small Pox —— —1429	Found dead — —— 67
Bedridden — —— 8	Grief —— —— 12	Sores and Ulcers —— 19	Found hang'd —— 1
Bloody Flux -—— 19	Headmoldſhot, Horſhoehead, and Water in the Head } 118	Sore Throat — —— 1	Fractured Skull — — 3
Burſten and Rupture-- 19		Stoppage in the Stomach 117	Killed by Falls and ſeveral other Accidents — } 39
Cancer — —— 40		Surfeit — —— 4	
Canker —— —— 9		Swelling —— —— 4	
Childbed — —— 203	Jaundies —— —— 155	Teeth —— ——1358	Made away themſelves 33
Cold —— —— 2	Impoſthume —— 24	Thruſh — —— 128	Murdered —— —— 11
Colick, Gripes, and Twiſting of the Guts —— } 109	Inflammation —— 51	Tympany —— —— 3	Overlaid — —— 63
	Leproſy —— —— 5	Vomiting and Looſneſs 12	Poiſoned —— — 1
	Lethargy — —— 10	Worms — —— 14	Scalded —— — 4
Conſumption ——4716	Livergrown —— 3		Shot —— —— 3
Convulſion -——6820	Lunatick —— — 80		Smothered — —— 1
Cough and Hooping Cough —— } 122	Meaſles — —— 981	CASUALTIES.	Stabbed —— —— 1
	Miſcarriage —— 3		Starved — —— 12
Diabetes — —— 1	Mortification —— 271	Broken Limbs —— 6	Suffocated — —— 9
Dropſy —— ——1110	Palſy —— —— 53	Bruiſed -—— 2	
Evil —— —— 24	Piles —— —— 1	Burnt —— —— 3	Total 426
Falling Sickneſs —— 1	Pleuriſy — —— 52	Choaked —— — 3	
Fever, Malignant Fever, Scarlet Fever, Spotted Fever, and Purples —— } 5108	Quinſy —— — 21	Cruſh'd — —— 4	
	Rheumatiſm —— 24	Died in the Street—— 2	
	Rickets —— —— 47		

CHRISTENED	Males — 7048	BURIED	Males — 13565
	Females 6703		Females 13918
	In all — 13751		In all — 27483

Decreaſed in the Burials this Year 4686

Whereof have died,

Under Two Years of Age 9030	Thirty and Forty — 2813	Eighty and Ninety — 582	A Hundred and Four — 2
Between Two and Five— 2642	Forty and Fifty — 2959	Ninety and a Hundred 100	A Hundred and Five — 1
Five and Ten —— 1035	Fifty and Sixty —— 2333	A Hundred —— 1	A Hundred and Seven— 1
Ten and Twenty —— 893	Sixty and Seventy — 1634	A Hundred and One 1	A Hundred and Ten— 1
Twenty and Thirty —— 2203	Seventy and Eighty 1250	A Hundred and Two 2	

1744.

A General BILL of all the Chriſtenings and Burials,

From the 13th of December 1743, to the 11th of December 1744.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	15
Alhallows Barkin	70
Alhallows in Bread-ſtreet	10
Alhallows the Great	58
Alhallows in Honey-lane	1
Alhallows the Leſs	13
Alhallows in Lombard-ſtreet	17
Alhallows Staining	13
Alhallows on London Wall	34
St Alphage near Sion College	22
St Andrew Hubbard	12
St Andrew Underſhaft	23
St Andrew Wardrobe	53
St Ann within Alderſgate	26
St Ann in Black Friars	136
St Anthony, vulg. Antholin	2
St Auguſtin, vulg. Auſtin	9
St Bartholomew by Exchange	19
St Benedict, v. Bennet Fink	15
St Bennet Gracechurch	12
St Bennet at Paul's Wharf	35
St Bennet Sherehog	2
St Botolph at Billinſgate	10
Chriſt Church Pariſh	83
St Chriſtopher's Pariſh	9
St Clement near Eaſtcheap	3
St Dionis Backchurch	22
St Dunſtan in the Eaſt	47
St Edmund the King	13
St Ethelburga's Pariſh	20
St Faith under St Paul's	23
St Gabriel in Fenchurch-ſtr.	4
St George in Botolph-lane	13
St Gregory by St Paul's	51
St Helen near Biſhopſgate	21
St James in Duke's Place	18
St James at Garlickhithe	14
St John Baptiſt by Dowgate	22
St John the Evangeliſt	4
St John Zachary	12
St Katherine Coleman	34
St Katherine Creechurch	23
St Laurence Jewry	18
St Laurence Pountney	6
St Leonard in Eaſtcheap	10
St Leonard in Foſter-lane	13
St Magnus by London Bridge	24
St Margaret in Lothbury	22
St Margaret Moſes	2
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattons	10
St Martin Ironmonger-lane	8
St Martin at Ludgate	6
St Martin Orgars	10
St Martin Outwich	3
St Martin Vintrey	33
St Mary Abchurch	16
St Mary in Aldermanbury	25
St Mary Aldermary	15
St Mary le Bow in Cheapſide	18
St Mary Bothaw at Dowgate	6
St Mary Colechurch	0
St Mary Hill by Billinſgate	34
St Mary Magd. in Milk-ſtr.	0
St Mary Magd. Old Fiſh-ſtr.	29
St Mary Mounthaw	8
St Mary Somerſet	26
St Mary Staining	10
St Mary Woolchurch	1
St Mary Woolnoth	6
St Matthew in Friday-ſtreet	7
St Michael Baſſiſhaw	25
St Michael in Cornhill	25
St Michael in Crooked-lane	17
St Michael at Queenhithe	25
St Michael at Quern	8
St Michael Royal	14
St Michael in Wood-ſtreet	1
St Mildred in Bread-ſtreet	7
St Mildred in the Poultry	4
St Nicholas Acons	8
St Nicholas Coleabby	3
St Nicholas Olave	4
St Olave in Hart-ſtreet	23
St Olave in the Old Jewry	4
St Olave in Silver-ſtreet	16
St Pancras in Pancras-lane	6
St Peter in Cheapſide	3
St Peter in Cornhill	20
St Peter near Paul's Wharf	14
St Peter Poor in Broad-ſtr.	12
St Stephen in Coleman-ſtreet	56
St Stephen in Walbrook	11
St Swithin at London-ſtone	11
St Thomas the Apoſtle	13
Trinity Pariſh	7
St Vedaſt, alias Foſter	22

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1044 Buried 1768

St Andrew in Holborn	819
St Bartholomew the Great	71
St Bartholomew the Leſs	10
St Botolph by Alderſgate	182
St Botolph by Aldgate	580
St Botolph by Biſhopſgate	424
Bridewell Precinct	2
St Bridget, vulg. St Bride's	181
St Dunſtan in the Weſt	139
St George in Southwark	224
St Giles by Cripplegate	499
St John in Southwark	303
St Olave in Southwark	349
St Saviour in Southwark	541
St Sepulchre's Pariſh	473
St Thomas in Southwark	182
Trinity in the Minories	32
The Peſt-houſe	

Chriſtened in the ſeventeen Pariſhes without the Walls 3966 Buried 5011

St Ann at Limehouſe —188	St George by Queen's ſquare 328	St Mary at Iſlington — —235
Chriſt Church in Surrey —156	St James at Clerkenwell —543	St Mary at Lambeth —464
Chriſt Church in Middleſex 710	St John at Hackney —222	St Mary Magd. Bermondſey 484
St Dunſtan at Stepney—1027	St John at Wapping —269	St Mary at Newington —290
St Giles in the Fields —944	St Katherine near the Tower 212	St Mary at Rotherhith —223
St George in Bloomſbury —597	St Leonard in Shoreditch —800	St Mary in Whitechapel—1136
St George in Middleſex - —585	St Luke in Middleſex—1071	St Paul at Shadwell —439

Chriſtened in the twenty-one Out Pariſhes in Middleſex and Surrey 5962 Buried 10923

St Ann in Weſtminſter - —657	St James in Weſtminſter—1163	St Mary le Strand — 107
St Clement Danes — —412	St Margaret in Weſtminſt. 981	The Precinct of the Savoy 90
St George by Hanover-ſqu. 805	St Martin in the Fields —1263	St Paul in Covent Garden 311
St John the Evangeliſt - —100		

Chriſtened in the ten Pariſhes in the City and Liberties of Weſtminſter 3790 Buried 5889

DISEASES and CASUALTIES.

Abortive and Stilborn	601	Fiſtula	10	Riſing of the Lights	5	Found dead	56
Aged	2429	Flux	23	St Anthony's Fire	4	Fractured Skull	3
Ague	5	French Pox	64	Scald Head	1	Killed by Falls and ſeveral other Accidents	54
Apoplexy and Suddenly	237	Gout	54	Small Pox	2029		
Aſthma and Tiſſick	611	Gravel, Stone, and Strangury	34	Sores and Ulcers	14	Killed in the Pillory	1
Bedridden	5	Grief	3	Stoppage in the Stomach	83	Made away themſelves	41
Bleeding	2	Headmoldſhot, Horſhoehead, and Water in the Head	124	Surfeit	1	Murdered	6
Bloody Flux	7			Swelling	4	Overlaid	75
Burſten and Rupture	21			Teeth	1121	Poiſoned	1
Cancer	61	Jaundies	134	Thruſh	89	Scalded	6
Canker	8	Impoſthume	29	Tympany	1	Shot accidentally	2
Childbed	176	Inflammation	60	Worms	10	Smothered	2
Cold	9	Itch	5			Stabbed	1
Colick, Gripes, and Twiſting of the Guts	136	Leproſy	4			Starved	5
		Lethargy	7			Suffocated	4
Conſumption	4353	Lunatick	75				
Convulſion	6761	Meaſles	17			Total	404
Cough and Hooping Cough	92	Miſcarriage	3				
		Mortification	206				
Diabetes	1	Palſy	40				
Dropſy	1043	Pleuriſy	51				
Evil	21	Quinſy	29				
Fever, Malignant Fever, Scarlet Fever, Spotted Fever, and Purples	3837	Raſh	4				
		Rheumatiſm	15				
		Rickets	27				

CASUALTIES.

Broken Limbs	5	Burnt	12
Bruiſed	6	Choaked with Fat	1
Died by the Bite of a mad Dog	3	Drowned	78
		Exceſſive Drinking	36
		Executed	6

CHRISTENED	Males — 7726	BURIED	Males — 12181
	Females 7324		Females 13019
	In all 15050		In all — 25200

Decreaſed in the Burials this Year 2283

Whereof have died,

Under Two Years of Age	8621	Thirty and Forty	2342	Eighty and Ninety	629	A Hundred and Three	3
Between Two and Five	1955	Forty and Fifty	2611	Ninety and a Hundred	93	A Hundred and Four	3
Five and Ten	947	Fifty and Sixty	2004	A Hundred	3	A Hundred and Five	2
Ten and Twenty	813	Sixty and Seventy	1729	A Hundred and One	1	A Hundred and Six	1
Twenty and Thirty	1935	Seventy and Eighty	1507	A Hundred and Two	1		

1745.

A General BILL of all the Chriſtenings and Burials,

From the 11th of December 1744, to the 10th of December 1745.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	27
Alhallows Barkin	55
Alhallows in Bread-ſtreet	7
Alhallows the Great	39
Alhallows in Honey-lane	0
Alhallows the Leſs	15
Alhallows in Lombard-ſtreet	24
Alhallows Staining	15
Alhallows on London Wall	46
St Alphage near Sion College	13
St Andrew Hubbard	3
St Andrew Underſhaft	29
St Andrew Wardrobe	47
St Ann within Alderſgate	32
St Ann in Black Friars	128
St Anthony, vulg. Antholin	5
St Auguſtin, vulg. Auſtin	9
St Bartholomew by Exchange	19
St Benedict, v. Bennet Fink	10
St Bennet Gracechurch	4
St Bennet at Paul's Wharf	37
St Bennet Sherehog	0
St Botolph at Billinſgate	5
Chriſt Church Pariſh	93
St Chriſtopher's Pariſh	6
St Clement near Eaſtcheap	7
St Dionis Backchurch	26
St Dunſtan in the Eaſt	49
St Edmund the King	12
St Ethelburga's Pariſh	21
St Faith under St Paul's	17
St Gabriel in Fenchurch-ſtr.	10
St George in Botolph-lane	11
St Gregory by St Paul's	53
St Helen near Biſhopſgate	25
St James in Duke's Place	15
St James at Garlickhithe	18
St John Baptiſt by Dowgate	18
St John the Evangeliſt	1
St John Zachary	15
St Katherine Coleman	37
St Katherine Creechurch	38
St Laurence Jewry	12
St Laurence Pountney	13
St Leonard in Eaſtcheap	4
St Leonard in Foſter-lane	15
St Magnus by London Bridge	13
St Margaret in Lothbury	21
St Margaret Moſes	1
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattons	9
St Martin Ironmonger-lane	10
St Martin at Ludgate	11
St Martin Orgars	15
St Martin Outwich	10
St Martin Vintrey	29
St Mary Abchurch	15
St Mary in Aldermanbury	24
St Mary Aldermary	23
St Mary le Bow in Cheapſide	10
St Mary Bothaw at Dowgate	6
St Mary Colechurch	0
St Mary Hill by Billinſgate	25
St Mary Magd. in Milk-ſtr.	2
St Mary Magd. Old Fiſh-ſtr.	23
St Mary Mounthaw	4
St Mary Somerſet	21
St Mary Staining	9
St Mary Woolchurch	0
St Mary Woolnoth	9
St Matthew in Friday-ſtreet	2
St Michael Baſſiſhaw	24
St Michael in Cornhill	23
St Michael in Crooked-lane	13
St Michael at Queenhithe	28
St Michael at Quern	8
St Michael Royal	8
St Michael in Wood-ſtreet	3
St Mildred in Bread-ſtreet	3
St Mildred in the Poultry	10
St Nicholas Acons	2
St Nicholas Coleabby	8
St Nicholas Olave	3
St Olave in Hart-ſtreet	25
St Olave in the Old Jewry	5
St Olave in Silver-ſtreet	13
St Pancras in Pancras-lane	2
St Peter in Cheapſide	5
St Peter in Cornhill	15
St Peter near Paul's Wharf	11
St Peter Poor in Broad-ſtr.	10
St Stephen in Coleman-ſtreet	74
St Stephen in Walbrook	15
St Swithin at London-ſtone	16
St Thomas the Apoſtle	6
Trinity Pariſh	19
St Vedaſt, alias Foſter	20

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1104 Buried 1766

St Andrew in Holborn	840
St Bartholomew the Great	53
St Bartholomew the Leſs	10
St Botolph by Alderſgate	170
St Botolph by Aldgate	600
St Botolph by Biſhopſgate	403
Bridewell Precinct	0
St Bridget, vulg. St Bride's	216
St Dunſtan in the Weſt	134
St George in Southwark	250
St Giles by Cripplegate	443
St John in Southwark	323
St Olave in Southwark	401
St Saviour in Southwark	491
St Sepulchre's Pariſh	506
St Thomas in Southwark	155
Trinity in the Minories	22
The Peſt-houſe	-

Chriſtened in the ſeventeen Pariſhes without the Walls 3846 Buried 5077

1745.

St Ann at Limehouſe ——216	St George by Queen's ſquare 260	St Mary at Iſlington — —207
Chriſt Church in Surrey —143	St James at Clerkenwell —386	St Mary at Lambeth — —384
Chriſt Church in Middleſex 661	St John at Hackney ——160	St Mary Magd. Bermondſey 402
St Dunſtan at Stepney ——793	St John at Wapping ——237	St Mary at Newington ——303
St Giles in the Fields ——752	St Katherine near the Tower 178	St Mary at Rotherhith ——257
St George in Bloomſbury—384	St Leonard in Shoreditch—770	St Mary in Whitechapel—1005
St George in Middleſex -—509	St Luke in Middleſex —1017	St Paul at Shadwell ——344

Chriſtened in the twenty-one Out Pariſhes in Middleſex and Surrey 5644 Buried 9368

St Ann in Weſtminſter - —640	St James in Weſtminſter —972	St Mary le Strand —— 80
St Clement Danes — ——298	St Margaret in Weſtminſt. 838	The Precinct of the Savoy 126
St George by Hanover-ſqu.665	St Martin in the Fields —1106	St Paul in Covent Garden 464
St John the Evangeliſt - — 96		

Chriſtened in the ten Pariſhes in the City and Liberties of Weſtminſter 3484 Buried 5085

DISEASES and CASUALTIES.

Abortive and Stilborn 512	Fiſtula —— —— 12	Rheumatiſm — — 13	Casualties.
Aged —— ——1843	Flux —— —— 34	Rickets — —— 40	
Ague —— —— 6	French Pox — —— 76	Riſing of the Lights— 4	Broken Limbs —— 10
Apoplexy and Suddenly 211	Gout —— —— 55	St Anthony's Fire -— 1	Bruiſed —— — 4
Aſthma and Tiſſick — 533	Gravel, Stone, and Strangury — 36	Scald Head -—— 4	Burnt —— —— 11
Bedridden — —— 7		Sciatica —— — 1	Choaked with Fat -— 2
Bleeding —— — 2	Grief —— —— 11	Small Pox — ——1206	Drowned — —— 99
Bloody Flux —— 15	Headmoldſhot, Horſhoehead, and Water in the Head 154	Sores and Ulcers —— 21	Exceſſive Drinking — 41
Burſten and Rupture-- 17		Sore Throat — —— 1	Executed — —— 17
Cancer — —— 46		Stoppage in the Stomach 112	Found dead —— — 52
Canker —— —— 1	Jaundies —— —— 128	Surfeit — —— 5	Fractured Skulls —— 10
Childbed —— — 197	Impoſthume —— 22	Swelling —— —— 7	Frighted — —— 1
Colick, Gripes, and Twiſting of the Guts —— 135	Inflammation —— — 62	Teeth — ——1048	Killed by Falls and ſeveral other Accidents — 46
	Itch —— —— 4	Thruſh —— —— 152	
Conſumption ——4015	Leproſy —— —— 3	Tympany — —— 2	Murdered — —— 3
Convulſion — ——5728	Lethargy — —— 5	Vapours — —— 1	Overlaid —— — 80
Cough and Hooping Cough — 135	Livergrown — — 1	Vomiting and Looſneſs 2	Poiſoned —— —— 1
	Lunatick — —— 75	Worms — —— 13	Scalded — —— 4
Diabetes — —— 1	Meaſles —— — 14		Self-Murder —— 32
Dropſy —— —1094	Miſcarriage — —— 2		Smothered —— — 2
Evil —— —— 23	Mortification —— 209		Stabbed —— —— 2
Fever, Malignant Fever, Scarlet Fever, Spotted Fever, and Purples —— 2690	Palſy —— —— 41		Starved — —— 5
	Piles —— —— 1		Suffocated — —— 7
	Pleuriſy — —— 59		
	Quinſy —— —— 13		Total 429
	Raſh —— —— 6		

CHRISTENED		BURIED	
Males — 7278		Males — 10468	
Females 6800		Females 10828	
In all — 14078		In all — 21296	

Increaſed in the Burials this Year 690

Whereof have died,

Under Two Years of Age 7689	Thirty and Forty — 1940	Eighty and Ninety-- 437	A Hundred and Three— 1
Between Two and Five— 1631	Forty and Fifty —— 2332	Ninety and a Hundred 77	A Hundred and Four — 1
Five and Ten —— 672	Fifty and Sixty —— 1741	A Hundred — — 3	A Hundred and Five— 3
Ten and Twenty —— 626	Sixty and Seventy— 1382	A Hundred and Two 1	A Hundred and Eleven— 1
Twenty and Thirty—— 1695	Seventy and Eighty 1064		

A General

1746.

A General BILL of all the Chriſtenings and Burials,

From the 10th of December 1745, to the 11th of December 1746.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	23
Alhallows Barkin	85
Alhallows in Bread-ſtreet	12
Alhallows the Great	62
Alhallows in Honey-lane	0
Alhallows the Leſs	14
Alhallows in Lombard-ſtreet	24
Alhallows Staining	20
Alhallows on London Wall	59
St Alphage near Sion College	30
St Andrew Hubbard	6
St Andrew Underſhaft	41
St Andrew Wardrobe	64
St Ann within Alderſgate	42
St Ann in Black Friars	171
St Anthony, vulg. Antholin	5
St Auguſtin, vulg. Auſtin	7
St Bartholomew by Exchange	14
St Benedict, v. Bennet Fink	14
St Bennet Gracechurch	11
St Bennet at Paul's Wharf	26
St Bennet Sherehog	0
St Botolph at Billinſgate	10
Chriſt Church Pariſh	104
St Chriſtopher's Pariſh	11
St Clement near Eaſtcheap	8
St Dionis Backchurch	41
St Dunſtan in the Eaſt	51
St Edmund the King	13
St Ethelburga's Pariſh	33
St Faith under St Paul's	25
St Gabriel in Fenchurch-ſtr.	9
St George in Botolph-lane	13
St Gregory by St Paul's	87
St Helen near Biſhopſgate	41
St James in Duke's Place	27
St James at Garlickhithe	26
St John Baptiſt by Dowgate	29
St John the Evangeliſt	2
St John Zachary	21
St Katherine Coleman	38
St Katherine Creechurch	68
St Laurence Jewry	26
St Laurence Pountney	15
St Leonard in Eaſtcheap	13
St Leonard in Foſter-lane	17
St Magnus by London Bridge	28
St Margaret in Lothbury	22
St Margaret Moſes	3
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattons	15
St Martin Ironmonger-lane	9
St Martin at Ludgate	25
St Martin Orgars	19
St Martin Outwich	9
St Martin Vintrey	43
St Mary Abchurch	10
St Mary in Aldermanbury	41
St Mary Aldermary	23
St Mary le Bow in Cheapſide	15
St Mary Bothaw at Dowgate	9
St Mary Colechurch	0
St Mary Hill by Billinſgate	29
St Mary Magd. in Milk-ſtr.	0
St Mary Magd. Old Fiſh-ſtr.	29
St Mary Mounthaw	13
St Mary Somerſet	38
St Mary Staining	13
St Mary Woolchurch	0
St Mary Woolnoth	10
St Matthew in Friday-ſtreet	6
St Michael Baſſiſhaw	38
St Michael in Cornhill	27
St Michael in Crooked-lane	28
St Michael at Queenhithe	42
St Michael at Quern	11
St Michael Royal	12
St Michael in Wood-ſtreet	2
St Mildred in Bread-ſtreet	16
St Mildred in the Poultry	9
St Nicholas Acons	8
St Nicholas Coleabby	11
St Nicholas Olave	7
St Olave in Hart-ſtreet	38
St Olave in the Old Jewry	12
St Olave in Silver-ſtreet	25
St Pancras in Pancras-lane	3
St Peter in Cheapſide	6
St Peter in Cornhill	24
St Peter near Paul's Wharf	14
St Peter Poor in Broad-ſtr.	14
St Stephen in Coleman-ſtreet	59
St Stephen in Walbrook	19
St Swithin at London-ſtone	23
St Thomas the Apoſtle	8
Trinity Pariſh	20
St Vedaſt, alias Foſter	35

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1058 Buried 2378

St Andrew in Holborn	1168
St Bartholomew the Great	104
St Bartholomew the Leſs	23
St Botolph by Alderſgate	268
St Botolph by Aldgate	827
St Botolph by Biſhopſgate	537
Bridewell Precinct	0
St Bridget, vulg. St Bride's	259
St Dunſtan in the Weſt	209
St George in Southwark	347
St Giles by Cripplegate	622
St John in Southwark	370
St Olave in Southwark	430
St Saviour in Southwark	698
St Sepulchre's Pariſh	648
St Thomas in Southwark	212
Trinity in the Minories	25
The Peſt-houſe	

Chriſtened in the ſeventeen Pariſhes without the Walls 4015 Buried 6747

St Ann at Limehouſe —204	St James at Clerkenwell —622	St Mary at Lambeth —529
Chriſt Church in Surrey —228	St John at Hackney —216	St Mary Magd. Bermondſey 468
Chriſt Church in Middleſex 733	St John at Wapping —338	St Mary at Newington —376
St Dunſtan at Stepney —803	St Katherine near the Tower 216	St Mary at Rotherhith —249
St George in Bloomſbury —500	St Leonard in Shoreditch —932	St Mary in Whitechapel—1297
St George in Middleſex —824	St Luke in Middleſex —1313	St Matthew at Bethnal Green 252
St George by Queen's ſquare 411	St Mary at Iſlington —270	St Paul at Shadwell —530
St Giles in the Fields —1255		

Chriſtened in the twenty-two Out Pariſhes in Middleſex and Surrey 5533 Buried 12566

St Ann in Weſtminſter —898	St James in Weſtminſter 1237	St Mary le Strand — 79
St Clement Danes — —459	St Margaret in Weſtminſt. 1046	The Precinct of the Savoy 191
St George by Hanover-ſqu. 818	St Martin in the Fields —1316	St Paul in Covent Garden 354
St John the Evangeliſt— 68		

Chriſtened in the ten Pariſhes in the City and Liberties of Weſtminſter 3971 Buried 6466

DISEASES and CASUALTIES.

Abortive and Stilborn	541	Fiſtula	14	Rheumatiſm	22
Aged	2424	Flux	40	Rickets	39
Ague	15	French Pox	100	Riſing of the Lights	5
Apoplexy and Suddenly	253	Gout	60	St Anthony's Fire	1
Aſthma and Tiſſick	553	Gravel, Stone, and Strangury	24	Scald Head	2
Bedridden	5	Grief	5	Scurvy	3
Bleeding	4	Headmoldſhot, Horſhoehead, and Water in the Head	148	Small Pox	3236
Bloody Flux	21	Jaundies	130	Sores and Ulcers	28
Burſten and Rupture	17	Impoſthume	19	Sore Throat	1
Cancer	50	Inflammation	88	Stoppage in the Stomach	102
Canker	3	Itch	6	Surfeit	5
Childbed	188	Leproſy	5	Swelling	3
Colick, Gripes, and Twiſting of the Guts	119	Lethargy	4	Teeth	1309
Conſumption	4887	Livergrown	2	Thruſh	121
Convulſion	6952	Lunatick	90	Tympany	2
Cough and Hooping Cough	95	Meaſles	250	Vapours	2
Dropſy	1196	Miſcarriage	3	Vomiting and Looſneſs	7
Evil	20	Mortification	251	Worms	12
Fever, Malignant Fever, Scarlet Fever, Spotted Fever, and Purples	4167	Palſy	61		
		Pleuriſy	43		
		Quinſy	17		
		Raſh	3		

Choaked	1	Killed by fighting	2
Died by the Bite of a mad Dog	1	Murdered	7
Drowned	94	Overlaid	51
Exceſſive Drinking	28	Scalded	5
Executed	20	Self-Murder	34
Found dead	52	Shot accidentally	4
Fractures	5	Stabbed	4
Frighted	2	Starved	11
Killed by Falls and ſeveral other Accidents	42	Suffocated	6
		Total	384

CASUALTIES.

Broken Limbs	6		
Bruiſed	1		
Burnt	8		

CHRISTENED	Males — 7573	BURIED	Males — 13771
	Females 7004		Females 14386
	In all — 14577		In all — 28157

Increaſed in the Burials this Year 6861.

Whereof have died,

Under Two Years of Age	9503	Thirty and Forty	2728	Seventy and Eighty	1444	A Hundred and One	1
Between Two and Five	2611	Forty and Fifty	2876	Eighty and Ninety	625	A Hundred and Three	3
Five and Ten	1089	Fifty and Sixty	2243	Ninety and a Hundred	78	A Hundred and Five	1
Ten and Twenty	895	Sixty and Seventy	1699	A Hundred	4	A Hundred and Six	1
Twenty and Thirty	2356						

1747.

A General BILL of all the Chriſtenings and Burials,

From the 10th of December 1746, to the 15th of December 1747.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	26
Alhallows Barkin	80
Alhallows in Bread-ſtreet	7
Alhallows the Great	47
Alhallows in Honey-lane	0
Alhallows the Leſs	26
Alhallows in Lombard-ſtreet	14
Alhallows Staining	29
Alhallows on London Wall	43
St Alphage near Sion College	34
St Andrew Hubbard	9
St Andrew Underſhaft	38
St Andrew Wardrobe	59
St Ann within Alderſgate	42
St Ann in Black Friars	142
St Anthony, vulg. Antholin	2
St Auguſtin, vulg. Auſtin	7
St Bartholomew by Exchange	19
St Benedict, v. Bennet Fink	19
St Bennet Gracechurch	8
St Bennet at Paul's Wharf	43
St Bennet Sherehog	1
St Botolph at Billinſgate	3
Chriſt Church Pariſh	110
St Chriſtopher's Pariſh	8
St Clement near Eaſtcheap	11
St Dionis Backchurch	33
St Dunſtan in the Eaſt	56
St Edmund the King	16
St Ethelburga's Pariſh	37
St Faith under St Paul's	19
St Gabriel in Fenchurch-ſtr.	17
St George in Botolph-lane	11
St Gregory by St Paul's	62
St Helen near Biſhopſgate	30
St James in Duke's Place	18
St James at Garlickhithe	25
St John Baptiſt by Dowgate	25
St John the Evangeliſt	2
St John Zachary	19
St Katherine Coleman	44
St Katherine Creechurch	50
St Laurence Jewry	28
St Laurence Pountney	12
St Leonard in Eaſtcheap	14
St Leonard in Foſter-lane	23
St Magnus by London Bridge	20
St Margaret in Lothbury	20
St Margaret Moſes	3
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattons	9
St Martin Ironmonger-lane	9
St Martin at Ludgate	15
St Martin Orgars	15
St Martin Outwich	8
St Martin Vintrey	42
St Mary Abchurch	21
St Mary in Aldermanbury	17
St Mary Aldermary	18
St Mary le Bow in Cheapſide	15
St Mary Bothaw at Dowgate	5
St Mary Colechurch	0
St Mary Hill by Billinſgate	40
St Mary Magd. in Milk-ſtr.	0
St Mary Magd. Old Fiſh-ſtr.	25
St Mary Mounthaw	10
St Mary Somerſet	22
St Mary Staining	12
St Mary Woolchurch	0
St Mary Woolnoth	9
St Matthew in Friday-ſtreet	4
St Michael Baſſiſhaw	27
St Michael in Cornhill	17
St Michael in Crooked-lane	18
St Michael at Queenhithe	20
St Michael at Quern	20
St Michael Royal	14
St Michael in Wood-ſtreet	2
St Mildred in Bread-ſtreet	4
St Mildred in the Poultry	9
St Nicholas Acons	5
St Nicholas Coleabby	9
St Nicholas Olave	6
St Olave in Hart-ſtreet	21
St Olave in the Old Jewry	5
St Olave in Silver-ſtreet	21
St Pancras in Pancras-lane	5
St Peter in Cheapſide	3
St Peter in Cornhill	14
St Peter near Paul's Wharf	9
St Peter Poor in Broad-ſtr.	7
St Stephen in Coleman-ſtreet	60
St Stephen in Walbrook	16
St Swithin at London-ſtone	16
St Thomas the Apoſtle	10
Trinity Pariſh	8
St Vedaſt, alias Foſter	21

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1092 Buried 2074

St Andrew in Holborn	822
St Bartholomew the Great	96
St Bartholomew the Leſs	22
St Botolph by Alderſgate	222
St Botolph by Aldgate	793
St Botolph by Biſhopſgate	461
Bridewell Precinct	0
St Bridget, vulg. St Bride's	231
St Dunſtan in the Weſt	181
St George in Southwark	307
St Giles by Cripplegate	547
St John in Southwark	308
St Olave in Southwark	405
St Saviour in Southwark	606
St Sepulchre's Pariſh	587
St Thomas in Southwark	181
Trinity in the Minories	31

Chriſtened in the ſeventeen Pariſhes without the Walls 4214 Buried 5800

St Ann in Middleſex——215	St James at Clerkenwell —529	St Mary at Lambeth — —479
Chriſt Church in Surrey —192	St John at Hackney ——223	St Mary Magd. Bermondſey 460
Chriſt Church in Middleſex 754	St John at Wapping ——395	St Mary at Newington ——317
St Dunſtan at Stepney ——435	St Katherine near the Tower 188	St Mary at Rotherhith ——276
St George in Bloomſbury—420	St Leonard in Shoreditch 1027	St Mary in Whitechapel—1207
St George in Middleſex -—681	St Luke in Middleſex —1120	St Matthew at Bethnal Green 583
St George by Queen's ſquare 352	St Mary at Iſlington — —275	St Paul at Shadwell ——476
St Giles in the Fields ——1072		

Chriſtened in the twenty-two Out Pariſhes in Middleſex and Surrey 5621 Buried 11676

St Ann in Weſtminſter - —716	St John the Evangeliſt - — 90	St Mary le Strand —— 78
St Clement Danes — ——363	St Margaret in Weſtminſt. 979	The Precinct of the Savoy 151
St George by Hanover-ſqu.998	St Martin in the Fields —1124	St Paul in Covent Garden 309
St James in Weſtminſter 1136		

Chriſtened in the ten Pariſhes in the City and Liberties of Weſtminſter 4015 Buried 5944

DISEASES and CASUALTIES.

Abortive and Stilborn	554	Fever, Malignant Fever, Scarlet Fever, Spotted Fever, and Purples	4779	Mortification ——	227	BIT by a mad Dog	1
Aged —— ——2010		Fiſtula —— ——	13	Palſy —— ——	52	Broken Limbs ——	4
Ague —— ——	8	Flux —— ——	28	Pleuriſy — ——	31	Bruiſed —— —	1
Apoplexy and Suddenly	194	French Pox — ——	69	Quinſy —— ——	24	Burnt —— ——	13
Aſthma and Tiſſick —	416	Gout —— ——	52	Raſh —— ——	8	Choaked with Fat -—	1
Bedridden — ——	2	Grief —— ——	6	Rheumatiſm — —	10	Drowned — ——	102
Bleeding —— —	3	Gravel, Stone, and Strangury —	31	Rickets — ——	36	Exceſſive Drinking —	38
Bloody Flux ——	6	Headmoldſhot, Horſhoehead, and Water in the Head	150	Riſing of the Lights—	4	Executed — ——	7
Burſten and Rupture--	18	Jaundies —— ——	139	Scald Head -——	1	Found dead —— —	35
Cancer — ——	47	Impoſthume ——	12	Scurvy —— ——	5	Fractures — ——	15
Canker —— ——	4	Inflammation —— —	53	Small Pox — ——1380		Frighted — ——	2
Childbed —— —	207	Itch —— ——	6	Sore Throat — ——	6	Killed by Falls and ſeveral other Accidents —	53
Colick, Gripes, and Twiſting of the Guts ——	160	Leproſy —— ——	6	Sores and Ulcers ——	28	Murdered — ——	7
Cold —— ——	2	Lethargy — ——	3	St Anthony's Fire -—	4	Overlaid —— —	41
Conſumption ——4560		Livergrown — —	1	Stoppage in the Stomach	81	Scalded — ——	4
Convulſion — —6783		Lunatick — ——	53	Surfeit — ——	5	Self-Murder ——	45
Cough and Hooping Cough —	151	Meaſles —— —	81	Swelling —— ——	3	Smothered —— —	1
Diabetes — ——	3	Miſcarriage — ——	6	Teeth — ——1283		Starved — ——	5
Dropſy — ——1133				Thruſh —— ——	144		
Evil —— ——	17			Vomiting and Looſneſs	11	Total	375
Falling Sickneſs ——	2			Worms — ——	8		

***

CHRISTENED	Males — 7737	BURIED	Males — 12417
	Females 7205		Females 13077
	In all — 14942		In all — 25494

Whereof have died,

Under Two Years of Age	8741	Thirty and Forty —	2649	Eighty and Ninety--	520	A Hundred and Two—	1
Between Two and Five—	2085	Forty and Fifty ——	2717	Ninety and a Hundred	68	A Hundred and Five—	1
Five and Ten ——	905	Fifty and Sixty ——	2079	A Hundred — —	2	A Hundred and Six —	1
Ten and Twenty ——	790	Sixty and Seventy—	1544	A Hundred and One	1	A Hundred and Seven—	1
Twenty and Thirty——	2190	Seventy and Eighty	1199				

Decreaſed in the Burials this Year 2663

1748.

A General BILL of all the Chriſtenings and Burials,

From the 15th of December 1747, to the 13th of December 1748.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	34
Alhallows Barkin	71
Alhallows in Bread-ſtreet	7
Alhallows the Great	31
Alhallows in Honey-lane	0
Alhallows the Leſs	23
Alhallows in Lombard-ſtreet	17
Alhallows Staining	16
Alhallows on London Wall	67
St Alphage near Sion College	29
St Andrew Hubbard	3
St Andrew Underſhaft	35
St Andrew Wardrobe	59
St Ann within Alderſgate	33
St Ann in Black Friars	126
St Anthony, vulg. Antholin	11
St Auguſtin, vulg. Auſtin	2
St Bartholomew by Exchange	17
St Benedict, v. Bennet Fink	20
St Bennet Gracechurch	10
St Bennet at Paul's Wharf	35
St Bennet Sherehog	0
St Botolph at Billinſgate	9
Chriſt Church Pariſh	81
St Chriſtopher's Pariſh	5
St Clement near Eaſtcheap	10
St Dionis Backchurch	22
St Dunſtan in the Eaſt	55
St Edmund the King	14
St Ethelburga's Pariſh	29
St Faith under St Paul's	9
St Gabriel in Fenchurch-ſtr.	12
St George in Botolph-lane	7
St Gregory by St Paul's	69
St Helen near Biſhopſgate	37
St James in Duke's Place	19
St James at Garlickhithe	19
St John Baptiſt by Dowgate	21
St John the Evangeliſt	3
St John Zachary	19
St Katherine Coleman	42
St Katherine Creechurch	43
St Laurence Jewry	17
St Laurence Pountney	14
St Leonard in Eaſtcheap	16
St Leonard in Foſter-lane	17
St Magnus by London Bridge	33
St Margaret in Lothbury	16
St Margaret Moſes	1
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattons	10
St Martin Ironmonger-lane	13
St Martin at Ludgate	24
St Martin Orgars	13
St Martin Outwich	7
St Martin Vintrey	19
St Mary Abchurch	13
St Mary in Aldermanbury	22
St Mary Aldermary	21
St Mary le Bow in Cheapſide	8
St Mary Bothaw at Dowgate	6
St Mary Colechurch	0
St Mary Hill by Billinſgate	40
St Mary Magd. in Milk-ſtr.	0
St Mary Magd. Old Fiſh-ſtr.	20
St Mary Mounthaw	7
St Mary Somerſet	23
St Mary Staining	13
St Mary Woolchurch	2
St Mary Woolnoth	14
St Matthew in Friday-ſtreet	6
St Michael Baſſiſhaw	27
St Michael in Cornhill	19
St Michael in Crooked-lane	17
St Michael at Queenhithe	21
St Michael at Quern	2
St Michael Royal	11
St Michael in Wood-ſtreet	3
St Mildred in Bread-ſtreet	2
St Mildred in the Poultry	6
St Nicholas Acons	9
St Nicholas Coleabby	7
St Nicholas Olave	2
St Olave in Hart-ſtreet	47
St Olave in the Old Jewry	5
St Olave in Silver-ſtreet	27
St Pancras in Pancras-lane	1
St Peter in Cheapſide	7
St Peter in Cornhill	22
St Peter near Paul's Wharf	12
St Peter Poor in Broad-ſtr.	7
St Stephen in Coleman-ſtreet	49
St Stephen in Walbrook	14
St Swithin at London-ſtone	17
St Thomas the Apoſtle	15
Trinity Pariſh	6
St Vedaſt, alias Foſter	41

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1014 Buried 1962

St Andrew in Holborn	776
St Bartholomew the Great	82
St Bartholomew the Leſs	20
St Botolph by Alderſgate	222
St Botolph by Aldgate	793
St Botolph by Biſhopſgate	438
Bridewell Precinct	0
St Bridget, vulg. St Bride's	240
St Dunſtan in the Weſt	165
St George in Southwark	287
St Giles by Cripplegate	527
St John in Southwark	335
St Olave in Southwark	347
St Saviour in Southwark	581
St Sepulchre's Pariſh	525
St Thomas in Southwark	188
Trinity in the Minories	31

Chriſtened in the ſeventeen Pariſhes without the Walls 4032 Buried 5557

St Ann in Middleſex ——214	St James at Clerkenwell —532	St Mary at Lambeth — —412
Chriſt Church in Surrey —186	St John at Hackney———237	St Mary Magd. Bermondſey 457
Chriſt Church in Middleſex 681	St John at Wapping———287	St Mary at Newington ——360
St Dunſtan at Stepney ——465	St Katherine near the Tower 208	St Mary at Rotherhith ——281
St George in Bloomſbury—393	St Leonard in Shoreditch —854	St Mary in Whitechapel—1173
St George in Middleſex -—551	St Luke in Middleſex——1058	St Matthew at Bethnal Green 449
St George by Queen's ſquare 334	St Mary at Iſlington ———262	St Paul at Shadwell ———365
St Giles in the Fields ——1064		

Chriſtened in the twenty-two Out Pariſhes in Middleſex and Surrey 5316 Buried 10823

St Ann in Weſtminſter —539	St John the Evangeliſt - — 66	St Mary le Strand ——— 77
St Clement Danes ———371	St Margaret in Weſtminſt. 918	The Precinct of the Savoy 179
St George by Hanover-ſq. 1010	St Martin in the Fields —1009	St Paul in Covent Garden 330
St James in Weſtminſter 1028		

Chriſtened in the ten Pariſhes in the City and Liberties of Weſtminſter 3791 Buried 5527

DISEASES and CASUALTIES.

Abortive and Stilborn 481	Fever, Malignant Fever, Scarlet Fever, Spotted Fever, and Purples — 3981	Palſy —— —— 80	BIT by mad Dogs— 2
Aged — ———2127		Pleuriſy — ——— 76	Broken Limbs — 7
Ague ——— — 9		Quinſy ——— — 18	Bruiſed — ——— 7
Apoplexy and Suddenly 222		Raſh ——— —— 6	Burnt ——— —— 12
Aſthma and Tiſſick — 599	French Pox -——— 73	Rheumatiſm ——— 7	Choaked ——— — 1
Bedridden — —— 2	Gout ——— —— 47	Rickets —— —— 15	Drowned — ——— 107
Bleeding ——— — 5	Gravel, Stone, and Strangury — 32	Scald Head — ——— 2	Exceſſive Drinking — 25
Bloody Flux -——— 10		Scurvy — ——— 5	Executed — ——— 6
Burſten and Rupture-- 14	Grief ——— —— 8	Small Pox —— —1789	Found dead — —— 55
Cancer — ——— 40	Head-ach — ——— 1	Sores and Ulcers —— 18	Frighted — ——— 1
Canker —— —— 6	Headmoldſhot, Horſhoehead, and Water in the Head 93	Sore Throat — —— 5	Killed by Falls and ſeveral other Accidents — 56
Childbed — ——— 197		Stoppage in the Stomach 38	
Colick, Gripes, and Twiſting of the Guts ——— 111		Surfeit — ——— 3	Murdered — —— 4
		Swelling —— —— 1	Overlaid — ——— 37
Conſumption ———4487	Jaundies —— —— 164	Teeth —— ——1064	Scalded ——— — 1
Convulſion -———5948	Impoſthume ——— 20	Thruſh — ——— 94	Self-Murder — —— 40
Cough and Hooping Cough —— 150	Inflammation ——— 34	Tympany —— —— 1	Smothered — ——— 7
	Itch ——— —— 5	Vapours —— —— 1	Starved — ——— 3
Diabetes — ——— 2	Leproſy —— ——— 7	Vomiting and Looſneſs 11	Total 371
Dropſy —— ——1012	Lethargy — —— 6	Worms — ——— 2	
Evil —— ——— 9	Livergrown ——— 1		
Fiſtula —— ——— 5	Lunatick ——— — 59		
Flux ——— —— 47	Meaſles — ——— 10		
	Miſcarriage ——— 7		
	Mortification ——— 231		

CHRISTENED	Males — 7223	BURIED	Males — 11814
	Females 6930		Females 12055
	In all — 14153		In all — 23869

Whereof have died,

Under Two Years of Age 7637	Twenty and Thirty 2142	Sixty and Seventy— 1704	A Hundred ——— 2
Between Two and Five— 1798	Thirty and Forty — 2491	Seventy and Eighty 1187	A Hundred and One— 1
Five and Ten ——— 760	Forty and Fifty — 2700	Eighty and Ninety— 558	A Hundred and Three-- 2
Ten and Twenty —— 661	Fifty and Sixty —— 2160	Ninety and a Hundred 66	

Decreaſed in the Burials this Year 1625

A General

1749.

A General BILL of all the Chriſtenings and Burials,

From the 13th of December 1748, to the 12th of December 1749.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	34
Alhallows Barkin	66
Alhallows in Bread-ſtreet	5
Alhallows the Great	34
Alhallows in Honey-lane	0
Alhallows the Leſs	19
Alhallows in Lombard-ſtreet	17
Alhallows Staining	20
Alhallows on London Wall	40
St Alphage near Sion College	23
St Andrew Hubbard	1
St Andrew Underſhaft	38
St Andrew Wardrobe	73
St Ann within Alderſgate	35
St Ann in Black Friars	172
St Anthony, vulg. Antholin	4
St Auguſtin, vulg. Auſtin	0
St Bartholomew by Exchange	17
St Benedict, v. Bennet Fink	12
St Bennet Gracechurch	16
St Bennet at Paul's Wharf	43
St Bennet Sherehog	2
St Botolph at Billinſgate	5
Chriſt Church Pariſh	129
St Chriſtopher's Pariſh	5
St Clement near Eaſtcheap	3
St Dionis Backchurch	35
St Dunſtan in the Eaſt	55
St Edmund the King	14
St Ethelburga's Pariſh	23
St Faith under St Paul's	8
St Gabriel in Fenchurch-ſtr.	12
St George in Botolph-lane	10
St Gregory by St Paul's	73
St Helen near Biſhopſgate	32
St James in Duke's Place	12
St James at Garlickhithe	15
St John Baptiſt by Dowgate	21
St John the Evangeliſt	3
St John Zachary	12
St Katherine Coleman	19
St Katherine Creechurch	47
St Laurence Jewry	23
St Laurence Pountney	14
St Leonard in Eaſtcheap	8
St Leonard in Foſter-lane	21
St Magnus by London Bridge	31
St Margaret in Lothbury	16
St Margaret Moſes	1
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattons	16
St Martin Ironmonger-lane	11
St Martin at Ludgate	27
St Martin Orgars	13
St Martin Outwich	6
St Martin Vintrey	34
St Mary Abchurch	11
St Mary in Aldermanbury	24
St Mary Aldermary	27
St Mary le Bow in Cheapſide	15
St Mary Bothaw at Dowgate	4
St Mary Colechurch	1
St Mary Hill by Billinſgate	19
St Mary Magd. in Milk-ſtr.	0
St Mary Magd. Old Fiſh-ſtr.	24
St Mary Mounthaw	5
St Mary Somerſet	22
St Mary Staining	10
St Mary Woolchurch	0
St Mary Woolnoth	16
St Matthew in Friday-ſtreet	8
St Michael Baſſiſhaw	22
St Michael in Cornhill	11
St Michael in Crooked-lane	31
St Michael at Queenhithe	22
St Michael at Quern	8
St Michael Royal	10
St Michael in Wood-ſtreet	6
St Mildred in Bread-ſtreet	6
St Mildred in the Poultry	10
St Nicholas Acons	5
St Nicholas Coleabby	13
St Nicholas Olave	11
St Olave in Hart-ſtreet	24
St Olave in the Old Jewry	2
St Olave in Silver-ſtreet	21
St Pancras in Pancras-lane	3
St Peter in Cheapſide	5
St Peter in Cornhill	18
St Peter near Paul's Wharf	10
St Peter Poor in Broad-ſtr.	8
St Stephen in Coleman-ſtreet	44
St Stephen in Walbrook	11
St Swithin at London-ſtone	10
St Thomas the Apoſtle	11
Trinity Pariſh	10
St Vedaſt, alias Foſter	29

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1026 Buried 1972

St Andrew in Holborn	963
St Bartholomew the Great	70
St Bartholomew the Leſs	28
St Botolph by Alderſgate	247
St Botolph by Aldgate	801
St Botolph by Biſhopſgate	416
Bridewell Precinct	0
St Bridget, vulg. St Bride's	232
St Dunſtan in the Weſt	155
St George in Southwark	351
St Giles by Cripplegate	593
St John in Southwark	353
St Olave in Southwark	340
St Saviour in Southwark	758
St Sepulchre's Pariſh	620
St Thomas in Southwark	172
Trinity in the Minories	23

Chriſtened in the ſeventeen Pariſhes without the Walls 4010 Buried 6122

1749.

St Ann in Middleſex——228	St James at Clerkenwell —588	St Mary at Lambeth ——451
Chriſt Church in Surrey —222	St John at Hackney ——236	St Mary Magd. Bermondſey 436
Chriſt Church in Middleſex 642	St John at Wapping ——443	St Mary at Newington ——405
St Dunſtan at Stepney ——490	St Katherine near the Tower 218	St Mary at Rotherhith ——284
St George in Bloomſbury —486	St Leonard in Shoreditch —860	St Mary in Whitechapel—1197
St George in Middleſex - —608	St Luke in Middleſex——1129	St Matthew at Bethnal Green 469
St George by Queen's ſquare 396	St Mary at Iſlington — —309	St Paul at Shadwell ——486
St Giles in the Fields ——1157		

Chriſtened in the twenty-two Out Pariſhes in Middleſex and Surrey 5539 Buried 11740

St Ann in Weſtminſter - —462	St John the Evangeliſt - — 56	St Mary le Strand—— 84
St Clement Danes — ——437	St Margaret in Weſtminſt. 851	The Precinct of the Savoy 94
St George by Hanover-ſqu. 975	St Martin in the Fields —1184	St Paul in Covent Garden 281
St James in Weſtminſter—1258		

Chriſtened in the ten Pariſhes in the City and Liberties of Weſtminſter 3685 Buried 5682

DISEASES and CASUALTIES.

Abortive and Stilborn 611	Fever, Malignant Fever, Scarlet Fever, Spotted Fever, and Purples — 4458	Pleuriſy —— —— 36	BIT by a mad Dog 1
Aged —— ——1983		Quinſy —— —— 13	Broken Limbs —— 7
Ague —— —— 15		Raſh —— —— 6	Bruiſed —— —— 10
Apoplexy and Suddenly 239		Rheumatiſm —— — 20	Burnt —— —— 10
Aſthma and Tiſſick — 410	French Pox — —— 73	Rickets —— —— 25	Choaked with Fat - — 1
Bedridden — —— 2	Gout —— —— 48	Riſing of the Lights— 5	Drowned — —— 111
Bleeding —— —— 8	Gravel, Stone, and Strangury — 22	Scald Head — —— 5	Exceſſive Drinking — 20
Bloody Flux —— 7		Scurvy —— —— 5	Executed —— —— 26
Burſten and Rupture-- 14	Grief —— —— 7	Small Pox — ——2625	Found dead — — 45
Cancer — —— 35	Headmoldſhot, Horſhoehead, and Water in the Head 116	Sores and Ulcers —— 13	Frighted — —— 3
Canker —— —— 6		Sore Throat — —— 3	Killed by Falls and ſeveral other Accidents — 52
Childbed —— — 187		St Anthony's Fire — 4	
Colick, Gripes, and Twiſting of the Guts —— 148	Jaundies —— — 147	Stoppage in the Stomach 32	
	Impoſthume — —— 18	Surfeit —— —— 3	Murdered —— — 5
Conſumption ——4623	Inflammation — — 40	Swelling — —— 1	Overlaid —— —— 32
Convulſion — ——6128	Itch —— —— 1	Teeth —— —1147	Poiſoned — —— 13
Cough and Hooping Cough — 82	Leproſy —— — 2	Thruſh —— —— 152	Scalded —— — 2
	Lethargy — —— 9	Tympany —— — 3	Self-Murder — —— 48
Diabetes — —— 1	Livergrown —— — 2	Vomiting and Looſneſs 6	Smothered — —— 11
Dropſy —— ——1036	Lunatick — —— 62	Worms —— —— 9	Stabbed — —— 1
Evil —— —— 16	Meaſles —— — 106		Starved —— —— 9
Fiſtula —— —— 5	Miſcarriage — — — 3		Stifled — —— 1
Flux —— —— 38	Mortification —— 201		
	Palſy —— —— 86		Total 408

CHRISTENED	Males — 7288	BURIED	Males — 12663
	Females 6972		Females 12853
	In all 14260		In all — 25516

Whereof have died,

Under Two Years of Age 8504	Thirty and Forty — 2753	Eighty and Ninety — 533	A Hundred and Four — 3
Between Two and Five— 2028	Forty and Fifty — 2855	Ninety and a Hundred 68	A Hundred and Five — 3
Five and Ten — —— 794	Fifty and Sixty —— 2113	A Hundred —— 1	A Hundred and Six —— 1
Ten and Twenty —— 719	Sixty and Seventy— 1691	A Hundred and One— 2	A Hundred and Twelve 1
Twenty and Thirty —— 2291	Seventy and Eighty—1155	A Hundred and Two— 1	

Increaſed in the Burials this Year 1647

A General

1750.

A General BILL of all the Chriſtenings and Burials,

From the 12th of December 1749, to the 11th of December 1750.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	21
Alhallows Barkin	57
Alhallows in Bread-ſtreet	10
Alhallows the Great	59
Alhallows in Honey-lane	0
Alhallows the Leſs	27
Alhallows in Lombard-ſtreet	13
Alhallows Staining	14
Alhallows on London Wall	71
St Alphage near Sion College	30
St Andrew Hubbard	15
St Andrew Underſhaft	40
St Andrew Wardrobe	51
St Ann within Alderſgate	39
St Ann in Black Friars	125
St Anthony, vulg. Antholin	2
St Auguſtin, vulg. Auſtin	3
St Bartholomew by Exchange	18
St Benedict, v. Bennet Fink	26
St Bennet Gracechurch	20
St Bennet at Paul's Wharf	31
St Bennet Sherehog	0
St Botolph at Billinſgate	8
Chriſt Church Pariſh	111
St Chriſtopher's Pariſh	9
St Clement near Eaſtcheap	11
St Dionis Backchurch	31
St Dunſtan in the Eaſt	55
St Edmund the King	12
St Ethelburga's Pariſh	32
St Faith under St Paul's	5
St Gabriel in Fenchurch-ſtr.	19
St George in Botolph-lane	8
St Gregory by St Paul's	51
St Helen near Biſhopſgate	30
St James in Duke's Place	15
St James at Garlickhithe	31
St John Baptiſt by Dowgate	15
St John the Evangeliſt	3
St John Zachary	10
St Katherine Coleman	38
St Katherine Creechurch	40
St Laurence Jewry	17
St Laurence Pountney	16
St Leonard in Eaſtcheap	6
St Leonard in Foſter-lane	21
St Magnus by London Bridge	31
St Margaret in Lothbury	17
St Margaret Moſes	3
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattons	7
St Martin Ironmonger-lane	4
St Martin at Ludgate	25
St Martin Orgars	11
St Martin Outwich	14
St Martin Vintrey	36
St Mary Abchurch	12
St Mary in Aldermanbury	26
St Mary Aldermary	15
St Mary le Bow in Cheapſide	22
St Mary Bothaw at Dowgate	4
St Mary Colechurch	0
St Mary Hill by Billinſgate	26
St Mary Magd. in Milk-ſtr.	0
St Mary Magd. Old Fiſh-ſtr.	35
St Mary Mounthaw	12
St Mary Somerſet	35
St Mary Staining	12
St Mary Woolchurch	0
St Mary Woolnoth	15
St Matthew in Friday-ſtreet	2
St Michael Baſſiſhaw	22
St Michael in Cornhill	13
St Michael in Crooked-lane	29
St Michael at Queenhithe	23
St Michael at Quern	8
St Michael Royal	12
St Michael in Wood-ſtreet	7
St Mildred in Bread-ſtreet	8
St Mildred in the Poultry	4
St Nicholas Acons	5
St Nicholas Coleabby	11
St Nicholas Olave	4
St Olave in Hart-ſtreet	25
St Olave in the Old Jewry	7
St Olave in Silver-ſtreet	18
St Pancras in Pancras-lane	0
St Peter in Cheapſide	3
St Peter in Cornhill	20
St Peter near Paul's Wharf	11
St Peter Poor in Broad-ſtr.	4
St Stephen in Coleman-ſtreet	44
St Stephen in Walbrook	15
St Swithin at London-ſtone	13
St Thomas the Apoſtle	6
Trinity Pariſh	18
St Vedaſt, alias Foſter	27

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1090 Buried 1987

St Andrew in Holborn	839	Bridewell Precinct	0
St Bartholomew the Great	66	St Bridget, vulg. St Bride's	260
St Bartholomew the Leſs	16	St Dunſtan in the Weſt	165
St Botolph by Alderſgate	224	St George in Southwark	350
St Botolph by Aldgate	833	St Giles by Cripplegate	473
St Botolph by Biſhopſgate	407	St John in Southwark	349
St Olave in Southwark	353		
St Saviour in Southwark	677		
St Sepulchre's Pariſh	555		
St Thomas in Southwark	223		
Trinity in the Minories	36		

Chriſtened in the ſeventeen Pariſhes without the Walls 4184 Buried 5826

St Ann in Middleſex ——224	St James at Clerkenwell —543	St Mary at Lambeth — —453
Chriſt Church in Surrey —183	St John at Hackney———190	St Mary Magd. Bermondſey 444
Chriſt Church in Middleſex 719	St John at Wapping———347	St Mary at Newington ——259
St Dunſtan at Stepney ——427	St Katherine near the Tower 216	St Mary at Rotherhith ——252
St George in Bloomſbury—377	St Leonard in Shoreditch —915	St Mary in Whitechapel—1136
St George in Middleſex ——556	St Luke in Middleſex——1126	St Matthew at Bethnal Green 508
St George by Queen's ſquare 367	St Mary at Iſlington ———265	St Paul at Shadwell ———441
St Giles in the Fields ——1068		

Chriſtened in the twenty-two Out Pariſhes in Middleſex and Surrey 5692 Buried 11016

St Ann in Weſtminſter ——380	St John the Evangeliſt - — 0	St Mary le Strand ——— 58
St Clement Danes ———369	St Margaret in Weſtminſt. 896	The Precinct of the Savoy 68
St George by Hanover-ſqu. 651	St Martin in the Fields —1081	St Paul in Covent Garden 281
St James in Weſtminſter 1114		

Chriſtened in the ten Pariſhes in the City and Liberties of Weſtminſter 3582 Buried 4898

DISEASES and CASUALTIES.

Abortive and Stilborn 581	Fever, Malignant Fever, Scarlet Fever, Spotted Fever, and Purples 4294	Pleuriſy — ——— 34	Broken Limbs —— 9
Aged — ———1896		Quinſy ——— — 16	Bruiſed —— — 6
Ague ——— — 11		Raſh ——— —— 4	Burnt ——— —— 8
Apoplexy and Suddenly 227		Rheumatiſm ——— 21	Drowned — ——— 100
Aſthma and Tiſſick — 468	French Pox -——— 73	Rickets —— —— 21	Exceſſive Drinking — 19
Bedridden — —— 2	Gout ——— —— 59	Riſing of the Lights— 1	Executed — ——— 27
Bleeding ——— — 3	Gravel, Stone, and Strangury — 30	Scald Head — ——— 1	Found dead — —— 25
Bloody Flux -——— 8		Scurvy — ——— 4	Killed by Falls and ſeveral other Accidents — 73
Burſten and Rupture-- 8	Grief ——— —— 8	Small Pox —— —1229	
Cancer — ——— 46	Headmoldſhot, Horſhoehead, and Water in the Head 107	Sores and Ulcers —— 22	
Canker —— —— 4		Sore Throat —— — 7	Killed themſelves—— 27
Childbed — ——— 228		St Anthony's Fire—— 3	Murdered —— — 4
Colick, Gripes, and Twiſting of the Guts 145	Jaundies —— —— 186	Stoppage in the Stomach 10	Overlaid — ——— 32
	Impoſthume ——— 17	Swelling —— —— 3	Poiſoned —— —— 8
	Inflammation ——— 41	Teeth —— ——1109	Scalded ——— — 1
Conſumption ———4543	Itch ——— —— 5	Thruſh — ——— 111	Shot ——— ——— 1
Convulſion -———5837	Leproſy —— —— 5	Tympany —— —— 3	Smothered — ——— 13
Cough and Hooping Cough —— 55	Lethargy — —— 11	Vapours —— —— 1	Starved — ——— 6
	Livergrown ——— 1	Vomiting and Looſneſs 8	Suffocated — —— 4
Diabetes — ——— 1	Lunatick ——— — 66	Worms — ——— 5	
Dropſy —— ——1051	Meaſles — ——— 321		Total 363
Evil —— ——— 14	Miſcarriage ——— 3		
Fiſtula —— ——— 8	Mortification ——— 259		
Flux ——— —— 24	Palſy ——— —— 105		

CHRISTENED	Males — 7394	BURIED	Males — 11742
	Females 7154		Females 11985
	In all — 14548		In all — 23727

Whereof have died,

Under Two Years of Age 8024	Twenty and Thirty 2031	Sixty and Seventy— 1728	A Hundred ———— 1
Between Two and Five— 1533	Thirty and Forty — 2542	Seventy and Eighty 1038	A Hundred and One— 3
Five and Ten ——— 709	Forty and Fifty —— 2708	Eighty and Ninety — 475	A Hundred and Two— 1
Ten and Twenty —— 746	Fifty and Sixty —— 2107	Ninety and a Hundred 80	A Hundred and Seven— 1

Decreaſed in the Burials this Year 1789

1751.

A General BILL of all the Chriſtenings and Burials,

From the 11th of December 1750, to the 10th of December 1751.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	25
Alhallows Barkin	52
Alhallows in Bread-ſtreet	8
Alhallows the Great	34
Alhallows in Honey-lane	0
Alhallows the Leſs	24
Alhallows in Lombard-ſtreet	8
Alhallows Staining	14
Alhallows on London Wall	60
St Alphage near Sion College	23
St Andrew Hubbard	9
St Andrew Underſhaft	21
St Andrew Wardrobe	50
St Ann within Alderſgate	40
St Ann in Black Friars	108
St Anthony, vulg. Antholin	6
St Auguſtin, vulg. Auſtin	11
St Bartholomew by Exchange	16
St Benedict, v. Bennet Fink	13
St Bennet Gracechurch	3
St Bennet at Paul's Wharf	32
St Bennet Sherehog	0
St Botolph at Billinſgate	4
Chriſt Church Pariſh	91
St Chriſtopher's Pariſh	16
St Clement near Eaſtcheap	9
St Dionis Backchurch	17
St Dunſtan in the Eaſt	59
St Edmund the King	11
St Ethelburga's Pariſh	25
St Faith under St Paul's	23
St Gabriel in Fenchurch-ſtr.	11
St George in Botolph-lane	5
St Gregory by St Paul's	74
St Helen near Biſhopſgate	30
St James in Duke's Place	9
St James at Garlickhithe	14
St John Baptiſt by Dowgate	15
St John the Evangeliſt	1
St John Zachary	19
St Katherine Coleman	28
St Katherine Creechurch	29
St Laurence Jewry	22
St Laurence Pountney	11
St Leonard in Eaſtcheap	6
St Leonard in Foſter-lane	17
St Magnus by London Bridge	24
St Margaret in Lothbury	8
St Margaret Moſes	2
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattens	3
St Martin Ironmonger-lane	2
St Martin at Ludgate	27
St Martin Orgars	14
St Martin Outwich	7
St Martin Vintrey	25
St Mary Abchurch	12
St Mary in Aldermanbury	18
St Mary Aldermary	22
St Mary le Bow in Cheapſide	13
St Mary Bothaw at Dowgate	4
St Mary Colechurch	0
St Mary Hill by Billinſgate	16
St Mary Magd. in Milk-ſtr.	0
St Mary Magd. Old Fiſh-ſtr.	23
St Mary Mounthaw	15
St Mary Somerſet	22
St Mary Staining	10
St Mary Woolchurch	0
St Mary Woolnoth	19
St Matthew in Friday-ſtreet	3
St Michael Baſſiſhaw	29
St Michael in Cornhill	14
St Michael in Crooked-lane	31
St Michael at Queenhithe	21
St Michael le Quern	2
St Michael Royal	7
St Michael in Wood-ſtreet	8
St Mildred in Bread-ſtreet	5
St Mildred in the Poultry	10
St Nicholas Acons	1
St Nicholas Coleabby	6
St Nicholas Olave	2
St Olave in Hart-ſtreet	36
St Olave in the Old Jewry	3
St Olave in Silver-ſtreet	21
St Pancras in Pancras-lane	4
St Peter in Cheapſide	2
St Peter in Cornhill	8
St Peter near Paul's Wharf	16
St Peter Poor in Broad-ſtr.	7
St Stephen in Coleman-ſtreet	56
St Stephen in Walbrook	13
St Swithin at London-ſtone	5
St Thomas the Apoſtle	10
Trinity Pariſh	15
St Vedaſt, alias Foſter	24

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1070 Buried 1748

St Andrew in Holborn	728
St Bartholomew the Great	70
St Bartholomew the Leſs	25
St Botolph by Alderſgate	215
St Botolph by Aldgate	675
St Botolph by Biſhopſgate	372
Bridewell Precinct	0
St Bridget, vulg. St Bride's	176
St Dunſtan in the Weſt	131
St George in Southwark	332
St Giles by Cripplegate	459
St John in Southwark	332
St Olave in Southwark	267
St Saviour in Southwark	598
St Sepulchre's Pariſh	510
St Thomas in Southwark	192
Trinity in the Minories	14

Chriſtened in the ſeventeen Pariſhes without the Walls 4158 Buried 5096

St Ann in Middleſex — 151	St James at Clerkenwell — 465	St Mary at Lambeth — — 388
Chriſt Church in Surrey — 183	St John at Hackney, — 188	St Mary Magd. Bermondſey 425
Chriſt Church in Middleſex 589	St John at Wapping — 322	St Mary at Newington — 244
St Dunſtan at Stepney — 374	St Katherine near the Tower 167	St Mary at Rotherhith — 249
St George in Bloomſbury — 365	St Leonard in Shoreditch — 754	St Mary in Whitechapel — 967
St George in Middleſex — 508	St Luke in Middleſex — 988	St Matthew at Bethnal Green 430
St George by Queen's ſquare 373	St Mary at Iſlington — — 198	St Paul at Shadwell — 378
St Giles in the Fields — 912		

Chriſtened in the twenty-two Out Pariſhes in Middleſex and Surrey 5819 Buried 9618

St Ann in Weſtminſter — 386	St John the Evangeliſt — 84	St Mary le Strand — 63
St Clement Danes — — 325	St Margaret in Weſtminſt. 796	The Precinct of the Savoy 60
St George by Hanover-ſqu. 658	St Martin in the Fields — 920	St Paul in Covent Garden 273
St James in Weſtminſter 1001		

Chriſtened in the ten Pariſhes in the City and Liberties of Weſtminſter 3644 Buried 4566

DISEASES and CASUALTIES.

Abortive and Stilborn 572	Fever, Malignant Fever, Scarlet Fever, Spotted Fever, and Purples 3219	Mortification — 225	Broken Limbs — 8
Aged — — 1688		Palſy — — 75	Bruiſed — 8
Ague — — 7		Pleuriſy — — 26	Burnt — — 2
Apoplexy and Suddenly 208		Quinſy — — 10	Drowned — — 66
Aſthma and Tiſſick — 427	Flux — — 21	Raſh — — 6	Exceſſive Drinking — 12
Bedridden — — 2	French Pox — — 75	Rheumatiſm — — 20	Executed — — 24
Bleeding — — 7	Gout — — 38	Rickets — — 23	Found dead — — 24
Bloody Flux — 3	Gravel, Stone, and Strangury — 28	Riſing of the Lights — 5	Frighted — — 1
Burſten and Rupture — 9		Scald Head — — 1	Killed by Falls and ſeveral other Accidents — 54
Cancer — — 46	Grief — — 5	Scurvy — — 7	
Canker — — 4	Headmoldſhot, Horſhoehead, and Water in the Head 115	Small Pox — — 998	
Childbed — — 172		Sores and Ulcers — 27	Killed themſelves — 47
Colick, Gripes, and Twiſting of the Guts 114	Jaundies — — 121	Sore Throat — — 3	Murdered — — 6
	Impoſthume — 13	St Anthony's Fire — 4	Overlaid — — 30
Conſumption — 4182	Inflammation — — 38	Stoppage in the Stomach 9	Scalded — — 4
Convulſion — — 5594	Itch — — 2	Swelling — — 4	Smothered — — 2
Cough and Hooping Cough — 275	Leproſy — — 3	Teeth — — 1053	Stabbed — — 1
	Lethargy — — 10	Thruſh — — 95	Starved — — 5
Dropſy — — 1000	Lunatick — — 76	Tympany — — 4	
Evil — — 14	Meaſles — — 21	Vomiting and Looſneſs 8	Total 294
Fiſtula — — 8	Miſcarriage — — 4	Worms — — 10	

CHRISTENED		BURIED	
Males —	7524	Males —	10339
Females	7167	Females	10689
In all —	14691	In all —	21028

Whereof have died,

Under Two Years of Age 7483	Thirty and Forty — 2207	Eighty and Ninety — 461	A Hundred and Five — 1
Between Two and Five — 1485	Forty and Fifty — 2234	Ninety and a Hundred 58	A Hundred and Six — 2
Five and Ten — — 575	Fifty and Sixty — 1815	A Hundred and One — 3	A Hundred and Eight — 1
Ten and Twenty — 588	Sixty and Seventy — 1490	A Hundred and Two — 3	A Hundred and Nine — 1
Twenty and Thirty — 1694	Seventy and Eighty — 925	A Hundred and Three 2	

Decreaſed in the Burials this Year 2699

1752.

A General BILL of all the Chriſtenings and Burials,

From the 10th of December 1751, to the 12th of December 1752.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	30
Alhallows Barkin	57
Alhallows in Bread-ſtreet	11
Alhallows the Great	34
Alhallows in Honey-lane	0
Alhallows the Leſs	14
Alhallows in Lombard-ſtreet	19
Alhallows Staining	21
Alhallows on London Wall	41
St Alphage near Sion College	36
St Andrew Hubbard	1
St Andrew Underſhaft	29
St Andrew Wardrobe	54
St Ann within Alderſgate	17
St Ann in Black Friars	119
St Anthony, vulg. Antholin	4
St Auguſtin, vulg. Auſtin	7
St Bartholomew by Exchange	7
St Benedict, v. Bennet Fink	22
St Bennet Gracechurch	11
St Bennet at Paul's Wharf	40
St Bennet Sherehog	0
St Botolph at Billinſgate	4
Chriſt Church Pariſh	71
St Chriſtopher's Pariſh	14
St Clement near Eaſtcheap	10
St Dionis Backchurch	11
St Dunſtan in the Eaſt	49
St Edmund the King	16
St Ethelburga's Pariſh	14
St Faith under St Paul's	21
St Gabriel in Fenchurch-ſtr.	13
St George in Botolph-lane	12
St Gregory by St Paul's	61
St Helen near Biſhopſgate	21
St James in Duke's Place	14
St James at Garlickhithe	19
St John Baptiſt by Dowgate	19
St John the Evangeliſt	6
St John Zachary	11
St Katherine Coleman	44
St Katherine Creechurch	0
St Laurence Jewry	10
St Laurence Pountney	8
St Leonard in Eaſtcheap	4
St Leonard in Foſter-lane	24
St Magnus by London Bridge	22
St Margaret in Lothbury	20
St Margaret Moſes	1
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattens	9
St Martin Ironmonger-lane	2
St Martin at Ludgate	16
St Martin Orgars	14
St Martin Outwich	5
St Martin Vintrey	24
St Mary Abchurch	20
St Mary in Aldermanbury	20
St Mary Aldermary	19
St Mary le Bow in Cheapſide	12
St Mary Bothaw at Dowgate	4
St Mary Colechurch	0
St Mary Hill by Billinſgate	13
St Mary Magd. in Milk-ſtr.	0
St Mary Magd. Old Fiſh-ſtr.	17
St Mary Mounthaw	15
St Mary Somerſet	21
St Mary Staining	8
St Mary Woolchurch	6
St Mary Woolnoth	10
St Matthew in Friday-ſtreet	8
St Michael Baſſiſhaw	29
St Michael in Cornhill	17
St Michael in Crooked-lane	28
St Michael at Queenhithe	29
St Michael le Quern	3
St Michael Royal	6
St Michael in Wood-ſtreet	0
St Mildred in Bread-ſtreet	8
St Mildred in the Poultry	7
St Nicholas Acons	6
St Nicholas Coleabby	4
St Nicholas Olave	9
St Olave in Hart-ſtreet	42
St Olave in the Old Jewry	6
St Olave in Silver-ſtreet	24
St Pancras in Pancras-lane	4
St Peter in Cheapſide	3
St Peter in Cornhill	14
St Peter near Paul's Wharf	15
St Peter Poor in Broad-ſtr.	7
St Stephen in Coleman-ſtreet	44
St Stephen in Walbrook	8
St Swithin at London-ſtone	15
St Thomas the Apoſtle	11
Trinity Pariſh	7
St Vedaſt, alias Foſter	17

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1121 Buried 1699

St Andrew in Holborn	670
St Bartholomew the Great	65
St Bartholomew the Leſs	9
St Botolph by Alderſgate	229
St Botolph by Aldgate	653
St Botolph by Biſhopſgate	344
Bridewell Precinct	0
St Bridget, vulg. St Bride's	192
St Dunſtan in the Weſt	137
St George in Southwark	251
St Giles by Cripplegate	366
St John in Southwark	286
St Olave in Southwark	219
St Saviour in Southwark	566
St Sepulchre's Pariſh	476
St Thomas in Southwark	172
Trinity in the Minories	16

Chriſtened in the ſeventeen Pariſhes without the Walls 4224 Buried 4651

St Ann in Middleſex——152	St James at Clerkenwell —468	St Mary at Lambeth ——380
Chriſt Church in Surrey —170	St John at Hackney——171	St Mary Magd. Bermondſey 333
Chriſt Church in Middleſex 544	St John at Wapping——316	St Mary at Newington——248
St Dunſtan at Stepney ——362	St Katherine near the Tower 172	St Mary at Rotherhith——218
St George in Bloomſbury —353	St Leonard in Shoreditch—769	St Mary in Whitechapel —962
St George in Middleſex —450	St Luke in Middleſex —1088	St Matthew at Bethnal Green 456
St George by Queen's ſquare 396	St Mary at Iſlington ——197	St Paul at Shadwell ——361
St Giles in the Fields — —884		

Chriſtened in the twenty-two Out Pariſhes in Middleſex and Surrey 6163 Buried 9450

St Ann in Weſtminſter —310	St John the Evangeliſt——153	St Mary le Strand —— 46
St Clement Danes— ——304	St Margaret in Weſtminſt. 906	The Precinct of the Savoy 71
St George by Hanover-ſqu.698	St Martin in the Fields — 940	St Paul in Covent Garden 265
St James in Weſtminſter—992		

Chriſtened in the ten Pariſhes in the City and Liberties of Weſtminſter 3800 Buried 4685

DISEASES and CASUALTIES.

Abortive and Stilborn	529	Fever, Malignant Fever, Scarlet Fever, Spotted Fever, and Purples	2070	Palſy	80	BIT by mad Dogs—	2
Aged — ———	1263	French Pox — ——	54	Pleuriſy —— ——	23	Bit by a Viper ——	1
Ague ——— ——	2	Gout —— ——	40	Quinſy —— ——	8	Broken Limbs ———	7
Apoplexy and Suddenly	178	Gravel, Stone, and Strangury —	28	Raſh —— ———	2	Bruiſed — ———	3
Aſthma and Tiſſick —	289	Grief ——— ——	4	Rheumatiſm — —	6	Burnt ——— —	8
Bedridden —— —	7	Headmoldſhot, Horſhoehead, and Water in the Head	85	Rickets — ———	11	Drowned — ———	98
Bleeding — ———	3	Jaundies ——— —	115	Riſing of the Lights—	4	Exceſſive Drinking —	10
Bloody Flux ———	3	Impoſthume — ——	17	Scald Head —— —	3	Executed — ———	17
Burſten and Rupture--	10	Inflammation ———	33	Scurvy ——— ——	5	Found dead - ———	22
Cancer — ———	53	Leproſy ——— —	3	Small Pox ——— —3538		Killed by Falls and ſeveral other Accidents ——	53
Canker —— ——	6	Lethargy —— ——	8	Sores and Ulcers ——	15		
Childbed — ———	156	Livergrown —— —	2	Sore Throat — — —	3		
Colick, Gripes, and Twiſting of the Guts ——	123	Lunatick — ———	69	St Anthony's Fire——	4	Killed themſelves ——	44
Conſumption ———3558		Meaſles —— ——	111	Stoppage in the Stomach	10	Murdered — ——	6
Convulſion — ——5431		Miſcarriage — ——	5	Surfeit ——— —	1	Overlaid — ———	37
Cough and Hooping Cough ——	188	Mortification ———	199	Swelling — ———	5	Poiſoned ——— —	1
Dropſy — ———	680			Teeth —— ———	968	Scalded —— ——	4
Evil ——— ——	21			Thruſh —— ——	99	Smothered —— —	2
Fiſtula —— ——	17			Tympany —— —	2	Starved ——— ——	1
Flux ——— ———	10			Vomiting and Looſneſs	5		
				Worms —— ——	7	Total	316

CHRISTENED	Males — 7868	BURIED	Males — 10306
	Females 7440		Females 10179
	In all — 15308		In all — 20485

Whereof have died,

Under Two Years of Age	8239	Thirty and Forty —	1823	Seventy and Eighty	738	A Hundred and One—	1
Between Two and Five—	2225	Forty and Fifty ——	1633	Eighty and Ninety—	316	A Hundred and Two —	1
Five and Ten —— ——	814	Fifty and Sixty ——	1348	Ninety and a Hundred	37	A Hundred and Three—	2
Ten and Twenty ——	660	Sixty and Seventy —	1079	A Hundred — ——	1	A Hundred and Five —	2
Twenty and Thirty——	1566						

Decreaſed in the Burials this Year 543

A General

1753.

A General BILL of all the Chriſtenings and Burials,

From the 12th of December 1752, to the 11th of December 1753.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	21
Alhallows Barkin	47
Alhallows in Bread-ſtreet	11
Alhallows the Great	27
Alhallows in Honey-lane	0
Alhallows the Leſs	22
Alhallows in Lombard-ſtreet	14
Alhallows Staining	13
Alhallows on London Wall	22
St Alphage near Sion College	24
St Andrew Hubbard	3
St Andrew Underſhaft	26
St Andrew Wardrobe	44
St Ann within Alderſgate	29
St Ann in Black Friars	107
St Anthony, vulg. Antholin	4
St Auguſtin, vulg. Auſtin	2
St Bartholomew by Exchange	0
St Benedict, v. Bennet Fink	11
St Bennet Gracechurch	8
St Bennet at Paul's Wharf	13
St Bennet Sherehog	0
St Botolph at Billinſgate	5
Chriſt Church Pariſh	78
St Chriſtopher's Pariſh	3
St Clement near Eaſtcheap	7
St Dionis Backchurch	30
St Dunſtan in the Eaſt	50
St Edmund the King	11
St Ethelburga's Pariſh	11
St Faith under St Paul's	28
St Gabriel in Fenchurch-ſtr.	14
St George in Botolph-lane	10
St Gregory by St Paul's	55
St Helen near Biſhopſgate	31
St James in Duke's Place	10
St James at Garlickhithe	18
St John Baptiſt by Dowgate	17
St John the Evangeliſt	1
St John Zachary	11
St Katherine Coleman	19
St Katherine Creechurch	37
St Laurence Jewry	16
St Laurence Pountney	8
St Leonard in Eaſtcheap	11
St Leonard in Foſter-lane	12
St Magnus by London Bridge	17
St Margaret in Lothbury	18
St Margaret Moſes	4
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattens	5
St Martin Ironmonger-lane	5
St Martin at Ludgate	14
St Martin Orgars	10
St Martin Outwich	3
St Martin Vintrey	30
St Mary Abchurch	18
St Mary in Aldermanbury	20
St Mary Aldermary	11
St Mary le Bow in Cheapſide	12
St Mary Bothaw at Dowgate	4
St Mary Colechurch	0
St Mary Hill by Billinſgate	14
St Mary Magd. in Milk-ſtr.	0
St Mary Magd. Old Fiſh-ſtr.	13
St Mary Mounthaw	17
St Mary Somerſet	24
St Mary Staining	21
St Mary Woolchurch	0
St Mary Woolnoth	13
St Matthew in Friday-ſtreet	2
St Michael Baſſiſhaw	29
St Michael in Cornhill	15
St Michael in Crooked-lane	24
St Michael at Queenhithe	26
St Michael le Quern	3
St Michael Royal	5
St Michael in Wood-ſtreet	5
St Mildred in Bread-ſtreet	2
St Mildred in the Poultry	5
St Nicholas Acons	4
St Nicholas Coleabby	6
St Nicholas Olave	4
St Olave in Hart-ſtreet	26
St Olave in the Old Jewry	6
St Olave in Silver-ſtreet	20
St Pancras in Pancras-lane	0
St Peter in Cheapſide	2
St Peter in Cornhill	13
St Peter near Paul's Wharf	11
St Peter Poor in Broad-ſtr.	7
St Stephen in Coleman-ſtreet	50
St Stephen in Walbrook	8
St Swithin at London-ſtone	16
St Thomas the Apoſtle	9
Trinity Pariſh	15
St Vedaſt, alias Foſter	19

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1130 Buried 1546

	Bur.
St Andrew in Holborn	690
St Bartholomew the Great	56
St Bartholomew the Leſs	10
St Botolph by Alderſgate	167
St Botolph by Aldgate	652
St Botolph by Biſhopſgate	362
Bridewell Precinct	0
St Bridget, vulg. St Bride's	149
St Dunſtan in the Weſt	151
St George in Southwark	233
St Giles by Cripplegate	314
St John in Southwark	299
St Olave in Southwark	303
St Saviour in Southwark	525
St Sepulchre's Pariſh	491
St Thomas in Southwark	178
Trinity in the Minories	32

Chriſtened in the ſeventeen Pariſhes without the Walls 4324 Buried 4612

1753.

St Ann in Middleſex——148	St James at Clerkenwell —440	St Mary at Lambeth ——391
Chriſt Church in Surrey —158	St John at Hackney ——186	St Mary Magd. Bermondſey 359
Chriſt Church in Middleſex 507	St John at Wapping ——254	St Mary at Newington ——227
St Dunſtan at Stepney ——368	St Katherine near the Tower 134	St Mary at Rotherhith ——212
St George in Bloomſbury —303	St Leonard in Shoreditch —840	St Mary in Whitechapel —890
St George in Middleſex - —383	St Luke in Middleſex ——964	St Matthew at Bethnal Green 369
St George by Queen's ſquare 329	St Mary at Iſlington — —177	St Paul at Shadwell ——325
St Giles in the Fields ——951		

Chriſtened in the twenty-two Out Pariſhes in Middleſex and Surrey 6141 Buried 8915

St Ann in Weſtminſter - —211	St John the Evangeliſt - —163	St Mary le Strand—— 41
St Clement Danes — ——287	St Margaret in Weſtminſt. 833	The Precinct of the Savoy 55
St George by Hanover-ſqu. 613	St Martin in the Fields — 858	St Paul in Covent Garden 221
St James in Weſtminſter —921		

Chriſtened in the ten Pariſhes in the City and Liberties of Weſtminſter 3849 Buried 4203

DISEASES and CASUALTIES.

Abortive and Stilborn 570	Fever, Malignant Fever, Scarlet Fever, Spotted Fever, and Purples — 2292	Palſy —— —— 60	BIT by mad Dogs— 3
Aged —— ——1466		Pleuriſy —— —— 14	Broken Limbs —— 5
Ague —— —— 4		Quinſy —— —— 11	Bruiſed —— —— 5
Apoplexy and Suddenly 238		Rheumatiſm —— — 6	Burnt —— —— 9
Aſthma and Tiſſick — 305	French Pox — —— 55	Rickets —— —— 7	Drowned — —— 86
Bedridden — —— 2	Gout —— —— 49	Riſing of the Lights— 1	Exceſſive Drinking — 15
Bleeding —— —— 5	Gravel, Stone, and Strangury — 32	Scald Head — —— 2	Executed —— —— 18
Bloody Flux —— 5		Sciatica —— — 1	Found dead — — 34
Burſten and Rupture-- 14	Grief —— —— 7	Scurvy —— —— 5	Frighted — —— 2
Cancer — —— 52	Headmoldſhot, Horſhoehead, and Water in the Head 64	Small Pox — —— 774	Killed by Falls and ſeveral other Accidents — 55
Canker —— —— 6		Sores and Ulcers —— 14	
Childbed —— — 169		Sore Throat — —— 7	
Colick, Gripes, and Twiſting of the Guts —— 128	Jaundies —— — 90	St Anthony's Fire — 2	Killed themſelves —— 36
	Impoſthume — —— 12	Stoppage in the Stomach 14	Murdered —— — 3
Conſumption ——3915	Inflammation — — 64	Surfeit —— —— 3	Overlaid —— —— 40
Convulſion — ——5977	Itch —— —— 3	Swelling — —— 3	Poiſoned — —— 1
Cough and Hooping Cough — 65	Leproſy —— — 2	Teeth —— — 961	Scalded —— — 5
	Lethargy — —— 9	Thruſh —— —— 83	Smothered — —— 1
Dropſy —— —— 794	Livergrown —— — 2	Vomiting and Looſneſs 6	Stabbed — —— 1
Evil —— —— 11	Lunatick — —— 86	Worms —— —— 11	Starved —— —— 7
Fiſtula —— —— 4	Meaſles —— — 253		Suffocated — —— 5
Flux —— —— 5	Miſcarriage — — — 4		Total 331
	Mortification —— 201		

CHRISTENED	Males — 7860	BURIED	Males — 9490
	Females 7584		Females 9786
	In all 15444		In all — 19276

Whereof have died,

Under Two Years of Age 7892	Thirty and Forty —— 1861	Eighty and Ninety —— 435
Between Two and Five— 1403	Forty and Fifty — —— 1775	Ninety and a Hundred — 54
Five and Ten —— —— 418	Fifty and Sixty —— — 1568	A Hundred —— —— 1
Ten and Twenty —— 478	Sixty and Seventy—— 1186	A Hundred and One —— 2
Twenty and Thirty —— 1338	Seventy and Eighty —— 864	A Hundred and Two - — 1

Decreaſed in the Burials this Year 1209

A General

1754.

A General BILL of all the Chriſtenings and Burials,

From the 11th of December 1753, to the 10th of December 1754.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	14
Alhallows Barkin	61
Alhallows in Bread-ſtreet	9
Alhallows the Great	28
Alhallows in Honey-lane	0
Alhallows the Leſs	26
Alhallows in Lombard-ſtreet	13
Alhallows Staining	20
Alhallows on London Wall	50
St Alphage near Sion College	36
St Andrew Hubbard	2
St Andrew Underſhaft	32
St Andrew Wardrobe	47
St Ann within Alderſgate	30
St Ann in Black Friars	159
St Anthony, vulg. Antholin	1
St Auguſtin, vulg. Auſtin	2
St Bartholomew by Exchange	0
St Benedict, v. Bennet Fink	17
St Bennet Gracechurch	8
St Bennet at Paul's Wharf	33
St Bennet Sherehog	0
St Botolph at Billinſgate	5
Chriſt Church Pariſh	90
St Chriſtopher's Pariſh	15
St Clement near Eaſtcheap	8
St Dionis Backchurch	8
St Dunſtan in the Eaſt	56
St Edmund the King	12
St Ethelburga's Pariſh	12
St Faith under St Paul's	50
St Gabriel in Fenchurch-ſtr.	17
St George in Botolph-lane	7
St Gregory by St Paul's	74
St Helen near Biſhopſgate	22
St James in Duke's Place	15
St James at Garlickhithe	14
St John Baptiſt by Dowgate	25
St John the Evangeliſt	0
St John Zachary	9
St Katherine Coleman	29
St Katherine Creechurch	45
St Laurence Jewry	14
St Laurence Pountney	15
St Leonard in Eaſtcheap	8
St Leonard in Foſter-lane	19
St Magnus by London Bridge	29
St Margaret in Lothbury	9
St Margaret Moſes	0
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattens	6
St Martin Ironmonger-lane	6
St Martin at Ludgate	24
St Martin Orgars	7
St Martin Outwich	7
St Martin Vintrey	32
St Mary Abchurch	17
St Mary in Aldermanbury	26
St Mary Aldermary	23
St Mary le Bow in Cheapſide	12
St Mary Bothaw at Dowgate	3
St Mary Colechurch	0
St Mary Hill by Billinſgate	30
St Mary Magd. in Milk-ſtr.	1
St Mary Magd. Old Fiſh-ſtr.	26
St Mary Mounthaw	23
St Mary Somerſet	36
St Mary Staining	12
St Mary Woolchurch	0
St Mary Woolnoth	18
St Matthew in Friday-ſtreet	3
St Michael Baſſiſhaw	27
St Michael in Cornhill	17
St Michael in Crooked-lane	30
St Michael at Queenhithe	21
St Michael le Quern	2
St Michael Royal	14
St Michael in Wood-ſtreet	0
St Mildred in Bread-ſtreet	6
St Mildred in the Poultry	8
St Nicholas Acons	3
St Nicholas Coleabby	12
St Nicholas Olave	7
St Olave in Hart-ſtreet	33
St Olave in the Old Jewry	7
St Olave in Silver-ſtreet	16
St Pancras in Pancras-lane	4
St Peter in Cheapſide	3
St Peter in Cornhill	14
St Peter near Paul's Wharf	22
St Peter Poor in Broad-ſtr.	8
St Stephen in Coleman-ſtreet	59
St Stephen in Walbrook	12
St Swithin at London-ſtone	21
St Thomas the Apoſtle	15
Trinity Pariſh	8
St Vedaſt, alias Foſter	29

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1191 Buried 1905

St Andrew in Holborn	895
St Bartholomew the Great	53
St Bartholomew the Leſs	28
St Botolph by Alderſgate	258
St Botolph by Aldgate	756
St Botolph by Biſhopſgate	363
Bridewell Precinct	0
St Bridget, vulg. St Bride's	211
St Dunſtan in the Weſt	183
St George in Southwark	258
St Giles by Cripplegate	352
St John in Southwark	323
St Olave in Southwark	279
St Saviour in Southwark	564
St Sepulchre's Pariſh	559
St Thomas in Southwark	199
Trinity in the Minories	21

Chriſtened in the ſeventeen Pariſhes without the Walls 4093 Buried 5302

St Ann in Middleſex ——179	St James at Clerkenwell —626	St Mary at Lambeth — —462
Chriſt Church in Surrey —199	St John at Clerkenwell—— 47	St Mary Magd. Bermondſey 326
Chriſt Church in Middleſex 640	St John at Hackney———181	St Mary at Newington ——265
St Dunſtan at Stepney ——408	St John at Wapping———327	St Mary at Rotherhith ——201
St George in Bloomſbury—385	St Katherine near the Tower 163	St Mary in Whitechapel—1102
St George in Middleſex ——456	St Leonard in Shoreditch —923	St Matthew at Bethnal Green 470
St George by Queen's ſquare 395	St Luke in Middleſex——1076	St Paul at Shadwell ———398
St Giles in the Fields ——1045	St Mary at Iſlington ———243	

Chriſtened in the twenty-three Out Pariſhes in Middleſex and Surrey 5950 Buried 10517

St Ann in Weſtminſter ——251	St John the Evangeliſt ——131	St Mary le Strand ——— 52
St Clement Danes ———381	St Margaret in Weſtminſt. 985	The Precinct of the Savoy 68
St George by Hanover-ſqu. 746	St Martin in the Fields —1014	St Paul in Covent Garden 275
St James in Weſtminſter 1069		

Chriſtened in the ten Pariſhes in the City and Liberties of Weſtminſter 3713 Buried 4972

DISEASES and CASUALTIES.

Abortive and Stilborn 578	Fever, Malignant Fever, Scarlet Fever, Spotted Fever, and Purples — 2964	Miſcarriage ——— 5	Broken Limbs —— 11
Aged — ———1946		Mortification ——— 218	Bruiſed —— — 7
Ague ——— — 4		Palſy ——— —— 68	Burnt ——— —— 10
Apoplexy and Suddenly 240		Pleuriſy — ——— 22	Drowned — ——— 103
Aſthma and Tiſſick — 398	Fiſtula —— ——— 10	Quinſy ——— — 10	Exceſſive Drinking — 12
Bedridden — —— 2	Flux ——— —— 18	Rheumatiſm ——— 22	Executed — ——— 10
Bleeding ——— — 11	French Pox ——— 73	Rickets —— —— 13	Found dead — —— 32
Bloody Flux ——— 4	Gout ——— —— 74	Riſing of the Lights— 2	Frighted — ——— 1
Burſten and Rupture-- 6	Gravel, Stone, and Strangury — 30	Scald Head — ——— 3	Killed by Falls and ſeveral other Accidents — 53
Cancer — ——— 48		Scurvy — ——— 5	
Canker —— —— 3	Grief —— ——— 4	Small Pox —— —2359	
Chicken Pox ——— 1	Head-ach —— —— 1	Sores and Ulcers —— 17	Killed themſelves—— 25
Childbed — ——— 213	Headmoldſhot, Horſhoehead, and Water in the Head 57	Sore Throat —— — 4	Murdered —— — 2
Colick, Gripes, and Twiſting of the Guts ——— 115		St Anthony's Fire—— 3	Overlaid — ——— 23
		Stoppage in the Stomach 20	Scalded ——— — 1
Conſumption ———4241	Jaundies —— —— 91	Surfeit — ——— 2	Smothered — ——— 1
Convulſion ———6115	Impoſthume ——— 14	Swelling —— —— 1	Starved — ——— 4
Cough and Hooping Cough —— 336	Inflammation ——— 60	Swine Pox — —— 1	Suffocated — —— 3
	Itch ——— —— 1	Teeth —— —— 841	
Diabetes — ——— 1	Leproſy —— ——— 3	Thruſh — ——— 77	Total 298
Dropſy —— —— 906	Lethargy — —— 9	Tympany —— —— 4	
Evil —— ——— 8	Livergrown ——— 1	Vomiting and Looſneſs 6	
Falling Sickneſs —— 1	Lunatick ——— — 86	Worms — ——— 10	
	Meaſles — ——— 12		

CHRISTENED	Males — 7754	BURIED	Males — 11164
	Females 7193		Females 11532
	In all — 14947		In all — 22696

Whereof have died,

Under Two Years of Age 8115	Twenty and Thirty 1685	Sixty and Seventy — 1642	A Hundred ——— 1
Between Two and Five— 1904	Thirty and Forty — 2141	Seventy and Eighty 1143	A Hundred and One— 2
Five and Ten ——— 640	Forty and Fifty — 2179	Eighty and Ninety — 586	A Hundred and Nine— 1
Ten and Twenty —— 628	Fifty and Sixty —— 1944	Ninety and a Hundred 85	

Increaſed in the Burials this Year 3420

1755.

A General BILL of all the Chriſtenings and Burials,

From the 10th of December 1754, to the 16th of December 1755.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	20
Alhallows Barkin	58
Alhallows in Bread-ſtreet	12
Alhallows the Great	17
Alhallows in Honey-lane	0
Alhallows the Leſs	18
Alhallows in Lombard-ſtreet	17
Alhallows Staining	11
Alhallows on London Wall	49
St Alphage near Sion College	33
St Andrew Hubbard	8
St Andrew Underſhaft	32
St Andrew Wardrobe	55
St Ann within Alderſgate	40
St Ann in Black Friars	119
St Anthony, vulg. Antholin	3
St Auguſtin, vulg. Auſtin	0
St Bartholomew by Exchange	7
St Benedict, v. Bennet Fink	18
St Bennet Gracechurch	5
St Bennet at Paul's Wharf	25
St Bennet Sherehog	0
St Botolph at Billinſgate	4
Chriſt Church Pariſh	95
St Chriſtopher's Pariſh	9
St Clement near Eaſtcheap	14
St Dionis Backchurch	9
St Dunſtan in the Eaſt	58
St Edmund the King	13
St Ethelburga's Pariſh	14
St Faith under St Paul's	43
St Gabriel in Fenchurch-ſtr.	12
St George in Botolph-lane	6
St Gregory by St Paul's	63
St Helen near Biſhopſgate	29
St James in Duke's Place	12
St James at Garlickhithe	13
St John Baptiſt by Dowgate	12
St John the Evangeliſt	0
St John Zachary	12
St Katherine Coleman	36
St Katherine Creechurch	54
St Laurence Jewry	24
St Laurence Pountney	13
St Leonard in Eaſtcheap	5
St Leonard in Foſter-lane	19
St Magnus by London Bridge	29
St Margaret in Lothbury	9
St Margaret Moſes	2
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattens	8
St Martin Ironmonger-lane	5
St Martin at Ludgate	13
St Martin Orgars	10
St Martin Outwich	4
St Martin Vintrey	18
St Mary Abchurch	12
St Mary in Aldermanbury	29
St Mary Aldermary	19
St Mary le Bow in Cheapſide	15
St Mary Bothaw at Dowgate	8
St Mary Colechurch	0
St Mary Hill by Billinſgate	19
St Mary Magd. in Milk-ſtr.	0
St Mary Magd. Old Fiſh-ſtr.	14
St Mary Mounthaw	25
St Mary Somerſet	28
St Mary Staining	14
St Mary Woolchurch	0
St Mary Woolnoth	11
St Matthew in Friday-ſtreet	3
St Michael Baſſiſhaw	17
St Michael in Cornhill	17
St Michael in Crooked-lane	22
St Michael at Queenhithe	32
St Michael le Quern	6
St Michael Royal	4
St Michael in Wood-ſtreet	7
St Mildred in Bread-ſtreet	6
St Mildred in the Poultry	6
St Nicholas Acons	3
St Nicholas Coleabby	10
St Nicholas Olave	6
St Olave in Hart-ſtreet	34
St Olave in the Old Jewry	6
St Olave in Silver-ſtreet	22
St Pancras in Pancras-lane	2
St Peter in Cheapſide	3
St Peter in Cornhill	20
St Peter near Paul's Wharf	28
St Peter Poor in Broad-ſtr.	5
St Stephen in Coleman-ſtreet	65
St Stephen in Walbrook	19
St Swithin at London-ſtone	8
St Thomas the Apoſtle	13
Trinity Pariſh	12
St Vedaſt, alias Foſter	17

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1189 Buried 1811

St Andrew in Holborn	917
St Bartholomew the Great	62
St Bartholomew the Leſs	14
St Botolph by Alderſgate	193
St Botolph by Aldgate	696
St Botolph by Biſhopſgate	371
Bridewell Precinct	0
St Bridget, vulg. St Bride's	173
St Dunſtan in the Weſt	145
St George in Southwark	322
St Giles by Cripplegate	333
St John in Southwark	292
St Olave in Southwark	287
St Saviour in Southwark	585
St Sepulchre's Pariſh	557
St Thomas in Southwark	194
Trinity in the Minories	19

Chriſtened in the ſeventeen Pariſhes without the Walls 4188 Buried 5160

St Ann in Middleſex —— 78	St James at Clerkenwell —597	St Mary at Lambeth — —510
Chriſt Church in Surrey —188	St John at Clerkenwell—— 45	St Mary Magd. Bermondſey 357
Chriſt Church in Middleſex 593	St John at Hackney ——168	St Mary at Newington ——263
St Dunſtan at Stepney ——385	St John at Wapping ——310	St Mary at Rotherhith ——232
St George in Bloomſbury—349	St Katherine near the Tower 189	St Mary in Whitechapel—1045
St George in Middleſex —451	St Leonard in Shoreditch—845	St Matthew at Bethnal Green 456
St George by Queen's ſquare 416	St Luke in Middleſex —1148	St Paul at Shadwell ——412
St Giles in the Fields ——1008	St Mary at Iſlington — —180	

Chriſtened in the twenty-three Out Pariſhes in Middleſex and Surrey 6110 Buried 10225

St Ann in Weſtminſter - —242	St John the Evangeliſt - —107	St Mary le Strand —— 42
St Clement Danes — ——352	St Margaret in Weſtminſt. 935	The Precinct of the Savoy 83
St George by Hanover-ſqu.681	St Martin in the Fields— 977	St Paul in Covent Garden 232
St James in Weſtminſter 1070		

Chriſtened in the ten Pariſhes in the City and Liberties of Weſtminſter 3722 Buried 4721

DISEASES and CASUALTIES.

Abortive and Stilborn 565	Fever, Malignant Fever, Scarlet Fever, Spotted Fever, and Purples 3042	Palſy —— —— 58	Bit by mad Dogs— 2
Aged —— ——1662		Pleuriſy — —— 12	Bruiſed — —— 4
Ague —— —— 5		Quinſy —— —— 14	Burnt —— —— 15
Apoplexy and Suddenly 208		Raſh —— —— 6	Choaked —— — 1
Aſthma and Tiſſick — 359	Flux —— —— 8	Rheumatiſm — — 9	Drowned — —— 142
Bedridden — —— 7	French Pox — —— 68	Rickets — —— 6	Exceſſive Drinking — 8
Bleeding —— — 1	Gout —— —— 79	Riſing of the Lights— 2	Executed — —— 10
Bloody Flux —— 6	Gravel, Stone, and Strangury — 24	Scald Head -—— 1	Found dead —— — 26
Burſten and Rupture-- 10		Scurvy —— —— 2	Frighted — —— 1
Cancer — —— 46	Green Sickneſs—— 1	Small Pox — ——1988	Killed by Falls and ſeveral other Accidents — 83
Canker —— —— 9	Grief —— —— 6	Sores and Ulcers —— 15	
Chicken Pox —— 1	Head-ach — —— 1	Sore Throat — —— 4	
Childbed —— — 208	Headmoldſhot, Horſhoehead, and Water in the Head 56	St Anthony's Fire -— 5	Killed themſelves—— 47
Colick, Gripes, and Twiſting of the Guts —— 81		Stoppage in the Stomach 14	Murdered — —— 9
		Surfeit — —— 4	Overlaid —— — 33
Conſumption ——4322	Jaundies —— —— 113	Swelling —— —— 4	Scalded — —— 1
Convulſion — ——5741	Impoſthume —— 11	Teeth — —— 813	Shot —— —— 1
Cough and Hooping Cough — 93	Inflammation —— — 57	Thruſh —— —— 81	Smothered —— — 2
	Lethargy — —— 6	Tympany — —— 2	Stabbed —— —— 1
Diabetes — —— 1	Livergrown — — 2	Vomiting and Looſneſs 11	Starved — —— 5
Dropſy — —— 919	Lunatick — —— 103	Worms — —— 11	
Evil —— —— 14	Meaſles —— — 423		Total 391
Fiſtula —— —— 14	Miſcarriage — —— 2		
	Mortification —— 190		

CHRISTENED	Males — 7773	BURIED	Males — 10779
	Females 7436		Females 11138
	In all — 15209		In all — 21917

Whereof have died,

Under Two Years of Age 7803	Twenty and Thirty 1651	Sixty and Seventy— 1433	Ninety and a Hundred— 77
Between Two and Five— 2001	Thirty and Forty — 2087	Seventy and Eighty 1018	A Hundred and One— 1
Five and Ten —— 612	Forty and Fifty —— 2234	Eighty and Ninety-- 504	A Hundred and Seven— 1
Ten and Twenty —— 577	Fifty and Sixty —— 1918		

Decreaſed in the Burials this Year 779

1756.

A General BILL of all the Chriſtenings and Burials,

From the 16th of December 1755, to the 14th of December 1756.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	24
Alhallows Barkin	58
Alhallows in Bread-ſtreet	7
Alhallows the Great	27
Alhallows in Honey-lane	0
Alhallows the Leſs	18
Alhallows in Lombard-ſtreet	17
Alhallows Staining	15
Alhallows on London Wall	38
St Alphage near Sion College	22
St Andrew Hubbard	2
St Andrew Underſhaft	16
St Andrew Wardrobe	59
St Ann within Alderſgate	35
St Ann in Black Friars	106
St Anthony, vulg. Antholin	1
St Auguſtin, vulg. Auſtin	2
St Bartholomew by Exchange	16
St Benedict, v. Bennet Fink	17
St Bennet Gracechurch	4
St Bennet at Paul's Wharf	45
St Bennet Sherehog	0
St Botolph at Billinſgate	10
Chriſt Church Pariſh	69
St Chriſtopher's Pariſh	9
St Clement near Eaſtcheap	4
St Dionis Backchurch	7
St Dunſtan in the Eaſt	48
St Edmund the King	10
St Ethelburga's Pariſh	16
St Faith under St Paul's	33
St Gabriel in Fenchurch-ſtr.	8
St George in Botolph-lane	9
St Gregory by St Paul's	83
St Helen near Biſhopſgate	25
St James in Duke's Place	21
St James at Garlickhithe	13
St John Baptiſt by Dowgate	16
St John the Evangeliſt	0
St John Zachary	11
St Katherine Coleman	35
St Katherine Creechurch	40
St Laurence Jewry	12
St Laurence Pountney	9
St Leonard in Eaſtcheap	9
St Leonard in Foſter-lane	21
St Magnus by London Bridge	21
St Margaret in Lothbury	19
St Margaret Moſes	4
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattens	9
St Martin Ironmonger-lane	9
St Martin at Ludgate	13
St Martin Orgars	11
St Martin Outwich	0
St Martin Vintrey	23
St Mary Abchurch	9
St Mary in Aldermanbury	30
St Mary Aldermary	23
St Mary le Bow in Cheapſide	13
St Mary Bothaw at Dowgate	5
St Mary Colechurch	0
St Mary Hill by Billinſgate	10
St Mary Magd. in Milk-ſtr.	0
St Mary Magd. Old Fiſh-ſtr.	17
St Mary Mounthaw	11
St Mary Somerſet	22
St Mary Staining	11
St Mary Woolchurch	0
St Mary Woolnoth	10
St Matthew in Friday-ſtreet	3
St Michael Baſſiſhaw	24
St Michael in Cornhill	11
St Michael in Crooked-lane	18
St Michael at Queenhithe	15
St Michael le Quern	10
St Michael Royal	8
St Michael in Wood-ſtreet	3
St Mildred in Bread-ſtreet	3
St Mildred in the Poultry	0
St Nicholas Acons	6
St Nicholas Coleabby	7
St Nicholas Olave	4
St Olave in Hart-ſtreet	28
St Olave in the Old Jewry	4
St Olave in Silver-ſtreet	25
St Pancras in Pancras-lane	4
St Peter in Cheapſide	3
St Peter in Cornhill	19
St Peter near Paul's Wharf	18
St Peter Poor in Broad-ſtr.	9
St Stephen in Coleman-ſtreet	40
St Stephen in Walbrook	7
St Swithin at London-ſtone	9
St Thomas the Apoſtle	10
Trinity Pariſh	11
St Vedaſt, alias Foſter	25

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1154 Buried 1641

St Andrew in Holborn	881
St Bartholomew the Great	43
St Bartholomew the Leſs	16
St Botolph by Alderſgate	181
St Botolph by Aldgate	679
St Botolph by Biſhopſgate	426
Bridewell Precinct	0
St Bridget, vulg. St Bride's	126
St Dunſtan in the Weſt	146
St George in Southwark	263
St Giles by Cripplegate	392
St John in Southwark	272
St Olave in Southwark	287
St Saviour in Southwark	517
St Sepulchre's Pariſh	501
St Thomas in Southwark	208
Trinity in the Minories	24

Chriſtened in the ſeventeen Pariſhes without the Walls 3944 Buried 4962

St Ann in Middleſex——138	St James at Clerkenwell —559	St Mary at Lambeth ——415
Chriſt Church in Surrey —162	St John at Clerkenwell—— 49	St Mary Magd. Bermondſey 361
Chriſt Church in Middleſex 602	St John at Hackney ——211	St Mary at Newington——266
St Dunſtan at Stepney ——352	St John at Wapping——240	St Mary at Rotherhith——258
St George in Bloomſbury —327	St Katherine near the Tower 168	St Mary in Whitechapel —961
St George in Middleſex —366	St Leonard in Shoreditch —887	St Matthew at Bethnal Green 506
St George by Queen's ſquare 362	St Luke in Middleſex —1023	St Paul at Shadwell ——334
St Giles in the Fields ——1037	St Mary at Iſlington ——181	

Chriſtened in the twenty-three Out Pariſhes in Middleſex and Surrey 5992 Buried 9765

St Ann in Weſtminſter —290	St John the Evangeliſt——123	St Mary le Strand —— 38
St Clement Danes— ——358	St Margaret in Weſtminſt. 809	The Precinct of the Savoy 79
St George by Hanover-ſqu.670	St Martin in the Fields — 946	St Paul in Covent Garden 189
St James in Weſtminſter 1002		

Chriſtened in the ten Pariſhes in the City and Liberties of Weſtminſter 3749 Buried 4504

DISEASES and CASUALTIES.

Abortive and Stilborn 588	Fever, Malignant Fever, Scarlet Fever, Spotted Fever, and Purples 2579	Lunatick — —— 79	Broken Limbs —— 8
Aged — ——1512		Meaſles —— —— 156	Bruiſed —— — 3
Ague —— —— 6		Mortification —— 196	Burnt —— — 12
Apoplexy and Suddenly 260		Palſy —— —— 51	Drowned — —— 125
Aſthma and Tiſſick — 313	Fiſtula —— —— 6	Pleuriſy —— —— 18	Exceſſive Drinking — 11
Bedridden — —— 6	Flux —— —— 9	Quinſy —— —— 14	Executed — —— 2
Bleeding — —— 5	French Pox — —— 68	Raſh —— —— 2	Found dead —— 14
Bloody Flux —— 7	Gout —— —— 60	Rheumatiſm — — 10	Killed by Falls and ſeveral other Accidents 66
Burſten and Rupture-- 8	Gravel, Stone, and Strangury — 26	Rickets — —— 6	
Cancer — —— 42		Riſing of the Lights— 6	
Canker —— —— 2	Grief —— —— 5	Scurvy —— —— 2	Killed themſelves —— 44
Childbed — —— 180	Head-ach — —— 2	Small Pox —— —1608	Killed in the Pillory— 1
Choaked with Fat —— 1	Headmoldſhot, Horſhoehead, and Water in the Head 43	Sores and Ulcers —— 12	Murdered — —— 5
Colick, Gripes, and Twiſting of the Guts —— 68		Sore Throat — — — 8	Overlaid — —— 21
		St Anthony's Fire—— 6	Scalded —— —— 9
Cold —— —— 1	Jaundies —— — 112	Stoppage in the Stomach 19	Smothered —— — 1
Conſumption ——4459	Impoſthume — —— 12	Surfeit — —— 1	Starved —— —— 4
Convulſion — ——5718	Inflammation —— 86	Swelling —— — 7	Suffocated — —— 3
Cough and Hooping Cough —— 199	Itch —— —— 2	Teeth —— —— 887	Total 329
	Leproſy —— — 3	Thruſh —— —— 84	
Dropſy — —— 944	Lethargy —— —— 4	Vomiting and Looſneſs 5	
Evil —— —— 17	Livergrown —— — 4	Worms —— —— 9	

CHRISTENED	Males — 7591	BURIED	Males — 10284
	Females 7248		Females 10588
	In all — 14830		In all — 20872

Whereof have died,

Under Two Years of Age 7466	Twenty and Thirty —— 1523	Sixty and Seventy —— 1412
Between Two and Five— 1973	Thirty and Forty —— 1982	Seventy and Eighty —— 976
Five and Ten — —— 605	Forty and Fifty — —— 2069	Eighty and Ninety —— 451
Ten and Twenty —— 572	Fifty and Sixty —— — 1788	Ninety and a Hundred— 55

Decreaſed in the Burials this Year 1045

A General

1757.

A General BILL of all the Chriſtenings and Burials,

From the 14th of December 1756, to the 13th of December 1757.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	23
Alhallows Barkin	65
Alhallows in Bread-ſtreet	10
Alhallows the Great	22
Alhallows in Honey-lane	0
Alhallows the Leſs	17
Alhallows in Lombard-ſtreet	14
Alhallows Staining	13
Alhallows on London Wall	38
St Alphage near Sion College	32
St Andrew Hubbard	6
St Andrew Underſhaft	30
St Andrew Wardrobe	42
St Ann within Alderſgate	24
St Ann in Black Friars	99
St Anthony, vulg. Antholin	2
St Auguſtin, vulg. Auſtin	1
St Bartholomew by Exchange	12
St Benedict, v. Bennet Fink	14
St Bennet Gracechurch	0
St Bennet at Paul's Wharf	23
St Bennet Sherehog	0
St Botolph at Billinſgate	10
Chriſt Church Pariſh	75
St Chriſtopher's Pariſh	11
St Clement near Eaſtcheap	8
St Dionis Backchurch	22
St Dunſtan in the Eaſt	59
St Edmund the King	10
St Ethelburga's Pariſh	25
St Faith under St Paul's	38
St Gabriel in Fenchurch-ſtr.	8
St George in Botolph-lane	12
St Gregory by St Paul's	72
St Helen near Biſhopſgate	18
St James in Duke's Place	20
St James at Garlickhithe	24
St John Baptiſt by Dowgate	28
St John the Evangeliſt	4
St John Zachary	7
St Katherine Coleman	22
St Katherine Creechurch	31
St Laurence Jewry	17
St Laurence Pountney	17
St Leonard in Eaſtcheap	9
St Leonard in Foſter-lane	25
St Magnus by London Bridge	14
St Margaret in Lothbury	17
St Margaret Moſes	3
St Margaret in New Fiſh-ſtr.	1
St Margaret Pattens	9
St Martin Ironmonger-lane	5
St Martin at Ludgate	12
St Martin Orgars	12
St Martin Outwich	9
St Martin Vintrey	24
St Mary Abchurch	9
St Mary in Aldermanbury	14
St Mary Aldermary	13
St Mary le Bow in Cheapſide	13
St Mary Bothaw at Dowgate	11
St Mary Colechurch	0
St Mary Hill by Billinſgate	27
St Mary Magd. in Milk-ſtr.	0
St Mary Magd. Old Fiſh-ſtr.	18
St Mary Mounthaw	23
St Mary Somerſet	17
St Mary Staining	11
St Mary Woolchurch	0
St Mary Woolnoth	15
St Matthew in Friday-ſtreet	4
St Michael Baſſiſhaw	23
St Michael in Cornhill	7
St Michael in Crooked-lane	15
St Michael at Queenhithe	14
St Michael le Quern	10
St Michael Royal	10
St Michael in Wood-ſtreet	2
St Mildred in Bread-ſtreet	7
St Mildred in the Poultry	8
St Nicholas Acons	9
St Nicholas Coleabby	5
St Nicholas Olave	5
St Olave in Hart-ſtreet	36
St Olave in the Old Jewry	11
St Olave in Silver-ſtreet	29
St Pancras in Pancras-lane	3
St Peter in Cheapſide	3
St Peter in Cornhill	12
St Peter near Paul's Wharf	13
St Peter Poor in Broad-ſtr.	12
St Stephen in Coleman-ſtreet	47
St Stephen in Walbrook	5
St Swithin at London-ſtone	9
St Thomas the Apoſtle	6
Trinity Pariſh	12
St Vedaſt, alias Foſter	20

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1086 Buried 1673

St Andrew in Holborn	864
St Bartholomew the Great	33
St Bartholomew the Leſs	15
St Botolph by Alderſgate	197
St Botolph by Aldgate	672
St Botolph by Biſhopſgate	432
Bridewell Precinct	0
St Bridget, vulg. St Bride's	157
St Dunſtan in the Weſt	198
St George in Southwark	272
St Giles by Cripplegate	404
St John in Southwark	311
St Olave in Southwark	255
St Saviour in Southwark	567
St Sepulchre's Pariſh	468
St Thomas in Southwark	256
Trinity in the Minories	31

Chriſtened in the ſeventeen Pariſhes without the Walls 3665 Buried 5132

St Ann in Middleſex——210	St James at Clerkenwell —565	St Mary at Lambeth ——414
Chriſt Church in Surrey —190	St John at Clerkenwell——153	St Mary Magd. Bermondſey 424
Chriſt Church in Middleſex 546	St John at Hackney ——198	St Mary at Newington——283
St Dunſtan at Stepney ——496	St John at Wapping ——299	St Mary at Rotherhith——236
St George in Bloomſbury—351	St Katherine near the Tower 185	St Mary in Whitechapel —980
St George in Middleſex - —439	St Leonard in Shoreditch —828	St Matthew at Bethnal Green465
St George by Queen's ſquare 337	St Luke in Middleſex ——946	St Paul at Shadwell ——415
St Giles in the Fields ——959	St Mary at Iſlington — —194	

Chriſtened in the twenty-three Out Pariſhes in Middleſex and Surrey 5782 Buried 10113

St Ann in Weſtminſter - —263	St John the Evangeliſt - —102	St Mary le Strand—— 58
St Clement Danes — ——325	St Margaret in Weſtminſt. 850	The Precinct of the Savoy 135
St George by Hanover-ſqu. 717	St Martin in the Fields — 875	St Paul in Covent Garden 172
St James in Weſtminſter —898		

Chriſtened in the ten Pariſhes in the City and Liberties of Weſtminſter 3520 Buried 4395

DISEASES and CASUALTIES.

Abortive and Stilborn	569	Fever, Malignant Fever, Scarlet Fever, Spotted Fever, and Purples	2564	Mortification	222	Broken Limbs	4
Aged	1545			Palſy	55	Bruiſed	9
Ague	4			Pleuriſy	13	Burnt	9
Apoplexy and Suddenly	205			Quinſy	14	Drowned	132
Aſthma and Tiſick	401	French Pox	53	Raſh	1	Exceſſive Drinking	7
Bedridden	7	Gout	58	Rheumatiſm	8	Executed	6
Bleeding	5	Gravel, Stone, and Strangury	21	Rickets	16	Found dead	9
Bloody Flux	6			Riſing of the Lights	2	Killed by Falls and ſeveral other Accidents	64
Burſten and Rupture	12	Grief	6	Scald Head	1		
Cancer	58	Head-ach	1	Sciatica	1		
Canker	10	Headmoldſhot, Horſhoehead, and Water in the Head	42	Scurvy	3	Killed themſelves	40
Childbed	175			Small Pox	3296	Licked by a mad Dog	2
Colick, Gripes, and Twiſting of the Guts	64	Jaundies	98	Sores and Ulcers	16	Murdered	3
		Impoſthume	13	Sore Throat	22	Overlaid	22
Cold	1	Inflammation	76	St Anthony's Fire	3	Poiſoned	1
Conſumption	3973	Itch	3	Stoppage in the Stomach	16	Scalded	2
Convulſion	5211	Leproſy	1	Surfeit	2	Smothered	1
Cough and Hooping Cough	239	Lethargy	7	Swelling	5	Starved	2
		Livergrown	2	Swine Pox	1	Suffocated	5
Dropſy	864	Lunatick	77	Teeth	766		
Evil	14	Meaſles	24	Thruſh	78	Total	318
Fiſtula	11	Miſcarriage	6	Vomiting and Looſneſs	11		
Flux	6			Worms	11		

CHRISTENED	Males — 7195	BURIED	Males — 10821
	Females 6858		Females 10492
	In all 14053		In all — 21313

Whereof have died,

Under Two Years of Age	7095	Thirty and Forty —	1906	Seventy and Eighty	1024
Between Two and Five—	2411	Forty and Fifty ——	1906	Eighty and Ninety—	431
Five and Ten —— ——	948	Fifty and Sixty ——	1710	Ninety and a Hundred	74
Ten and Twenty ——	687	Sixty and Seventy —	1418	A Hundred — ——	2
Twenty and Thirty——	1695				

A Hundred and One—	2
A Hundred and Two —	1
A Hundred and Three—	1
A Hundred and Five —	2

Increaſed in the Burials this Year 441

1758.

A General BILL of all the Chriſtenings and Burials,

From the 13th of December 1757, to the 12th of December 1758.

According to the Report made to the King's moſt excellent Majeſty,

By the Company of Pariſh Clerks of LONDON, &c.

	Bur.
St ALBAN in Wood-ſtreet	13
Alhallows Barkin	53
Alhallows in Bread-ſtreet	8
Alhallows the Great	29
Alhallows in Honey-lane	0
Alhallows the Leſs	11
Alhallows in Lombard-ſtreet	9
Alhallows Staining	12
Alhallows on London Wall	28
St Alphage near Sion College	31
St Andrew Hubbard	5
St Andrew Underſhaft	33
St Andrew Wardrobe	34
St Ann within Alderſgate	31
St Ann in Black Friars	81
St Anthony, vulg. Antholin	12
St Auguſtin, vulg. Auſtin	1
St Bartholomew by Exchange	6
St Benedict, v. Bennet Fink	6
St Bennet Gracechurch	1
St Bennet at Paul's Wharf	34
St Bennet Sherehog	2
St Botolph at Billinſgate	4
Chriſt Church Pariſh	47
St Chriſtopher's Pariſh	11
St Clement near Eaſtcheap	8
St Dionis Backchurch	8
St Dunſtan in the Eaſt	53
St Edmund the King	15
St Ethelburga's Pariſh	11
St Faith under St Paul's	37
St Gabriel in Fenchurch-ſtr.	5
St George in Botolph-lane	10
St Gregory by St Paul's	72
St Helen near Biſhopſgate	17
St James in Duke's Place	13
St James at Garlickhithe	14
St John Baptiſt by Dowgate	12
St John the Evangeliſt	1
St John Zachary	10
St Katherine Coleman	25
St Katherine Creechurch	32
St Laurence Jewry	17
St Laurence Pountney	5
St Leonard in Eaſtcheap	10
St Leonard in Foſter-lane	29
St Magnus by London Bridge	14
St Margaret in Lothbury	14
St Margaret Moſes	6
St Margaret in New Fiſh-ſtr.	0
St Margaret Pattens	8
St Martin Ironmonger-lane	5
St Martin at Ludgate	27
St Martin Orgars	13
St Martin Outwich	7
St Martin Vintrey	11
St Mary Abchurch	9
St Mary in Aldermanbury	14
St Mary Aldermary	20
St Mary le Bow in Cheapſide	10
St Mary Bothaw at Dowgate	6
St Mary Colechurch	0
St Mary Hill by Billinſgate	21
St Mary Magd. in Milk-ſtr.	0
St Mary Magd. Old Fiſh-ſtr.	14
St Mary Mounthaw	6
St Mary Somerſet	13
St Mary Staining	10
St Mary Woolchurch	0
St Mary Woolnoth	17
St Matthew in Friday-ſtreet	2
St Michael Baſſiſhaw	19
St Michael in Cornhill	8
St Michael in Crooked-lane	17
St Michael at Queenhithe	23
St Michael le Quern	8
St Michael Royal	9
St Michael in Wood-ſtreet	2
St Mildred in Bread-ſtreet	9
St Mildred in the Poultry	8
St Nicholas Acons	4
St Nicholas Coleabby	5
St Nicholas Olave	9
St Olave in Hart-ſtreet	21
St Olave in the Old Jewry	10
St Olave in Silver-ſtreet	19
St Pancras in Pancras-lane	1
St Peter in Cheapſide	3
St Peter in Cornhill	5
St Peter near Paul's Wharf	20
St Peter Poor in Broad-ſtr.	8
St Stephen in Coleman-ſtreet	47
St Stephen in Walbrook	10
St Swithin at London-ſtone	7
St Thomas the Apoſtle	8
Trinity Pariſh	14
St Vedaſt, alias Foſter	21

Chriſtened in the ninety-ſeven Pariſhes within the Walls 1089 Buried 1468

St Andrew in Holborn	643
St Bartholomew the Great	25
St Bartholomew the Leſs	16
St Botolph by Alderſgate	159
St Botolph by Aldgate	553
St Botolph by Biſhopſgate	341
Bridewell Precinct	0
St Bridget, vulg. St Bride's	126
St Dunſtan in the Weſt	107
St George in Southwark	215
St Giles by Cripplegate	403
St John in Southwark	231
St Olave in Southwark	263
St Saviour in Southwark	455
St Sepulchre's Pariſh	415
St Thomas in Southwark	177
Trinity in the Minories	22

Chriſtened in the ſeventeen Pariſhes without the Walls 3670 Buried 4151

St Ann in Middleſex ——140	St James at Clerkenwell —454	St Mary at Lambeth — —325
Chriſt Church in Surrey —143	St John at Clerkenwell—— 68	St Mary Magd. Bermondſey 332
Chriſt Church in Middleſex 454	St John at Hackney———205	St Mary at Newington ——177
St Dunſtan at Stepney ——375	St John at Wapping———221	St Mary at Rotherhith ——177
St George in Bloomſbury—316	St Katherine near the Tower 159	St Mary in Whitechapel —768
St George in Middleſex - —346	St Leonard in Shoreditch —686	St Matthew at Bethnal Green 415
St George by Queen's ſquare291	St Luke in Middleſex ——826	St Paul at Shadwell ———324
St Giles in the Fields ——796	St Mary at Iſlington———197	

Chriſtened in the twenty-three Out Pariſhes in Middleſex and Surrey 5976 Buried 8195

St Ann in Weſtminſter —197	St John the Evangeliſt - —152	St Mary le Strand ——— 61
St Clement Danes ———274	St Margaret in Weſtminſt. 665	The Precinct of the Savoy 92
St George by Hanover-ſqu. 612	St Martin in the Fields — 784	St Paul in Covent Garden 124
St James in Weſtminſter—801		

Chriſtened in the ten Pariſhes in the City and Liberties of Weſtminſter 3474 Buried 3762.

DISEASES and CASUALTIES.

Abortive and Stilborn	597	Evil	7	Lunatick	72	Broken Limbs	3
Aged	1397	Fever, Malignant Fever, Scarlet Fever, Spotted Fever, and Purples	2472	Meaſles	696	Bruiſed	3
Ague	1			Miſcarriage	2	Burnt	6
Apoplexy and Suddenly	191			Mortification	154	Choaked with Fat	1
Aſthma and Tiſſick	294			Palſy	66	Drowned	109
Bedridden	4	Fiſtula	5	Pleuriſy	17	Exceſſive Drinking	2
Bleeding	8	Flux	7	Quinſy	21	Executed	14
Bloody Flux	5	French Pox	46	Raſh	4	Found dead	4
Burſten and Rupture	8	Gout	39	Rheumatiſm	10	Froze to Death	2
Cancer	34	Gravel, Stone, and Strangury	19	Rickets	14	Killed by Falls and ſeveral other Accidents	58
Canker	8	Grief	5	Riſing of the Lights	1		
Chicken Pox	1	Headmoldſhot, Horſhoehead, and Water in the Head	40	Small Pox	1273	Killed themſelves	30
Childbed	185			Sores and Ulcers	14	Murdered	5
Colick, Gripes, and Twiſting of the Guts	50	Jaundies	87	Sore Throat	5	Overlaid	26
		Impoſthume	9	St Anthony's Fire	4	Scalded	3
Conſumption	3411	Inflammation	54	Stoppage in the Stomach	13	Smothered	3
Convulſion	4417	Itch	2	Teeth	644	Starved	4
Cough and Hooping Cough	84	Leproſy	2	Thruſh	91	Suffocated	9
		Lethargy	4	Tympany	2		
Diabetes	2	Livergrown	1	Vomiting and Looſneſs	7	Total	282
Dropſy	682			Worms	6		

CHRISTENED	Males — 7347	BURIED	Males — 8931
	Females 6862		Females 8645
	In all — 14209		In all — 17576

Whereof have died,

Under Two Years of Age	5971	Twenty and Thirty	1362	Sixty and Seventy	1208	A Hundred and Two	2
Between Two and Five	1795	Thirty and Forty	1589	Seventy and Eighty	961	A Hundred and Three	1
Five and Ten	717	Forty and Fifty	1606	Eighty and Ninety	370	A Hundred and Four	1
Ten and Twenty	556	Fifty and Sixty	1368	Ninety and a Hundred	68	A Hundred and Six	1

Decreaſed in the Burials this Year 3737

Natural

NATURAL and POLITICAL

OBSERVATIONS &c.

CHAP. I.

Of the Bills of Mortality, their beginning and progreſs.

THE firſt of the continued weekly bills of mortality extant at the pariſh clerks hall begins the twenty ninth of December 1603, being the firſt year of King JAMES his reign; ſince when a weekly account hath been kept there of burials and chriſtnings. It is true, there were bills before, viz. for the years 1592,-93,-94; but ſo interrupted ſince, that I could not depend upon the ſufficiency of them, rather relying upon thoſe accounts, which have been kept ſince in order, as to all the uſes I ſhall make of them.

2. I believe, that the riſe of keeping theſe accounts was taken from the plague: for the ſaid bills (for ought appears) firſt began in the ſaid year 1592, being a time of great mortality; and, after ſome diſuſe, were reſumed again in the year 1603, after the great plague then happening likewiſe.

3. Theſe bills were printed and publiſhed, not only every week, on Thurſdays, but alſo a general account of the whole year was given in upon the Thurſday before Chriſtmas-day: which ſaid general accounts have been preſented in the ſeveral manners following, viz. from the year 1603 to the year 1624, incluſive, according to the pattern here inſerted.

1623. 1624.

The general bill for the whole year, of all the burials and chriſtnings, as well within the city of London, and the liberties thereof, as in the nine out pariſhes adjoining to the city, with the Peſt-houſe belonging to the ſame: from Thurſday the 18th of December 1623, to Thurſday the 16th of December 1624, according to the report made to the King's moſt Excellent Majeſty by the company of the pariſh-clerks of London.

BURIED this year in the fourſcore and ſeventy pariſhes of London within the walls, } 3386

Whereof of the plague, —1

Buried this year in the ſixteen pariſhes of London, and the Peſt-houſe, being within the liberties, and without the walls, } 5924
Whereof, of the plague, —5
The whole ſum of all the burials in London, and the liberties thereof, is this year, } 9310
Whereof, of the plague, —6
Buried of the plague without the liberties in Middleſex and Surrey, this whole year, } 0
Chriſtened in London, and the liberties thereof, this year, —6368
Buried this year in the nine out-pariſhes, adjoining to London, and out of the freedom, } 2900
Whereof, of the plague, —5
The total of all the burials in the places aforeſaid, is —12210
Whereof, of the plague, —11
Chriſtened in all the aforeſaid places this year, —8299
Pariſhes clear of the plague, —116
Pariſhes that have been infected this year, —6

4. In the year 1625, every pariſh was particularized, as in the following bill; where note, that this next year of plague cauſed the augmentation and correction of the bills; as the former year of plague did the very being of them.

1624. 1625.

A general, or great bill for this year, of the whole number of burials, which have been buried of all diſeaſes, and alſo of the plague in every pariſh within the city of London, and the liberties thereof; as alſo in the nine out-pariſhes adjoining to the ſaid city; with the Peſt-houſe belonging to the ſame: from Thurſday the 16th day of December, 1624, to Thurſday the 15th day of December, 1625, according to the report made to the King's moſt Excellent Majeſty by the company of pariſh-clerks of London.

LONDON,	Bur.	Plag.
ALBANS in Wood-ſtreet	188	78
Allhallows Barking	397	263
Allhallows Bread-ſtreet	34	14
Allhallows the Great	442	302
Allhallows Hony-lane	18	8
Allhallows the Leſs	259	205
Allhallows Lombard-ſtreet	86	44
Allhallows Stainings	183	138
Allhallows the Wall	301	155
Alphage Cripple-gate	240	190
Andrew-Hubbard	146	101
Andrews Underſhaft	219	149
Andrews by Wardrobe	373	191
Anns at Alderſgate	196	128

LONDON,	Bur.	Plag.
Anns Black-Fryars	336	215
Antholins Pariſh	62	31
Auſtins Pariſh	72	40
Bartholomew at the Exchange	52	24
Bennets Fink	108	57
Bennets Grace-Church	48	14
Bennets at Paul's Wharf	226	131
Bennets Shearhog	24	8
Botolphs Billings-gate	99	66
Chriſt's-Church Pariſh	611	371
Chriſtopher's Pariſh	48	28
Clements by Eaſtcheap	87	72
Dionys Back-Church	99	59
Dunſtans in the Eaſt	335	225
Edmunds Lumbard-ſtreet	78	49
Ethelborow in Biſhops-gate	205	101
St. Faiths	89	45
St. Foſters in Foſter-lane	149	102
Gabriel Fen-Church	71	54
George Botolphs-lane	30	19
Gregories by Paul's	296	196
Hellens in Biſhops-gate ſtreet	136	71
James by Garlick-hith	180	109
John Baptiſt	122	79
John Evangeliſt	7	0
John Zacharies	143	97
James Dukes-place	310	154
Katherine Colemanſtreet	26	175
Katherine Cree-Church	886	373
Lawrence in the Jewry	91	55
Lawrence Pountney	206	127
Leonards Eaſtcheap	55	26
Leonards Foſter-lane	292	209
Magnus Pariſh by the Bridge	137	85
Margarets Lothbury	114	64
Margarets Moſes	37	25
Margarets New Fiſhſtreet	123	82
Margarets Pattons	77	50
Mary Ab-Church	98	58
Mary Aldermanbury	126	79
Mary Aldermary	92	54
Mary le Bow	35	19
Mary Bothaw	22	14
Mary Coal-Church	26	11
Mary at the Hill	152	84

LONDON,	Bur.	Plag.
Mary Mounthaw	76	58
Mary Sommerſet	270	192
Mary Stainings	70	44
Mary Woolchurch	58	35
Mary Woolnoth	82	50
Martins Ironmonger-lane	25	18
Martins at Ludgate	254	164
Martins Orgars	88	47
Martins Outwich	60	30
Martins in the Vintry	339	208
Matthew Friday-ſtreet	24	11
Maudlins in Milk-ſtreet	402	23
Maudlins Old-fiſh-ſtreet	225	142
Michael Baſſiſhaw	199	139
Michael Cornhill	159	79
Michael Crooked-lane	144	91
Michael Queen-hith	215	157
Michael in the Quern	53	30
Michael in the Royal	111	61
Michael in Wood-ſtreet	189	68
Mildreds Bread-ſtreet	60	44
Mildreds Poultrey	94	45
Nicholas Acons	33	13
Nicholas Coal-Abby	87	67
Nicholas Olaves	70	43
Olaves in Hart-ſtreet	266	195
Olaves in the Jewry	43	25
Olaves in Silver-ſtreet	274	103
Pantras by Soper-lane	17	8
Peters in Cheap	68	44
Peters in Cornhill	918	78
Peters at Paul's Wharf	97	68
Peters Poor in Broad-ſtreet	52	27
Stevens in Coalman-ſtreet	506	350
Stevens in Walbrook	25	13
Swithins at London-ſtone	99	60
Thomas Apoſtles	141	107
Trinity Pariſh	148	87

Buried within the 97 pariſhes within the walls of all diſeaſes, } 14340

Whereof, of the plague, —9197

Andrews

	Bur.	Plag.
Andrews in Holborn	2190	1636
Bartholomew the Great	516	360
Bartholomew the Leſs	111	65
Brides Pariſh	1481	1031
Botolph Aldgate	2573	1653
Bridewel Precinct	213	152
Botolphs Biſhops-gate	2334	714
Botolphs Alders-gate	578	307
Dunſtans the Weſt	860	642
Georges Southwark	1608	912
Giles Cripplegate	3988	2338
Olaves in Southwark	3689	2600
Saviours in Southwark	2746	1671
Sepulchres Pariſh	3425	2420
Thomas in Southwark	336	277
Trinity in the Minories	131	87
At the Peſthouſe	194	189

Buried in the 16 pariſhes without the walls, ſtanding part within the liberties, and part without, in Middleſex, and Surrey, and at the Peſt-houſe. 26972

Whereof, of the plague, —17153

Buried in the nine out-pariſhes.

	Bur.	Plag.
Clements Temple-bar	1284	755
Giles in the Fields	1333	947
James at Clarken-well	1191	903
Katherines by the Tower	998	744
Leonards in Shoreditch	1995	1407
Martins in the Fields	1470	973
Mary White-chapel	3305	2272
Magdalens Bermondſey	1127	889
Savoy Pariſh	250	176

Buried in the nine out-pariſhes, in Middleſex and Surrey, —12953

Whereof, of the plague, — 9067

The total of all the burials of all diſeaſes, within the walls, without the walls, in the liberties, in Middleſex and Surrey: with the nine out-pariſhes, and the Peſt-houſe, 54265

Whereof, buried of the plague, this preſent year, is —35417

Chriſtnings this preſent year, is — 6983

Pariſhes clear this year, is — 1

Pariſhes infected this year, is — 121

5. In

5. In the year 1626, the city of Weſtminſter in imitation of London was inſerted. The groſs account of burials and chriſtenings, with diſtinction of the plague, being only taken notice of therein; the fifth, or laſt canton, or lined-ſpace, of the ſaid bill, being varied into the form following, viz.

In Weſtminſter this year { Buried 471 / Plague 13 / Chriſtnings 361

6. In the year 1629, an account of the diſeaſes and caſualties, whereof any died, together with the diſtinction of males and females, making the ſixth canton of the bill, was added in manner following.

The canton of caſualties; and of the bill for the year 1632, *being of the ſame form with that of* 1629.

The diſeaſes and caſualties this year, being 1632.

ABORTIVE and ſtillborn	415	French pox	12
Affrighted	1	Gangrene	5
Aged	628	Gout	4
Ague	43	Grief	11
Apoplex and Meagrim	17	Jaundice	43
Bit with a mad dog	1	Jaw faln	78
Bleeding	3	Impoſthume	44
Bloody flux, ſcowring, and flux	348	Killed by ſeveral accidents	6
Bruiſed, iſſues, ſores, and ulcers,	28	King's evil	38
Burnt and ſcalded	5	Lethargy	2
Burſt and rupture	9	Livergrown	87
Cancer and wolf	10	Lunatick	5
Canker	1	Made away themſelves	15
Childbed	171	Meaſles	80
Chriſomes and infants	2268	Murthered	7
Cold and cough	55	Overlaid, and ſtarved at nurſe	7
Colick, ſtone, ſtrangury	56	Palſy	25
Conſumption	1797	Piles	1
Convulſion	241	Plague	8
Cut of the Stone	5	Planet	13
Dead in the ſtreet, and ſtarved	6	Pleureſy and ſpleen	36
Dropſy and ſwelling	267	Purples and ſpotted fever	38
Drowned	4	Quinſy	7
Executed and preſt to death	38	Riſing of the lights	98
Falling ſickneſs	17	Sciatica	1
Fever	1108	Scurvy and itch	9
Fiſtula	13	Suddenly	62
Flox and ſmall pox	531	Surfeit	86

Swine

Swine pox	6	Tiſſick	34
Teeth	470	Vomiting	1
Thruſh and ſore-mouth	40	Worms	27
Tympany	13		

Chriſtened	Males	4994	Buried	Males	4932
	Females	4590		Females	4603
	In all	9584		In all	9535
			Whereof, of the plague		8

Increaſed in the burials in the 122 pariſhes, and at the Peſt-houſe this year, 993
Decreaſed of the plague in the 122 pariſhes, and at the Peſt-houſe this year, 662

7. In the year 1636, the account of the burials and chriſtnings, in the pariſhes of Iſlington, Lambeth, Stepney, Newington, Hackney, and Redriff were added in the manner following, making a ſeventh canton, viz.

In Margarets Weſtminſter	Chriſtned	440	Newington	Chriſtned	99
	Buried	890		Buried	181
	Plague	0		Plague	0
Iſlington	Chriſtned	36	Hackney	Chriſtned	30
	Buried	113		Buried	91
	Plague	0		Plague	0
Lambeth	Chriſtned	132	Redriff	Chriſtned	16
	Buried	220		Buried	48
	Plague	0		Plague	0
Stepney	Chriſtned	892			
	Buried	1486			
	Plague	0			

The total of all the burials in the ſeven laſt pariſhes this year,	2958
Whereof, of the plague,	0
The total of all the chriſtnings,	1645

8. Covent-Garden being made a pariſh, the nine out-pariſhes were called the ten out-pariſhes, the which in former years were but eight.

9. In the year 1660, the laſt-mentioned ten pariſhes, with Weſtminſter, Iſlington, Lambeth, Stepney, Newington, Hackney, and Redriff, are entered under two diviſions, viz. the one containing the twelve pariſhes lying in Middleſex and Surrey, and the other the five pariſhes within the city and liberties of Weſtminſter, viz. St. Clement Danes, St. Paul's Covent-Garden, St. Martin's in the Fields, St. Mary-Savoy, and St. Margaret's Weſtminſter.

10. We have hitherto deſcribed the ſeveral ſteps, whereby the bills of mortality are come up to their preſent ſtate: we come next to ſhew how they are made and compoſed, which is in this manner, viz. When any one dies, then, either by tolling, or ringing of a bell, or by beſpeaking of a grave of the ſexton, the ſame is known to the ſearchers, correſponding with the ſaid ſexton.

11. The

11. The ſearchers hereupon (who are antient matrons, ſworn to their office) repair to the place where the dead corps lies, and by view of the ſame, and by other enquiries, they examine by what diſeaſe or caſualty the corps died. Hereupon they make their report to the pariſh clerk, and he, every Tueſday night, carries in an account of all the burials and chriſtnings happening that week, to the clerk of the hall. On Wedneſday the general account is made up and printed, and on Thurſday publiſhed and diſperſed to the ſeveral families, who will pay four ſhillings per annum for them.

12. Memorandum, that although the general yearly bills have been ſet out in the ſeveral varieties aforementioned, yet the original entries in the hall-books were as exact in the very firſt year, as to all particulars, as now; and the ſpecifying of caſualties and diſeaſes was probably more.

General obſervations upon the caſualties.

IN my diſcourſes upon theſe bills, I ſhall firſt ſpeak of the caſualties; then give my obſervations with reference to the places and pariſhes comprehended in the bills; and next of the years and ſeaſons.

1. There ſeems to be good reaſon, why the magiſtrate ſhould himſelf take notice of the numbers of burials and chriſtnings, viz. to ſee whether the city increaſe or decreaſe in people; whether it increaſe proportionably with the reſt of the nation; whether it be grown big enough, or too big, &c. But why the ſame ſhould be made known to the people, otherwiſe than to pleaſe them, as with a curioſity, I ſee not.

2. Nor could I ever yet learn (from the many I have aſked, and thoſe not of the leaſt ſagacity) to what purpoſe the diſtinction between males and females is inſerted, or at all taken notice of? or why that of marriages was not equally given in? Nor is it obvious to every body, why the account of caſualties (whereof we are now ſpeaking) is made? The reaſon, which ſeems moſt obvious for this latter, is, that the ſtate of health in the city may at all times appear.

3. Now it may be objected, that the ſame depends moſt upon the accounts of epidemical diſeaſes, and upon the chief of them all, the plague. Wherefore the mention of the reſt ſeems only matter of curioſity.

4. But to this we anſwer, that the knowledge even of the numbers, which die of the plague, is not ſufficiently deduced from the meer report of the ſearchers, which only the bills afford; but from other ratiocinations, and comparings of the plague with ſome other caſualties.

5. For we ſhall make it probable, that in the years of plague, a quarter part more dies of that diſeaſe than are ſet down: the ſame we ſhall prove by other caſualties. Wherefore, if it be neceſſary to impart to the world a good account of ſome few caſualties, which ſince it cannot well be done without giving an account of them all, then is our common practice of ſo doing very apt and rational.

6. Now, to make theſe corrections upon the, perhaps, ignorant and careleſs ſearchers reports, I conſidered firſt of what authority they were of themſelves; that is, whether any credit at all were to be given to their diſtinguiſhments: and finding that many of the caſualties were but matter of ſenſe, as whether a child were abortive

abortive or ſtillborn; whether men were aged, that is to ſay, above ſixty years old, or thereabouts, when they died, without any curious determination; whether ſuch aged perſons died purely of age, as for that the innate heat was quite extinct, or the radical moiſture quite dried up (for I have heard ſome candid phyſicians complain of the darkneſs, which themſelves were in hereupon) I ſay, that theſe diſtinguiſhments being but matter of ſenſe, I concluded the ſearchers report might be ſufficient in the caſe.

7. As for conſumptions, if the ſearchers do but truly report (as they may) whether the dead corps were very lean and worn away, it matters not to many of our purpoſes, whether the diſeaſe were exactly the ſame, as phyſicians define it in their books. Moreover, in caſe a man of ſeventy five years old died of a cough (of which had he been free, he might have poſſibly lived to ninety) I eſteem it little error (as to many of our purpoſes) if this perſon be in the table of caſualties reckoned among the aged, and not placed under the title of coughs.

8. In the matters of infants I would deſire but to know clearly, what the ſearchers mean by infants; as whether children, that cannot ſpeak, as the word infant ſeems to ſignify, or children under two or three years old; although I ſhould not be ſatisfied, whether the infant died of wind, or of teeth, or of the convulſion, &c. or were choaked with phlegm, or elſe of teeth, convulſion, and ſcowring, apart, or together, which, they ſay, do often cauſe one another; for, I ſay, it is ſomewhat to know how many die uſually before they can ſpeak, or how many live paſt any aſſigned number of years.

9. I ſay, it is enough, if we know from the ſearchers but the moſt predominant ſymptoms; as that one died of the head-ach, who was ſorely tormented with it, though the phyſicians were of opinion, that the diſeaſe was in the ſtomach. Again, if one died ſuddenly, the matter is not great, whether it be reported in the bills, ſuddenly, apoplexy, or planet-ſtrucken, &c.

10. To conclude, in many of theſe caſes the ſearchers are able to report the opinion of the phyſician, who was with the patient, as they receive the ſame from the friends of the defunct: and in very many caſes, ſuch as drowning, ſcalding, bleeding, vomiting, making away themſelves, lunatics, ſores, ſmall-pox, &c. their own ſenſes are ſufficient, and the generality of the world are able pretty well to diſtinguiſh the gout, ſtone, dropſy, falling-ſickneſs, palſy, agues, pleuriſy, rickets, one from another.

11. But now as for thoſe caſualties, which are apteſt to be confounded and miſtaken, I ſhall in the enſuing diſcourſe preſume to touch upon them ſo far, as the learning of theſe bills hath enabled me.

12. Having premiſed theſe general advertiſements, our firſt obſervation upon the caſualties ſhall be, that in twenty years there dying of all diſeaſes and caſualties 229250, that 71124 died of the thruſh, convulſion, rickets, teeth and worms; and as abortives, chryſomes, infants, livergrown, and overlaid; that is to ſay, that about $\frac{1}{3}$ of the whole died of thoſe diſeaſes, which we gueſs did all light upon children under four or five years old.

13. There died alſo of the ſmall-pox, ſwine-pox, and meaſles, and of worms without convulſions, 12210, of which number we ſuppoſe likewiſe, that about $\frac{1}{2}$ might be children under ſix years old. Now, if we conſider that ſixteen of the ſaid

229250 died of that extraordinary and grand caſualty, the plague, we ſhall find that about thirty ſix per centum of all quick conceptions died before ſix years old.

14. The ſecond obſervation is, that of the ſaid 229250 dying of all diſeaſes, there died of acute diſeaſes (the plague excepted) but about 50000, or $\frac{2}{7}$ parts. The which proportion doth give a meaſure of the ſtate, and diſpoſition of this climate and air as to health; theſe acute and epidemical diſeaſes happening ſuddenly and vehemently, upon the like corruptions and alterations in the air.

15. The third obſervation is, that of the ſaid 229250, about ſeventy died of chronical diſeaſes, which ſhews (as I conceive) the ſtate and diſpoſition of the country (including as well its food as air) in reference to health, or rather to longevity: for as the proportion of acute and epidemical diſeaſes ſhews the aptneſs of the air to ſudden and vehement impreſſions; ſo the chronical diſeaſes ſhew the ordinary temper of the place: ſo that upon the proportion of chronical diſeaſes ſeems to hang the judgment of the fitneſs of the country for long life. For, I conceive, that in countries ſubject to great epidemical ſweeps, men may live very long, but, where the proportion of the chronical diſtempers is great, it is not likely to be ſo; becauſe men being long ſick, and always ſickly, cannot live to any great age, as we ſee in ſeveral ſorts of metal-men, who, although they are leſs ſubject to acute diſeaſes than others, yet ſeldom live to be old, that is, not to reach unto thoſe years, which DAVID ſays is the age of man.

16. The fourth obſervation is, that of the ſaid 229250, not 4000 died of outward griefs, as of cancers, fiſtulas, ſores, ulcers, broken and bruiſed limbs, impoſthumes, itch, king's-evil, leproſy, ſcald-head, ſwine-pox, wens, &c. viz. not one in ſixty.

17. In the next place, whereas many perſons live in great fear and apprehenſion of ſome of the more formidable and notorious diſeaſes following; I ſhall only ſet down how many died of each: that the reſpective numbers, being compared with the total 229250, thoſe perſons may the better underſtand the hazard they are in.

Table of notorious diſeaſes.

Apoplexy	1306
Cut of the ſtone	38
Falling-ſickneſs	74
Dead in the ſtreets	243
Gout	134
Head-ach	51
Jaundice	998
Lethargy	67
Leproſy	6
Lunatic	158
Overlaid and ſtarved	529
Palſy	423
Rupture	201
Stone and ſtrangury	863
Sciatica	5
Suddenly	434

Table of caſualties.

Bleeding	69
Burnt and ſcalded	125
Drowned	829
Exceſſive drinking	2
Frighted	22
Grief	279
Hanged themſelves	222
Killed by ſeveral accidents	1021
Murdered	86
Poiſoned	14
Smothered	26
Shot	7
Starved	51
Vomiting	136

18. In

18. In the foregoing obſervations we ventured to make a ſtandard of the healthfulneſs of the air from the proportion of acute and epidemical diſeaſes, and of the wholſomneſs of the food from that of the chronical. Yet, foraſmuch as neither of them alone do ſhew the longevity of the inhabitants, we ſhall in the next place come to the more abſolute ſtandard and correction of both, which is the proportion of the aged, viz. 15757 to the total 229250; that is, of about 1 to 15, or 7 per cent. Only the queſtion is, what number of years the ſearchers call aged, which I conceive muſt be the ſame that DAVID calls ſo, viz. 70. For no man can be ſaid to die properly of age, who is much leſs. It follows from hence, that if in any other country more than ſeven of the 100 live beyond 70, ſuch country is to be eſteemed more healthful than this of our city.

19. Before we ſpeak of particular caſualties, we ſhall obſerve, that among the ſeveral caſualties ſome bear a conſtant proportion unto the whole number of burials; ſuch are chronical diſeaſes, and the diſeaſes whereunto the city is moſt ſubject; as for example, conſumptions, dropſies, jaundice, gout, ſtone, palſy, ſcurvy, riſing of the lights or mother, rickets, aged, agues, fevers, bloody-flux and ſcowring: nay, ſome accidents, as grief, drowning, men's making away themſelves, and being killed by ſeveral accidents, &c. do the like: whereas epidemical and malignant diſeaſes, as the plague, purples, ſpotted fever, ſmall-pox and meaſles do not keep that equality; ſo as in ſome years, or months, there died ten times as many as in others.

CHAP. III.

Of particular caſualties.

1. MY firſt obſervation is, that few are ſtarved. This appears, for that of the 229250, which have died, we find not above fifty one to have been ſtarved, excepting helpleſs infants at nurſe, which being cauſed rather by careleſsneſs, ignorance, and infirmity of the milch-women, is not properly an effect or ſign of want of food in the country, or of means to get it.

2. The obſervation, which I ſhall add hereunto, is, that the vaſt number of beggars, ſwarming up and down this city, do all live, and ſeem to be moſt of them healthy and ſtrong: whereupon I make this queſtion, whether, ſince they do all live by begging, that is, without any kind of labour; it were not better for the ſtate to keep them, even although they earned nothing? that ſo they might live regularly, and not in that debauchery, as many beggars do; and that they might be cured of their bodily impotencies, or taught to work, each according to his condition and capacity; or by being employed in ſome work (not better undone) might be accuſtomed and fitted for labour.

3. To this ſome may object, that beggars are now maintained by voluntary contributions, whereas in the other way the ſame muſt be done by general tax; and conſequently, the objects of charity would be removed and taken away.

4. To which we anſwer, that in Holland, although no where fewer beggars appear to charm up commiſeration in the credulous, yet no where is there greater

or more frequent charity: only indeed the magiſtrate is both the beggar, and the diſpoſer of what is got by begging; ſo as all givers have a moral certainty, that their charity ſhall be well applied.

5. Moreover, I queſtion, whether what we give to a wretch, that ſhews us lamentable ſores and mutilations, be always out of the pureſt charity? that is, purely for GOD's ſake; for as much as when we ſee ſuch objects, we then feel in ourſelves a kind of pain and paſſion by conſent, of which we eaſe ourſelves, when we think we eaſe them, with whom we ſympathized; or elſe we beſpeak aforehand the like commiſeration in others towards ourſelves, when we ſhall (as we fear we may) fall into the like diſtreſs.

6. We have ſaid, 'twere better the public ſhould keep the beggars, though they earned nothing, &c. But moſt men will laugh to hear us ſuppoſe, that any able to work (as indeed moſt beggars are, in one kind of meaſure or another) ſhould be kept without earning any thing. But we anſwer, that if there be but a certain proportion of work to be done, and that the ſame be already done by the non-beggars, then to employ the beggars about it, will but transfer the want from one hand to another; nor can a learner work ſo cheap as a ſkilful practiſed artiſt can. As for example, a practiſed ſpinner ſhall ſpin a pound of wool, worth two ſhillings, for ſix-pence; but a learner, undertaking it for three-pence, ſhall make the wool indeed into yarn, but not worth twelve-pence.

7. This little hint is the model of the greateſt work in the world, which is the making of England as conſiderable for trade as Holland; for there is but a certain proportion of trade in the world, and Holland is prepoſſeſſed of the greateſt part of it, and is thought to have more ſkill and experience to manage it. Wherefore to bring England into Holland's condition, as to this particular, is the ſame, as to ſend all the beggars about London into the Weſt Country to ſpin, where they ſhall only ſpoil the clothiers wool, and beggar the preſent ſpinners at beſt; but, at worſt, put the whole trade of the country to a ſtand, until the Hollander being more ready for it, have ſnapt that with the reſt.

8. My next obſervation is, that but few are murthered, viz. not above 86 of the 229250, which have died of other diſeaſes and caſualties; whereas in Paris few nights ſcape without their tragedy.

9. The reaſons of this we conceive to be two: one is the government and guard of the city by citizens themſelves, and that alternately; no man ſettling into a trade for that employment. And the other is the natural and cuſtomary abhorrence of that inhuman crime, and all bloodſhed, by moſt Engliſhmen: for of all, that are executed, few are for murther. Beſides, the great and frequent revolutions and changes in government ſince the year 1650, have been with little bloodſhed; the uſurpers themſelves having executed few in compariſon, upon the account of diſturbing their innovations.

10. In brief, when any dead body is found in England, no algebraiſt, or uncypherer of letters, can uſe more ſubtile ſuppoſitions and variety of conjectures to find out the demonſtration or cypher, than every common unconcerned perſon doth to find out the murtherers, and that for ever, until it be done.

11. The lunatics are alſo but few, viz. 158 in 229250, though I fear many more than are ſet down in our bills, few being entered for ſuch, but thoſe, who

who die at Bethlehem; and there all ſeem to die of their lunacy, who died lunatics; for there is much difference in computing the number of lunatics, that die (though of fevers and all other diſeaſes, unto which lunacy is no ſuperſedeas) and thoſe, that die by reaſon of their madneſs.

12. So that, this caſualty being ſo uncertain, I ſhall not force myſelf to make any inference from the numbers and proportions we find in our bills concerning it: only I dare enſure any man at this preſent, well in his wits, for one in a thouſand, that he ſhall not die a lunatic in Bethlehem within theſe ſeven years, becauſe I find not above one in one thouſand five hundred have done ſo.

13. The like uſe may be made of the accounts of men, that made away themſelves, who are another ſort of mad-men, that think to eaſe themſelves of pain by leaping into hell; or elſe are yet more mad, ſo as to think there is no ſuch place; or that men may go to reſt by death, though they die in ſelf-murther, the greateſt ſin.

14. We ſhall ſay nothing of the numbers of thoſe, that have been drowned, killed by falls from ſcaffolds, or by carts running over them, &c. becauſe the ſame depends upon the caſual trade and employment of men, and upon matters, which are but circumſtantial to the ſeaſons and regions we live in, and affords little of that ſcience and certainty we aim at.

15. We find one caſualty in our bills, of which, though there be daily talk, there is little effect, much like our abhorrence of toads and ſnakes as moſt poiſonous creatures, whereas few men dare ſay upon their own knowledge they ever found harm by either; and this caſualty is the French pox, gotten, for the moſt part, not ſo much by the intemperate uſe of venery (which rather cauſeth the gout) as of many common women.

16. I ſay, the bills of mortality would take off theſe bars, which keep ſome men within bounds, as to theſe extravagances: for in the aforementioned 229250, we find not above 392 to have died of the pox. Now, foraſmuch as it is not good to let the world be lulled into a ſecurity and belief of impunity by our bills, which we intend ſhall not be only as deaths heads to put men in mind of their mortality, but alſo as Mercurial ſtatues to point out the moſt dangerous ways, that lead us into it and miſery; we ſhall therefore ſhew, that the pox is not as the toads and ſnakes aforementioned, but of a quite contrary nature, together with the reaſon why it appears otherwiſe.

17. Foraſmuch as by the ordinary diſcourſe of the world it ſeems a great part of men have, at one time or other, had ſome ſpecies of this diſeaſe, I wondering why ſo few died of it, eſpecially becauſe I could not take that to be ſo harmleſs, whereof ſo many complained very fiercely; upon enquiry, I found, that thoſe, who died of it out of the hoſpitals (eſpecially that of Kingſland, and the Lock in Southwark) were returned of ulcers and ſores. And in brief, I found, that all mentioned to die of the French pox were returned by the clerks of St. Giles's and St. Martin's in the Fields only, in which place I underſtood that moſt of the vileſt and moſt miſerable houſes of uncleanneſs were: from whence I concluded, that only hated perſons, and ſuch, whoſe very noſes were eaten off, were reported by the ſearchers to have died of this too frequent malady.

18. In

18. In the next place, it ſhall be examined, under what name or caſualty ſuch, as die of theſe diſeaſes are brought in: I ſay, under the conſumption; foraſmuch as all dying thereof die ſo emaciated and lean (their ulcers diſappearing upon death) that the old-women ſearchers, after the miſt of a cup of ale, and the bribe of a two-groat fee, inſtead of one, given them, cannot tell whether this emaciation or leanneſs were from a phthiſis, or from an hectic fever, atrophy, &c. or from an infection of the ſpermatic parts, which in length of time, and in various diſguiſes, hath at laſt vitiated the habit of the body, and by diſabling the parts to digeſt their nouriſhment, brought them to the condition of leanneſs abovementioned.

19. My next obſervation is, that of the rickets we find no mention among the caſualties, until the year 1634, and then but of 14 for that whole year.

20. Now the queſtion is, whether that diſeaſe did firſt appear about that time; or whether a diſeaſe, which had been long before, did then firſt receive its name?

21. To clear this difficulty out of the bills (for I dare venture on no deeper arguments) I enquired what other caſualty before the year 1634, named in the bills, was moſt like the rickets; and found, not only by pretenders to know it, but alſo from other bills, that livergrown was the neareſt. For in ſome years I find livergrown, ſpleen, and rickets, put all together, by reaſon (as I conceive) of their likeneſs to each other. Hereupon I added the livergrowns of the year 1634, viz. 77. to the rickets of the ſame year, viz. 14, making in all 91: which total, as alſo the number 77 itſelf, I compared with the livergrown of the precedent year 1633, viz. 82: all which ſhewed me, that the rickets was a new diſeaſe over and above.

22. Now, this being but a faint argument, I looked both forwards and backwards, and found, that in the year 1629, when no rickets appeared, there were but 94 livergrowns; and in the year 1636 there were 99 livergrown, although there were alſo 50 of the rickets: only this is not to be denied, that when the rickets grew very numerous (as in the year 1660, viz. 521) then there appeared not above 15 of livergrown.

23. In the year 1659 were 441 rickets, and 8 livergrown. In the year 1658 were 476 rickets, and 51 livergrown. Now, though it be granted, that theſe diſeaſes were confounded in the judgment of the nurſes, yet it is moſt certain, that the livergrown did never but once, viz. anno 1630 exceed 100; whereas anno 1660, livergrown and rickets were 536.

24. It is alſo to be obſerved, that the rickets were never more numerous than now, and that they are ſtill increaſing; for anno 1649, there were but 190, next year 260, next after that 329, and ſo forwards, with ſome little ſtarting backwards in ſome years, until the year 1660, which produced the greateſt of all.

25. Now, ſuch back-ſtartings ſeem to be univerſal in all things; for we do not only ſee in the progreſſive motion of the wheels of watches, and in the rowing of boats, that there is a little ſtarting or jerking backwards between every ſtep forwards, but alſo (if I am not much deceived) there appeared the like in the motion of the moon, which in the long teleſcopes at Greſham-college one may ſenſibly diſcern.

26. There ſeems alſo to be another new diſeaſe, called by our bills the ſtopping of the ſtomach, firſt mentioned in the year 1636; the which malady, from that year

year to 1647, increaſed but from 6 to 29; anno 1655 it came to 145; in 57, to 277; in 60 to 314. Now theſe proportions far exceeding the difference of proportion generally ariſing from the increaſe of inhabitants, and from the reſort of advenæ to the city, ſhews, there is ſome new diſeaſe, which appeareth to the vulgar, as a ſtopping of the ſtomach.

27. Hereupon I apprehended, that this ſtopping might be the green-ſickneſs, foraſmuch as I find few or none to have been returned upon that account, although many be viſibly ſtained with it. Now, whether the ſame be forborn out of ſhame, I know not: for ſince the world believes, that marriage cures it, it may ſeem indeed a ſhame, that any maid ſhould die uncured, when there are more males than females, that is an overplus of huſbands to all that can be wives.

28. In the next place, I conjectured, that this ſtopping of the ſtomach might be the mother, foraſmuch as I have heard of many troubled with mother-fits (as they call them) although few returned to have died of them; which conjecture, if it be true, we may then ſafely ſay, that the mother-fits have alſo increaſed.

29. But I was ſomewhat taken off from thinking this ſtopping of the ſtomach to be the mother, becauſe I gueſſed rather the riſing of the lights might be it. For I remembred, that ſome women, troubled with the mother-fits, did complain of a choaking in their throats. Now, as I underſtand, it is more conceivable, that the lights or lungs (which I have heard called the bellows of the body) not blowing, that is, neither venting out, nor taking in breath, might rather cauſe ſuch a choaking, than that the mother ſhould riſe up thither, and do it. For methinks, when a woman is with child, there is a greater riſing, and yet no ſuch fits at all.

30. But what I have ſaid of the rickets and ſtopping of the ſtomach, I do in ſome meaſure ſay of the riſing of the lights alſo, viz. that theſe riſings (be they what they will) have increaſed much above the general proportion; for in 1629 there were but 44, and in 1660, 249, viz. almoſt ſix times as many.

31. Now foraſmuch as rickets appear much in the overgrowing of childrens livers and ſpleens (as by the bills may appear) which ſurely may cauſe ſtopping of the ſtomach, by ſqueezing and crowding upon that part; and foraſmuch as theſe choakings or riſings of the lights may proceed from the ſame ſtuffings, as make the liver and ſpleen to over-grow their due proportion; and laſtly, foraſmuch as the rickets, ſtopping of the ſtomach, and riſing of the lights, have all increaſed together, and in ſome kind of correſpondent proportions; it ſeems to me, that they depend one upon another; and that what is the rickets in children, may be the other in more grown bodies: for ſurely children, which recover of the rickets, may retain ſomewhat to cauſe what I have imagined. But of this let the learned phyſicians conſider, as I preſume they have.

32. I had not meddled thus far, but that I have heard, the firſt hints of the circulation of blood were taken from a common perſon's wondering what became of all the blood, which iſſued out of the heart, ſince the heart beats above three thouſand times an hour, although but one drop ſhould be pump'd out of it at every ſtroke.

33. The ſtone ſeemed to decreaſe: for in 1632, 33, 34, 35, and 36, there died of the ſtone and ſtrangury 254; and in the years 1655, 56, 57, 58, 59, and 1660, but 250: which numbers, although indeed they be almoſt equal, yet conſidering

the burials of the firſt named five years were but half thoſe of the latter, it ſeems to be decreaſed by about one half.

34. Now the ſtone and ſtrangury are diſeaſes, which moſt men know, that feel them, unleſs it be in ſome few caſes, where (as I have heard phyſicians ſay) a ſtone is held up by the films of the bladder, and ſo kept from grating or offending it.

35. The gout ſtands much at a ſtay, that is, it anſwers the general proportion of burials: there dies not above one of 1000 of the gout, although I believe that more die gouty. The reaſon is, becauſe thoſe, that have the gout, are ſaid to be long livers; and therefore, when ſuch die, they are returned as aged.

36. The ſcurvy hath likewiſe increaſed, and that gradually from 12, anno 1629, to 95, anno 1660.

37. The tiſick ſeems to be quite worn away; but that it is probable the ſame is entred as cough or conſumption.

38. Agues and fevers are entred promiſcuouſly, yet in the few bills, wherein they have been diſtinguiſhed, it appears that not above 1 in 40 of the whole are agues.

39. The abortives and ſtillborn are about the twentieth part of thoſe, that are chriſtned; and the numbers ſeemed the ſame thirty years ago as now, which ſhews there were more in proportion in thoſe years than now; or elſe, that in theſe latter years due accounts have not been kept of the abortives, as having been buried without notice, and perhaps not in church-yards.

40. For that there hath been a neglect in the accounts of the chriſtnings is moſt certain, becauſe until the year 1642, we find the burials but equal with the chriſtnings, or near thereabouts; but in 1648, when the differences in religion had changed the government, the chriſtnings were but two thirds of the burials. And in the year 1659, not half, viz. the burials were 14720 (of the plague but 36) and the chriſtnings were but 5670; which great diſproportion could be from no other cauſe than that abovementioned, foraſmuch as the ſame grew as the confuſions and changes grew.

41. Moreover, although the bills give us in anno 1659 but 5670 chriſtnings, yet they give us 421 abortives, and 226 dying in child-bed; whereas in the year 1631, when the abortives were 410, that is, near the number of the year 1659, the chriſtnings were 8288. Wherefore by the proportion of abortives, anno 1659, the chriſtnings ſhould have been about 8500: but if we ſhall reckon by the women dying in childbed, of whom a better account is kept than of ſtillborns and abortives, we ſhall find anno 1659 there were 226 childbeds; and anno 1631, 112, viz. not $\frac{1}{2}$. Wherefore I conceive, that the true number of the chriſtnings, anno 1659, is above double to the 5690 ſet down in our bills; that is, about 11500, and then the chriſtnings will come near the ſame proportion to the burials, as hath been obſerved in former times.

42. In regular times, when accounts were well kept, we find, that not above three in 200 died in childbed, and that the number of abortives was about treble to that of the women dying in childbed: from whence we may probably collect, that not one woman of an hundred (I may ſay of two hundred) dies in her labour; foraſmuch as there be other cauſes of a woman's dying within the month, than the hardneſs of her labour.

43. If

43. If this be true in theſe countries, where women hinder the facility of their child-bearing by affected ſtraitnings of their bodies; then certainly in America, where the ſame is not practiſed, nature is little more to be taxed as to women, than in brutes, among whom not one in ſome thouſands do die of their deliveries. What I have heard of the Iriſh women confirms me herein.

44. Before we quite leave this matter, we ſhall inſert the cauſes, why the account of chriſtnings hath been neglected more than that of burials: one, and the chief whereof, was a religious opinion againſt baptizing of infants either as unlawful, or unneceſſary. If this were the only reaſon, we might by our defects of this kind conclude the growth of this opinion, and pronounce, that not half the people of England, between the years 1650 and 1660, were convinced of the need of baptizing.

45. A ſecond reaſon was, the ſcruples, which many public miniſters would make of the worthineſs of parents to have their children baptized, which forced ſuch queſtioned parents, who did alſo not believe the neceſſity of having their children baptized by ſuch ſcruplers, to carry their children unto ſuch other miniſters, as having performed the thing, had not the authority or command of the regiſter to enter the names of the baptized.

46. A third reaſon was, that a little fee was to be paid for the regiſtry.

47. Upon the whole matter it is moſt certain, that the number of heterodox believers was very great between the ſaid year 1650 and 1660; and ſo peeviſh were they, as not to have the births of their children regiſtred, although thereby the time of their coming of age might be known, in reſpect of ſuch inheritances, as might belong unto them; and withal, by ſuch regiſtring it would have appeared unto what pariſh each child had belonged, in caſe any of them ſhould happen to want its relief.

48. Of convulſions there appeared very few, viz. but 52 in the year 1629, which in 1636 grew to 709, keeping about that ſtay till 1659, though ſometimes riſing to about 1000.

49. It is to be noted, that from 1629 to 1636, when the convulſions were but few, the number of chriſoms and infants was greater: for in 1629, there were of chriſoms and infants 2596, and of the convulſion 52, viz. of both 2648. And in 1636 there were of infants 1895, and of the convulſions 709; in both 2604, by which it appears, that this difference is likely to be only a confuſion in the accounts.

50. Moreover, we find that for theſe later years, ſince 1636, the total of convulſions and chriſoms added together are much leſs, viz. by about 400 or 500 per annum, than the like totals from 1629 to 36; which makes me think, that teeth alſo were thruſt in under the title of chriſoms and infants, inaſmuch as in the ſaid years, from 1629 to 1636, the number of worms and teeth wants by above 400 per annum of what we find in following years.

CHAP. IV.

Of the plague.

1. BEFORE we leave to diſcourſe of the caſualties, we ſhall add ſomething concerning that greateſt diſeaſe or caſualty of all, the plague.

There have been in London, within this age, four times of great mortality, that is to ſay, the years 1592 and 1593, 1603, 1625, and 1636.

There died anno 1592, from March to December	25886
Whereof, of the plague	11503
Anno 1593	17844
Whereof of the plague	10662
Chriſtned in the ſaid year	4021
Anno 1603, within the ſame ſpace of time, were buried	37294
Whereof of the plague	30561
Anno 1625, within the ſame ſpace	51758
Whereof of the plague	35417
Anno 1636, from April to December	23359
Whereof of the plague	10460

2. Now it is manifeſt of itſelf, in which of theſe years moſt died; but in which of them was the greateſt mortality of all diſeaſes in general, or of the plague in particular, we diſcover thus. In the years 1592, and 1636, we find the proportion of thoſe dying of the plague in the whole to be near alike, that is, about 10 to 23, or 11 to 25, or as about 2 to 5.

3. In the year 1625, we find the plague to bear unto the whole in proportion as 35 to 51, or 7 to 10, that is, almoſt the triplicate of the former proportion; for the cube of 7 being 343, and the cube of 10 being 1000, the ſaid 343 is not $\frac{1}{3}$ of 1000.

4. In anno 1603, the proportion of the plague to the whole was as 30 to 37, viz. as 4 to 5, which is yet greater than the laſt of 7 to 10: for if the year 1625 had been as great a plague year as 1603, there muſt have died not only 7 to 10, but 8 to 10, which in thoſe great numbers makes a vaſt difference.

5. We muſt therefore conclude the year 1603 to have been the greateſt plague year of this age.

6. Now to know in which of theſe four was the greateſt mortality at large, we reaſon thus:

Anno 1592	Buried	26490 or 6
	Chriſtned	4277 as 1
Anno 1603	There died in the whole year of all	38244 or 8
	Chriſtned	4784 as 1
1 to 8, or 1¼ to 10	Anno 1625 Died in the the whole year	54265 or 8
	Chriſtned	6983 as 1
Anno 1636	There died, *ut ſupra*,	23359 or 5
	Chriſtned	9522 as 2

7. From

7. From whence it appears, that anno 1636, the chriſtnings were about $\frac{3}{4}$ parts of the burials: anno 1592 but $\frac{1}{2}$; but in the year 1603, and 1625, not above an eighth: ſo that the ſaid two years were the years of greateſt mortality. We ſaid that the year 1603 was the greateſt plague year. And now we ſay, that the ſame was not a greater year of mortality than anno 1625. Now to reconcile theſe two poſitions, we muſt alledge, that anno 1625, there was an error in the accounts or diſtinctions of the caſualties; that is, more died of the plague than were recounted for under that name. Which allegation we alſo prove thus, viz.

8. In the ſaid year 1625 there are ſaid to have died of the plague 35417, and of all other diſeaſes 18848; whereas in the years, both before and after the ſame, the ordinary number of burials was between 7 and 8000; ſo that if we add about 11000 (which is the difference between 7 and 18) to our 35, the whole will be 46000, which bears to the whole 54000, as about 4 to 5, thereby rendering the ſaid year 1625 to be as great a plague year as that of 1603, and no greater; which anſwers to what we proved before, viz. that the mortality of the two years was equal.

9. From whence we may probably ſuſpect, that about $\frac{1}{4}$ part more died of the plague than are returned for ſuch; which we further prove by noting, that anno 1636 there died 10400 of the plague, the $\frac{1}{4}$ whereof is 2600. Now there are ſaid to have died of all other diſeaſes that year 12959, out of which number deducting 2600, there remain 10359, more than which there died not in ſeveral years next before and after the ſaid year 1636.

10. The next obſervation we ſhall offer is, that the plague of 1603 laſted eight years. In ſome whereof there died above 4000, in others above 2000, and in but one fewer than 600: whereas in the year 1624 next preceding, and in the year 1626 next following the ſaid great plague year 1625, there died in the former but 11, and in the latter but 134 of the plague. Moreover, in the ſaid year 1625, the plague decreaſed from its utmoſt number 4461 a week, to below 1000 within ſix weeks.

11. The plague of 1636 laſted twelve years, in eight whereof there died 2000 per annum one with another, and never under 300. The which ſhews, that the contagion of the plague depends more upon the diſpoſition of the air, than upon the effluvia from the bodies of men.

12. Which alſo we prove by the ſuddain jumps, which the plague hath made, leaping in one week from 118 to 927; and back again from 993 to 258; and from thence again the very next week to 852. The which effects muſt ſurely be rather attributed to change of the air, than of the conſtitution of men's bodies, otherwiſe than as this depends upon that.

13. It may be alſo noted, that many times other peſtilential diſeaſes, as purple-fevers, ſmall-pox, &c. do fore-run the plague a year, two or three; for in 1622 there died but 8000: in 1623, 11000: in 1624, about 12000: till in 1625 there died of all diſeaſes above 54000.

CHAP. V.

Other obſervations upon the plague, and caſualties.

1. THE decreaſe and increaſe of people is to be reckoned chiefly by chriſtnings, becauſe few bear children in London but inhabitants, though others die there. The accounts of chriſtnings were well kept, until differences in religion occaſioned ſome neglect therein, although even theſe neglects we muſt confeſs to have been regular and proportionable.

2. By the numbers and proportions of chriſtnings, therefore, we obſerve as followeth, viz.

Firſt, that, when from December 1602, to March following, there was little or no plague, then the chriſtnings at a medium were between 110 and 130 per week, few weeks being above the one, or below the other; but when from thence to July the plague increaſed, that then the chriſtnings decreaſed to under 90.

Secondly, the queſtion is, whether teeming-women died, or fled, or miſcarried? The latter at this time ſeems moſt probable, becauſe even in the ſaid ſpace between March and July, there died not above 20 per week of the plague: which ſmall number could neither cauſe the death or flight of ſo many women, as to alter the proportion $\frac{1}{4}$ part lower.

3. Moreover, we obſerve from the 21 of July to the 12 of October, the plague increaſing reduced the chriſtnings to 70 at a medium, diminiſhing the above proportion down to $\frac{2}{3}$. Now the cauſe of this muſt be flying, and death, as well as miſcarriages and abortions; for there died within that time about 25000, whereof many were certainly women-with-child: beſides, the fright of ſo many dying within ſo ſmall a time, might drive away ſo many others, as to cauſe this effect.

4. From December 1624, to the middle of April 1625, there died not above five a week of the plague, one with another. In this time, the chriſtnings were one with another 180. The which decreaſed gradually by the 22d of September to 75, or from the proportion of 12 to 5, which evidently ſquares with our former obſervation.

5. The next obſervation we ſhall offer is, the time, wherein the city hath been re-peopled after a great plague; which we affirm to be by the ſecond year. For in 1627 the chriſtnings (which are our ſtandard in this caſe) were 8408, which in 1624, next preceding the plague-year 1625 (that had ſwept away above 54000) were but 8299; and the chriſtnings of 1626 (which were but 6701) mounted in one year to the ſaid 8408.

6. Now the cauſe hereof, foraſmuch as it cannot be a ſupply by procreation; *ergo*, it muſt be by new affluxes to London out of the country.

7. We might fortify this aſſertion by ſhewing, that before the plague-year 1603, the chriſtnings were about 6000, which were in that very year reduced to 4789, but crept up the next year 1604 to 5458, recovering their former ordinary proportion

proportion in 1605 of 6504, about which proportion it ſtood till the year 1610.

8. I ſay it followeth, that let the mortality be what it will, the city repairs its loſs of inhabitants within two years; which obſervation leſſens the objection made againſt the value of houſes in London, as if they were liable to great prejudice through the loſs of inhabitants by the plague.

CHAP. VI.

Of the ſicklineſs, healthfulneſs, and fruitfulneſs of ſeaſons.

1. HAVING ſpoken of caſualties, we come next to compare the ſicklineſs, healthfulneſs, and fruitfulneſs of the ſeveral years and ſeaſons one with another. And firſt, having in the chapters aforegoing mentioned the ſeveral years of plague, we ſhall next preſent the ſeveral other ſickly years; we meaning by a ſickly year ſuch, wherein the burials exceed thoſe both of the precedent and ſubſequent years, and not above two hundred dying of the plague, for ſuch we call plague years; and this we do, that the world may ſee, by what ſpaces and intervals we may hereafter expect ſuch times again. Now, we may not call that a more ſickly year, wherein more die, becauſe ſuch exceſs of burials may proceed from increaſe and acceſs of people to the city only.

2. Such ſickly years were 1618, 20, 23, 24, 1632, 33, 34, 1649, 52, 54, 56, 58, 61, as may be ſeen by the tables.

3. In reference to this obſervation we ſhall preſent another, namely, that the more ſickly the years are, the leſs fecund or fruitful of children alſo they be. Which will appear, if the number of children born in the ſaid ſickly years be leſs than that of the years both next preceding and next following: all which, upon view of the tables, will be found true, except in a very few caſes, where ſometimes the precedent and ſometimes the ſubſequent years vary a little, but never both together. Moreover, for the confirmation of this truth, we preſent you the year 1660, where the burials were fewer than in either of the two next precedent years by 2000, and fewer than in the ſubſequent by above 4000. And withal, the number of chriſtnings in the ſaid year 1660 was far greater than in any of the three years next aforegoing.

4. As to this year 1660, although we would not be thought ſuperſtitious, yet it is not to be neglected, that in the ſaid year was the King's reſtoration to his empire over theſe three nations, as if God Almighty had cauſed the healthfulneſs and fruitfulneſs thereof to repair the bloodſhed and calamities ſuffered in his abſence. I ſay, this conceit doth abundantly counterpoiſe the opinion of thoſe, who think great plagues come in with Kings reigns, becauſe it happened ſo twice, viz. anno 1603, and 1625; whereas as well the year 1648, wherein the preſent King commenced his right to reign, as alſo the year 1660, wherein he commenced the exerciſe of the ſame, were both eminently healthful: which clears both monarchy, and our preſent King's family, from what ſeditious men have ſurmiſed againſt them.

5. The

5. The diſeaſes, which beſide the plague make years unhealthful in this city, are ſpotted-fevers, ſmall-pox, dyſentery, called by ſome the plague in the guts; and the unhealthful ſeaſon is the autumn.

CHAP. VII.

Of the difference between burials and chriſtnings.

1. THE next obſervation is, that in the ſaid bills there are far more burials than chriſtnings. This is plain, depending only upon arithmetical computation; for, in 40 years, from the year 1603, to the year 1644, excluſive of both years, there have been ſet down (as happening within the ſame ground, ſpace, or pariſhes) although differently numbered and divided, 363935 burials, and but 330747 chriſtnings within the 97, 16, and 10 out-pariſhes; thoſe of Weſtminſter, Lambeth, Newington, Rotherhith, Stepney, Hackney and Iſlington, not being included.

2. From this ſingle obſervation it will follow, that London ſhould have decreaſed in its people; the contrary whereof we ſee by its daily increaſe of buildings upon new foundations, and by the turning of great palacious houſes into ſmall tenements. It is therefore certain, that London is ſupplied with people from out of the country, whereby not only to ſupply the overplus differences of burials abovementioned, but likewiſe to increaſe its inhabitants according to the ſaid increaſe of houſing.

3. This ſupplying of London ſeems to be the reaſon, why Wincheſter, Lincoln, and ſeveral other cities have decreaſed in their buildings, and conſequently in their inhabitants. The ſame may be ſuſpected of many towns in Cornwal, and other places, which probably, when they were firſt allowed to ſend burgeſſes to the parliament, were more populous than now, and bore another proportion to London than now; for ſeveral of thoſe boroughs ſend two burgeſſes, whereas London itſelf ſends but four, although it bears the fifteenth part of the charge of the whole nation in all public taxes and levies.

4. But, if we conſider what I have upon exact enquiry found true, viz. that in the country, within ninety years, there have been 6339 chriſtnings, and but 5280 burials, the increaſe of London will be ſalved without inferring the decreaſe of the people in the country; and withal, in caſe all England have but fourteen times more people than London, it will appear, how the ſaid increaſe of the country may increaſe the people, both of London and itſelf; for if there be in the 97, 16, 10, and 7 pariſhes, uſually comprehended within our bills, but 460000 ſouls, as hereafter we ſhall ſhew; then there are in all England and Wales 6440000 perſons, out of which ſubtract 460000, for thoſe in and about London, there remain 5980000 in the country, the which increaſing about $\frac{1}{7}$ part in 40 years, as we ſhall hereafter prove doth happen in the country, the whole increaſe of the country will be about 854000 in the ſaid time; out of which number, if but about 250000 be ſent up to London in the ſaid 40 years, viz. about 6000 per annum, the ſaid miſſions will make good the alterations, which we find to have been in and about London, between

tween the years 1603 and 1644 abovementioned: but that 250000 will do the ſame, I prove thus: viz. in the 8 years from 1603 to 1612, the burials in all the pariſhes, and of all diſeaſes, the plague included, were at a medium 9750 per annum. And between 1635 and 1644 were 18000, the difference whereof is 8250, which is the total of the increaſe of the burials in 40 years, that is, about 206 per annum. Now, to make the burials increaſe 206 per annum, there muſt be added to the city 30 times as many (according to the proportion of 3 dying out of 11 families) viz. 6180 advenæ, the which number multiplied again by the 40 years, makes the product 247200, which is leſs than the 250000 above-propounded; ſo as there remain above 600000 of increaſe in the country within the ſaid 40 years, either to render it more populous, or ſend forth into other colonies, or wars. But that England hath fourteen times more people, is not improbable, for the reaſons following.

1. London is obſerved to bear about the fifteenth proportion of the whole tax.

2. There are in England and Wales about 39000 ſquare miles of land; and we have computed, that in one of the greateſt pariſhes in Hantſhire, being alſo a market-town, and containing twelve ſquare miles, there are 220 ſouls in every ſquare mile, out of which I abate $\frac{1}{4}$ for the overplus of people more in the pariſh than in other wild counties. So as the $\frac{3}{4}$ parts of the ſaid 220, multiplied by the total of ſquare miles, produces 6400000 ſouls in all, London included.

3. There are about 10000 pariſhes in England and Wales, and which, although they ſhould not contain the $\frac{1}{3}$ part of the land, nor the $\frac{1}{4}$ of the people of that country-pariſh, which we have examined, yet may be ſuppoſed to contain about 600 people, one with another: according to which account there will be ſix millions of people in the nation. I might add, that there are in England and Wales about five and twenty millions of acres at $16\frac{1}{2}$ foot to the perch; and if there be ſix millions of people, then there is about four acres for every head, which how well it agrees to the rules of plantation, I leave unto others, not only as a means to examine my aſſertion, but as a hint to their enquiry concerning the fundamental trade, which is huſbandry and plantation.

4. Upon the whole matter we may therefore conclude, that the people of the whole nation do increaſe, and conſequently the decreaſe of Wincheſter, Lincoln, and other like places, muſt be attributed to other reaſons, than that of re-furniſhing London only.

5. We come to ſhew, why, although in the country the chriſtnings exceed the burials, yet in London they do not. The general reaſon of this muſt be, that in London the proportion of thoſe ſubject to die, unto thoſe capable of breeding, is greater than in the country; that is, let there be an hundred perſons in London, and as many in the country; we ſay, that if there be ſixty of them breeders in London, there are more than ſixty in the country, or elſe we muſt ſay, that London is more unhealthful, or that it inclines men and women more to barrenneſs, than the country: which by comparing the burials and chriſtnings of Hackney, Newington, and the other country pariſhes, with the moſt ſmoky and ſtinking parts of the city, is ſcarce diſcernible in any conſiderable degree.

6. Now that the breeders in London are proportionably fewer than thoſe in the country, ariſes from theſe reaſons, viz.

1. All, that have buſineſs to the court of the King, or to the courts of juſtice, and all country-men coming up to bring proviſions to the city, or to buy foreign commodities, manufactures, and rarities, do for the moſt part leave their wives in the country.

2. Perſons coming to live in London out of curioſity and pleaſure, as alſo ſuch as would retire and live privately, do the ſame, if they have any.

3. Such as come up to be cured of diſeaſes do ſcarce uſe their wives *pro tempore.*

4. That many apprentices of London, who are bound ſeven or nine years from marriage, do often ſtay longer voluntarily.

5. That many ſea-men of London leave their wives behind them, who are more ſubject to die in the abſence of their huſbands, than to breed either without men, or with the uſe of many promiſcuouſly.

6. As for unhealthineſs, it may well be ſuppoſed, that although ſeaſoned bodies may, and do live near as long in London, as elſewhere, yet new-comers and children do not: for the ſmoaks, ſtinks, and cloſe air, are leſs healthful than that of the country. Otherwiſe why do ſickly perſons remove into the country-air? and why are there more old men in countries than in London *per rata?* And although the difference in Hackney and Newington abovementioned be not very notorious, yet the reaſon may be their vicinity to London, and that the inhabitants are moſt ſuch, whoſe bodies have firſt been impaired with the London-air, before they withdraw thither.

7. As to the cauſes of barrenneſs in London, I ſay, that although there ſhould be none extraordinary in the native air of the place; yet the intemperance in feeding, and eſpecially the adulteries and fornications, ſuppoſed more frequent in London than elſewhere, do certainly hinder breeding. For a woman, admitting ten men, is ſo far from having ten times as many children, that ſhe hath none at all.

8. Add to this, that the minds of men in London are more thoughtful, and full of buſineſs, than in the country, where their work is corporal labour and exerciſes; all which promote breeding, whereas anxieties of the mind hinder it.

CHAP. VIII.

Of the difference between the numbers of males and females.

THE next obſervation is, that there be more males than females.

1. There have been buried from the year 1628, to the year 1662, excluſive, 209436 males, and but 190474 females. But it will be objected, that in London it may be indeed ſo, though otherwiſe elſewhere; becauſe London is the great ſtage and ſhop of buſineſs, wherein the maſculine ſex bears the greateſt part. But we anſwer, that there have been alſo chriſtned within the ſame time 139782 males, and but 130866 females, and that the country accounts are conſonant enough to thoſe of London upon this matter.

2. What the cauſes hereof are, we ſhall not trouble ourſelves to conjecture, as in other caſes: only we ſhall deſire, that travellers would enquire, whether it be the ſame in other countries.

3. We ſhould have given an account, how in every age theſe proportions change here, but that we have bills of diſtinction but for 32 years; ſo that we ſhall paſs from hence to ſome inferences from this concluſion; as firſt,

I. That Chriſtian religion, prohibiting polygamy, is more agreeable to the law of nature, that is, the law of God, than Mahometiſm, and others, that allow it: for one man's having many women, or wives, by law, ſignifies nothing, unleſs there were many women to one man in nature alſo.

II. The obvious objection hereunto is, that one horſe, bull, or ram, having each of them many females, do promote increaſe. To which I anſwer, that although perhaps there be naturally, even of theſe ſpecies, more males than females; yet artificially, that is, by making geldings, oxen, and weathers, there are fewer. From whence it will follow, that when by experience it is found how many ews (ſuppoſe twenty) one ram will ſerve, we may know what proportion of male-lambs to caſtrate or geld, viz. nineteen, or thereabouts: for if you emaſculate fewer, viz. but ten, you ſhall, by promiſcuous copulation of each of thoſe ten with two females, hinder the increaſe, ſo far as the admittance of two males will do it: but, if you caſtrate none at all, it is highly probable, that every of the twenty males copulating with every of the twenty females, there will be little or no conception in any of them all.

III. And this I take to be the trueſt reaſon, why foxes, wolves, and other vermin animals, that are not gelt, increaſe not faſter than ſheep, when as ſo many thouſands of theſe are daily butchered, and very few of the other die otherwiſe than of themſelves.

4. We have hitherto ſaid, there are more males than females; we ſay next, that the one exceed the other by about a thirteenth part. So that although more men die violent deaths than women, that is, more are ſlain in wars, killed by miſchance, drowned at ſea, and die by the hand of juſtice; moreover, more men go to colonies, and travel into foreign parts, than women; and laſtly, more remain unmarried than of women, as fellows of colleges, and apprentices above eighteen, &c. yet the ſaid thirteenth part difference bringeth the buſineſs but to ſuch a paſs, that every woman may have a huſband, without the allowance of polygamy.

5. Moreover, although a man be prolific forty years, and a woman but five and twenty, which makes the males to be as 560 to 325 females; yet the cauſes abovenamed, and the later marriage of the men, reduce all to an equality.

6. It appearing, that there were fourteen men to thirteen women, and that they die in the ſame proportion alſo; yet I have heard phyſicians ſay, that they have two women patients to one man: which aſſertion ſeems very likely; for that women have either the green-ſickneſs, or other like diſtempers, are ſick of breedings, abortions, child-bearing, ſore-breaſts, whites, obſtructions, fits of the mother, and the like.

7. Now, from this it ſhould follow, that more women ſhould die than men, if the number of burials anſwered in proportion to that of ſickneſſes: but this muſt be ſalved, either by the alledging, that the phyſicians cure thoſe ſickneſſes, ſo as few more die than if none were ſick; or elſe that men being more intemperate than women, die as much by reaſon of their vices, as women do by the infirmity of their ſex; and conſequently, more males being born than females, more alſo die.

8. In the year 1642 many males went out of London into the wars then beginning, inſomuch as I expected in the ſucceeding year 1643 to have found the burials of females to have exceeded thoſe of males: but no alteration appeared; foraſmuch, as I ſuppoſe, trading continuing the ſame in London, all thoſe, who loſt their apprentices, had others out of the country; and if any left their trades and ſhops, that others forthwith ſucceeded them: for, if employment for hands remain the ſame, no doubt but the number of them could not long continue in diſproportion.

9. Another pregnant argument to the ſame purpoſe (which hath already been touched on) is, that although in the very year of the plague the chriſtnings decreaſed, by the dying and flying of teeming-women, yet the very next year after they increaſed ſomewhat, but the ſecond after to as full a number as in the ſecond year before the ſaid plague. For I ſay again, if there be encouragement for an hundred in London, that is, a way how an hundred may live better than in the country, and if there be void houſing there to receive them, the evacuating of a fourth or a third part of that number muſt ſoon be ſupplied out of the country; ſo as the great plague doth not leſſen the inhabitants of the city, but of the country, who in a ſhort time remove themſelves from thence hither, ſo long, until the city, for want of receipt and encouragement, regurgitates and ſends them back.

10. From the difference between males and females, we ſee the reaſon of making eunuchs in thoſe places where polygamy is allowed; the latter being uſeleſs as to multiplication, without the former, as was ſaid before in caſe of ſheep and other animals uſually gelt in theſe countries.

11. By conſequence, this practice of caſtration ſerves as well to promote increaſe, as to meliorate the fleſh of thoſe beaſts that ſuffer it. For that operation is equally practiſed upon horſes, which are not uſed for food, as upon thoſe that are.

12. In popiſh countries, where polygamy is forbidden, if a greater number of males oblige themſelves to celibate, than the natural over-plus, or difference between them and females amounts unto; then multiplication is hindered: for if there be eight men to ten women, all of which eight men are married to eight of the ten women, then the other two bear no children, as either admitting no man at all, or elſe admitting men as whores (that is, more than one;) which commonly procreates no more than if none at all had been uſed: or elſe ſuch unlawful copulations beget conceptions, but to fruſtrate them by procured abortions, or ſecret murthers; all which returns to the ſame reckoning. Now, if the ſame proportion of women oblige themſelves to a ſingle life likewiſe, then ſuch obligation makes no change in this matter of increaſe.

13. From what hath been ſaid appears the reaſon, why the law is and ought to be ſo ſtrict againſt fornications and adulteries: for, if there were univerſal liberty, the increaſe of mankind would be but like that of foxes at beſt.

14. Now foraſmuch as princes are not only powerful, but rich, according to the number of their people (hands being the father, as lands are the mother and womb of wealth) it i no wonder, why ſtates, by encouraging marriage, and hindering licentiouſneſs, advance their own intereſt, as well as preſerve the laws of GOD from contempt and violation.

15. It is a bleſſing to mankind, that by this overplus of males there is this natural bar to polygamy: for in ſuch a ſtate women could not live in that parity and equality of expence with their huſbands, as now, and here they do.

16. The reaſon whereof is, not that the huſband cannot maintain as ſplendidly three as one; for he might, having three wives, live himſelf upon a quarter of his income, that is, in a parity with all three, as well as, having but one, live in the ſame parity at half with her alone: but rather, becauſe that to keep them all quiet with each other, and himſelf, he muſt keep them all in greater awe, and leſs ſplendor; which power he having, he will probably uſe it to keep them all as low as he pleaſes, and at no more coſt than makes for his own pleaſure; the pooreſt ſubjects (ſuch as this plurality of wives muſt be) being moſt eaſily governed.

CHAP. IX.

Of the growth of the city.

1. IN the year 1593 there died in the ninety ſeven pariſhes within the walls, and the ſixteen without the walls (beſides 421 of the plague) 3508. And the next year 3478, beſides 29 of the plague: in both years 6986. Twenty years after there died in the ſame ninety ſeven, and ſixteen pariſhes, 12110, viz. anno 1614, 5873; and anno 1615, 6237: ſo as the ſaid pariſhes are increaſed, in the ſaid time, from ſeven to twelve, or very near thereabouts.

2. Moreover, the burials within the like ſpace of the next twenty years, viz. anno 1634 and 1635, were 15625, viz. as about twenty four to thirty one: the which laſt of the three numbers, 15625, is much more than double to the firſt 6986; viz. the ſaid pariſhes have in forty years increaſed from twenty three to fifty two.

3. Where is to be noted, that although we were neceſſitated to compound the ſaid ninety ſeven with the ſixteen pariſhes, yet the ſixteen pariſhes have increaſed faſter than the ninety ſeven. For, in the year 1620, there died within the walls 2726, and in 1660 there died but 3098 (both years being clear of the plague:) ſo as in this forty years the ſaid ninety ſeven pariſhes have increaſed but from nine to ten, or thereabouts, becauſe the houſing of the ſaid ninety ſeven pariſhes could be no otherwiſe increaſed, than by turning great houſes into tenements, and building upon a few gardens.

4. In the year 1604 there died in the ninety ſeven pariſhes 1518, and of the plague 280. And in the year 1660, 3098, and none of the plague; ſo as in fifty ſix years the ſaid pariſhes have doubled. Where note, that foraſmuch as the ſaid year 1604 was the very next after the great plague 1603 (when the city was not yet re-peopled) we ſhall rather make the compariſon between 2014, which died anno 1605, and 3431 anno 1659; chuſing rather from hence to aſſert, that the ſaid ninety ſeven and ſixteen pariſhes increaſed from twenty to thirty four, or from ten to ſeventeen in fifty four years, than from one to two in fifty ſix, as in the laſt aforegoing paragraph is ſet down.

5. Anno 1605 there died in the ſixteen out-pariſhes 2974, and anno 1659, 6988: ſo as in the fifty four years the ſaid pariſhes have increaſed from three to ſeven.

6. Anno 1605 there died in the eight out-pariſhes 960, anno 1659 there died in the ſame ſcope of ground, although called now ten pariſhes (the Savoy and Covent-Garden being added) 4301: ſo as the ſaid pariſhes have increaſed, within the ſaid fifty four years, more than from one to four.

7. Moreover, there were buried in all, anno 1605, 5948, and anno 1659, 14720, viz. about two to five.

8. Having ſet down the proportions, wherein we find the ſaid three great diviſions of the whole pile, called London, to have increaſed; we come next to ſhew what particular pariſhes have had the moſt remarkable ſhare in theſe augmentations, viz. of the ninety ſeven pariſhes within the walls the increaſe is not diſcernible, but where great houſes, formerly belonging to noblemen, before they built others near White-hall, have been turned into tenements; upon which account Allhallows upon the Wall is increaſed by the converſion of the Marquis of Wincheſter's houſe, lately the Spaniſh ambaſſador's, into a new ſtreet: the like of Alderman FREEMAN's, and LA MOTTE's, near the Exchange: the like of the Earl of Arundel's in Lothbury: the like of the Biſhop of London's palace, the Dean of Paul's, and the Lord Rivers's houſe now in hand; as alſo of the Duke's-Place, and others heretofore.

9. Of the ſixteen pariſhes, next without the walls, St. Giles Cripplegate hath been moſt enlarged, next to that St. Olaves Southwark; then St. Andrew's Holborn, then White-Chapel; the difference in the reſt not being conſiderable.

10. Of the out-pariſhes, now called ten, formerly nine, and before that eight, St. Giles's and St. Martins in the Fields are moſt increaſed, notwithſtanding St. Paul's Covent-Garden was taken out of them both.

11. The general obſervation, which ariſes from hence, is, that the city of London gradually removes weſtward; and did not the Royal-Exchange and London-Bridge ſtay the trade, it would remove much faſter: for Leaden-Hall-ſtreet, Biſhop's-Gate, and part of Fen-Church-ſtreet, have loſt their antient trade; Grace-Church-ſtreet indeed keeping itſelf yet entire, by reaſon of its conjunction with, and relation to London Bridge.

12. Again, Canning-ſtreet and Watlin-ſtreet have loſt their trade of woollen-drapery to Paul's Church-Yard, Ludgate-hill, and Fleet-ſtreet. The mercery is gone from out of Lombard-ſtreet and Cheap-ſide into Pater-Noſter Row and Fleet-ſtreet.

13. The reaſons whereof are, that the King's court (in old times frequently kept in the city) is now always at Weſtminſter. Secondly, the uſe of coaches, whereunto the narrow ſtreets of the old city are unfit, hath cauſed the building of thoſe broader ſtreets in Covent-Garden, &c.

14. Thirdly, where the conſumption of a commodity is, viz. among the gentry, the venders of the ſame muſt ſeat themſelves.

15. Fourthly, the cramming up of the void ſpaces and gardens within the walls with houſes, to the prejudice of light and air, hath made men build new ones, where they leſs fear thoſe inconveniences.

16. Con-

16. Conformity in building to other civil nations hath diſpoſed us to let our old wooden dark houſes fall to decay, and to build new ones, whereby to anſwer all the ends abovementioned.

17. Where note, that when Lud-gate was the only weſtern gate of the city, little building was weſtward thereof: but, when Holborn began to increaſe, New-gate was made. But now both theſe gates are not ſufficient for the communication between the walled city, and its enlarged weſtern ſuburbs, as daily appears by the intolerable ſtops and embarraſſes of coaches near both theſe gates, eſpecially Lud-gate.

CHAP. X.

Of the inequality of pariſhes.

1. BEFORE we paſs from hence, we ſhall offer to conſideration the inequality of pariſhes in and about London, evident in the proportion of their reſpective burials; for in the ſame year were buried in Cripplegate pariſh 1191, that but twelve died in Trinity Minories, St. Saviour's Southwark, and Botolph's Biſhop's-gate, being of the middle ſize, as burying 5 and 600 per annum: ſo that Cripplegate is an hundred times as big as the Minories, and 200 times as big as St. John the Evangeliſt's, Mary-Coal-Church, Bennet's-Grace-Church, Matthew-Friday-ſtreet, and ſome others within the city.

2. Hence may ariſe this queſtion, wherefore ſhould this inequality be continued? If it be anſwered, becauſe that paſtors of all ſorts and ſizes of abilities may have benefices, each man according to his merit; we anſwer, that a two hundredth part of the beſt parſon's learning is ſcarce enough for a ſexton. But beſides, there ſeems no reaſon of any difference at all, it being as much ſcience to ſave one ſingle ſoul, as one thouſand.

3. We incline therefore to think the pariſhes ſhould be equal, or near, becauſe, in the reformed religions, the principal uſe of churches is to preach in. Now the bigneſs of ſuch a church ought to be no greater, than that unto which the voice of a preacher of middling lungs will eaſily extend; I ſay eaſily, becauſe they ſpeak an hour or more together.

4. The uſe of ſuch large churches as Paul's, is now wholly loſt, we having no need of ſaying perhaps fifty maſſes all at one time; nor of making thoſe grand proceſſions frequent in the Romiſh church; nor is the ſhape of our cathedral proper at all for our preaching auditories, but rather the figure of an amphitheatre with galleries, gradually overlooking each other: for unto this condition the pariſh-churches of London are driving apace, as appears by the many galleries every day built in them.

5. Moreover, if pariſhes were brought to the ſize of Coalman-ſtreet, Allhallows-Barking, Chriſt-Church, Black-Friers, &c. in each whereof die between 100 and 150 per annum, then an hundred pariſhes would be a fit and equal diviſion of this great charge, and all the miniſters (ſome whereof have now ſcarce forty pounds per annum) might obtain a ſubſiſtence.

6. And

6. And laſtly, the church-wardens and over-ſeers of the poor might find it poſſible to diſcharge their duties; whereas now in the greater out-pariſhes many of the poorer pariſhioners through neglect do periſh, and many vicious perſons get liberty to live as they pleaſe, for want of ſome heedful eye to overlook them.

CHAP. XI.

Of the number of inhabitants.

I HAVE been ſeveral times in company with men of great experience in this city, and have heard them talk ſeldom under millions of people to be in London: all which I was apt enough to believe, until on a certain day, one of eminent reputation was upon occaſion aſſerting, that there was in the year 1661 two millions of people more than anno 1625 before the great plague. I muſt confeſs, that, until this provocation, I had been frighted, with that miſunderſtood example of DAVID, from attempting any computation of the people of this populous place: but hereupon I both examined the lawfulneſs of making ſuch enquiries, and, being ſatisfied thereof, went about the work itſelf in this manner: viz.

2. Firſt, I imagined, that, if the conjecture of the worthy perſon aforementioned had any truth in it, there muſt needs be about ſix or ſeven millions of people in London now: but, repairing to my bills, I found, that not above 15000 per annum were buried; and conſequently, that not above one in four hundred muſt die per annum, if the total were but ſix millions.

3. Next conſidering, that it is eſteemed an even lay, whether any man lives ten years longer, I ſuppoſed it was the ſame, that one of any ten might die within one year. But when I conſidered, that of the 15000 aforementioned about 5000 were abortive and ſtillborn, or died of teeth, convulſion, rickets, or as infants and chriſoms, and aged; I concluded, that of men and women, between ten and ſixty, there ſcarce died 10000 per annum in London, which number being multiplied by 10, there muſt be but 100000 in all, that is not the $\frac{1}{6}$ part of what the Alderman imagined. Theſe were but ſudden thoughts on both ſides, and both far from truth: I thereupon endeavoured to get a little nearer, thus: viz.

4. I conſidered, that the number of child-bearing women might be about double to the births: foraſmuch as ſuch women, one with another, have ſcarce more than one child in two years. The number of births I found, by thoſe years wherein the regiſtries were well kept, to have been ſomewhat leſs than the burials. The burials in theſe late years at a medium are about 13000, and conſequently the chriſtnings not above 12000. I therefore eſteemed the number of teeming-women to be 24000: then I imagined, that there might be twice as many families, as of ſuch women; for that there might be twice as many women aged between 16 and 76, as between 16 and 40, or between 20 and 44; and that there were about eight perſons in a family, one with another, viz. the man and his wife, three children and three ſervants or lodgers: now 8 times 48000 makes 384000.

5. Secondly, I find by telling the number of families in ſome pariſhes within the walls, that 3 out of 11 families per annum have died: wherefore, 13000 having died

died in the whole, it ſhould follow, there were 48000 families according to the laſt-mentioned account.

6. Thirdly, the account, which I made of the trained-bands and auxiliary-ſoldiers, doth enough juſtify this account.

7. And laſtly, I took the map of London ſet out in the year 1658 by RICHARD NEWCOURT, drawn by a ſcale of yards. Now I gueſſed, that in 100 yards ſquare there might be about 54 families, ſuppoſing every houſe to be 20 foot in the front: for on two ſides of the ſaid ſquare there will be 100 yards of houſing in each, and in the two other ſides 80 each; in all 360 yards: that is, 54 families in each ſquare, of which there are 220 within the walls, making in all 11880 families within the walls. But foraſmuch as there die within the walls about 3200 per annum, and in the whole 13000; it follows, that the houſing within the walls is $\frac{1}{4}$ part of the whole, and conſequently, that here are 47520 families in and about London, which agrees well enough with all my former computations: the worſt whereof doth ſufficiently demonſtrate, that there are two millions of people in London, which nevertheleſs moſt men do believe, as they do, that there be three women for one man; whereas there are fourteen men for thirteen women, as elſewhere hath been ſaid.

8. We have (though perhaps too much at random) determined the number of the inhabitants of London to be about 384000: the which being granted, we aſſert, that 199112 are males, and 184886 females.

9. Whereas we have found, that of 100 quick conceptions about 36 of them die before they be ſix years old, and that perhaps but one ſurviveth 76; we having ſeven decads between 6 and 76, we ſought ſix mean proportional numbers between 64, the remainder, living at ſix years, and the one, which ſurvives 76, and find, that the numbers following are practically near enough to the truth; for men do not die in exact proportions, nor in fractions, from whence ariſes this table following.

Viz. Of an hundred there die within the firſt ſix years	36	The fourth	6
		The next	4
The next ten years, or decad	24	The next	3
The ſecond decad	15	The next	2
The third decad	9	The next	1

10. From whence it follows, that of the ſaid 100 conceived, there remain alive at ſix years end 64.

At ſixteen years end	40	At fifty ſix	6
At twenty ſix	25	At ſixty	3
At thirty ſix	16	At ſeventy ſix	1
At forty ſix	10	At eighty	0

11. It follows alſo, that of all, which have been conceived, there are now alive 40 per cent. above ſixteen years old, 25 above twenty ſix years old, *& ſic deinceps*, as in the above table. There are therefore of aged between 16 and 56 the number of 40 leſs by ſix, viz. 34; of between 26 and 66 the number of 25 leſs by three, viz. 22: *& ſic deinceps.*

Wherefore, ſuppoſing there be 199112 males, and the number between 16 and 56 being 34; it follows, there are 34 per cent. of all thoſe males fighting men in London,

London, that is, 67694, viz. near 70000; the truth whereof I leave to examination, only the $\frac{1}{5}$ of 67694, viz. 13559, is to be added for Weſtminſter, Stepney, Lambeth, and the other diſtant pariſhes; making in all 81233 fighting men.

12. The next enquiry will be, in how long time the city of London ſhall, by the ordinary proportion of breeding and dying, double its breeding people? I anſwer, in about ſeven years, and (plagues conſidered) eight. Wherefore, ſince there be 24000 pair of breeders, that is $\frac{1}{8}$ of the whole, it follows, that in eight times eight years the whole people of the city ſhall double, without the acceſs of foreigners: the which contradicts not our account of its growing from two to five in 56 years with ſuch acceſſes.

13. According to this proportion, one couple, viz. ADAM and EVE, doubling themſelves every 64 years of the 5610 years, which is the age of the world according to the ſcriptures, ſhall produce far more people than are now in it. Wherefore the world is not above 100 thouſand years old, as ſome vainly imagine, nor above what the ſcripture makes it.

CHAP. XII.

Of the country bills.

WE have, for the preſent, done with our obſervations upon the accounts of burials and chriſtnings in and about London. We ſhall next preſent the accounts of both burials, chriſtnings, and alſo of weddings in the country, having to that purpoſe inſerted tables of 90 years for a certain pariſh in Hantſhire, being a place neither famous for longevity and healthfulneſs, nor for the contrary. Upon which tables we obſerve,

1. That every wedding, one with another, produces four children; and conſequently, that that is the proportion of children, which any marriageable man or woman may be preſumed ſhall have. For, though a man may be married more than once, yet, being onee married, he may die without any iſſue at all.

2. That in this pariſh there were born 15 females for 16 males, whereas in London there were 13 for 14; which ſhews, that London is ſomewhat more apt to produce males than the country. And it is poſſible, that in ſome other places there are more females born than males: which, upon this variation of proportion, I again recommend to the examination of the curious.

3. That in the ſaid whole 90 years the burials of the males and females were exactly equal, and that in ſeveral decads they differed not $\frac{1}{100}$ part; that in one of the two decads, wherein the difference was very notorious, there were buried of males 337, and of females but 284, viz. 53 difference; and in the other there died contrariwiſe 338 males, and 386 females, differing 46.

4. There are alſo decads, where the birth of males and females differ very much, viz. about 60.

5. That in the ſaid 90 years there have been born more than buried in the ſaid pariſh (the which, both 90 years ago, and alſo now, conſiſted of about 2700 ſouls) but 1059, viz. not 12 per annum, one year with another.

6. That theſe 1059 have in all probability contributed to the increaſe of London; ſince, as was ſaid even now, it neither appears by the burials, chriſtnings, or by the built of new houſing, that the ſaid pariſh is more populous now, than 90 years ago, by above 2 or 300 ſouls. Now, if all other places ſend about $\frac{1}{30}$ of their increaſe, viz. about one out of 900 of their inhabitants annually to London, and that there be 14 times as many people in England as there be in London (for which we have given ſome reaſons) then London increaſes by ſuch advenæ every year above 6000: the which will make the account of burials to ſwell about 270 per annum, and will anſwer the increaſes we obſerve. It is clear, that the ſaid pariſh is increaſed about 300, and it is probable, that three or four hundred more went to London; and it is known, that about 400 went to New-England, the Caribbee-Iſlands, and Newfound-Land, within theſe laſt forty years.

7. According to the medium of the ſaid whole 90 years, there have been five chriſtnings for four burials; although in ſome ſingle years and decads there have been three to two; although ſometimes (though more rarely) the burials have exceeded the births, as in the caſe of epidemical diſeaſes.

8. Our former obſervation, that healthful years are alſo the moſt fruitful, is much confirmed by our country accounts; for, 70 being our ſtandard for births, and 58 for burials, you ſhall find, that where fewer than 58 died, more than 70 were born. Having given you a few inſtances thereof, I ſhall remit you to the tables for the general proof of this aſſertion: viz. anno 1633, when 103 were born, there died but 29. Now, in none of the whole 90 years, more were born than 103, and but in one fewer than 29 died, viz. 28 anno 1658. Again anno 1568, when 93 were born, but 42 died. Anno 1584, when 90 were born, but 41 died. Anno 1650, when 86 were born, but 52 died. So that by how much more are born, by ſo much (as it were) the fewer die. For when 103 were born, but 29 died: but when but 86 were born, then 52 died.

On the other ſide, anno 1638, when 156 died per annum, which was the greateſt year of mortality, then leſs than the meer ſtandard 70, viz. but 66, were born. Again anno 1644, when 137 died, but 59 were born. Anno 1597, when 117 died, but 48 were born. And anno 1583, when 87 died, but 59 were born.

A little irregularity may be found herein, as, that anno 1612, when 116 died (viz. a number double to our ſtandard 58, yet) 87 (viz. 17 above the ſtandard 79) were born; and that when 89 died, 75 were born: but theſe differences are not ſo great, nor ſo often, as to evert our rule, which, beſides the authority of theſe accounts, is probable in itſelf.

9. Of all the ſaid 90 years the year 1638 was the moſt mortal. I therefore enquired, whether the plague was then in that pariſh, and having good ſatisfaction, that it was not, (which I the rather believe, becauſe that the plague was not then conſiderable at London) but that it was a malignant fever, raging ſo fiercely about harveſt, that there appeared ſcarce hands enough to take in the corn: which argues, conſidering there were 2700 pariſhioners, that ſeven might be ſick for one, that died: whereas of the plague more die than recover: laſtly, theſe people lay longer ſick than is uſual in the plague, nor was there any mention of ſores, ſwellings, blew-tokens, &c. among them: it follows, that the proportions between the greateſt and the leaſt mortalities in the country are far greater than at

London: forasmuch as the greatest 156 is above quintuple unto 28 the least; whereas in London (the plague excepted, as here it hath been) the number of burials upon other accounts within no decad of years hath been double; whereas in the country it hath been quintuple not only within the whole ninety years, but also within the same decad: for anno 1633 there died but 29, and anno 1638 the abovementioned number of 156. Moreover, as in London, in no decad, the burials of one year are double to those of another; so in the country they are seldom not more than so; as by this table appears.

Decad	greatest number of	least burials	Decad	greatest number of	least burials
1	66	34	6	89	50
2	87	39	7	156	35
3	117	38	8	137	46
4	53	30	9	80	28
5	116	51			

Which shews, that the opener and freer airs are most subject both to the good and bad impressions; and that the fumes, steams and stenches of London do so medicate and impregnate the air about it, that it becomes capable of little more, as if the said fumes rising out of London met with, opposed and justled backwards the influences falling from above, or resisted the incursion of the country-airs.

10. In the last paragraph we said, that the burials in the country were sometime quintuple to one another; but of the christnings we affirm, that within the same decad they are seldom double, as appears by this table, viz.

Decad	greatest number of	least births	Decad	greatest number of	least births
1	70	50	6	85	63
2	90	45	7	103	66
3	71	52	8	87	62
4	93	60	9	86	52
5	87	61			

Now, although the disproportions of births be not so great as that of burials, yet these disproportions are far greater than at London: for let it be shewn in any of the London bills, that within two years the christnings have decreased $\frac{1}{2}$, or increased double, as they did anno 1584, when 90 were born, and anno 1586, wherein were but 45: or to rise from 52, as anno 1593, to 71, as in the next year 1594. Now these disproportions both in births and burials confirm what hath been afore asserted, that healthfulness and fruitfulness go together, as they would not, were there not disproportions in both, although proportional.

11. By the standard of burials in this parish I thought to have computed the number of inhabitants in it, viz. by multiplying 58 by 4, which made the product

232,

232, the number of families. Hereupon I wondered, that a pariſh containing a large market-town, and 12 miles compaſs, ſhould have but 232 houſes. I then multiplied 232 by 8, the product whereof was 1856, thereby hoping to have had the number of the inhabitants, as I had for London. But when upon enquiry, I found there had been 2100 communicants in that pariſh, in the time of a miniſter, who forced too many into that ordinance, and that 1500 was the ordinary number of communicants in all times; I found alſo, that foraſmuch as there were near as many under 16 years old, as there are above, viz. Communicants, I concluded, that there muſt be about 2700 or 2800 ſouls in that pariſh: from whence it follows, that little more than one of 50 dies in the country, whereas in London it ſeems manifeſt, that about one in 32 dies, over and above what die of the plague.

12. It follows therefore from hence, what I more faintly aſſerted in the former chapter, that the country is more healthful than the city; that is to ſay, although men die more regularly, and leſs *per ſaltum* in London, than in the country, yet, upon the whole matter, there die fewer *per rata*; ſo as the fumes, ſteams, and ſtenches abovementioned, although they make the air of London more equal, yet not more healthful.

13. When I conſider, that in the country ſeventy are born for fifty eight buried, and that before the year 1600 the like happened in London, I conſidered, whether a city, as it becomes more populous, doth not, for that very cauſe, become more unhealthful: and inclined to believe, that London now is more unhealthful than heretofore; partly for that it is more populous, but chiefly becauſe I have heard, that ſixty years ago few ſea-coals were burnt in London, which are now univerſally uſed. For I have heard, that Newcaſtle is more unhealthful than other places, and that many people cannot at all endure the ſmoak of London, not only for its unpleaſantneſs, but for the ſuffocations which it cauſes.

14. Suppoſe, that anno 1569 there were 2400 ſouls in that pariſh, and that they increaſed by the births 70, exceeding the burials 58, it will follow, that the ſaid 2400 cannot double under 200. Now, if London be leſs healthful than the country, as certainly it is, the plague being reckoned in, it follows, that London muſt be doubling itſelf by generation in much above 200: but if it hath increaſed from 2 to 5 in 54, as aforeſaid, the ſame muſt be by reaſon of tranſplantation out of the country.

The Concluſion.

IT may be now aſked, to what purpoſe tends all this laborious buſtling and groping to know,

1. The number of the people?
2. How many males and females?
3. How many married and ſingle?
4. How many teeming-women?
5. How many of every ſeptenary, or decad of years in age?
6. How many fighting men?
7. How much London is, and by what ſteps it hath, increaſed?

8. In what time the houſing is repleniſhed after a plague?

9. What proportion die of each general and particular caſualties?

10. What years are fruitful and mortal, and in what ſpaces and intervals they follow each other?

11. In what proportion men neglect the orders of the church, and ſects have increaſed?

12. The diſproportion of pariſhes?

13. Why the burials in London exceed the chriſtnings, when the contrary is viſible in the country?

To this I might anſwer in general, by ſaying, that thoſe, who cannot apprehend the reaſon of theſe enquiries, are unfit to trouble themſelves to aſk them.

2. I might anſwer by aſking, why ſo many have ſpent their times and eſtates about the art of making gold? which, if it were much known, would only exalt ſilver into the place, which gold now poſſeſſeth; and if it were known but to ſome one perſon, the ſame ſingle adeptus could not, nay, durſt not enjoy it, but muſt be either a priſoner to ſome Prince, and ſlave to ſome voluptuary, or elſe ſkulk obſcurely up and down for his privacy and concealment.

3. I might anſwer, that there is much pleaſure in deducing ſo many abſtruſe and unexpected inferences out of theſe poor deſpiſed bills of mortality; and in building upon that ground, which hath lain waſte theſe eighty years. And there is pleaſure in doing ſomething new, though never ſo little, without peſtering the world with voluminous tranſcriptions.

4. But I anſwer more ſeriouſly, by complaining, that whereas the art of governing, and the true politics, is how to preſerve the ſubject in peace and plenty; that men ſtudy only that part of it, which teacheth how to ſupplant and over-reach one another, and how, not by fair out-running, but by tripping up each other's heels, to win the prize.

Now, the foundation or elements of this honeſt harmleſs policy is to underſtand the land, and the hands of the territory, to be governed according to all their intrinſic and accidental differences: as for example; it were good to know the geometrical content, figure, and ſituation of all the lands of a kingdom, eſpecially according to its moſt natural, permanent, and conſpicuous bounds. It were good to know how much hay an acre of every ſort of meadow will bear; how many cattle the ſame weight of each ſort of hay will feed and fatten; what quantity of grain and other commodities the ſame acre will bear in one, three, or ſeven years, *communibus annis*; unto what uſe each ſoil is moſt proper. All which particulars I call the intrinſic value: for there is alſo another value meerly accidental, or extrinſic, conſiſting of the cauſes, why a parcel of land, lying near a good market, may be worth double to another parcel, though but of the ſame intrinſic goodneſs; which anſwers the queries, why lands in the North of England are worth but ſixteen years purchaſe, and thoſe of the Weſt above eight and twenty. It is no leſs neceſſary to know, how many people there be of each ſex, ſtate, age, religion, trade, rank, or degree, &c. by the knowledge whereof, trade and government may be made more certain and regular; for, if men knew the people, as aforeſaid, they might know the conſumption they would make, ſo as trade might not be hoped for where it is impoſſible. As for inſtance, I have heard much complaint, that trade is not ſet in

ſome

ſome of the South-weſtern or North-weſtern parts of Ireland, there being ſo many excellent harbours for that purpoſe; whereas in ſeveral of thoſe places I have alſo heard, that there are few other inhabitants, but ſuch as live *ex ſponte creatis*, and are unfit ſubjects of trade, as neither employing others, nor working themſelves.

Moreover, if all theſe things were clearly and truly known (which I have but gueſſed at) it would appear, how ſmall a part of the people work upon neceſſary labours and callings, viz. how many women and children do juſt nothing, only learning to ſpend what others get; how many are meer voluptuaries, and as it were meer gameſters by trade; how many live by puzzling poor people with unintelligible notions in divinity and philoſophy; how many by perſuading credulous, delicate, and litigious perſons, that their bodies or eſtates are out of tune, and in danger; how many by fighting as ſoldiers; how many by miniſtries of vice and ſin; how many by trades of meer pleaſure, or ornaments; and how many in a way of lazy attendance, &c. upon others: and on the other ſide, how few are employed in raiſing and working neceſſary food and covering; and of the ſpeculative men, how few do ſtudy nature and things! the more ingenious not advancing much further than to write and ſpeak wittily about theſe matters.

I conclude, that a clear knowledge of all theſe particulars, and many more, whereat I have ſhot but at rovers, is neceſſary, in order to good, certain, and eaſy government, and even to balance parties and factions both in church and ſtate. But whether the knowledge thereof be neceſſary to many, or fit for others than the ſovereign and his chief miniſters, I leave to conſideration.

AN

AN

APPENDIX.

FORASMUCH as a long and ſerious peruſal of all the bills of mortality, which this great city hath afforded for almoſt fourſcore years, hath advanced but the few obſervations compriſed in the foregoing treatiſe; I hope very little will be expected from the few ſcattered papers, that have come to my hands ſince the publiſhing thereof, eſpecially from one, that hath learned from the Royal Society, how many obſervations go to the making up of one theorem, which (like oaks and other trees fit for durable building) muſt be of many years growth.

The accounts, which follow, I reckon but as timber and ſtones; and the beſt inferences I can make, are but as hewing them to a ſquare. As for compoſing a beautiful and firm ſtructure out of them, I leave it to the architecture of the ſaid Society, under whom I think it honour enough to work as a labourer.

My firſt obſervation ſhall be, that at Dublin the number of weekly burials being about 20, and thoſe of London about 300, as alſo the number of people reckoned to be within the limits of the bills of mortality at London to be 460000; it will follow, that the number of inhabitants of Dublin be about 30000, viz. about one fifteenth part of thoſe in and about London: which agrees with that number, which I have heard the books of poll-money, raiſed but little before the time of this bill, have exhibited as the number of inhabitants of that city: ſo as although I do not think one ſingle weekly bill is ſufficient to ground ſuch a concluſion upon, yet I think, that ſeveral yearly bills are the beſt of the eaſy ways, from which to collect the number of the people.

Secondly, although I take it for granted, that in Dublin there be more born than buried, becauſe the ſame hath appeared to be ſo in London by the bills of mortality before the year 1641, when the civil wars began, and much more eminently in Amſterdam, as ſhall be hereafter ſhewn; yet there are but 14 ſet down as chriſtned; which ſhews, that the defect there is much the ſame as at London. Whether the cauſe thereof be negligence in the regiſter, or non-conformity to public order, or both, I leave to the curious. I believe the cauſe is alſo the ſame, foraſmuch as I heard it to be a maxim at Dublin, to follow, if not forerun, all that is, or as they underſtand will be, practiſed in London; and that in all particulars incident to human affairs.

I have here inſerted two other country bills, the one of Cranbrook in Kent, the other of Tiverton in Devonſhire, which with that of Hantſhire, lying about the midway between them, give us a view of the moſt eaſterly, ſoutherly, and weſterly parts of England. I have endeavoured to procure the like account from Northumberland, Cheſhire, Norfolk and Nottinghamſhire; thereby to have a view of ſeven counties moſt differently ſituated, from whence I am ſorry to obſerve, that my

Southern friends have been hitherto more curious and diligent than thoſe of the North. The full obſervation from theſe bills is, that all theſe three country bills agree, that each wedding produces four children, which is likewiſe confirmed from the bills of Amſterdam. Secondly, they all agree, that there be more males born than females, but in different proportions, for at Cranbrook there be 20 males for 19 females, Hantſhire 16 for 15, in London 14 for 13, and at Tiverton 12 for 11. Thirdly, I have inſerted the bills themſelves, to the end, that whoever pleaſes may examine, by all three together, the obſervations I raiſed from the Hantſhire bill alone; conceiving it will be more pleaſure and ſatisfaction to do it themſelves, than to receive it from another hand. Only I ſhall add, as a new obſervation from them all, that in the years 1648 and 1649, being the time when the people of England did moſt reſent the horrid parricide of his late ſacred Majeſty, that there were but nine weddings in that year in the ſame places, when there were ordinarily between 30 and 40 per annum; and but 16, when there were ordinarily at other times between 50 and 60. And it may be alſo obſerved, that ſomething of this black murder appeared in the years 1643 and 1644, when the civil war was at the higheſt, but the contrary in the years 1654, 1655, &c. to prevent the new way of marriage then impoſed upon the people.

I have alſo ſupplied the tables from the three general bills for the years 1662, 1663, and 1664, which you will find to juſtify the former obſervations. But moſt eminently that, which I take to be of moſt concernment, namely, of the difference between the numbers of males and females.

In the former obſervations I did endeavour to deduce the number of the inhabitants about the city of Londom, from the bills of mortality, concluding them to be about 460000, and did likewiſe ſet forth by what ſteps the people of the ſaid city have increaſed from two to five ſince the year 1600. And particularly in what proportions the city increaſed in its ſeveral parts from time to time. I have now procured an account of the men, women, and children, which were anno 1631 found within the liberties of London, which are circumſcribed by Temple-Bar, Holborn-Bars, Smithfield-Bars, Shoreditch-Bars, Whitechapel-Bars, and to the Tower liberties, and meal-market in Southwark; by which account I hope it will appear, that I computed too many rather than too few, although the moſt part of men have thought otherwiſe. Nor do I wonder at it, ſince I never obſerved more enormous miſtakes in any matter than concerning the number of people, ale-houſes, coaches, ſhips, ſea-men, water-men, and ſeveral other tradeſmen, &c. The proportions of all which I have always thought is neceſſary to be known, in order to an exact ſymmetry of the ſeveral members of a common-wealth. I ſay, that the whole number of inhabintants exceeds not 460000.

1. The number of men, women, and children, found in the city and liberties 1631 was 130178.

2. The liberties of the city of London conſiſt of the 97 pariſhes within the walls, and of $\frac{2}{3}$ of the 16 pariſhes next without them: which eſtimate of mine, nevertheleſs, I leave to examination.

The liberties of London from the year 1631 to the year 1661 increaſed from 8 to 11, as may appear by the tables; and conſequently the ſaid 130000 found in the year 1631, were increaſed to 179000, in anno 1661. Laſtly,

Laſtly, the liberties of London in the year 1661 were in proportion to the whole, as 4 to 9; and conſequently if there were 179000 ſouls, in the ſaid liberties, there was not above 403000 in the whole number of pariſhes then comprehended in the bills of mortality.

The ſubſtance of the Amſterdam bills of mortality is, viz.

1. That there died in the ſeveral years of the plague, as followeth:

Anno	1622	4141	Anno	1628	4497
	1623	5929		1636	17193
	1624	11795		1655	16727
	1625	6781		1663	9752
	1626	4425		1664	24148
	1627	3976			

2. That there are eleven burying-places, beſides the Hoſpital and Peſt-houſe, 257 ſtreets and lanes, with 43 burgwalls and grachts in that city.

3. That in ſeven years, beginning from the 15th of Auguſt 1617 to the ſame day 1624, there were chriſtned in the reformed churches of Amſterdam 52537, and that there died in the ſame time 32532. So as there were 20005 more born than buried, beſides thoſe, that were chriſtned in other congregations. And in the ſame time were 16430 publiſhed marriages.

4. That in the firſt week of September 1664 there died 1041, and in eighteen weeks before the burials increaſed from 331 up to the ſaid number of 1041, and in twelve weeks after decreaſed back to the like number of 330.

5. In February following there died but 118 a week, and the ordinary number of weekly burials is about 100, ſo as London ſeems to be three times as big as Amſterdam.

6. I have likewiſe happened on ſome other accounts, relating to mortalities of ſome great cities of the world; of what authority I know not, but as printed at Amſterdam 1664, viz. anno 1619 there died in Grand Cairo in ten weeks 73500, without any viſible diminution of the people.

7. Anno 1625 there died in Leyden 9597. Anno 1635 there died in the ſame city of Leyden from the 14th of July, to the 29th of December 14381: the greateſt week of mortality being the latter end of October was 1452. This plague in 15 weeks increaſed from 96 to the ſaid number of 1452, and in ten weeks after decreaſed to 107. Anſwerable to the time of increaſe and decreaſe aforementioned in Amſterdam, anno 1655, there died in 21 weeks from July to November 13287, the greateſt week being September 25, when died 896.

8. At Harlem there died in the ſame year, in the months of Auguſt, September, October and November 5723.

9. Anno 1637, in Conſtantinople there died 1500 per diem: but how long this plague laſted, appeareth not.

10. The ſame year died in Prague 20000 Chriſtians, and 10000 Jews.

11. Anno 1652 there died in Cracovia 17000 Chriſtians, and 20000 Jews.

12. Anno 1653 there died in Dantzick in the laſt week of September 640, and in Conningſburg 490.

13. 1654 there died in Copenhagen for ſeveral weeks 700 per week.

14. Anno 1655 there died at Amſterdam and Leyden, as abovementioned; and at Deventer 70, 80, and 90 per diem.

15. At Leeuwardeen 56 per diem.

Anno 1656 there was ſo ſweeping a plague at Naples, that there died of it at the latter end of May 1300, or 1400 per diem. The ſixth of June there were 80000 ſick, that the well were not able to help, or bury the dead; preſently after there died 5000 in three days; in Auguſt it began to ceaſe, after it had deſtroyed 300000 people.

17. The town of Scala in Italy was quite diſpeopled, and at Minory there eſcaped but 22. At Rome there died in the ſame year about 100 per diem for a great while together.

18. 1657 There died at Genoa in Midſummer week 1200, afterwards there died 1600 per diem; inſomuch that in the beginning of Auguſt they burnt the dead corps for want of hands to bury them, which great mortality decreaſed to five or ſix per diem before September was out. The total ſum of all that died was about 70000.

19. At Bergen in Norway, anno 1618 the plague is repreſented to have been very terrible, by ſaying, that there died 50 or 60 per diem, and that the whole city was in tears; that the coffin-makers refuſed to make coffins; that parents carried their children, and children their parents to the grave. But foraſmuch as it was not mentioned how populous this place was, nor for how many days the mortality continued, I can make but little eſtimate of this plague, by what is above related.

20. The general obſervations ariſing from the abovementioned particulars are as followeth:

Firſt, that Northern, as well as Southern countries are infeſted with great plagues; although in the Southern countries they are more vehement, and do both begin and end more ſuddenly.

21. Secondly, from the year 1652 the plague was at Cracow, 1653 at Dantzick and Coningſburg, 1654 at Copenhagen, 1655 at Leyden and Amſterdam, and other towns in the Netherlands, 1656 at Naples and Rome, 1657 at Genoa; ſo as it well deſerves enquiry, whether the plague in all theſe places were a ſickneſs of the ſame kind, and did ſucceſſively perambulate the ſeveral countries abovementioned; or whether it were a ſeveral diſeaſe in each place.

22. Thirdly, that the plague is longer in riſing to its height, than in decreaſing to the ſame pitch; and the proportion thereof, in ſuch caſes where it hath moſt plainly appeared, is about three to two; for at Amſterdam it was eighteen weeks riſing, and twelve decreaſing; and at Leyden fifteen upon the increaſe, and ten decreaſing.

It may be further obſerved, that in the four ſeveral times of great mortality, the height was not always in the ſame month; for anno 1592 it was the ſecond week in Auguſt, when there died 1550 of all diſeaſes; in the year 1603 the height was the ſecond week of September, when there died 3129 of all diſeaſes; in 1625 the extremity was in the third week in Auguſt, when there died 5205. Anno 1636 the like extremity was in the firſt week of October, there then dying 4005 of all diſ-

ceaſes. In this place I think fit to intimate, that conſidering the preſent increaſe of the city from anno 1625 to this time, which is from eight to thirteen, that until the burials exceed 8400 per week, the mortality will not exceed that of 1625. Which GOD for ever avert.

It may be further obſerved, that the time of the plague's continuance at the height was of ſeveral durations; for anno 1592 it continued from the firſt week in July to the ſecond of September, without increaſing or decreaſing above 100 in 1600; whereas in 1603 it remained but three weeks at a ſtay, increaſing near $\frac{1}{4}$ the next week after the height; anno 1625 it remained not three weeks at a ſtay, increaſing $\frac{1}{16}$ part the next week before the height, and decreaſing as much the next week after. Anno 1636 it ſtood five weeks without increaſing or decreaſing above $\frac{1}{16}$ part aforementioned.

Concerning the diſeaſe of the plague, anno 1592 it increaſed to $\frac{1}{16}$ of the greateſt number that died in twenty weeks; anno 1603, it did the ſame in eleven; anno 1625, in nine weeks; anno 1636, as it was not ſo fierce as in the other years, ſo it was of longer continuance, as hath been elſe-where noted.

The laſt thing I ſhall obſerve is, that in all the four great years of mortality abovementioned, I do not find, that any week the plague increaſed to the double of the precedent week above five times.

Anno 1631. *Ann.* 7. *Caroli* I.

THE number of men, women, and children, in the ſeveral wards of London, and liberties, taken in Auguſt 1631, by ſpecial command from the Right Honourable the Lords of his Majeſty's Privy Council.

Aldgate-ward	04763	Alderſgate	03594
Biſhopſgate	07788	Limeſtreet	01107
Baſſiſhaw	01006	Queenhith	03358
Breadſtreet	02568	Vintry	02742
Bridge-ward within	02392	Tower-ward	04248
Bridge-ward without	18660	Dowgate	03516
Billingſgate	02597	Langbourn	03168
Broadſtreet	03503	Portſoken-ward	05703
Colemanſtreet	02634	Cheap-ward	02500
Cornhill	01439	Wallbrook	02069
Cripplegate without	06445	Candleweek-ward	01696
Cripplegate within	04231	Caſtle-Baynard	04793
Farrington without	20846		28404
Farrington within	08770		
Cordwainer	02238	Bartholomew the great	01388
	89880	Bartholomew the leſs.	00506
			38404
			89880
			130178

The

1633	1634	1635	1636	1629 1630 1631 1632	1633 1634 1635 1636	1647 1648 1649 1650	1651 1652 1653 1654	1655 1656 1657 1658	1629 1649 1659	In 20 years
500	475	507	523	1793	2005	1342	1587	1832	1247	8559
704	623	794	714	2475	2814	3336	3452	3680	2377	15759
95	1279	1622	2360	4418	6235	3865	4903	436	4010	23784
24	35	26		75	85	28	421	445	177	1306
						4	9	1	1	15
0	4		4	54	14	5	12	14	16	99
4	8			16	7	11	12	19	17	65
278	512	346	330	1587	1466	1422	2181	1161	1597	7818
1	3	12	3	25	15	24	31	26	19	125
		1	3		4	2	4	3		13
27	30	24	30	85	112 8	105	157	150	114	609 8
		5	74	15	79	190	244	161	133	689
132	143	163	230	590	668	498	769	839	490	3364
1130	2315	2113	1895	9277	8453	4678	4910	4788	4519	32106
		37	50	105	87	341	359	497	247	1389
45	54	50	57	174	207	00	77	140	43	598
754	1955	2080	2477	5157	8266	8999	9914	12157	7197	44487
221	386	418	799	498	1734	2198	2650	3377	1324	9073
0	0	0	0	01	01	01	0	0	1	2
1	5	2	2	5	10	6	4	13	47	38
266	250	329	389	1048	1734	1538	2321	2982	1302	9623
37	32	32	45	139	147	144 2	182	215	130 2	827 2
13	13	13	13 8	62	52	97	70 1	79	55	384 1
2	5	6	127	27	21	10	8	8	9	74
72	1354	293	24	701	1846	1913	2755	3361	2785	10576
13	8	24	22	83	69	29	34	27	29	243
7	17	12	3 8	53 2	48 3	80 9	81 5	130 2	83 2	392 21
4	5	7	20	14	24	3	25	30	28	134
14	17	5	7	71	56	48	59	45	47	279
	3	8	2	37	18	49	47	72	33	222
		4	63	0	6	14	14	17	49	051
35	45	54	11	184	197	180	212	225	188	998
10	10	4	130	47	35	02	5	1	10	95
50	62	73		282	315	260	35	428	228	1639
10			60	00	10	01				11

The table of burials, and chriſtnings, in London.

Anno Dom.	97 pariſhes.	16 pariſhes.	Out-pariſhes.	Buried in all	Beſides of the plague.	Chriſt-ned.
1604	1518	2097	708	4323	896	5458
1605	2014	2974	960	5948	444	6504
1606	1941	2920	935	5796	2124	6614
1607	1879	2772	1019	5670	2352	6582
1608	2391	3218	1149	6758	2262	6845
1609	2494	3610	1441	7545	4240	6388
1610	2326	3791	1369	7486	1803	6785
1611	2152	3398	1166	6716	627	7014
	16715	24780	8747	50242	14752	52190
1612	2473	3843	1462	7778	64	6986
1613	2406	3679	1418	7503	16	6846
1614	2369	3504	1494	7367	22	7208
1615	2446	3791	1613	7850	37	7682
1616	2490	3876	1697	8063	9	7685
1617	2397	4109	1774	8280	6	7747
1618	2815	4715	2066	9596	18	7735
1619	2339	3857	1804	7999	9	8127
	19735	31374	13328	64436	171	60316
1620	2726	4819	2146	9691	21	7845
1621	2438	3759	1915	8112	11	8039
1622	2811	4217	2392	8943	16	7894
1623	3591	4721	2783	11095	17	7945
1624	3385	5919	2895	12199	11	8299
1625	5143	9819	3886	18848	35417	6983
1626	2150	3285	1965	7401	134	6701
1627	2325	3400	1988	7711	4	8408
	24569	39940	19970	84000	35631	62114
1628	2412	3311	2017	7740	3	8564
1629	2536	3992	2243	8771	0	9901
1630	2506	4201	2521	9237	1317	9315
1631	2459	3697	2132	8288	274	8524
1632	2704	4412	2411	9527	8	9584
1633	2378	3936	2078	8393	0	9997
1634	2937	4980	2982	10393	1	9855
1635	2742	4966	2943	10651	0	10034
	20694	33495	19327	73505	1603	75774

The table of burials, and chriſtnings, in London.

Anno Dom.	97 pariſhes.	16 pariſhes.	Out-pariſhes.	Buried in all	Beſides of the plague	Chriſt-ned
1636	2825	6924	3210	12959	10400	9522
1637	2288	4265	2128	8681	3082	9160
1638	3584	5926	3751	13261	363	10311
1639	2592	4344	2612	9548	314	10150
1640	2919	5156	3246	11321	1450	10850
1641	3248	5092	3427	11767	1375	10670
1642	3176	5245	3578	11999	1274	10370
1643	3395	5552	3269	12216	996	9410
	23987	42544	25221	91752	19244	80443
1644	2593	4274	2574	9441	1492	8104
1645	2524	4639	2445	9608	1871	7966
1646	2746	4872	2797	10415	2365	7163
1647	2672	4749	3041	10462	3597	7332
1648	2480	4288	2515	9283	611	6544
1649	2865	4714	2920	10499	67	5825
1650	2301	4138	2310	8749	15	5612
1651	2845	5002	2597	10804	23	6071
	21026	36676	21199	78896	10041	54617
1652	3293	5719	3546	12553	16	6128
1653	2527	4635	2919	10081	6	6155
1654	3323	6063	3845	13231	16	6620
1655	2781	5148	3439	11348	9	7004
1656	3327	6573	4015	13915	6	7050
1657	3014	5646	3770	12430	4	6685
1658	3613	1692	4443	14979	14	6170
1659	3431	6988	4301	14720	36	5690
	25288	47695	30278	103261	107	51502
1660	3098	5644	2926	12668	13	6971
1661	3804	7309	5532	16645	20	8855
1662	3123	6094	4423	13652	12	10019
1663	3001	5602	4129	12732	09	10292
1664	3448	7166	4829	15448	05	11722

The table following contains the number of burials and chriſtnings in the ſeven pariſhes hereafter mentioned, from the year 1636 unto the year 1659 incluſive; all which time the burials and chriſtnings were jointly mentioned: the five laſt years the chriſtnings were omitted in the yearly bills. This table conſiſts of ſeventeen columns, the total of all the burials being contained in the ſixteenth column: which number being added to the total in the precedent table of buria's and chriſtnings, makes the total of every yearly or general bill.

Note,

Note, where there follows a second number under any year, it denotes those which died that year of the plague.

Anno Dom.	Weſtminſter		Iſlington		Lambeth		Stepney		Newington		Hackney		Redriff		Total in the 7 Pariſhes	
	Bur.	Ch.	B.	C.	B.	Ch.	Bur.	Ch.	B.	Ch.	B.	C.	B.	C.	Bur.	Ch.
1630	1207	556	95	56	213	137	1895	861	584	155	68	77	90	62	4056	1924
	442		30		45		909		242		14		2		1702	
1637	963	496	94	72	173	137	952	838	183	172	68	70	74	1	2507	1836
	301		17		18		153		16		6		10		521	
1638	1021	563	116	49	221	140	1209	908	25	146	101	69	74	78	2997	1953
	126				8		11								145	
1639	546	543	88	53	195	132	970	956	187	159	84	53	81	52	2151	1948
	4		2				2						1		9	
1640	754	665	94	54	187	142	1106	983	189	194	76	54	53	77	24 9	2159
	62		3		6		117						1		189	
1641	697	625	92	76	168	137	1250	1037	170	137	82	73	69	64	2508	2159
	40		4		9		70				4				128	
1642	671	630	98	71	149	124	1270	115	160	145	78	8	63	76	2489	2262
	37		4		12		20		17		5		4		99	
1643	666	592	105	69	177	114	1167	1013	240	147	65	36	42	67	247	2038
	25		3		45		83		86				2		245	
1644	570	429	61	55	115	105	1187	933	123	101	54	45	70	82	2189	1750
	35		8		8		269		44		3		17		384	
1645	621	444	55	63	146	114	1171	873	183	119	58	60	50	60	2284	1753
	62		6		3		150		18		7		1		2 6	
1646	691	503	84	61	137	108	1230	960	155	130	76	63	47	43	2421	1868
	76		8		5		97		14		9		2		203	
1647	739	464	108	56	161	94	1126	926	129	65	88	45	42	44	2393	1688
	114		12		25		155		28		16		4		434	
1648	561	384	68	46	87	57	837	767			57	42	45	59	1635	1305
	41		4				31				6				82	
1649	558	333	90	44	131	55	838	625			90	49			1807	1106
			1				3								4	
1650	470	413	78	54	88	50	748	572	55	65	61	48	50	62	1550	1264
1651	580	345	107	51	127	49	961	634	172	59	60	30	84	43	2091	1213
1652	649	432	99	36	179	50	1212	637	198	85	72	33	74	37	2483	1330
					1										1	
1653	567	394	69	46	120	54	1064	620	195	76	71	48	69	21	2155	1250
1654	657	401	96	65	166	76	1252	803	236	106	88	31	75	46	257	1526
1655	676	414	95	86	134	128	1199	859	172	120	68	37	62	57	2456	1701
1656	761	498	139	89	176	152	1255	963	48	127	67	46	66	45	2701	1920
1657	705	473	112	67	231	137	1213	876	204	123	96	42	51	31	2612	1749
1658	890	440	113	36	220	32	1486	892	181	99	91	30	48	16	2958	1645
1659	822	415	116	56	193	103	1392	695	138	86	83	50	84	13	2828	1418
1660	783		108		183		1151		114		65		33		2437	
1661	983		102		330		1561		341		102		87		3505	
1662	848		59		210		1531		76		101		77		2902	
1663	793		41		199		1241		188		73		80		2615	
1664	801		50		236		1392		235		80		40		2848	

The

The TABLE of males, and females, for London.

An. Dom.	Buried		Chriſtned	
	males	females	males	females
1629	4668	4103	5218	4683
1630	5660	4894	4858	4457
1631	4549	4013	4422	4102
1632	4932	4603	4994	4590
1633	4369	4023	5158	4839
1634	5676	5224	5035	4820
1635	5548	5103	5106	4928
1636	12377	10982	4917	4605
	47779	43945	39708	37024
1637	6392	5371	4703	4457
1638	7168	6456	5359	4952
1639	5351	4511	5366	4784
1640	6761	6010	5518	5332
Total	73451	65293	60664	56549
1641	6872	6270	5470	5200
1642	7049	6224	5460	4910
1643	6842	6360	4793	4617
1644	5659	5274	4107	3997
1645	6014	5465	4047	3919
1646	6683	6097	3768	3395
1647	7313	6746	3796	3536
1648	5145	4749	3363	3181
	51577	47185	34804	32755
1649	5454	5112	3079	2746
1650	4548	4216	2890	2722
1651	5680	5147	3231	2840
1652	6543	6026	3220	2908
1653	5416	4671	3196	2959
1654	6972	6275	3441	3179
1655	6027	5330	3655	3349
1656	7365	6556	3668	3382
	44005	41333	26380	24085
1657	6572	5850	3396	3289
1658	7936	7057	3157	3013
1659	7451	7305	3209	2781
1660	7960	7158	3724	3247
1661	10448	9287	4748	4107
1662	8623	7931	5216	4803
1663	8035	7321	5411	4881
1664	9169	8928	6041	5681
	67400	60843	34002	31802
Total	232247	214658	156750	146231

The

The TABLE of the country pariſh.

Years	Communicants	Weddings	Chriſtned M.	F.	Both	Buried M.	F.	Both
1569		14	38	30	68	23	21	44
1570		19	29	32	61	21	25	46
1571		18	28	26	54	23	27	50
1572		23	32	32	54	20	14	34
1573		21	34	36	20	24	13	37
1574		16	21	29	50	28	38	66
1575		24	37	29	66	15	19	34
1576		22	33	37	70	16	18	34
1577		13	29	26	55	19	21	40
1578		20	31	35	66	25	25	50
		190	312	302	614	214	221	435
1579		15	35	36	71	27	27	54
80		21	43	31	74	38	41	79
81		29	29	33	62	34	24	58
82		22	28	29	57	18	21	39
83		22	32	27	59	35	52	87
84		15	46	44	90	22	19	41
85		15	26	21	47	15	27	42
86		18	22	23	45	24	37	61
87		13	34	31	65	43	36	79
1588		15	33	34	67	31	18	49
		185	328	309	637	287	302	589
1589		20	31	27	58	28	16	44
90		16	40	29	69	36	21	57
91		12	37	28	65	35	30	65
92		14	40	25	65	28	19	47
93		20	32	20	52	33	32	65
94		24	34	37	71	16	22	38
95		16	32	28	60	33	28	61
96		9	36	26	62	42	29	71
97		23	23	25	48	53	64	117
98		21	37	29	66	33	23	66
		175	342	274	616	337	219	631
1599		19	45	31	76	21	22	43
600		16	26	34	60	20	26	46
601		16	39	32	71	18	12	30
602		14	31	32	63	29	18	47
603		12	31	38	69	32	39	71
604		21	42	35	77	26	27	53
605		19	47	34	81	21	12	33
606		19	29	41	70	28	23	51
607		27	36	47	83	33	19	52
608		17	40	53	93	21	21	42
		181	366	377	743	249	219	468

The

The table of the country parish.

Years	Weddings	Christned M.	Christned F.	Christned Both	Buried M.	Buried F.	Buried Both
1609	23	30	31	61	24	41	65
10	19	46	30	76	33	40	73
11	25	40	41	81	41	32	73
12	20	55	32	87	53	63	116
13	24	41	33	74	47	41	88
14	25	50	35	85	27	36	63
15	22	35	48	83	28	36	64
16	14	38	36	74	27	41	68
17	17	45	31	76	35	28	63
1618	8	37	41	78	23	28	51
	197	417	358	775	338	386	724
1619	21	37	43	80	26	28	54
20	20	34	51	85	18	30	48
21	21	31	37	68	28	36	64
22	23	45	38	83	20	26	46
23	14	40	36	76	56	31	87
24	19	30	33	63	29	35	64
25	7	37	41	78	30	20	56
26	9	30	35	65	21	29	50
27	18	45	23	68	24	29	53
1628	16	39	36	75	47	42	89
	168	368	373	741	305	306	611
1629	22	53	38	91	46	28	74
30	8	58	45	103	26	27	53
31	20	42	29	71	26	33	59
32	16	43	50	93	15	21	36
33	12	38	65	103	18	11	29
34	23	30	45	75	18	26	44
35	11	39	32	71	18	17	35
36	15	50	37	87	42	48	90
37	13	35	36	71	25	35	60
1638	13	30	36	66	83	73	156
	153	418	413	831	317	319	636
1639	18	24	31	55	48	66	114
40	11	44	41	85	35	39	74
41	21	34	29	63	34	39	70
42	21	48	39	87	32	29	61
43	8	30	42	72	59	28	87
44	16	33	26	59	65	72	137
45	10	43	41	84	28	29	57
46	11	32	35	67	24	32	56
47	12	28	46	74	25	21	46
48	9	35	27	62	25	31	56
	137	351	357	708	375	386	758
1649	9	22	37	59	46	34	80
50	9	55	31	86	25	27	52
51	7	25	27	52	11	21	32
52	14	34	28	62	20	25	45
53	9	47	24	71	21	14	35
54	15	34	37	71	14	25	39
55	38	35	34	69	28	19	47
56	28	40	30	70	18	15	33
57	37	23	43	66	22	25	47
58	16	39	29	68	13	15	28
	182	354	320	674	218	220	438

The

The table by decads of years for the country pariſh.

Decads of years	Maried	Chriſtned males	Chriſtned females	Chriſtned Both	Buried males	Buried females	Buried Both
15 69–78	190	312	302	614	214	221	435
15 79–88	185	328	309	637	287	302	589
15 89–98	175	342	274	616	337	284	621
1 599–608	181	366	377	743	249	219	468
16 09–18	197	417	358	775	338	386	724
16 19–28	168	368	373	741	305	306	611
16 29–38	53	418	413	831	317	319	636
16 39–48	137	351	357	708	375	383	758
16 49–58	182	354	320	674	218	220	438
	1598	3256	3083	6339	2640	2640	5280

The number of the weddings, chriſtnings and burials, that were in the town and pariſh of Tiverton, from March 1560 *to January* 1664; *as appeareth by the regiſters.*

Years	Weddings	Chriſtned M.	Chriſtned F.	Chriſtned Both	Buried M.	Buried F.	Buried Both
1560	37	23	29	52	43	28	71
61	51	35	31	66	36	34	70
62	16	49	50	109	32	34	66
63	19	39	50	89	27	15	42
64	19	47	50	97	21	15	36
65	14	51	27	78	26	28	54
66	19	67	44	111	23	12	35
67	23	52	42	94	28	16	44
68	15	50	34	84	25	25	50
69	19	40	37	77	23	38	61
	232	463	394	857	284	245	529
1570	17	51	45	96	45	58	103
71	21	46	26	72	70	68	138
72	35	52	44	96	30	23	53
73	38	55	39	94	22	19	41
74	37	42	50	92	25	28	53
75	32	51	71	122	33	21	54
76	27	62	65	127	43	93	136
77	27	79	46	125	54	76	130
78	38	59	57	116	42	54	96
79	45	56	59	115	35	63	98
	317	553	502	1055	399	502	902

The

The table of the parish of Tiverton.

Years	Weddings	Christned M.	Christned F.	Christned Both	Buried M.	Buried F.	Buried Both
1580	35	61	03	124	36	43	79
81	34	62	64	126	37	39	76
82	34	68	67	135	45	38	83
83	33	54	44	98	31	47	78
84	28	77	59	136	39	43	82
85	11	69	64	133	32	52	84
86	27	42	40	82	49	40	89
87	27	57	63	120	76	94	170
88	36	67	65	132	57	43	100
89	33	83	70	153	47	55	102
	298	640	599	1239	419	494	943
1590	39	60	64	124	62	87	149
91	48	56	44	100	268	282	550
92	43	75	77	152	37	48	85
93	43	63	48	111	37	65	102
94	37	66	98	164	31	47	78
95	38	54	52	106	37	60	97
96	22	60	58	18	51	77	128
97	18	37	29	66	124	153	277
98	23	44	38	82	45	103	148
99	42	50	73	123	27	27	54
	353	565	521	1146	719	949	1668
1600	38	64	54	118	28	38	66
1	33	52	82	134	28	36	64
2	37	65	62	127	41	42	83
3	52	60	83	143	50	36	86
4	28	75	63	138	27	63	90
5	49	62	68	130	33	48	81
6	37	79	77	156	45	42	87
7	47	89	77	166	34	52	86
8	37	60	86	146	51	64	115
9	34	70	69	139	27	49	76
	392	676	721	1379	364	470	834
1610	31	83	88	171	62	50	112
11	51	83	96	179	39	41	80
12	47	79	70	149	58	45	103
13	38	74	77	151	39	40	79
14	46	90	88	178	42	41	83
15	55	88	84	172	39	44	83
16	24	211	100	211	53	59	112
17	41	99	79	178	57	57	114
18	46	102	79	181	32	44	76
19	30	104	102	206	65	72	137
	409	913	863	1776	486	493	979

The

The table of the parish of Tiverton.

Years	Weddings	Christned M.	Christned F.	Christned Both	Buried M.	Buried F.	Buried Both
1620	42	105	72	177	53	53	106
21	74	111	111	222	61	51	112
22	40	89	104	193	60	86	146
23	52	108	88	196	80	101	181
24	52	95	95	190	60	68	128
25	57	131	117	248	86	61	147
26	66	97	101	198	73	95	168
27	67	143	110	253	98	45	143
28	66	103	114	217	87	98	185
29	77	124	108	232	62	68	130
	593	1106	1020	2126	720	726	1446
1630	73	117	123	240	104	74	178
31	40	118	100	218	85	92	177
32	63	106	104	210	84	83	167
33	63	114	121	235	75	71	146
34	54	114	95	209	73	91	164
35	82	124	111	235	84	92	176
36	43	135	113	248	85	87	172
37	42	110	98	208	106	142	248
38	62	112	112	224	194	170	364
39	62	119	106	225	115	137	252
	584	1169	1083	2252	1005	1039	2044
1640	66	124	114	238	82	104	186
41	52	122	114	236	83	88	171
42	59	102	136	238	110	128	238
43	54	115	117	232	102	88	190
44	22	76	78	154	232	213	445
45	47	95	175	270	99	92	191
46	41	61	50	111	3	3	6 Pl.
47	23	116	106	222	7	3	10
48	22	85	67	152	24	17	41
49	16	96	92	188	21	30	51
	402	991	1049	2041	763	766	1529
1650	9	66	79	145	7	9	16
51	9	50	63	113	5	10	15
52	9	80	73	153	48	51	99
53	21	89	219	208	47	78	125
54	108	105	104	206	72	68	140
55	140	87	104	191	87	114	201
56	109	107	90	197	56	86	142
57	102	94	101	195	67	59	126
58	60	70	83	153	77	85	162
59	37	77	78	155	72	80	152
	604	825	891	1716	538	640	1178
1660	27	61	68	129	70	69	139
1	38	83	93	176	73	85	158
2	36	73	56	129	91	95	186
3	35	68	64	132	72	74	146
4	41	68	72	140	98	114	212
	177	353	353	706	404	437	841

The number of the weddings, chriſtnings and burials, that were in the pariſh of Cranbrooke, from March 26, 1560, to March 24, 1649; (as appeareth by the regiſter) only in the years 1574 and 1575 the chriſtnings are wholly omitted, becauſe the regiſter is very imperfect for the greater part of thoſe years.

Years	Weddings	Chriſtned M.	F.	Both	Buried M.	F.	Both	
1560	20	30	33	69	29	21	50	
61	24	46	33	79	23	22	45	
62	23	32	36	58	40	31	71	
63	15	28	21	49	19	24	43	
64	23	29	29	58	10	8	18	
65	29	44	29	73	37	34	71	
66	25	39	26	65	69	35	104	
67	28	42	41	83	36	21	56	
68	22	38	44	82	31	31	62	
69	22	36	35	71	25	19	44	
	231	370	317	687	319	246	564	
1570	18	30	44	74	26	36	62	
71	21	31	27	58	31	16	47	
72	25	35	34	69	24	39	63	
73	29	28	25	53	29	21	50	
74	23				28	28	56	
75	25				18	14	32	
76	29	49	42	91	17	16	33	
77	16	36	48	84	23	21	44	
78	24	42	39	81	19	16	35	
79	21	47	44	91	26	18	44	
	235	298	303	601	241	225	465	
1580	30	47	42	89	26	23	49	Pl.
81	28	61	46	107	32	30	62	18
82	26	58	49	117	52	37	89	41
83	24	59	44	103	24	20	44	22
84	25	53	55	108	24	29	53	
85	22	60	52	112	16	14	30	
86	17	53	50	103	28	22	50	
87	20	45	53	98	28	24	52	
88	24	57	59	116	24	21	45	
89	19	59	44	103	17	28	45	
	235	552	504	1051	271	248	519	
1590	25	64	58	116	21	17	38	
91	26	41	52	93	34	43	77	
92	20	59	46	105	39	31	70	
93	23	54	47	101	22	17	39	
94	22	48	37	85	24	23	47	
95	14	55	53	108	35	36	71	
96	17	36	42	78	42	25	67	Pl.
97	22	37	19	56	112	110	222	181
98	22	47	41	88	27	34	59	Pl.8
99	30	56	40	96	19	20	39	
	221	497	429	926	373	356	729	

The

The table of the parish of Cranbrook.

Years	Weddings	Christned M.	Christned F.	Christned Both	Buried M.	Buried F.	Buried Both
1600	16	48	44	92	16	18	34
1	19	44	41	85	19	29	48
2	26	50	43	93	28	26	54
3	22	68	51	119	36	28	64 pl.9
4	36	47	61	108	20	24	44
5	23	56	39	95	38	30	68
6	23	42	44	86	30	31	61 pl.1
7	29	51	65	116	48	30	78
8	13	56	35	19	33	31	64
9	16	40	37	77	43	46	89 pl.1
	223	502	460	962	311	292	603
1610	26	45	42	87	32	42	74
11	27	39	44	83	44	53	97
12	16	44	39	83	50	43	93
13	22	43	41	84	46	50	96
14	22	50	44	94	55	35	90
15	35	56	44	100	64	61	125
16	29	35	54	89	40	47	87
17	20	49	52	101	50	48	98
18	32	38	51	89	37	58	95
19	32	47	40	87	50	44	94
	261	446	451	897	468	481	949
1620	27	59	61	120	45	52	97
21	26	54	50	104	40	46	86
22	14	61	65	126	27	28	55
23	18	37	37	74	33	34	67
24	45	59	60	119	44	31	75
25	22	44	59	103	54	56	110
26	26	36	45	81	48	49	97
27	25	45	50	95	36	38	74
28	38	57	60	117	56	70	126
29	48	60	58	118	51	44	95
	289	512	545	1057	434	448	882
1630	25	58	64	122	41	52	93
31	15	51	46	97	46	42	88
32	20	57	56	113	56	52	108
33	19	73	55	128	44	44	88
34	30	63	52	115	46	51	97
35	18	54	57	111	56	50	106
36	15	52	55	107	39	60	99
37	31	61	85	126	47	49	96
38	22	49	56	105	73	80	153
39	28	31	36	67	63	51	114
	223	549	542	1019	511	531	1042
1640	30	65	50	115	70	54	124
1	20	51	62	113	51	36	87
2	27	47	40	87	39	53	92
3	20	68	63	131	68	59	117
4	23	51	60	111	37	49	86
5	31	55	46	101	30	46	76
6	14	63	51	114	69	65	134
7	18	44	36	83	72	47	119
8	6	35	23	58	55	60	115
9	7	37	26	63	58	48	106
	196	516	460	976	549	517	1066

Dub-

Dublin, a bill of mortality from the 26th of July to the second of Auguſt 1662.

	Baptiz.	Plague	Spot.Fev.	Small-pox	Conſum.	Fever	Aged	Rickets	Flux
St. Michans	1			1			1		
St. Katharines and St. James	2								1
St. Audœns					1				
St. Michaels	2				2				2
St. Johns							2		2
St. Nicholas without	5				1		1		1
St. Nicholas within	1								1
St. Warbrows and St. Andrews	2				1				
St. Keavans					1				
St. Brides.	1				2				

The total baptized 14. Total buried 20.

JACOB THRING, Reg.

Some

Some further

OBSERVATIONS

OF

Major JOHN GRAUNT.

WHEREAS in the month of December, in the year 1672, there were chriſtned in the ſeveral pariſhes of the city and ſuburbs of Paris 1366, and weddings 68, and buried 1153; yet of the reformed religion, in the ſame ſpace of time and place, there were chriſtned but 27, and buried but 14: at a medium being compared to the groſs ſum, the proteſtants in Paris are but as one to 65.

A further obſervation may be made; that whereas in the whole year of 1672, there were buried 17584, and the chriſtnings then were 18427, which difference between chriſtnings and burials was very agreeable with the difference formerly in the city of London, before phanaticiſm and the anabaptiſts were known in thoſe parts: but in the ſame year of 1672 in the city of London and places adjacent, the burials were 18230, and the chriſtnings but 12563: by which it plainly appears that $\frac{1}{7}$ of the inhabitants of the places aforeſaid are ſuch, as do not conform to the doctrine and diſcipline of the church of England.

As concerning the common queſtion, whether Paris or London hath moſt inhabitants, my anſwer muſt be framed after this manner, upon ſome obſervations made upon the numbers of burials of each city.

I find that in the city and ſuburbs of Paris in the years 1670, 1671, and 1672, the total number of the burials was 56443, and in the years aforeſaid in the city of London, ſuburbs and places adjacent (as appears by the annual bills of mortality) were buried 54157.

But ſince that Hackney, Lambeth, Newington, Iſlington, Rotherhith, Stepney, and Weſtminſter, although put into the bills of mortality, they cannot properly be reckoned as parts of the city of London (Weſtminſter being a diſtinct city of itſelf, and the other above-named country villages) and there having been buried in the places laſt named in the three years aforeſaid (as appears by the ſaid annual bills) 10000, which being deducted out of the number aforeſaid, the remaining number is 44157, upon which I think the compariſon muſt be made.

By which it appears, that Paris hath exceeded the city of London in the number of burials 12286, which number is between a fourth and a fifth of the ſaid number of 56443, which is the proportion of the difference in the number of inhabitants; the city of Paris having more than a fourth, and yet not a fifth more than the city of London.

Chriſtnings,

Chriſtnings, marriages, and burials in the city of Paris, 1670.

	Chriſtnings.	Marriages.	Burials.
January.	1596	353	2350
February.	1712	589	2159
March.	1661	048	2033
April.	1351	267	1882
May.	1342	374	1714
June.	1222	354	1644
July.	1348	420	1540
Auguſt.	1420	314	2162
September.	1408	343	1845
October.	1312	313	1502
November.	1324	479	1290
December	1120	076	1340
Total	16810	3930	21461

Chriſtnings, marriages, and burials in the city of Paris, 1671.

	Chriſtnings.	Burials.	Marriages.
January.	1675	548	1150
February.	1656	489	1068
March.	1860	56	1218
April.	1595	447	1350
May.	1478	324	1431
June.	1331	334	1219
July.	1424	337	1358
Auguſt.	1606	324	1502
September.	1507	327	1897
October.	1587	321	1753
November.	1560	437	2709
December.	1253	42	1743
Total	18532	3986	17398

Chriſtnings,

Chriſtnings, marriages, and burials in the city of Paris, 1672.

	Chriſtnings.	Marriages.	Burials.
January.	1837	325	1930
February.	1920	625	1554
March.	1636	108	2008
April.	1572	130	1664
May.	1528	332	1551
June.	1359	349	1602
July.	1414	334	1323
Auguſt.	1498	271	1407
September.	1379	278	1216
October.	1481	309	1119
November.	1437	433	1057
December	1366	068	1153
Total	18427	3562	17584

A table ſhewing how many died weekly, as well of all diſeaſes, as of the plague,

Buried of all diſeaſes in the year 1592.			Buried of all diſeaſes in the year 1603.			Buried of all diſeaſes in the year 1625.		
	Tot.	Plag.		Tot.	Plag.		Tot.	Plag.
March 17	230	3	March 17	108	3	March 17	262	4
March 24	351	31	24	6[illegible]	2	24	226	8
March 31	219	29	31	78	6	31	243	11
April 7	307	27	April 7	66	4	April 7	239	10
April 14	203	33	14	79	4	14	256	24
April 21	290	37	21	98	8	21	230	25
April 28	310	41	28	109	10	28	305	26
May 5	35[illegible]	29	May 5	90	11	May 5	292	30
May 12	339	38	12	112	18	12	232	45
May 19	30[illegible]	42	19	122	22	19	379	71
May 26	450	58	26	122	32	26	401	78
June 2	410	62	June 2	114	30	June 2	395	69
June 9	441	81	9	131	43	9	434	91
June 16	399	99	16	144	59	16	510	161
June 23	401	108	23	182	72	23	640	239
June 30	850	118	30	267	158	30	942	390
July 7	1440	927	July 7	445	263	July 7	1222	593
July 14	1510	893	14	612	424	14	1781	1004
July 21	1491	238	The out-pariſhes this week were joined with the city			21	2850	1819
July 28	1507	852				28	3583	2471
Auguſt 4	1 03	983				Auguſt 4	4517	3659
Auguſt 11	155[illegible]	797	July 21	1186	917	11	4855	4115
Auguſt 18	1532	651	28	172[illegible]	1396	18	5205	4463
Auguſt 25	1505	449	Auguſt 4	22 6	1922	25	4841	4718
September 1	1490	507	11	2077	1745	September 1	3897	3344
September 8	1210	563	18	305[illegible]	2713	8	3157	2550
September 15	621	451	25	2853	2539	15	2148	1672
September 22	629	349	September 1	3385	3035	22	1994	1551
September 29	450	330	8	3078	2724	29	236	852
October 6	408	327	1[illegible]	3129	2818	October 6	833	538
October 13	422	323	22	245[illegible]	2195	13	815	511
October 20	330	308	29	1961	1732	20	651	331
October 27	320	302	October 6	1831	1641	27	375	134
November 3	310	301	13	1312	1149	November 3	357	89
November 10	30[illegible]	209	20	76[illegible]	642	10	319	92
November 17	301	107	27	625	508	17	274	48
November 24	321	93	November 3	737	594	24	231	27
December 1	349	94	10	545	442	December 1	190	15
December 8	331	85	17	384	251	8	181	15
December 15	329	71	24	198	105	15	168	6
December 22	386	39	December 1	223	102	22	157	1
			8	16[illegible]	55			
			1[illegible]	200	96			
			22	168	74			
The total of all that have been buried is		25886	The total of all is		37204	The total of all is		51578
Whereof of the plague		11503	Whereof of the pl.		30561	Whereof of the Plague		35403

in the years 1592, 1603, 1625, 1630, 1636; *and this preſent year* 1665.

Buried of all diſeaſes in the year 1630.

	Tot.	Plag.
June 24	205	19
July 1	200	25
8	217	43
15	250	50
22	229	40
29	279	77
Auguſt 5	250	56
12	24[illegible]	65
19	269	54
26	270	67
September 2	230	66
9	259	63
16	264	68
23	274	57
30	260	56
October 7	236	66
14	261	73
21	248	60
28	214	34
November 4	242	29
11	215	29
18	200	18
25	226	7
December 2	221	20
9	198	19
16	212	5

Buried in the 97 pariſhes within the walls 2696
Whereof of the plague 190
Buried in the 16 pariſhes without the walls 4813
Whereof of the plague 603
Buried in the 9 out-pariſhes in Middleſex and Surrey, and at the Peſt-houſe 3045
Whereof of the pl. 524
Buried in Weſtminſter 566
Whereof of the pl. 31

The total of all the burials this time 10554
Whereof of the pl. 1317

Buried of all diſeaſes in the year 1636.

	Tot.	Plag.
April 7	115	2
14	205	4
This week theſe pariſhes were added; S. Marg. Weſtminſter, Lambeth pariſh, S. M. Newington, Rotherhith pariſh, S. M. Iſlington, Stepney and Hackney pariſhes.		
April 21	285	14
28	259	17
May 5	251	10
12	308	55
19	299	35
26	330	62
June 2	339	77
9	345	87
16	381	103
23	304	79
30	352	104
July 7	215	81
14	372	104
21	365	120
28	423	151
Auguſt 4	491	206
11	538	283
18	638	321
25	787	429
September 1	1011	638
8	1069	650
15	1306	865
22	1229	775
29	1403	928
October 6	1405	921
13	1302	792
20	1002	555
27	900	458
November 3	1300	838
10	1104	715
17	950	573
24	857	476
December 1	614	321
8	459	16[illegible]
15	385	85

The total of the burials this year is 23359
Whereof of the pl. 10400

Buried of all diſeaſes in the year 166[illegible].

	Tot.	Plag
December 27	291	
January 3	349	
10	391	
17	415	
24	474	
31	409	
February 7	393	
14	461	1
21	393	
28	396	
March 7	441	
14	433	
21	365	
28	353	
April 4	344	
11	382	
18	344	
25	390	2
May 2	388	
9	347	9
16	353	3
23	385	14
30	399	17
June 6	405	43
13	558	112
20	611	168
27	684	267
July 4	1006	470
11	1268	727
18	1761	1089
25	2785	1843
Auguſt 1	3014	2010
8	4030	2817
15	5319	3880
22	5568	4237
29	7496	6102
September 5	8252	6988
12	7690	6544
19	8297	7165
26	6460	5533
October 3	5720	4929
10	5068	4327
17	3219	2665
24	1866	1421
31	1388	1031
November 7	1787	1414
14	1359	1050
21	905	652
28	544	333
December 5	428	210
12	442	243
19	525	281

The total of the burials this year is 97306
Whereof of the pl. 68596

Ad-

Advertiſements for the better underſtanding of the ſeveral tables: videlicet,

Concerning the table of caſualties conſiſting of thirty columns.

THE firſt column contains all the caſualties happening within the 22 ſingle years mentioned in this bill.

The 14 next columns contain two of the laſt ſeptenaries of years, which being the lateſt are firſt ſet down.

The 8 next columns repreſent the 8 firſt years, wherein the caſualties were taken notice of.

Memorandum, that the ten years between 1636 *and* 1647 *are omitted as containing nothing extraordinary, and as not conſiſtent with the incapacity of a ſheet.*

The 5 next columns are the 8 years from 1629 to 1636 brought into 2 quaternions, and the 12 of the 14 laſt years brought into three more; that compariſon might be made between each 4 years taken together, as well as each ſingle year apart.

The next column contains three years together, taken at 10 years diſtance from each other; that the diſtant years, as well as conſequent, might be compared with the whole 20, each of the 5 quaternions, and each of the 22 ſingle years.

The laſt column contains the total of all the 15 quaternions or 25 years.

The number 229250 is the total of all the burials in the ſaid 20 years, as 34190 is of the burials in the ſaid three diſtant years. Where note, that the $\frac{1}{7}$ of the latter total is 11396, and the $\frac{1}{10}$ of the former is 11462; differing but 66 from each other in ſo great a ſum, videlicet, ſcarce $\frac{1}{100}$ part.

The

The table of burials and chriſtnings, conſiſting of ſeven columns.

IT is to be noted, that in all the ſeveral columns of the burials thoſe dying of the plague are left out, being reckoned all together in the ſixth column: whereas in the original bills, the plague, and all other diſeaſes are reckoned together, with mention how many of the reſpective totals are of the plague.

Secondly, From the year 1642 forwards, the account of the chriſtnings is not to be truſted, the neglects of the ſame beginning about that year: for in 1642 there are ſet down 10370, and about the ſame number ſeveral years before, after which time the ſaid chriſtnings decreaſed to between 5000 and 6000, by omiſſion of the greater part.

Thirdly, the ſeveral numbers are caſt up into octonaries, that compariſon may be made of them as well as of ſingle years.

The table of males and females, containing five columns.

Firſt, the numbers are caſt up for 12 years; videlicet, from 1629, when the diſtinction between males and females firſt began, until 1640 incluſive, when the exactneſs in that account ceaſed.

Secondly, from 1640 to 1660 the numbers are caſt up into another total, which ſeems as good for comparing the number of males with females, the neglect being in both ſexes alike and proportionable.

The tables concerning the country pariſh, the former of decads beginning at 1569, and continuing until 1658, and the latter being for ſingle years, being for the ſame time, are ſo plain, that they require no further explanation than the bare reading the chapter relating to them, &c.

The

ANOTHER

ESSAY

IN

POLITICAL ARITHMETIC

Concerning the growth of the

CITY OF LONDON:

WITH THE

MEASURES, PERIODS, CAUSES, and CONSEQUENCES thereof.

By Sir WILLIAM PETTY F.R.S.

Reprinted from the Edition printed at LONDON in 1683.

The PRINCIPAL POINTS of this DISCOURSE.

THAT London doubles in forty years, and all England in three hundred and ſixty years.

2. *That there be, anno* 1682, *about ſix hundred and ſeventy thouſand ſouls in London, and about ſeven millions, four hundred thouſand in all England and Wales; and about twenty millions of acres of land.*

3. *That the periods of doubling the people are found to be in all degrees, from between ten, to twelve hundred years.*

4. *That the growth of London muſt ſtop of itſelf, before the year* 1800.

5. *A table helping to underſtand the ſcriptures, concerning the number of people mentioned in them.*

6. *That the world will be fully peopled within the next two thouſand years.*

7. *Twelve touch-ſtones, whereby to try any propoſal, pretended for the public good.*

8. *How the city of London may be made (morally ſpeaking) invincible.*

9. *An help to uniformity in Religion.*

10. *That 'tis poſſible to increaſe mankind by generation four times more than at preſent.*

11. *The plagues of London is the chief impediment and objection againſt the growth of the city.*

12. *That an exact account of the people is neceſſary in this matter.*

Of the growth of the city of LONDON: and of the MEASURES, PERIODS, CAUSES, and CONSEQUENCES thereof.

What is meant by London.

BY the city of London, we mean the houſing within the walls of the old city, with the liberties thereof, Weſtminſter, the Borough of Southwark, and ſo much of the built ground in Middleſex and Surrey, whoſe houſes are contiguous unto, or within call of thoſe aforementioned. Or elſe we mean the houſing, which ſtand upon the ninety ſeven pariſhes within the walls of London; upon the ſixteen pariſhes next, without them; the ten pariſhes of Weſtminſter, and the ſeven pariſhes without them all; all which one hundred and thirty pariſhes are comprehended within the weekly bills of mortality.

What is meant by the growth of London.

The growth of this city is meaſured, 1. By the quantity of ground, or number of acres upon which it ſtands. 2. By the number of houſes, as the ſame appears by the hearth-books and late maps. 3. By the cubical content of the ſaid houſing. 4. By the flooring of the ſame. 5. By the number of days-work, or charge of building the ſaid houſes. 6. By the value of the ſaid houſes, according to their yearly rent, and number of years purchaſe. 7. By the number of inhabitants; according to which latter ſenſe only, we make our computations in this eſſay.

Till a better rule can be obtained, we conceive, that the proportion of the people may be ſufficiently meaſured by the proportion of the burials in ſuch years, as were neither remarkable for extraordinary healthfulneſs or ſicklineſs.

In what meaſures the city hath increaſed.

That the city hath increaſed in this latter ſenſe appears from the bills of mortality, repreſented in the two following tables, viz. one whereof is a continuation for eighteen years, ending 1682, of that, table which was publiſhed in the 117th* page of the book of the obſervations upon the London bills of mortality, printed in the year 1676. The other ſheweth what number of people died at a medium of two years, indifferently taken, at about twenty years diſtance from each other.

* P. 44 of the preſent edition.

The first of the said two tables.

An. Dom.	97 parishes.	16 parishes.	Out-parishes.	Buried in all.	Besides of the plague.	Christned.
1665	5320	12463	10925	28708	68596	9967
1666	1689	3969	5082	10740	1998	8997
1667	7761	6405	8641	15807	35	10938
1668	796	6865	9603	17267	14	11633
1669	1323	7500	10440	19263	3	12335
1670	1890	7808	10500	20198		11997
1671	1723	5938	8063	15724	5	12510
1672	2237	6788	9200	18225	5	12593
1673	2307	6302	8890	17499	5	11895
1674	2801	7522	10875	21198	3	11851
1675	2555	5986	8702	17243	1	11775
1676	2756	6508	9466	18730	2	12399
1677	2817	6632	9616	19065	2	12626
1678	3060	6705	10908	20673	5	12601
1679	3074	7481	11173	21728	2	12288
1680	3076	7066	10911	21053		12747
1681	3669	8136	12166	23971		13355
1682	2975	7009	10707	20691		12653

According to which latter table there died as followeth.

The latter of the said two tables.

There died in London, at a medium, between the years

1604 and 1605 —— 5135. A.
1621 and 1622 —— 8527. B.
1641 and 1642 —— 11883. C.
1661 and 1662 —— 15148. D.
1681 and 1682 —— 22331. E.

Wherein observe, that the number C is double to A, and 806 over; that D is double to B within 1906; that C and D is double to A B within 293; that E is double to C within 1435; that D and E is double to B and C within 3341; and that C and D and E are double to A and B and C within 1736; and that E is above quadruple to A. All which differences (every way considered) do allow the doubling of the people of London in forty years to be a sufficient estimate thereof in round numbers, and without the trouble of fractions. We also say, that

that 669930 is near the number of people now in London, becauſe the burials are 22331, which multiplied by 30, (one dying yearly out of 30, as appears in the 94th * page of the aforementioned obſervations) maketh the ſaid number; and becauſe there are 84 thouſand tenanted houſes (as we are credibly informed) which, at 8 in each, makes 672 thouſand ſouls; the ſaid two accounts differing inconſiderably from each other.

We have thus pretty well found out in what number of years (viz. in about 40,) the city of London hath doubled, and the preſent number of inhabitants to be about 670 thouſand. We muſt now alſo endeavour the ſame for the whole territory of England and Wales. In order whereunto, we firſt ſay,

The people of London are about the eleventh part of all England and Wales. And the people of England about 7 millions and 400 thouſands.

That the aſſeſſment of London is about an eleventh part of the whole territory, and therefore that the people of the whole may well be eleven times that of London, viz. about 7 millions, 369 thouſand ſouls; with which account that of the poll-money, hearth-money, and the Biſhops late numbering of the communicants, do pretty well agree. Wherefore, although the ſaid number of 7 millions, 369 thouſand, be not (as it cannot be) a demonſtrated truth, yet it will ſerve for a good ſuppoſition, which is as much as we want at preſent.

As for the time in, which the people double, it is yet more hard to be found: for we have good experience (in the ſaid 94th † page of the aforementioned obſervations) that in the country, but one of fifty die per annum; and by other late accounts, that there have been ſometimes but 24 births for 23 burials: the which two points, if they were univerſally, and conſtantly true, there would be colour enough to ſay, that the people doubled but in about 1200 years. As for example: ſuppoſe there be 600 people, of which let a fiftieth part die per annum, then there ſhall die 12 per annum; and if the births be as 24 to 23, then the increaſe of the people ſhall be ſomewhat above half a man per annum, and conſequently the ſuppoſed number of 600, cannot be doubled but in 1126, which to reckon in round numbers, and for that the aforementioned fractions were not exact, we had rather call 1200.

There are alſo other good obſervations, that even in the country, one in about 30, or 32 per annum hath died, and that there have been five births for four burials. Now, according to this doctrine, 20 will die per annum out of the above 600, and 25 will be born, ſo as the increaſe will be 5, which is a hundred and twentieth part of the ſaid 600. So as we have two fair computations, differing from each other as one to ten; and there are alſo ſeveral other good obſervations for other meaſures.

I might here inſert, that although the births in this laſt computation be 25 of 600, or a twenty fourth part of the people; yet that in natural poſſibility, they may be near thrice as many, and near 75. For that by ſome late obſervations, the teeming females between 15 and 44, are about 180 of the ſaid 600, and the males of between 18 and 59, are about 180 alſo, and that every teeming woman can bear a child once in two years; from all which

* P. 35 of the preſent edition † P. 35 ibid.

it is plain, that the births may be 90 (and abating 15 for ſickneſs, young abortions, and natural barenneſs) there may remain 75 births, which is an eighth of the people; which by ſome obſervations we have found to be but a two and thirtieth part, or but a quarter of what is thus ſhewn to be naturally poſſible. Now, according to this reckoning, if the births may be 75 of 600, and the burials but 15, then the annual increaſe of the people will be 60; and ſo the ſaid 600 people may double in 10 years, which differs yet more from 1200, abovementioned. Now, to get out of this difficulty, and to temper thoſe vaſt diſagreements, I took the medium of 50 and 30 dying per annum, and pitched upon 40; and I alſo took the medium between 24 births and 23 burials, and 5 births for 4 burials, viz. allowing about 10 births for 9 burials; upon which ſuppoſition, there muſt die 15 per annum out of the abovementioned 600, and the births muſt be 16 and two thirds and the increaſe 1, and two thirds, or five thirds of a man, which number compared with 1800 thirds *, or 600 men, gives 360 years for the time of doubling (including ſome allowance for wars, plagues, and famine, the effects whereof, though they be terrible at the times and places where they happen, yet in a period of 360 years, is no great matter in the whole nation. For the plagues of England in 20 years have carried away ſcarce an eightieth part of the people of the whole nation; and the late 10 years civil wars, (the like whereof hath not been in ſeveral ages before) did not take away above a fortieth part of the whole people.)

According to which account or meaſure of doubling, if there be now in England and Wales, 7 millions 400 thouſand people, there were about 5 millions 526 thouſand in the beginning of Queen ELIZABETH's reign, anno 1560, and about two millions at the Norman conqueſt, of which conſult the Dooms-day book, and my Lord HALE's *Origination of mankind.*

Three hundred and twenty millions now in the world.

Memorandum, that if the people double in 360 years, that the preſent 320 millions, computed by ſome learned men, (from the meaſures of all the nations of the world, their degrees of being peopled, and good accounts of the people in ſeveral of them) to be now upon the face of the earth, will, within the next 2000 years, ſo increaſe, as to give one head for every two acres of land in the habitable part of the earth. And then, according to the prediction of the Scriptures, there muſt be wars and great ſlaughter, &c.

Wherefore, as an expedient againſt the abovementioned difference between 10 and 1200 years, we do for the preſent, and in this country admit of 360 years to be the time, wherein the people of England do double, according to the preſent laws and practice of marriages.

Now, if the city double its people in 40 years, and the preſent number be 670 thouſand, and if the whole territory be 7 millions 400 thouſand, and double in 360 years, as aforeſaid; then by the underwritten table it appears, that anno 1840, the people of the city will be 10718880, and thoſe of the whole country but 10917389, which is but inconſiderably more. Wherefore it is certain and ne-

* That the time of doubling is here and now 360 years.

ceſſary,

ceſſary, that the growth of the city muſt ſtop before the ſaid year 1840: and will be at its utmuſt height in the next preceding period, anno 1800, when the number of the city will be eight times its preſent number, viz. 5 millions 359 thouſand. And when (beſides the ſaid number) there will be 4 millions 466 thouſand to perform the tillage, paſturage, and other rural works neceſſary to be done without the ſaid city, as by the following table, viz.

	Annis.	Burials.	People in London.	People in England.
	1565	2568	77040	5526929.
As in the former table.	1605	5135		
	1642	11883		
	1682	22331	669930	7369230.
	1722	44662		
	1762	89324		
	1802	178648	5359440	9825650.
	1842	357296	10718880	10917389.

That London will be at its higheſt growth, and eight times as great as now, anno 1800.

Now when the people of London ſhall come to be ſo near the people of all England, then it follows, that the growth of London muſt ſtop before the ſaid year 1842, as aforeſaid, and muſt be at its greateſt height anno 1800, when it will be eight times more than now, with above four millions for the ſervice of the country and ports, as aforeſaid.

A digreſſion of the uſe of the vaſt difference between 10 *and* 1200 *years of doubling.*

Of the aforementioned vaſt difference between 10 years and 1200 years for doubling the people, we make this uſe, viz. to juſtify the Scriptures and all other good hiſtories concerning the number of the people in antient time. For ſuppoſing the eight perſons, who came out of the ark, increaſed by a progreſſive doubling in every ten years, might grow in the firſt hundred years after the flood from 8 to 8000, and that in 350 years after the flood (when abouts NOAH died) to one million, and by this time 1682, to 320 millions (which by rational conjecture, are thought to be now in the world) it will not be hard to compute, how in the intermediate years, the growth may be made, according to what is ſet down in the following table, wherein making the doubling to be ten years at firſt, and within 1200 years at laſt, we take a diſcretionary liberty, but juſtifiable by obſervations and the Scriptures for the reſt, which table we leave to be corrected by hiſtorians, who know the bigneſs of antient cities, armies, and colonies in the reſpective ages of the world; in the mean time affirming, that without ſuch difference in the meaſures and periods for doubling (the extreams whereof we have demonſtrated to be real and true) it is impoſſible to ſolve what is written in the holy Scriptures and other authentic books. For if we pitch upon any one number throughout for this purpoſe, 150 years is the fitteſt of all round numbers; according to which, there would have been but 512 ſouls in the whole world in MOSES's time (being 800 years after

after the flood) when 603 thouſand Iſraelites of above twenty years old (beſides thoſe of other ages, tribes, and nations) were found upon an exact ſurvey appointed by GOD. Whereas our table makes 12 millions. And there would have been but 8000 in DAVID's time, when were found 1100 thouſand of above twenty years old (beſides others, as aforeſaid) in Iſrael, upon the ſurvey inſtigated by ſatan, whereas our table makes 32 millions. And there would have been but a quarter of a million about the birth of CHRIST, or AUGUSTUS's time, when Rome and the Roman empire were ſo great, whereas our table makes 100 millions. Where note, that the Iſraelites in about 500 years, between their coming out of Egypt to DAVID's reign, increaſed from 603 thouſand to 1100 thouſand.

On the other hand, if we pitch upon a leſs number, as 100 years, the world would have been over-peopled 700 years ſince. Wherefore, no one number will ſolve the phænomena, and therefore we have ſuppoſed ſeveral in order to make the following table, which we again deſire hiſtorians to correct, according to what they find in antiquity concerning the number of the people in each age and country of the world.

We did (not long ſince) aſſiſt a worthy divine, writing againſt ſome ſceptics, who would have baffled our belief of the reſurrection, by ſaying, that the whole globe of the earth could not furniſh matter enough for all the bodies that muſt riſe at the laſt day, much leſs would the ſurface of the earth furniſh footing for ſo vaſt a number: whereas we did (by the method aforementioned) aſſert the number of men now living, and alſo of thoſe that had died ſince the beginning of the world, and did withal ſhew, that half the iſland of Ireland would afford them all, not only footing to ſtand upon, but graves to lie down in, for that whole number; and that two mountains in that country were as weighty as all the bodies, that had ever been from the beginning of the world to the year 1680, when this diſpute happened. For which purpoſe, I have digreſſed from my intended purpoſe, to inſert this matter, intending to proſecute this hint further, upon ſome more proper occaſion.

A table

A table ſhewing how the people might have doubled in the ſeveral ages of the world.

	Anno after the flood.		
Periods of doubling	1	8	perſons.
	10	16	
	20	32	
	30	64	
	40	128	
In 10 years	50	256	
	60	512	
	70	1024	
	80	2048	
	90	4096	
	100	8000	and more
	120 years after		
In 20 years	the flood.	16	thouſand.
	140	32	
	170	64	
30			
	200	128	
40	240	256	
50	290	512	
60	350	1	million and more.
70	420	2	millions.
100	520	4	millions.
190	710	8	millions.
290	1000	16	In MOSES's time.
400	1400	32	About DAVID's time.
550	1950	64	
750	2700	128	About the birth of CHRIST.
1000	3700	256	
In 300 to 1200	4000	320	

It is here to be noted, that in this table we have aſſigned a different number of years for the time of doubling the people in the ſeveral ages of the world, and might have done the ſame for the ſeveral countries of the world; and therefore the ſaid ſeveral periods aſſigned to the whole world in the lump may well enough conſiſt with the 360 years eſpecially aſſigned to England, between this day, and the Norman conqueſt; and the ſaid 360 years may well enough ſerve for a ſuppoſition between

tween this time, and that of the world's being fully peopled; nor do we lay any ſtreſs upon one or the other in this diſquiſition concerning the growth of the city of London.

We have ſpoken of the growth of London, with the meaſures and periods thereof: we come next to the cauſes and conſequences of the ſame.

The cauſes of its growth from 1642 to 1682, may be ſaid to have been as followeth, viz. from 1642 to 1650, that men came out of the country to London, to ſhelter themſelves from the outrages of the civil wars, during that time: from 1650 to 1660, the royal party came to London, for their more private and inexpenſive living: from 1660 to 1670, the King's friends and party came to receive his favours after his happy reſtoration: from 1670 to 1680, the frequency of plots and parliaments might bring extraordinary numbers to the city. But what reaſons to aſſign for the like increaſe from 1604 to 1642, I know not, unleſs I ſhould pick out ſome remarkable accident happening in each part of the ſaid period, and make that to be the cauſe of this increaſe (as vulgar people make the cauſe of every man's ſickneſs, to be what he did laſt eat): wherefore, rather than ſo to ſay *quidlibet de quolibet*, I had rather quit even what I have above ſaid to be the cauſe of London's increaſe from 1642 to 1682, and put the whole upon ſome natural and ſpontaneous benefits and advantages, that men find by living in great more than in ſmall ſocieties; and ſhall therefore ſeek for the antecedent cauſes of this growth in the conſequences of the like, conſidered in greater characters and proportions.

Now, whereas in arithmetic, out of two falſe poſitions, the truth is extracted, ſo I hope out of two extravagant contrary ſuppoſitions, to draw forth ſome ſolid and conſiſtent concluſion, viz.

The firſt of the ſaid two ſuppoſitions is, that the city of London is ſeven times bigger than now, and that the inhabitants of it are four millions 690 thouſand people, and that in all the other cities, ports, towns, and villages, there are but two millions 710 thouſand more.

The other ſuppoſition is, that the city of London is but a ſeventh part of its preſent bigneſs, and that the inhabitants of it are but 96 thouſand, and that the reſt of the inhabitants (being 7 millions 304 thouſand) do cohabit thus, 104 thouſand of them in ſmall cities and towns, and that the reſt, being ſeven millions 200 thouſand, do inhabit in houſes not contiguous to one another, viz. in 1200 thouſand houſes, having about 24 acres of ground belonging to each of them, accounting about 28 millions of acres to be in the whole territory of England, Wales, and the adjacent iſlands; which any man that pleaſes may examine upon a good map.

Now, the queſtion is, in which of theſe two imaginary ſtates would be the moſt convenient, commodious and comfortable livings?

But this general queſtion divides itſelf into the ſeveral queſtions, relating to the following particulars, viz.

1. For the defence of the kingdom againſt foreign powers.
2. For preventing the inteſtine commotions of parties and factions.
3. For peace and uniformity in religion.
4. For the adminiſtration of juſtice.
5. For the proportionably taxing of the people, and eaſy levying the ſame.

6. For

6. For gain by foreign commerce.
7. For huſbandry, manufacture, and for arts of delight and ornament.
8. For leſſening the fatigue of carriages and travelling.
9. For preventing beggars and thieves.
10. For the advancement and propagation of uſeful learning.
11. For increaſing the people by generation.
12. For preventing the miſchiefs of plagues and contagions. And withal, which of the ſaid two ſtates is moſt practicable and natural; for in theſe, and the like particulars, do lie the teſts and touch-ſtones of all propoſals, that can be made for the public good.

Firſt, as to practicable, we ſay, that although our ſaid extravagant propoſals are both in nature poſſible, yet it is not obvious to every man to conceive, how London, now ſeven times bigger than in the beginning of Queen ELIZABETH's reign, ſhould be ſeven times bigger than now it is, and 49 times bigger than anno 1560. To which I ſay, 1. That the preſent city of London ſtands upon leſs than 1500 acres of ground: wherefore a city ſeven times as large may ſtand upon 10500 acres, which is about equivalent to a circle of four miles and a half in diameter, and leſs than 15 miles in circumference. 2. That a circle of ground of 35 miles ſemidiameter will bear corn, garden-ſtuff, fruits, hay, and timber for the four millions 690 thouſand inhabitants of the ſaid city and circle, ſo as nothing of that kind need be brought from above 35 miles diſtance from the ſaid city; for the number of acres within the ſaid circle, reckoning one acre ſufficient to furniſh bread and drink-corn for every head, and two acres will furniſh hay for every neceſſary horſe; and that the trees, which may grow in the hedge-rows of the fields within the ſaid circle, may furniſh timber for 600 thouſand houſes. 3. That all live cattle and great animals can bring themſelves to the ſaid city; and that fiſh can be brought from the Land's-end and Berwick as eaſily as now. 4. Of coals there is no doubt: and for water, 20 s. per family (or 600 thouſand pounds per annum in the whole) will ſerve this city, eſpecially with the help of the New River. But if by practicable be underſtood, that the preſent ſtate may be ſuddenly changed into either of the two abovementioned propoſals, I think it is not practicable. Wherefore the true queſtion is, unto or towards which of the ſaid two extravagant ſtates it is beſt to bend the preſent ſtate by degrees, whether it be beſt to leſſen or enlage the preſent city? in order whereunto, we enquire (as to the firſt queſtion) which ſtate is moſt defenſible againſt foreign powers, ſaying, that if the abovementioned houſing, and a border of ground, of three quarters of a mile broad, were encompaſſed with a wall and ditch of 20 miles about (as ſtrong as any in Europe, which would coſt but a million, or about a penny in the ſhilling of the houſe-rent for one year) what foreign prince could bring an army from beyond ſeas, able to beat, 1. our ſea-forces, and next with horſe harraſs'd at ſea, to reſiſt all the freſh horſe, that England could make, and then conquer above a million of men, well united, diſciplined, and guarded within ſuch a wall, diſtant every where three quarters of a mile from the houſing, to elude the granadoes and great ſhot of the enemy? 2. As to inteſtine parties and factions, I ſuppoſe that 4 millions 690 thouſand people united within this great city could eaſily govern half the ſaid number ſcattered without it; and that a few men in arms within the ſaid city, and wall, could alſo eaſily govern the

reſt unarmed, or armed in ſuch manner as the ſovereign ſhall think fit. 3. As to uniformity in religion, I conceive, that if St. Martin's pariſh may (as it doth) conſiſt of about 40 thouſand ſouls, that this great city alſo may as well be made but as one pariſh, with ſeven times 130 chapels, in which might not only be an uniformity of common prayer, but in preaching alſo; for that a thouſand copies of one judiciouſly and authentically compoſed ſermon might be every week read in each of the ſaid chapels without any ſubſequent repetition of the ſame, as in the caſe of homilies. Whereas in England (wherein are near ten thouſand pariſhes, in each of which upon Sundays, holidays, and other extraordinary occaſions, there ſhould be about 100 ſermons per annum, making about a million of ſermons per annum in the whole) it were a miracle, if a million of ſermons compoſed by ſo many men, and of ſo many minds and methods, ſhould produce uniformity upon the diſcompoſed underſtandings of about eight millions of hearers.

4. As to the adminiſtration of juſtice; if in this great city ſhall dwell the owners of all the lands, and other valuable things in England; if within it ſhall be all the traders, and all the courts, offices, records, juries, and witneſſes; then it follows, that juſtice may be made with ſpeed and eaſe.

5. As to the equality and eaſy levying of taxes, it is too certain, that London hath at ſome times paid near half the exciſe of England; and that the people pay thrice as much for the hearths in London as thoſe in the country, in proportion to the people of each; and that the charges of collecting theſe duties have been about a ſixth part of the duty itſelf. Now, in this great city, the exciſe alone, according to the preſent laws, would not only be double to the whole kingdom, but alſo more equal. And the duty of hearths of the ſaid city would exceed the preſent proceed of the whole kingdom. And as for the cuſtoms, we mention them not at preſent.

6. Whether more would be gained by foreign commerce.

The gain, which England makes by lead, coals, thef reight of ſhipping, &c. may be the ſame, for ought I ſee, in both caſes. But the gain, which is made by manufactures, will be greater, as the manufacture itſelf is greater and better. For in ſo vaſt a city manufactures will beget one another, and each manufacture will be divided into as many parts as poſſible, whereby the work of each artiſan will be ſimple and eaſy; as for example. In the making of a watch, if one man ſhall make the wheels, another the ſpring, another ſhall engrave the dial-plate, and another ſhall make the caſes; then the watch will be better and cheaper, than if the whole work be put upon any one man. And we alſo ſee, that in towns, and in the ſtreets of a great town, where all the inhabitants are almoſt of one trade, the commodity peculiar to thoſe places is made better and cheaper than elſewhere. Moreover, when all ſorts of manufactures are made in one place, there every ſhip, that goeth forth, can ſuddenly have its loading of ſo many ſeveral particulars and ſpecies, as the port whereunto ſhe is bound can take off. Again, when the ſeveral manufactures are made in one place, and ſhipped off in another, the carriage, poſtage, and travelling charges will inhance the price of ſuch manufactures, and leſſen the gain upon foreign commerce. And laſtly, when the imported goods are ſpent in the port itſelf, where they are landed, the carriage of the ſame into other places will create no ſur-charge upon ſuch commodity; all which particulars tend to the greater gain by foreign commerce.

7. As

7. As for arts of delight and ornament,

They are beſt promoted by the greateſt number of emulators. And it is more likely, that one ingenious curious man may rather be found out amongſt four millions than 400 perſons. But as for huſbandry, viz. tillage and paſturage, I ſee no reaſon, but the ſecond ſtate (when each family is charged with the culture of about 24 acres) will beſt promote the ſame.

8. As for leſſening the fatigue of carriage and travelling,

The thing ſpeaks itſelf; for if all the men of buſineſs and all artiſans do live within five miles of each other; and if thoſe, who live without the great city, do ſpend only ſuch commodities, as grow where they live, then the charge of carriage and travelling could be little.

9. As to the preventing of beggars and thieves,

I do not find how the differences of the ſaid two ſtates ſhould make much difference in this particular; for impotents (which are but one in about 600) ought to be maintained by the reſt. 2. Thoſe, who are unable to work through the evil education of their parents, ought (for ought I know) to be maintained by their neareſt kindred, as a juſt puniſhment upon them. 3. And thoſe, who cannot find work (though able and willing to perform it) by reaſon of the unequal application of hands to lands, ought to be provided for by the magiſtrate and landlord till that can be done; for there need be no beggars in countries, where there are many acres of unimproved improvable land to every head, as there are in England. As for thieves, they are, for the moſt part, begotten from the ſame cauſe; for it is againſt nature, that any man ſhould venture his life, limb, or liberty, for a wretched livelihood, whereas moderate labour will produce a better. But of this ſee Sir THOMAS MORE, in the firſt part of his Utopia.

10. As to the propagation and improvement of uſeful learning,

The ſame may be ſaid concerning it as was above ſaid concerning manufactures, and the arts of delight and ornaments; for in the great vaſt city, there can be no ſo odd a conceit or deſign, whereunto ſome aſſiſtance may not be found, which in the thin, ſcattered way of habitation may not be.

11. As for the increaſe of people by generation,

I ſee no great difference from either of the two ſtates, for the ſame may be hindered or promoted in either, from the ſame cauſes.

12. As to the plague,

It is to be remembered, that one time with another, a plague happeneth in London once in 20 years, or thereabouts; for in the laſt hundred years, between the years 1582 and 1682, there have been five great plagues, viz. anno 1592, 1603, 1625, 1636, and 1665. And it is alſo to be remembered, that the plagues of London do commonly kill one fifth part of the inhabitants. Now, if the whole people of England do double but in 360 years, then the annual increaſe of the ſame is but 20000, and in 20 years 400000. But if in the city of London there ſhould be two millions of people, (as there will be about 60 years hence) then the plague (killing one fifth of them, namely, 4000000, once in 20 years) will deſtroy as many in one year, as the whole nation can re-furniſh in 20: and conſequently the people of the nation ſhall never increaſe. But if the people of London ſhall be above four millions (as in the firſt of our two extravagant ſuppoſitions is premiſed)

then the people of the whole nation ſhall leſſen above 20000 per annum. So as if people be worth 70 l. per head (as hath elſewhere been ſhewn) then the ſaid greatneſs of the city will be a damage to itſelf and the whole nation of 14 hundred thouſand pounds per annum, and ſo *pro rata*, for a greater or a leſſer number. Wherefore to determine, which of the two ſtates is beſt, that is to ſay, towards which of the ſaid two ſtates authority ſhould bend the preſent ſtate; a juſt balance ought to be made between the diſadvantages from the plague with the advantages accruing from the other particulars abovementioned; unto which balance a more exact account of the people and a better rule for the meaſure of its growth is neceſſary, than what we have here given, or are yet able to lay down.

POSTSCRIPT.

IT was not very pertinent to a diſcourſe concerning the growth of the city of London, to thruſt in conſiderations of the time, when the whole world will be fully peopled; and how to juſtify the Scriptures concerning the number of people mentioned in them; and concerning the number of the quick and the dead, that may riſe at the laſt day, &c. Nevertheleſs, ſince ſome friends liking the ſaid digreſſions and impertinencies (perhaps as ſauce to a dry diſcourſe) have deſired, that the ſame might be explained and made out, I therefore ſay as followeth:

1. If the number of acres in the habitable part of the earth be under 50 thouſand millions; if twenty thouſand millions of people are more than the ſaid number of acres will feed; (few or no countries being ſo fully peopled;) and for that in ſix doublings (which will be in 2000 years) the preſent 320 millions will exceed the ſaid 20 thouſand millions.

2. That the number of all thoſe, who have died ſince the flood, is the ſum of all the products made by multiplying the number of the doubling periods mentioned in the firſt column of the laſt table, by the number of people reſpectively affixed to them, in the third column of the ſame table; the ſaid ſum being divided by 40 (one dying out of 40 per annum, out of the whole maſs of mankind) which quotient is 12570 millions; whereunto may be added, for thoſe that died before the flood, enough to make the laſt mentioned number 20 thouſand millions, as the full number of all that died, from the beginning of the world, to the year 1682; unto which, if 320 millions, the number of thoſe who are now alive, be added, the total of the quick and the dead will amount but unto one fifth part of the graves, which the ſurface of Ireland will afford, without ever putting two bodies into any one grave; for there be in Ireland 28 thouſand ſquare Engliſh miles, each whereof will afford about 4 millions of graves, and conſequently above 114 thouſand millions of graves, viz. about 5 times the number of the quick and the dead, which ſhould ariſe at the laſt day, in caſe the ſame had been in the year 1682.

3. Now, if there may be place for five times as many graves in Ireland, as are ſufficient for all that ever died; and if the earth of one grave weigh five times as much as the body interred therein, then a turf, leſs than a foot thick, pared off from a fifth part of the ſurface of Ireland, will be equivalent in bulk and weight to all the bodies that ever were buried; and may ſerve as well for that purpoſe, as the two mountains aforementioned in the body of this diſcourſe. From all which it is plain, how madly they were miſtaken, who did ſo petulantly vilify what the holy Scriptures have delivered.

OBSERA-

OBSERVATIONS

ON THE

PAST GROWTH and PRESENT STATE

OF THE

CITY of LONDON.

To which are annexed,

A complete table of the chriſtnings and burials within this city from 1601 to 1750, both years incluſive; together with a table of the numbers, which have annually died of each diſeaſe from 1675 to the preſent time; and alſo a further table repreſenting the reſpective numbers, which have annually died of each age from 1728 to this year; from which is particularly attempted to be ſhewn the increaſing deſtruction of infants and adults in this city; and conſequent thereto, the exceſſive drain, which it continually makes upon all the provinces of this kingdom for recruits. To which are added ſome propoſals for a better regulation of the police of this metropolis

By CORBYN MORRIS, Eſq;

——Pudet hæc opprobria nobis
Et dici potuiſſe, & non potuiſſe refelli.

Firſt printed at LONDON in 1751; and reprinted in 1758, with a continuation of the tables to the end of the year 1757.

Table I.

AN

ACCOUNT

OF THE

Chriſtnings and burials, and of the ſeveral proportions they have ſucceſſively held to each other, and alſo of the numbers, which died of the plague, during every year, from 1601 to 1750, both years incluſive

Years	Chriſtned males	Chriſtned females	Buried males	Buried females	Died of the plague	Burials not of the plague	Chriſt-nings	Totals of burials not of the plague	Totals of chriſt-nings	Medium of burials not of the plague	Medium of chriſt-nings	Proportion of burials to chriſtnings
1601	not	not	not	not	c	near 6000	near 6000					
1602	regiſtered	regiſtered	regiſtered	regiſtered	o	near 6000	near 6000					
1603					36269	5773	4789					
1604					896	4323	5458					
1605					444	5943	6504					
1606					2124	5796	6614					
1607					2352	5670	6582					
1608					2262	6758	6845					
1609					4240	7545	6338					
1610					1803	7486	6785					
					50390	61299	61965	61299	61965	6130	6196	1000 to 1010
1611					627	6716	7014					
1612					64	7778	6986					
1613					16	7503	6845					
1614					22	7307	7208					
1615					37	7850	7682					
1616					9	8263	7985					
1617					6	8280	7747					
1618					18	9596	7735					
1619					9	7999	8127					
1620					21	9691	7845					
					51219	80843	75175	80843	75175	8084	7517	1000 to 929
1621					11	8112	8039					
1622					16	9420	7894					
1623					17	11095	7945					
1624					11	12199	8299					
1625					35417	18848	6983					
1626					134	7400	6711					
1627					4	7713	8438					
1628					3	7740	8564					
1629					0	8771	9901					
1630					1317	9228	9315					
					88149	100526	82049	100526	82149	10052	8205	1000 to 816
								242668	219189			

Table I. continued.

Year	Christned males	Christned females	Buried males	Buried females	Died of the plague	Burials not of the plague	Christnings	Totals of burials not of the plague	Totals of christnings	Medium of burials not of the plague	Medum of christnings	Proportion of burials to christnings
			Brought	over - -	88149			242668	219189			
1631					274	8288	8524					
1632					8	9527	9584					
1633					c	8392	9997					
1634					1	10899	9855					
1635					c	10631	10034					
1636					10400	12959	9522					
1637					3083	8881	9160					
1638					363	1326	10311					
1639					314	9548	10150					
1640					145	11321	10850					
					104041	103527	97987	103527	97987	10353	9799	1000 to 948
1641					1375	11767	10670					
1642					1274	11999	10370					
1643					996	12216	9410					
1644					1492	9441	8104					
1645					1871	9608	7966					
1646					2365	10415	7163					
1647					3597	10462	7332					
1648					611	9283	6544					
1649					67	10499	5825					
1650					15	8749	5612					
					117704	104439	78996	104439	78996	10444	7899	1000 to 755
1651					23	10444	6071					
1652					16	12588	6128					
1653					6	10081	6155					
1654					16	13231	6620					
1655					9	11368	7004					
1656					6	13915	7050					
1657					4	12430	6685					
1658					14	14979	6170					
1559					36	14720	5690					
1660					14	15104	6971					
					117848	128860	64544	128860	64544	12886	6454	1000 to 500
1661					20	19791	8855					
1662					12	16542	10019					
1663					9	15347	10292					
1664	6041	5681	9369	8928	6	18291	11722					
1665	5114	4853	48569	48737	68596	28700	9967					
1666	4658	4319	6487	6251	1998	10740	8997					
1667	5616	5322	8223	7616	35	15807	10938					
1668	6078	5560	9111	8167	14	17264	11633					
1669	6500	5829	10206	9226	3	19429	12335					
1670	6278	5719	10614	9584	0	20198	11997					
	40306	37283	102579	98512	188541	182109	106755	182109	106755	18211	10675	1000 to 586
								161603	567471			

Table I. continued.

Years	Chriſtned males	Chriſtned females	Buried males	Buried females	Died of the plague	Burials not of the plague	Chriſtnings	Tota's of burials not of the plague	Totals of chriſtnings	Medium of burials not of the plague	Medium of chriſtnings	Proportion of burial to chriſtnings
			Brought	over -	188541	- - -	- - -	761603	561471	- - -	- - -	1000 to 589
1671	644[illegible]	6061	8475	7254	5	15724	12510					
1672	6443	6120	9560	8670	5	18[illegible]	12363					
1673	6073	5822	9302	8202	5	17499	11895					
1674	6113	5738	11005	10196	3	21198	11851					
1675	6058	5717	8934	831[illegible]	1	17243	11775					
1676	6552	5847	9734	899[illegible]	2	1873	12399					
1677	6423	6203	9836	9231	2	19065	12626					
1678	6368	6033	10681	9997	5	20673	12601					
1679	6147	6041	11154	10576	2	21728	12288					
1680	6[illegible]48	6199	11039	10014	0	210[illegible]3	12747					
	63474	59781	99720	91448	188571	191138	123255	191138	123255	19114	12325	1000 to 644
1681	6822	6533	12386	11585		23971	13355					
1682	6909	6744	10617	10074		20691	12653					
1683	7577	7158	10702	988[illegible]		20587	14735					
1684	7575	7127	11919	1128[illegible]		23202	14702					
1685	7484	7246	11891	11331		23212	14730					
1686	7575	7119	11828	10781		22609	14694					
1687	7737	7214	11174	10286		21460	14951					
1688	7487	7101	11763	11158		22921	14588					
1689	7604	7167	12374	11128		23502	14771					
1690	7909	7302	11144	10317		21461	15211					
	74679	70711	115798	107828		223626	144390	223626	144390	21363	14439	1000 to 645
1691	7662	7392	11491	11200		22691	15054					
1692	7602	7316	10651	10223		20874	14918					
1693	7676	7483	10655	10304		20959	151[illegible]9					
1694	698[illegible]	6647	12107	11993		24100	13632					
1695	7163	6713	9639	9408		19037	13876					
1696	7632	7229	9712	8916		18638	14861					
1697	8062	7767	10819	10151		20970	1[illegible]829					
1698	8426	7626	10925	9258		20183	16052					
1699	7911	7452	11020	9775		20795	15363					
1700	7578	7061	9653	9790		19443	14639					
	76697	72686	106672	101028		207700	149383	207700	149383	20770	14938	1000 to 719
1701	8102	7514	10270	10201		20471	15616					
1702	8031	7656	9781	9700		19481	15687					
1703	7765	7683	10354	10366		20720	15448					
1704	8153	7742	11401	11283		22684	15895					
1705	8366	7779	11011	11086		22097	16145					
	40417	38374	52817	52636		105453	78791	105453	78791	21091	15758	1000 to 747
1706	7952	7417	9988	9859		19847	15369					
1707	8379	7687	10785	10815		21600	16065					
1708	8239	7623	10604	10687		21291	15861					
1709	7840	7380	10907	10893		21800	15220					
1710	7640	7288	11972	12648		24620	14928					
	40050	37395	54256	54902		109158	77445	109158	77445	21832	15489	1000 to 709
								1[illegible]98678	1134735			

Table I. continued.

Years	Chriſtned males	Chriſtned females	Buried males	Buried females	Died of the plague	Burials not of the plague	Chriſtnings	Totals of burials not of the plague	Totals of chriſtnings	Medium of burials not of the plague	Medium of chriſtnings	Proportion of burials to chriſtnings
			Brought	over -	188571	- - -	- - -	1598678	1134735	- - -	- - -	1000 to 709
1711	7482	7224	9841	9992		19833	14706					
1712	8029	7631	10376	10812		21198	15660					
1713	8262	7665	10412	10645		21057	15927					
1714	8950	8545	13139	13430		26569	17495					
1715	8788	8446	11083	11149		22232	17234					
	41511	39521	54851	56038		110889	81022	110889	81022	22178	16204	1000 to 731
1716	9076	8345	12356	12080		24436	17421					
1717	9630	8845	11934	11512		23446	18475					
1718	9444	8863	13339	13184		26523	18307					
1719	9516	8897	14157	14190		28347	18413					
1720	8877	8602	12713	12741		25454	17479					
	46543	43552	64499	63707		128206	90095	128206	90095	25641	18019	1000 to 706
1721	9430	8940	13146	12996		26142	18370					
1722	9325	9014	12956	12794		25750	18339					
1723	9811	9392	14738	14459		29197	19203					
1724	9902	9468	13252	12700		25952	19370					
1725	9661	9198	12847	12676		25523	18859					
	48129	46012	66939	65625		132564	94141	132564	94141	26513	18828	1000 to 710
1726	9605	9203	15030	14617		29647	18808					
1727	9241	9011	14104	14314		28418	18252					
1728	8497	8155	13538	14272		27810	16652					
1729	8736	8324	14898	14824		29722	17060					
1730	8606	8512	13306	13455		26761	17218					
	44685	43205	70876	71482		142358	87890	142358	87890	28472	17578	1000 to 618
1731	9177	8653	12608	12654		25262	17830					
1732	9144	8644	11655	11703		23358	17788					
1733	8811	8654	14372	14861		29233	17465					
1734	8956	8675	13016	13046		26062	17630					
1735	8658	8215	11699	11839		23538	16873					
	44745	42841	63350	64103		127453	87586	127453	87586	25491	17517	1000 to 688
1736	8471	8020	13695	13886		27581	16491					
1737	8482	8278	13690	14133		27823	16760					
1738	8212	7848	12750	13075		25825	16060					
1739	8228	7953	12416	13016		25432	16181					
1740	7833	7398	14985	15826		30811	15231					
	41226	39497	67536	69936		137472	80723	137472	80723	27494	16145	1000 to 587
					188571			2377620	1656192			

Concluſion of table I.

Years	Chriſtned males	Chriſtned females	Buried males	Buried females	Died of the plague	Burials not of the plague	Chriſtnings	Totals of burials not of the plague	Totals of chriſtnings	Medium of burials not of the plague	Medium of chriſtnings	Proportion of burials to chriſtnings
			Brought over -		188571	- - -	- - -	2377620	1656192	- - -	- - -	1000 to 587
1741	7667	7290	15465	16704		32169	14957					
1742	7048	6703	13565	13918		27483	13751					
1743	7726	7324	12181	13019		25200	15050					
1744	7321	6940	10146	10460		20606	14261					
1745	7278	6800	10468	10828		21296	14078					
	37040	35057	61825	64929		126754	72097	126754	72097	25351	14419	1000 to 568
1746	7573	7004	13771	14386		28157	14577					
1747	7737	7205	12417	13077		25494	14942					
1748	7223	6930	11814	12055		23869	14153					
1749	7288	6972	12663	12855		25516	14260					
1750	7394	7154	11742	11985		23727	14548					
	37215	35265	62407	64358		126763	72480	126763	72480	25353	14496	1000 to 571
1751	7524	7167	10339	10689		21028	14691					
1752	7868	7440	10306	10179		20485	15308					
1753	7860	7584	9490	9786		19276	15444					
1754	7754	7193	11164	11532		22696	14947					
1755	7773	7436	10779	11138		21917	15209					
	38779	36820	52078	53324	188571	105402	75599	105402	75599	21080	15119	1000 to 719
1756	7591	7248	10284	10588		20872	14839					
1757	7195	6858	10821	10492		21313	14053					

Table II.

AN

ACCOUNT

OF THE

Chriſtnings, and burials, and of the reſpective ages of the perſons buried, within the city and ſuburbs of London, from 1728 to 1757, both years incluſive.

Years	Total number of burials	Whereof have died of the following ages.													Total number of chriſtnings
		Under 2 years of age	Between two and five	Five and ten	Ten and twenty	Twenty and thirty	Thirty and forty	Forty and fifty	Fifty and ſixty	Sixty and ſeventy	Seventy and eighty	Eighty and ninety	Ninety and a hundred	A hundred and upwards	
1728	27815	9851	2407	1038	950	2254	2490	2624	2123	1863	1290	785	135	5	16652
1729	29729	10735	2516	1056	999	2371	2784	2698	2338	1938	1375	769	143	7	17060
1730	26761	10368	2448	1092	901	2048	2471	2373	1713	1577	1001	622	138	9	17118
Totals	84305	30954	7371	3186	2850	6673	7745	7695	6174	5378	3666	2176	416	21	50830
Medium	28101	10318	2457	1062	950	2224	2581	2565	2058	1792	1222	725	138	7	16943
Proportions	1000	367	87	38	33	79	92	91	73	63	43	25	5	7 / 2811	603
1731	25262	9907	2096	932	806	1916	2351	2261	1839	1500	913	628	108	5	17830
1732	23358	9502	1517	716	611	1627	2175	2121	1741	1581	974	660	121	12	17788
1733	29233	11738	2409	957	754	1857	2564	2685	2195	1871	1188	804	198	2	17465
1734	26062	10752	2830	1228	829	1718	2212	2154	1668	1324	793	484	66	4	17630
1735	23538	9072	1963	755	691	1605	2158	2138	1684	1339	872	565	84	12	16873
Totals	127453	51571	10815	4588	3691	8723	11460	11359	9128	7615	4740	3141	577	45	87580
Medium	25490	10314	2163	917	738	1744	2292	2271	1825	1523	948	628	115	9	17517
Proportions	1000	404	85	36	29	68	89	89	71	59	37	24	4	0 / 25490	666
1736	27581	10580	2706	993	816	2139	2445	2357	2121	1666	1114	557	83	4	16491
1737	27823	10054	2613	8008	885	2241	2652	2578	2270	1650	1164	576	127	5	16760
1738	25825	9600	2366	784	783	2072	2439	2363	2106	1551	1121	529	101	10	16060
1739	25432	9587	2302	844	875	1866	2218	2378	2039	1421	1166	547	76	13	16181
1740	30811	10765	2862	1235	947	2205	2783	2861	2585	1977	1716	758	100	12	15231
Totals	137472	50686	12849	4864	4306	10523	12537	12542	11121	8265	6281	2967	487	44	80723
Medium	27494	10137	2569	972	861	2104	2507	2508	2224	1653	1256	593	97	8	16144
Proportions	1000	368	93	35	31	76	81	81	81	60	45	21	3	8 / 27494	587

Concluſion of table II.

Years	Total number of burials	Whereof have died of the following ages.													Total number of chriſtnings
		Under 2 years of age	Between two and five	Five and ten	Ten and twenty	Twenty and thirty	Thirty and forty	Forty and fifty	Fifty and ſixty	Sixty and ſeventy	Seventy and eighty	Eighty and ninety	Ninety and a hundred	A hundred and upwards	
1741	32169	10456	2368	1072	1048	2816	3476	3731	2851	1933	1540	734	130	14	14957
1742	27483	9030	2642	1035	893	2203	2813	2959	2333	1634	1250	582	100	9	13751
1743	25200	8621	1955	947	813	1935	2342	2611	2004	1729	1507	629	93	14	15050
1744	20606	7394	1657	679	663	1744	2019	2123	1637	1307	920	387	73	3	14261
1745	21296	7689	1631	672	626	1695	1940	2332	1741	1382	1064	437	77	10	14078
Totals	126754	43190	10253	4405	4043	10393	12590	13756	10566	7985	6281	2769	473	50	72097
Medium	25350	8638	2050	881	808	2078	2518	2751	2113	1597	1256	553	94	10	14419
Proportions	1000	338	81	34	31	82	99	108	83	63	45	21	3	10/25350	568
1746	28157	9503	2611	1089	895	2356	2728	2876	2243	1699	1444	625	78	10	14577
1747	25494	8741	2085	905	790	2190	2649	2717	2079	1544	1199	520	68	7	14942
1748	23809	7637	1798	760	661	2142	2491	2700	2160	1704	1187	558	65	5	14153
1749	25516	8504	2028	794	719	2291	2753	2855	2113	1691	1155	533	68	12	14260
1750	23727	8024	1533	709	746	2031	2542	2708	2107	1728	1038	475	80	6	14548
Totals	126763	42409	10055	4257	3811	11010	13163	13856	10702	8366	6023	2711	360	40	72480
Medium	25352	8481	2011	851	762	2202	2632	2771	2140	1673	1204	542	72	8	14496
Proportions	1000	334	79	33	30	86	103	109	84	66	47	21	3	8/25352	571
1751	21028	7483	1485	575	588	1694	2207	2234	1815	490	925	461	58	13	14691
1752	20485	8239	2225	814	660	1561	1823	1633	1348	979	738	316	37	7	15308
1753	19276	7892	1403	418	478	1338	1861	1775	1568	186	864	435	54	4	15444
1754	22696	8115	1904	640	628	1685	2141	2179	1944	1642	1143	586	85	4	14947
1755	21917	7803	2001	612	577	1651	2087	2234	1918	1433	1018	504	77	2	15209
Totals	105402	39532	9018	3059	2931	7934	10119	10055	8593	6830	4688	2302	311	30	75599
Medium	21080	7906	1804	612	586	1587	2024	2011	1719	1366	937	460	62	6	15119
Proportions	1000	375	86	29	28	75	96	95	81½	65	44½	22	3	6/21080	717
1756	20871	7466	1973	605	572	1523	1982	2069	1788	1412	976	451	55		14839
1757	21313	7095	2411	948	687	1695	1906	190	1710	1418	1024	431	74	8	14053

OBSERVA-

	1698	1699	1700	1701	1702	1703	1704	1705	1706	
Abortive, &c.	Numbers dying of each diſeaſe not regiſtered.	Numbers dying of each diſeaſe not regiſtered.	Numbers dying of each diſeaſe not regiſtered.	701	66c	630	689	634	612	
Aged				1456	1455	1563	1799	1746	1563	
Ague				6	3	7	6	3	2	
Apoplexy, &c.				167	136	159	147	157	155	
Aſthma, &c.				285	251	313	306	377	273	
Chincough, &c.				47	75	56	43	48	23	
Childbed, &c.				225	222	217	266	288	238	
Cholic, &c.				1306	1333	1113	1303	1181	1089	
Conſumption, &c.				2768	2792	2937	3101	2864	2809	
Convulſions				5532	5639	5493	5987	6248	5961	
Dropſy, &c.				1196	1134	1275	1338	112c	997	
King's-evil, &c.				265	286	333	317	286	280	
French-pox				57	56	63	52	2c	47	
Fevers, &c.				2960	2746	3247	3318	3355	2725	
Gout, &c.				28	35	52	65	53	48	
Gravel, &c.				49	41	52	55	63	54	
Head-moldſhot, &c.				501	488	433	486	323	237	
Lethargy, &c.				70	84	86	112	75	82	
Meaſles, &c.				4	27	51	12	319	361	
Pluriſy, &c.				37	16	23	40	51	27	
Small-pox, &c.				1172	370	983	1576	1148	784	
Teeth				1261	1304	1305	1332	1384	1185	
Thruſh, &c.				41	56	55	54	88	46	
Caſualties				337	272	274	278	257	249	
Total of burials	20183	20795	19443	20471	19481	20720	22684	22097	19847	

An account of the total number of burials, and of the numbe during every year, from

	1675	1676	1677	1678	1679	168c	16
Abortive, chriſoms, infant and ſtillborn	1112	1097	1053	1011	943	824	9
Aged	1014	1007	994	1021	1141	1081	13
Ague, N. B. Joined in the bills for ſome years with fevers							
Apoplexy, palſy, cramp, and ſuddenly	102	58	92	107	129	118	1
Aſthma and phthiſic, N. B. Joined in the bills for ſome years with conſumptions							
Chincough, cough, hooping-cough, and worms	57	45	59	49	49	4c	
Child-bed and miſcarriages	284	258	236	272	300	302	3
Cholic, gripes, twiſting of the guts, flux, vomiting, looſeneſs, bloody-flux, and bleeding	2335	3559	2925	3407	3219	3488	30
Conſumption, jaundice, diabetes, and falling-ſickneſs	3221	3312	3355	3512	3744	3494	38
Convulſions	1961	2363	2357	2525	2837	3055	32
Dropſy, tympany, ſtoppage in the ſtomach, riſing of the lights and ſwelling	1135	1207	1321	1274	1295	1178	14
King's-evil, itch, leproſy, ſcurvy, St. Anthony's fire, ſcald-head, impoſthumes, ſores, and ulcers, cancer, canker, and fiſtula	321	312	365	338	450	405	4
French-pox	75	97	10c	101	104	114	
Fevers, calentures, inflammations, ſore-throat, raſh and ſurfeits	2438	2447	2004	2665	3247	3735	36
Gout, rheumatiſm, and ſciatica	15	15	16	14	24	24	
Gravel, ſtone, and ſtrangury	65	77	73	72	73	62	
Head-moldſhot, horſeſhoe-head, watry-head, rickets, livergrown, burſten, and ruptures	560	514	53c	528	456	387	4
Lethargy, choaked with fat, grief, lunatic, vapours, megrim, and ſpleen, head-ach, blaſted, planet-ſtruck, bedriden, gangreen and mortification	108	134	78	138	90	59	
Meaſles, chicken-pox, N. B. Joined in the bills for ſome years with ſmall-pox	6	83	87	93	117	49	1
Pluriſy	30	26	24	15	16	16	
Small-pox, purples, and ſpotted-fevers	1141	517	1833	2002	2127	1029	31
Teeth	910	1217	119	111c	1034	1141	9
Thruſh, quincy	64	62	96	101	17	132	1
Caſualties, bruiſed, burnt, drowned, executed, frighted, falls, and other accidents, ſelf-murder, murdered, overlaid, poiſoned, ſcalded, ſhot, ſtrangled, ſmothered, ſtarved, and ſuffocated	290	325	324	323	318	311	3
Total of burials	17244	18732	19067	20678	21730	21053	239

	1698	1699	1700	1701	1702	1703	1704	1705	1706	
Abortive, &c.	Numbers dying of each diſeaſe not regiſtered.	Numbers dying of each diſeaſe not regiſtered.	Numbers dying of each diſeaſe not regiſtered.	701	660	630	689	634	612	
Aged				1456	1455	1563	1799	1746	1563	
Ague				6	3	7	6	3	2	
Apoplexy, &c.				167	136	159	147	157	155	
Aſthma, &c.				285	251	313	306	377	273	
Chincough, &c.				47	75	56	43	48	23	
Childbed, &c.				225	222	217	266	288	238	
Cholic, &c.				1306	1333	1113	1303	1181	1089	
Conſumption, &c.				2768	2792	2937	3101	2864	2809	
Convulſions				5532	5639	5493	5987	6248	5961	
Dropſy, &c.				1196	1134	1275	1338	1120	997	
King's-evil, &c.				265	286	333	317	286	280	
French-pox				57	56	63	52	29	47	
Fevers, &c.				2960	2746	3247	3318	3355	2725	
Gout, &c.				28	35	52	65	53	48	
Gravel, &c.				49	41	52	55	63	54	
Head-moldſhot, &c.				501	488	433	488	323	237	
Lethargy, &c.				70	84	86	112	75	82	
Meaſles, &c.				4	27	51	12	319	361	
Pluriſy, &c.				37	16	23	40	51	27	
Small-pox, &c.				1172	370	983	1576	1148	784	
Teeth				1261	1304	1305	1332	1384	1185	
Thruſh, &c.				41	56	55	54	88	46	
Caſualties				337	272	274	278	257	249	
Total of burials	20183	20795	19443	20471	19481	20720	22684	22097	19847	

OBSERVATIONS

POLITICAL and NATURAL, &c.

To THOMAS POTTER, Eſq;

DEAR SIR,

YOU did me great honour in our converſation a few days paſt, in thinking me capable of drawing from the bills of mortality ſuch concluſions as they truly afford, and are worthy of being ſubmitted to the public.—You rightly judged, that many obſervations might be drawn from them, which would yield valuable information.—At leaſt, that it was highly proper to be known by the public, what concluſions could be diſcovered from theſe bills, which would give their evidence independent of all party, and prejudice.—You ſtill went farther, and ſuggeſted the courſe to be ſteered, pointing out the ſhoals and currents, which would certainly be met with, as well as the means of navigating through them, in this undertaking.

In deference therefore to your deſire, and in fond hopes of ſerving the public, I have adventured upon this work. It would perhaps be impertinent to mention in this place, what is known to another gentleman, of very high rank and honour, who approved the attempt, as well as to yourſelf, how very few days have been allotted to it; fewer than the months or even years, requiſite to the full treating of ſuch a ſubject. But as no further time could be granted, the piece appears as it is, at all adventures.—It is ſufficient to add, that the grounds, upon which the calculations are founded, and the ſeveral proportions by which they are regulated, are ſubmitted to public inſpection; from whence the defect of any part of the building may be clearly diſcerned, and rectified by better judgments.—And in a work of particular curioſity and difficulty, ſuch judgments being ſenſible of the difficulty, and capable of being pleaſed with the curioſity, will ever be candid.—As this attempt therefore owes itſelf to you, it is to your patronage reſpectfully ſubmitted by,

DEAR SIR,

Your moſt obedient,

humble ſervant,

CORBYN MORRIS.

Holles-Street,
Cavendiſh-Square,
March 12, 175⅞.

OBSER-

Observation I.

Of the cauſes whence the burials in London exceed the chriſtnings.—And, on the contrary, whence the chriſtnings in the country exceed the burials.

Cause *the firſt.*

MULTITUDES of adult perſons are continually called to London from various parts, by occaſional buſineſs. To inſtance particulars,—Many by the courts of juſtice; as country attorneys, and perſons concerned in law-ſuits.—Others by commercial affairs; as foreign and provincial merchants, tradeſmen, captains of ſhips, graziers, and all ſorts of apprentices.—Great numbers by attendance upon the court and parliament; as perſons from different counties, intereſted in public acts, officers civil and military, and others ſolliciting preferment.

Many of theſe perſons are not married, and few of thoſe who are, bring their wives with them to London upon theſe occaſions.—All theſe perſons are therefore liable to die, and do conſiderably increaſe the amount of the burials; but can add nothing to the amount of the chriſtnings, except by promiſcuous venery with other mens wives, or with common women; which practices are found rather to prevent than promote the procreation of children.

Cause *the ſecond.* Another ſource of the exceſs of the burials beyond the chriſtnings, is the large number of ſervants, of both ſexes, retained by the great families continually reſident in London, or who retire to it from the country in winter; theſe ſervants being generally unmarried, ſtand in the condition of the perſons in the former article. In that, they all contribute to the amount of the burials, and very little, or not at all, to the chriſtnings.

Cause *the third.* The unhealthineſs of the air of London to children is the occaſion that a much greater portion of the infants, which are born there, die under five years old, than of thoſe born in the country. Add to which, many adult perſons, of weak conſtitutions, who would enjoy competent health in the country, find the air of London extremely noxious, and yet continue to linger in it to death, compelled by the neceſſity of their affairs. The lives alſo of many other adults in London are ſhortened, or cut off by venereal diſeaſes, beyond what ſuffer from the ſame evil in the country.—This mixture of cauſes therefore, under this head, muſt likewiſe contribute to raiſe the proportion of the burials in London, beyond that for the ſame number of people reſident in the provinces.

Cause *the fourth.* The diſcouragement to matrimony in London is a grand operating cauſe of the diminution of the chriſtnings, and conſequently of the exceſs of the burials. The unmarried ladies and gentlemen in this city, of moderate fortunes, which are the great bulk, are unable to ſupport the expence of a family with any magnificence; and therefore cannot intermarry together, without retiring from high life, and ſubmitting to relinquiſh thoſe pleaſures of the town, to which

which their appetites have long been raiſed; they therefore acquieſce in celibacy; each ſex compenſating itſelf, as it can, by other diverſions.—Perſons alſo of inferior ſituation in London, have their taſte for pleaſures inflamed; and avoid, with caution, the marriage ſtate with their equals.—And as to the vaſt body of common manufacturers, labourers, and porters, the expences in London of houſe-rent, including taxes, together with the high rate of milk, roots, and other proviſions proper for children, are ſuch, that, undoubtedly ſuch perſons enter at the ſame time into matrimony, and poverty and diſtreſs.—Hence therefore a great checque to the births in London, and a vaſt body of people furniſhing to the amount of the burials, and not at all to the chriſtnings.

Whereas the chriſtnings in the country exceed the burials; for the chief part of the adult inhabitants there are little ſhopkeepers, farmers, and labourers; the two firſt are generally married for the convenience of their buſineſs; to which they are alſo encouraged, by the cheapneſs of houſe-rent and proviſions; and even the labourers there alſo, finding the rent of a cottage, together with milk, roots, and other food proper for children, cheap, and within their income, uſually marry, eſpecially if they bend their minds to reſide in the country.—All theſe, which are the general body of the provincial houſekeepers, having little luxury, and who live temperately, in a pure air, with few anxieties, are liable to rear great numbers of healthy children;—and (having no conflux of ſtrangers to them) to raiſe the amount of the births above the burials;—many of which children, when they afterwards become adult, flock to the metropolis, and other towns. Whence it is, that the numbers deſtroyed by war, peſtilence, and the luxury of great cities, are continually recruited by theſe ſupplies from the country.

CAUSE *the fifth.* But above all, the preſent increaſing diminution of the chriſtnings in London beneath the burials, with many other evils, is particularly to be attributed to the enormous uſe of ſpirituous liquors. For it is beyond all diſpute, that ſuch liquors are become the common drink, and even the food too, if it may be ſo termed, of theſe people. The effects of which therefore muſt neceſſarily appear.—And the certain notorious ones are, that it debilitates and enervates the drinkers, drying up and burning their radical ſtrength and moiſture, ſo as to render them leſs capable of labour, or the procreation of children.—With adult perſons, theſe fatal draughts operate in enfeebling them, and carrying many to their graves.—But they trebly operate in reſpect to infants; 1ſt, In preventing many from being begotten, by the debility of the males. 2dly, Where the weakneſs is not on the male ſide, by preventing many conceptions, by the ſterility of the females; which ſterility is known to be a certain conſequence of the drinking of theſe potions. And, laſtly, by rendering ſuch as are born meagre and ſickly, and unable to paſs through the firſt ſtages of life.—This laſt effect therefore contributes to increaſe the burials, and the two former to diminiſh the chriſtnings.—No wonder then, under the ſhocking influence of this ſingle cauſe, that the chriſtnings in London ſhould be inferior to the burials. And that they are not only ſo, but that the chriſtnings have proceeded, of late years, ſince the uſe of theſe liquors, in a continually decreaſing proportion, in reſpect to the burials, is a ſerious truth, evident beyond all contradiction, by the annexed annual amounts of both, extracted

from the bills of mortality.—But for exciting the juſt attention of the public to the ſhocking conſumption of theſe liquors by the common people, and for pointing out their fatal effects upon the morals and health of the preſent, and the growth of the future race, the whole nation is greatly obliged to the worthy and pathetic repreſentations of the Biſhop of Worceſter.

Observation II.

Whatever deſtruction ſhall be made of the people of London, by ſickneſs, or other evil, will be quickly replaced by freſh ſupplies of people from the country; ſo as that early in the firſt year after, this city will ſet out again with the ſame ſtock as before, of even married adults; and will raiſe the ſame annual produce of new-born infants, as before, within the ſecond year after ſuch evil.

The high notion which country traders hold of the wealth of London, carries them with wings thither, upon the firſt news of the ceaſing of the plague, and of vacancies wanting to be filled in this metropolis.—At the ſame time, the new demand for common manufacturers and labourers, to replace thoſe who have been deſtroyed, brings a vaſt conflux of theſe people to London.—Of all which, ſome few, eſpecially of the traders, being married, are followed by their wives and children. And others of all ſorts ſeeing opportunities of ſettling themſelves in conſtant livelihoods here, immediately marry, and take poſſeſſion of the deſerted ſhops and ſtalls of their predeceſſors;—every one, in ſuch caſes, ſtriving to be foremoſt, and the ſtruggle commencing within few months after the ceaſing of the ſickneſs.—So that, conſidering alſo the number of infirm, unhealthy people of London ſwept away at ſuch times, who could add little to the amount of the chriſtnings, and are yet replaced by vigorous, active perſons from the country, it appears probable, from theſe principles, that the procreative power of London is rather increaſed, and the actual number, even of married adults therein, is compleatly repaired, within very few months, after ſuch evil.

The truth of this theory is clearly confirmed, in fact, beyond all diſpute, by the bills of mortality.—For, during the years 1603, 1625, 1636, and 1665, the plague was in London. Now, the level of the chriſtnings in the years next antecedent to 1603, according to Graunt, who had poſſeſſion of the bills, amounted to about 6000 annually; which ſunk in that plague year 1603 to 4789; but roſe again in the next year 1604 to 5458; and in 1605, the ſecond year after the plague, the chriſtnings amounted to 6504, which was above the level before the plague, and ſtill proceeded gradually increaſing.

It is evident therefore, that the old annual amount of new-born infants in London appeared again in the ſecond year after this plague; and as to the amount of married adults there, and the time when this was reſtored alſo, they may both be readily collected from the ſame principle.—For it is certain, that all the children, who were born there the ſecond year after the plague, muſt have been begotten within the following ſpace; that is, within nine months before the beginning of this ſecond year, and nine months before the end of it; wherefore the earlieſt part

of

of theſe children was begotten about three months after the plague year, and the lateſt part about fifteen months after it. Whence the number of married adults in London muſt have been as great during that ſpace; that is, from three months after the plague year, to fifteen months after it, as in any one of the years preceding the plague.—Therefore it appears, in this inſtance, that after the plague in London in 1603, the old amount of married adults was compleatly replaced there, long before the end of the firſt year after; and the annual produce of children as great in the ſecond year after, as in any year antecedent.

To give further inſtances.—In 1624, the year next preceding a plague year, the chriſtnings amounted to 8299.—In 1625, the plague year itſelf, the chriſtnings ſunk to 6983.—In 1626, the next year after this plague, the chriſtnings ſtill ſunk to 6701; occaſioned, perhaps, by the ſudden approach of this plague, and its violent ravages during its ſhort continuance; the terror of which might probably drive more people than uſual out of London, in the very plague year, and conſequently diminiſh the chriſtnings in the firſt year after.—But in 1627, the ſecond year after the plague, the chriſtnings amounted again to 8408, which exceeded the old level before it, and went on rapidly increaſing.

Thirdly,—In 1635, the year antecedent to the plague year, the chriſtnings amounted to 10,034.—In 1636, the plague year itſelf, the chriſtnings ſunk to 9522.—In 1637, (the plague not being yet entirely ceaſed, 3082 having died of it that year) the chriſtnings ſtill ſunk to 9160.—But in 1638, the ſecond year after the height of the plague, the chriſtnings aroſe to 10,311, which exceeded the old level before it, and went on increaſing till the year 1642.—In which, and ſeveral ſucceeding years of civil war, the large proportion of the married men carried out of London, ſeem to have diminiſhed the amount of the chriſtnings; or rather the diſſenſions in religion then prevalent, probably ſuppreſſed the true amount of the chriſtnings from that time to the reſtoration.

Laſtly, in 1664, the year antecedent to the plague year, the chriſtnings amounted to 11,722.—In 1665, the plague year itſelf, the chriſtnings ſunk to 9967.—In 1666, the next year after the plague, and the year of the great fire alſo in London, it is to be expected that the chriſtnings ſhould ſtill ſink, as they accordingly did; but yet even under this new evil, no lower than to 8997.—But in 1667, the ſecond year after the plague, and the very firſt after the fire, they aroſe to 10,938.—And in 1668, the ſecond year after the fire, which was before the houſes could be all rebuilt, the chriſtnings amounted to 11,623; which was nearly the level before the plague, and went on to the year 1724, when ſpirituous liquors began to make havock, in a conſtant ſtate of increaſe.

It appears therefore, by all theſe repeated inſtances, that within the ſecond year after a plague, or fire, in London, or even both jointly, the annual produce of new-born infants there, will be as great as it was in the year before ſuch evil; and conſequently, that even the married adults there, as well as of all other adults, will have been fully reſtored to their former level, early in the firſt year after ſuch evil.

This immediate renewal of the adults and new-born infants in London, after any plague, or violent deſtruction there, will take place, in all caſes, whilſt this city continues to be the ſeat of the court and parliament.—Whatſoever ſhall have been the tendency before, whether the total number of people therein ſhall have been in

a ſtate of growth, or declenſion, or nearly at a ſtand, it will be reſtored immediately after ſuch evil to the ſame ſtate again, and flow onwards, in reſpect to the number of adults and new-born infants, in the manner it would have done, had there been no ſuch interruption.

But as to the children or non-adults deſtroyed by the plague, as there is little demand for ſuch in London, it is probable that their number would not be renewed immediately; but that a leſs portion of theſe than formerly would be found in London, and continue to be ſo till the year of adultage again, reckoning from one year after the plague; by which time, their whole race, by the ſucceſſive new births, would be renewed.

OBSERVATION III.

Of the preſent bill of mortality, and of a general bill propoſed to be kept, under new regulations, through the whole kingdom.

The preſent annual bills of mortality for London, though kept in a better method than formerly, are yet defective in many particulars of the moſt important concern.

1ſt. The extent of time at the beginning of life, is not ſufficiently divided, although the degrees of ſtrength at this time are continually varying from each other, and with ſwift ſteps.—Inſomuch, that one month in the earlieſt infancy produces greater alterations, than ſeveral years in manhood—Theſe ſucceſſive and violent ravages in infancy ought therefore to be minutely deſcribed, in order to furniſh cautions for the better ſecurity of life in its tender years; upon which the very preſervation, and much more the increaſe, of our ſpecies principally depends.

2dly. The diſeaſes are not connected with the ſeveral ages: thus, for inſtance, although it appears by the bill for the laſt year 1750, that 4543 died of conſumptions, 5837 of convulſions, 4294 of fevers, and 1229 of the ſmall-pox; yet of what ages theſe ſeveral perſons were, is uncertain.—Whereas, by annexing to every diſeaſe the number of perſons of each age dying thereof, it would appear, from remarks upon a competent ſeries of years, to what diſeaſes perſons of every age were particularly ſubject. From whence, if theſe bills were extended throughout the kingdom, the growth or declenſion of every particular diſeaſe would be clearly diſcovered.—This would furniſh a conſtant fund of inſtruction to the intelligent phyſician;—and at particular critical junctures might ſuggeſt cautions, not unworthy the attention of the legiſlative body of the kingdom;—at leaſt, would make a faithful report to it of the ſtate of the national health, and of the annual increaſe or diminution of the people.

It will alſo be requiſite, that the amount of the weddings ſhould be inſerted in this bill; and alſo the reſpective amounts of thoſe accidentally ſickning of the ſmall-pox, and dying thereof; and of thoſe receiving it from inoculation, and dying under this proceſs.—For which purpoſe, an account ſhould be given to the officers of each pariſh of every perſon receiving this diſtemper, as ſoon as it is clearly diſcerned, under a penalty upon the maſter of the houſe, where the patient firſt ſickned, for neglect.—This, in a proper ſeries of time, would furniſh ample conviction,

Under the bill of mortality propoſed, one noble inſtance of information, which might clearly be drawn from it at any period, readily ſuggeſts itſelf.—This is, that the total number of perſons living of all ages, and alſo the reſpective numbers living of each age, might from hence accurately be aſcertained;—ſuppoſing this bill to have been kept for a time paſt, equal to the utmoſt extent of life, and alſo the acceſſion of foreigners, during that time, to have been nearly equal to the egreſſion of natives.

Thus, imagine ſuch a bill of mortality to have been regularly kept in any place, for any number of years, as for inſtance ten backwards from Chriſtmas laſt, and that the following problem was given.

Problem I.

To find the number of perſons in ſuch place above nine, and not exceeding ten years old;—ſuppoſing the acceſſion of foreign children of every age to this place, for ten years backwards, to have been equal to the egreſſion of natives of the ſame ages.

Solution.

The number of perſons ſurviving at Chriſtmas laſt above nine, and yet not exceeding ten years old, is the total number of births in the tenth year backwards, reduced by the ſeveral following deductions;—that is, by the part of this total number of births, which died in that tenth year; by the part of the ſame total, which died within the next, or ninth year backwards; by the part of the ſame total, which died within the eighth year backwards; and ſo on, by the ſeveral parts, which died in the ſeventh, ſixth, fifth, fourth, third, ſecond, and firſt, or laſt year backwards.—The amount of all which parts being ſubſtracted from the total number of births in the tenth year, will leave the true number of perſons ſurviving at Chriſtmas laſt, who have paſſed nine, and not exceeded ten years of age, demanded by the problem.

N. B. It is imagined, that this ſingle ſolution will ſufficiently ſhew the uſe of the new bill of mortality propoſed.

Problem II.

To find the total amount of all the non-adults living in the ſame place at Chriſtmas laſt, not exceeding ten years old; the ſame things being ſuppoſed as in the laſt problem.

Solution.

This is eaſy to be attained, by the method uſed in the former ſolution, whereby the number of perſons ſurviving at Chriſtmas laſt, who had paſſed nine, and not exceeded ten years of age, was diſcovered.—And by the ſame method, referring to the

A general bill of the weddings, births, and burials, and alſo of th
of London, for the y

Total

Whereof ha

Whereof have died of the following diſeaſes:	One month old and under	From one to three months	Three months to one year	One year to two years	Two to three	Three to four	Four to five
Abortive							
Ague							
Apoplexy, palſy, cramp, and ſuddenly							
Aſthma, ptyſic							
Chincough, hooping cough, and worms							
Child-bed and miſcarriages							
Cholic, gripes, twiſting of the bowels, flux, vomiting, looſeneſs, bloody-flux, and bleeding							
Conſumption, Jaundice, diabetes, and falling ſickneſs							
Convulſions							
Dropſy, tympany, ſtopping in the ſtomach, riſing of the lights, and ſwelling							
King's-evil, itch, leproſy, ſcurvy, St. Anthony's fire, ſcal'd head, impoſthumes, ſores, and ulcers, cancer, canker, fiſtula, gangrene, and mortification							
French-pox							
Small-pox and purples { Inoculated / Not inoculated							
Fevers, calentures, inflammations, ſore-throat and quinſy							
Gout, rheumatiſm, and ſciatica							
Gravel, ſtrangury, and ſtone							
Rickets, and infantine diſorders in the head, liver-grown, and ruptures							
Lethargy, grief, lunatic, vapours, megrim, ſpleen, head-ach, blaſted, planet ſtruck, and bedridden							
Meaſles, chicken-pox, ſwine-pox, and raſh							
Pleuriſy							
Teeth							
Thruſh							
Caſualties, bruiſed, burnt, choak'd, drowned, executed, ſelf-murder, murdered, overlaid, poiſoned, ſcalded, ſhot, ſtrangled, ſmothered, ſtarved and ſuffocated							
Totals of each age, dying of each diſeaſe reſpectively							

Total number of births

Of which { Males / Females

Total

the ſeveral ſucceſſive births ſince the tenth year, the numbers ſurviving at Chriſtmas laſt from eight to nine, ſeven to eight, ſix to ſeven, five to ſix, four to five, three to four, two to three, one to two, 0 to one, years old compleat, may all be obtained reſpectively. The laſt of which is the part ſurviving of thoſe who were born in the laſt year;—and the aggregate ſum of all theſe numbers is the total of the non-adults, not exceeding ten years old, required by the problem.

And if ſuch an annual bill of mortality had been kept through the whole kingdom, for a number of years paſt, equal to the utmoſt extent of life, the total amount of perſons of all ages, and the reſpective numbers of each age, now living in the kingdom, might accurately be determined by the ſame method;—ſuppoſing the annual egreſſion of natives during that time to have been compenſated by the acceſſion of foreigners.

OBSERVATION IV.

Of the annual births to which the numbers annually dying in the ſeveral diviſions of life, inſerted in the preſent bills of mortality, are to be referred.

SOLUTION.

If London received no continual acceſſion of ſtrangers, beyond what is ſent forth of its own growth to other places, the ſeveral proportions of perſons dying within the various diviſions of life, would be very different from thoſe which are now to be derived from the preſent bills of mortality; they would gradually decreaſe from the beginning to the end of life: and ſuch proportions would nearly repreſent the true numbers dying within theſe diviſions, out of every hundred of the burials, whatever ſhould be the progreſs of the people of this city, whether upon an increaſe, level, or declenſion,—as they would repreſent the reſpective proportions annually dying out of what had been born in this city.—But the vaſt acceſſion of ſtrangers to London, above what it ſends forth of its own growth, renders it impracticable to determine the rate of mortality from thoſe numbers, unleſs the annual amount of ſuch acceſſion of ſtrangers, and of their ſeveral ages alſo, be firſt obtained.

However, ſome concluſions may be attempted to be drawn, from laying down the following poſtulatum; which is, that the egreſſion of native non-adults from London, under twenty years old, is nearly equal to the acceſſion of non-adults thither of the ſame ages;—many of ſuch going out from thence to ſchools in the country, and great numbers alſo continually arriving under this age, to become apprentices and ſervants in London.—If this poſtulatum be allowed, then the number of non-adults continually reſident in London, of the ſeveral ages under twenty, is nearly equal to what it raiſes of its own growth under theſe ages.

Hence a very conſiderable circumſtance is obtained; which is, that whereas the reſpective numbers of perſons annually dying within the ſeveral diviſions of life, under twenty years old, before appeared to be portions of the whole number of annual burials, they are now admitted to be the true portions annually dying out of

of the whole number, annually filling theſe diviſions, of the ſole growth of London.

But it is here to be examined, with due caution, what is to be underſtood by the whole number of perſons annually filling theſe diviſions, out of which the ſeveral annual burials, or waſtes, repreſented in the preſent bill of mortality, have happened.—To determine this, take the aggregate ſum, upon a medium, of the perſons ſurviving together, of all ages under twenty, at the very commencement of the year paſt; and ſuppoſe ſuch aggregate ſum to have flowed uniformly at an equal rate, without diminution or increaſe, for the ſpace of one year, continually waſting in every part, and continually recruited alſo in every part, during its progreſs;—then is the total amount of ſuch waſte equal to the whole number of perſons dying within twenty; which number for the laſt year ended at Chriſtmas 1750, appears to have been 10,012.

Thus it is not to be imagined, that the perſons dying under two years old, during the courſe of the laſt year, were ſolely what died out of the births of this laſt, or firſt year backwards, together with what died out of the births of the antecedent, or ſecond year backwards.—There are ſtill more included;—that is, all who, during the laſt year, died under two years old, out of the births of the third year backwards.—For during the courſe of the laſt year, what died during the firſt month of it might have been of the births of any of the junior eleven months of the third year.—Again, what died within the ſecond month of the laſt year, might have been of the births of any of the ten junior months of the third year.—And in the ſame manner, all who died within the eleventh month of the laſt year, might have been of the births of the laſt month of the third year.

Therefore if the aggregate ſum of the perſons ſurviving of all ages under twenty be taken at the end of the year 1749, and the waſte of this unrecruited ſum, during its flow through the laſt year, be aſſumed, ſuch waſte will be leſs than the foregoing number aſſigned of perſons dying under twenty.—But by what ſum?—By the amount of the perſons, which would ſucceſſively have died, during that year, out of its continual recruit.

The true idea, therefore, of the ſeveral numbers, which are repreſented in the preſent bills of mortality, to have died within the various diviſions of life therein marked, is now obtained;—which is, that each of theſe numbers repreſents not the waſte made, during the firſt week of this year, out of the original amount of people then filling each diviſion, added to the waſte out of the remainder during the ſecond week; and, in the ſame manner, added to all the waſtes made upon the ſucceſſive remainders through the whole year.--But they repreſent the ſeveral waſtes which have been made out of the reſpective original amounts in each diviſion, during the paſt year, ſuppoſing ſuch original amounts to have been continually recruited in every part, during that year.

Thus, in common fact, the waſte in the bill of mortality, during every month in the year, of the perſons within each diviſion, is ſuppoſed to be equal;—at leaſt no diminution of the burials is ſuppoſed liable to happen in the laſt months of the years, rather than in the earlier; which would not be the caſe, unleſs the burials in theſe laſt months, and in every month, happened out of the ſame conſtant recruited amount of people.

If this idea of the ſeveral annual waſtes of people, in the ſeveral diviſions of life, ſhall appear to be at all abſtract, and difficult to be retained, it is not owing to its appearing ſo in this place, but to the preſent method of keeping the bill of mortality, which furniſhes ſuch complicated data.

PROBLEM.

To diſcover the rates of Mortality in the ſeveral diviſions of life, or at leaſt a quantity to which theſe rates are proportional.

SOLUTION.

The annual waſte made in each diviſion of life is, as the whole number of perſons, who have been therein during any part of that year, and as the rate of mortality, jointly.

But the whole number of perſons, which have been in any diviſion during every moment of a year paſt, being only a continued repetition of the medium number in ſuch diviſion, at the commencement, or end of this year, is therefore ſimilar alſo to either of theſe laſt numbers.

Wherefore, the annual waſte in one diviſion, compared with that in any other diviſion, is as the reſpective number of perſons in each, at the commencement, or end of the year, and as the rate of mortality in each, jointly.

Therefore the reſpective rates of mortality, in any two diviſions of life, during any two years given, will be to each other, as their reſpective waſtes in the years given, divided by the total amounts of the perſons ſtanding in each diviſion, at the commencement of each year given, reſpectively,—Suppoſing ſuch amounts to be nearly the medium.

Which proportion let be kept in reſerve for future occaſion.

REMARK.

The total extent of life, from earlieſt infancy to its extinction, is cut by the preſent bills of mortality into the following intervals, or diviſions, viz.

1. Under two years old,	2. Between two and five,	3. Five and ten,	4. Ten and twenty,	5. Twenty, and thirty,	6. Thirty and forty,	7. Forty and fifty,
8481	2011	851	762	2202	2632	2771

8. Fifty and ſixty,	9. Sixty and ſeventy,	10. Seventy and eighty,	11. Eighty and ninety,	12. Ninety and hundred,	13. A hundred and upwards.
2140	1673	1204	542	72	8

The number of which diviſions is thirteen; and the reſpective annual waſtes upon a medium for the laſt five years ended at Chriſtmas 1750, in the city of London, are repreſented by the numbers ſeverally written under each diviſion.

This, at firſt view, ſufficiently points out the vaſt quantity of adults in London, beyond thoſe of its own growth; for if the waſte in the fifth diviſion had been only of perſons of its own growth, it would have been leſs than the waſte in the foregoing diviſion; as the total number, out of which ſuch fifth waſte would have ariſen, muſt have been leſs than the total number in the former diviſion; being, upon a medium, only their ſurvivors. This vaſt number of adults ſubſiſting in London, beyond thoſe of its own produce, coincides with what has been already delivered, upon this head, under the firſt obſervation.

But yet the ſeveral amounts of perſons continually ſubſiſting in London, upon a medium for five years paſt, within the ſeveral diviſions of life, are not raſhly to be eſtimated, according to the foregoing numbers; becauſe the rate of mortality in different diviſions, is extremely different.

It may therefore be proper to be premiſed, that the rate, or force of mortality, during any ſhort ſpace, at the commencement of life, is greater than this force, for the ſame ſpace, at any other interval; but this greater rate, or force of mortality at the commencement, if then eſcaped, proceeds decreaſing, with a very ſwift pace, in the ſecond year, and alſo in the third; after which it advances, ſtill decreaſing more ſlowly and gradually to the end of the fifth year; and from hence likewiſe it flows onwards decreaſing, but by yet ſlower ſteps, to the end of the tenth year; from which time to the end of the thirtieth, it proceeds nearly at an equal pace; however, the point of leaſt rate of mortality, may perhaps be truly fixed in the middle between both, which is at the end of the twentieth year.—After the thirtieth year, the tide is generally upon the return, and the force of mortality begins viſibly to increaſe again, but yet very ſlowly to the fortieth year; from whence in every ſucceeding decad, to the end of life, it continues to gain additional increments: yet theſe additional increments ſteal onwards, with gradual and gentle ſteps, and not with the rapidity of the decrements at the commencement. Otherwiſe life would be ſoon extinguiſhed, and could never approach to that extremity of years, to which it is now extended.

This theory is only premiſed in order to point out the general courſe of the rate of mortality: but the increaſing neglect, or care of infants, and the growing debaucheries, or temperance of adults, together with other cauſes, occaſion great alterations in the amount of this rate, in the ſame diviſions of life, at different periods, even in the ſame places.—And the queſtion here is, to obtain the ſeveral amounts of this rate in London, at ſucceeding periods; which requires a diſcovery to be firſt made of the total amount of the perſons ſubſiſting at ſuch periods, in each diviſion of life, out of which the ſeveral given waſtes have ariſen. But

But firſt, for diſtinction's ſake, let all the perſons under twenty years old in London, which have already been laid down to be of its own growth, or equivalent, be called non-adults; and all of twenty years old and upwards be called adults; and let the following problems be required to be ſolved, from ſuch data as are at preſent furniſhed by the bills of mortality.

PROBLEM I.

To find the proportion which the non-adults of the growth of London, who have paſſed into adultage during any one year given, hath held to the number of ſuch non-adults which paſſed into adultage during any other year given.—Suppoſing the rate of mortality in the ſeveral diviſions of life, for twenty years antecedent to each of the years given, to have been equal.

Thus ſuppoſe, for inſtance, the years 1745 and 1750 were pitched upon, and it was required,

To find the proportion which the number ſupplied by London, of its own growth, towards recruiting its waſte of adults, during one of theſe years, bore to the number it ſupplied towards recruiting its waſte of the ſame ſort, during the other.

PROBLEM II.

To find the proportion which the total amounts of the non-adults of all ages, ſubſiſting in London, at the end of any two given years, have born to each other;—Suppoſing not the ſeveral waſtes, but the rate of mortality in all the non-adult diviſions of life, for twenty years antecedent to each year given, to have been equal.

PROBLEM III.

To find the actual total numbers of non-adults ſubſiſting in London, at the commencement of the years 1750 and 1751, reſpectively.

PROBLEM IV.

To find that part of the whole number of non-adults actually ſubſiſting in London at the end of the laſt year 1750, who were nineteen years old, and under twenty.

This will be the number, which will all paſs into adultage, during this preſent year 1751, excepting what part ſhall die out of them under twenty, during this year; and will be the whole recruit of adults, which London will, this year 1751, obtain from its own produce.

PROBLEM V.

To find the number of adults, which London annually waſtes, beyond the number of ſuch adults, which it annually ſupplies to itſelf, of its own produce.

PROBLEM VI.

To find the number of perſons waſted in London, from the revolution year 1688, *to the year* 1750, *both years incluſive; above what have been raiſed, during the ſame time of the growth of this city;—ſuppoſing it only to contain the ſame number of perſons at the end of this term, as it did at the commencement.*

The ſolution of theſe problems, if it can be obtained with tolerable accuracy, would evidently afford very uſeful public information.

To begin therefore with

PROBLEM I.

To find the proportion, which the numbers ſupplied by London, of its own growth, during any two years, towards recruiting its own annual waſte of adults, during theſe years, hold to each other reſpectively; ſuppoſing the rate of mortality, in the ſeveral diviſions of life, for twenty years antecedent to each year given, to have been equal.

SOLUTION.

Imagine the years given to be 1745 and 1751; then the annual number of non-adults ſucceſſively flowing into adultage, during the years 1745 and 1751, will be as the annual births of each of the twenty years antecedent to the two years given; that is, as the births of the years 1724 and 1730, reſpectively: for the ſurviving part of the births of the year 1724, will, after twenty years from its commencement, that is, at the end of the year 1744, all ſtand between nineteen and twenty years old; and that part of theſe births, which ſhall arrive to their twentieth year compleat, will, during the year 1745, all ſucceſſively paſs into adultage, and be the ſole recruit this adultage will obtain during that year 1745, of the growth of London. Therefore univerſally, the rates of mortality being ſuppoſed to flow equally, for each of the twenty years antecedent to the bar of adultage, the numbers paſſing this bar, during any two years given, will be to each other, as the whole births of the years of their nativity reſpectively. Which is the general ſolution of the problem required. Q. E. S.

But the annual births for the years 1724 and 1730, were 19,370 and 17,118, reſpectively, or to each other, as 1000 to 884. Therefore, the annual numbers which London ſupplied towards its own recruit of adults, during theſe laſt years, have been to each other in the ſame proportion, that is, continually decreaſing.

creaſing.—And the annual births from 1729, to the laſt year 1750, having alſo proceeded continually decreaſing, therefore the numbers which London will annually ſupply to its own recruit of adults for twenty years to come, will alſo be continually decreaſing.

PROBLEM II.

To find the proportion, which the total amounts of the non-adults, of all ages, ſubſiſting in London at the end of any two given years, have born to each other reſpectively;—Suppoſing the rates of mortality to have been equal in the ſame diviſions of life, for twenty years antecedent to each of the years given.

SOLUTION.

This proportion will evidently be, as the aggregate ſums of the annual births, for twenty years antecedent to the two years given, are to each other. The non-adults of each age, ſubſiſting at any one inſtant, or for any whole year, being as the reſpective amounts of the annual births of the years of their ſeveral nativities, by the former problem: therefore the aggregate ſums of all the non adults, at any two different periods, are as the aggregate ſums of all their annual births, for the twenty years antecedent to each of the years given; that is, as the aggregate ſums of all the births, in the ſeveral years of their nativity, reſpectively.

PROBLEM III.

To find the actual number of non-adults, from nineteen to twenty years old, ſubſiſting in London, at the commencement of the laſt year 1750, nearly.

SOLUTION.

It appears by the bill of mortality of the year 1749, that 719 died during that year, between ten and twenty years old; therefore the queſtion is, to find the whole number of non-adults, which continually filled this diviſion during that year.—Suppoſe then the rate of mortality, in this diviſion in London, to have been no greater than what flowed through perſons of the ſame ages, in the city of Breſlau. This Suppoſition will be very far from exaggerating the rate of mortality in London, in this diviſion. Now, by Dr. Halley's table of obſervations, eſtimated from the bills of mortality of this city in Sileſia, wherein the egreſſion of natives of all ages was ſuppoſed, as is here done in London, in reſpect to the non-adults only, to have been equal to the acceſſion of ſtrangers, the following proportions are given of the annual waſte of perſons of every age, in that diviſion reſpectively.

Years

Years old.	Survivors.	Annual waſte.	Medium numbers of perſons ſubſiſting.
9	670	9	From 10 to 11—657
10	661	8	11 to 12—649
11	653	8	12 to 13—643
12	646	7	13 to 14—637
13	640	6	14 to 15—631
14	634	6	15 to 16—625
15	628	6	16 to 17—619
16	622	6	17 to 18—613
17	616	6	18 to 19—607
18	610	6	19 to 20—601
19	604	6	
20	598	6	

Medium proportion of perſons ſubſiſting together at any one time from ten to twenty years old. — 6282

Therefore it appears, out of 6282 perſons, ſucceſſively paſſing from ten inclusive, to twenty years old, that about 63 died in the courſe of a year; which is nearly one out of every hundred: therefore, ſuppoſing the ſame waſte to have happened to perſons of theſe ages in London, in proportion to their number, during the year 1749, we ſhall have,

As 63 to 6282 ſo is 719 to 71695, which was nearly the whole number of non-adults of ten years old, and under twenty, ſubſiſting in London, at the end of the year 1749, and during every part of that year, upon a medium; according to the amount of the burials in this diviſion, inſerted in the London bills of mortality.

This number can err but very little from the truth, as the rate of mortality here aſſigned coincides with other various experience. For the annual burials of non-adults, from ten years old inclusive, to under twenty, for each of theſe laſt five years ended at Chriſtmas 1750, have been no more than 762 upon a medium: and as there is no reaſon to imagine, that the non-adults within this diviſion in London have been more healthy, than thoſe of Breſlau within the ſame diviſion, the juſt concluſion to be drawn is, that the number of non-adults within this diviſion, ſubſiſting together in London at any one time for five years paſt, hath not exceeded 76200, upon a medium.

It appearing then that 71695 non-adults, ſubſiſted within this diviſion in London at the end of the year 1749, it is required by this problem to find what part of theſe were nineteen years old, and under twenty.—To anſwer this, ſince the number at Breſlau was 601 of this age, out of 6282 from ten to twenty; therefore $\frac{601}{6282} \times 71695$, or 6860, will be the whole number of non-adults from nineteen to twenty, which ſubſiſted in London, at the end of the year 1749; out of which a portion equal to $\frac{598}{601}$ or 6825 all compleatly attained their twentieth year, and during the courſe of the laſt year paſſed into adultage.—And this appears to have

have been very nearly the actual number of its own growth according to the foregoing ſuppoſition, which London ſupplied, during the laſt year, towards its own recruit of adults.

That this ſuppoſition hath been carried vaſtly too far in favour of London, is now evident. And it appears plain, that the number of perſons ſubſiſting in London under twenty years old, are much beyond what it raiſes of its own growth; the number 72000 of non-adults from ten to twenty years old conſtantly ſubſiſting in London, which hath here been diſcovered, muſt be near to the truth; but theſe can never be thought to be of the ſole growth of London, by any intelligent obſerver of the bills of mortality, and of the vaſt annual ſhare which the numbers dying under ten years old are of the whole annual births. The number ſurviving of which reſults, upon ſome computations I have made, ſo extremely ſmall, that I cannot venture to deliver it as I intended, without having further proof of its being juſt by the teſt of other trials and computations. But it is certain, upon re-examining the former poſition, that London drains vaſtly more from the country between ten and twenty years old, than it ſends thither conſidering that many of ſuch ages come from the country to ſchools and academies in London; beſides which, a great number are continually ſent hither to be put apprentices: and above all, a very large multitude of young ſervants of both ſexes, who have not yet paſſed their twentieth year, are continually flocking to London. From all which, it muſt be admitted, that this city draws far greater ſupplies, even of non-adults to itſelf, than it ever repays to the country.

Had the method of ſeparating the extent of life into theſe ſeveral diviſions, imperfect as they are, been long eſtabliſhed, it would have now yielded valuable lights to the public, in regard to the variations which may have ſucceſſively happened, in the annual proportions of the perſons dying under each diviſion.—For it is much to be believed, that the preſent portion of poor infants dying under two years of age, is a far greater ſhare, out of all who have been born in this city, than it was formerly before the horrid introduction of ſpirituous liquors. But the misfortune is, that no account of the ages of the perſons dying hath been kept antecedent to the year 1728: and the account of that year too, is imperfect. 'Tis perhaps poſſible, that this might be tolerably approached by a judicious perſon, who could nearly diſtinguiſh the diſeaſes incident to different ages; eſpecially by comparing together the numbers dying in every diviſion, and by the moſt ravaging diſeaſes, during the ſeveral years for which this new account hath been kept; and thence forming the law of gradation backwards. But this requires particular medicinal ſagacity, and good information of the cuſtomary method of ſearchers, in ſettling the diſeaſes of the perſons deceaſed.—To furniſh the means of which, a table is here annexed of the ſeveral diſeaſes inſerted in the bills of mortality, and of the numbers dying of each diſeaſe from the year 1675, the firſt year this account was kept, to 1750, both years incluſive; excepting the years 1698, 1699, and 1700, during which, no account of the numbers dying of the ſeveral diſeaſes is now to be found in the books of the company of pariſh clerks of London, by whom the bill of mortality hath been annually publiſhed.

This table it is hoped, will oblige the curioſity of intelligent medicinal gentlemen: but as to the method of joining the diſeaſes together, which in many inſtances may

may be very incongruous, it is chiefly to be imputed to the original mixtures of theſe diſeaſes in the bills of mortality, which it having been impracticable for me to ſeparate, it hath therefore been neceſſary to deliver, as they were publiſhed; beſides which there hath only been added together in parcels ſome diſeaſes of leſſer fatality, which have ſeemed to bear an affinity to each other, for the ſake of avoiding too great prolixity in the tables.

However, for the time, during which the ſeveral ages of the perſons dying have been kept, a diſcovery may now be obtained of the ſeveral proportions, which the rates of mortality in the firſt diviſion of life under two years old, have born to each other, from the year 1731 to the year 1750, both years incluſive. Theſe reſpective rates of mortality, being to each other, as the ſeveral annual waſtes of perſons in each diviſion, divided by the whole medium number of perſons, ſubſiſting together at one time during each year in ſuch diviſion, as hath been before determined: which medium number of perſons is, however, firſt to be obtained. But this, and many other problems of great curioſity, and public information, which ſuggeſt themſelves, in the ſhort time allotted to this work, cannot be duly unravelled.

PROBLEM VI.

To find the number of perſons waſted in London, from the revolution year 1688, *to the year* 1750, *both years incluſive, above what have been raiſed during the ſame time, of the growth of this city,—ſuppoſing it only to contain at preſent the ſame number of perſons, which it did at the commencement of this term.*

SOLUTION.

Imagine the whole number of perſons ſubſiſting in London, at the commencement of the year 1688, to be denoted by the letter A, or any other character, or ſymbol aſſumed at pleaſure.

Then imagine this body A to have moved forwards for ſixty-three years, that is, to the end of the laſt year 1750; during which time it hath been continually waſted by the ſucceſſive annual burials, and continually filled again by its own ſucceſſive annual births, and alſo by recruits from the country: but the total amount of the burials for theſe ſixty three years, is the whole of its waſte. And the total amount of the births, during that time, is the whole ſupply it hath received of its own growth. Therefore the difference between the annual burials and births during this time, is the recruit it hath required to ſupport its original amount. Which is the general ſolution. Q. E. S.

Now the total amount of the burials from the revolution year 1688, to the year 1750, both incluſive, hath been ——	1,522,624.
And the total number of the chriſtnings during that time, hath amounted to —— —— —— ——	1,016,214.

There-

Therefore the difference, or the amount of the recruit which hath been furniſhed during this time by the country provinces of England, for repairing this waſte in London, hath been no leſs than the aſtoniſhing number of above five hundred thouſand perſons	506,410.

Theſe numerous recruits from the country have all been the flower of it, in the prime of their years, and in full poſſeſſion of their beſt activity and vigour.

What a monſtrous loſs hath this been to the nation? Compute the worth of each to have been only an hundred pounds upon a medium, which is the leaſt price ſuch perſons would bear upon an average, were they to be ſold for ſervants to any country, where ſuch purchaſes are admitted. Many of them being ſcholars, and perſons of ſkill in various ſciences, and manufactures; and the whole ſum will amount to fifty millions ſterling. This therefore is the value which hath been loſt to this nation by their deſtruction.

But it is further to be obſerved, that the number of the inhabitants of this city is conſiderably increaſed within the laſt ſixty three years: which increaſe alſo is to be added to the former recruit drawn from the country; for all which hath been ſupplied by London of its own growth hath already been eſtimated.

It is here probable, that two objections may be made; 1. That theſe people conſumed in London ſince the late revolution, have not all been a drain ſolely upon the reſt of this kingdom; but that many of them have been foreigners, natives of France; and other countries. In anſwer to which I muſt firſt obſerve, that as the births of theſe are not inſerted, ſo neither are the burials of a great part of them, in the foregoing account; which has chiefly conſiſted of thoſe in communion with the church of England: and ſecondly, that if the burials of theſe foreign adults had been inſerted, it would not prove the former account erroneous; becauſe London hath probably ſent forth as great a number of the adults of its own growth to America, and other foreign countries, as it hath received from thence towards its own recruit: therefore the annual acceſſion of foreigners to London, hath only kept the ſupply of adults, which it hath furniſhed to itſelf of its own growth, full; but hath not at all diminiſhed the provincial recruit.

The ſecond objection may, perhaps, be, that this loſs from the deſtruction of country adults, is ſtrangely exaggerated; for that moſt of them, had they continued in the country, might have done little more than have maintained themſelves, or perhaps might have been a burden to their ſeveral pariſhes. This is juſt as pleaſant, to compare it to a familiar inſtance, as if any one ſhould take my horſe, admitted to be worth ten pounds, from the ſervice he is capable of performing, and deſtroy him by labour and bad food, and then aver that he hath done me no damage, becauſe, he apprehended inſtead of employing my horſe myſelf, I ſhould rather have found him an uſeleſs expence.

But will it ſeriouſly be averred, that this half a million of active adults, had they continued in the country, would have yielded no benefit to the public?—Would they have added nothing to the improvement of the lands of this kingdom?—And hath no loſs really accrued to this nation from the deſtruction of country adults?—Let the provinces of the kingdom be all ſummoned to bear their teſti-

mony?—Let the country gentlemen be called forth, and declare,—Have they not continually felt for many years paſt, an increaſing want of huſbandmen, and day labourers? Have the farmers throughout the kingdom no juſt complaints of the exceſſive increaſing prices of workmen, and of the impoſſibility of procuring a ſufficient number at any prices? If this be ſo,—is it not an evil the moſt deſtructive, and fundamental? is it not attacking the great ſources of our national wealth? Our produces of corn, wool, and of all other ſorts, both of proviſions and materials for manufactures? is it not diminiſhing their annual growth in general, and raiſing the price of what is grown, without any advantage to the farmer or landlord? And whereto does this tend? is it not the direct courſe by the increaſing prices of proviſions throughout the kingdom to raiſe our own manufactures to a monſtrous dearneſs, and conſequently to ſtop their exportation? will not the ſure conſequence of this be, to encourage what are cheaper to be imported, and ſmuggled upon us, from other countries: which will carry abroad the wealth, which our more prudent anceſtors had procured for us, and urge our manufacturers alſo to ſeek employment in other countries; leaving a poor debauched remainder behind them, unworthy the glorous name of Britons.

Theſe are the direct conſequences flowing from this vaſt annual deſtruction of country adults, and non-adults alſo, above twelve years old, in London. And it well behoves the gentlemen of every province in the kingdom, to attend to this evil, without delay. The drain is upon them; and will continue ſo; For London will not feel any want of recruits, till there are no people left in the country.

'Tis therefore the peculiar buſineſs of the country gentlemen, to regulate the policy of London; 'tis more immediately their concern than of the gentlemen reſident in this city: to prevent the deſtruction of infants and adults in London, as far as poſſible, demands the inceſſant care of every true patriot. And every provincial gentleman ſhould be moved, not by mere curioſity alone, to inſpect at the beginning of every year the bill of mortality of London for the year antecedent, in order to obſerve the progreſs of its annual waſte, and conſequently of its annual drain from the country.

Was ſuch a juſt policy introduced in this city, as that the annual births might equal or exceed the burials, it would produce glorious and happy effects: the growth of all produces in the country, and the improvement of lands throughout the kingdom, would be greatly promoted; the country adults would have little temptation to come to London, where at preſent not only ſo many are deſtroyed, but multitudes of others who eſcape the deſtruction therein, and return from thence, teach the leſſons they have there learnt of idleneſs and debauchery to their country neighbours.—And that ſuch policy might be introduced, is evident from the ſtate of the annual births of Paris, which generally exceed the burials.—As will appear from the annexed account of the births and burials there, for a ſeries of nine years from 1728 to 1736, both years incluſive, publiſhed by Mr. Maitland.

An

An account of the births and burials in the city of Paris, for the following years reſpectively.

Years.	Births.	Burials.	Married.	Foundlings.
1728	18,189	16,887	4198	2166
1729	18,163	19,852	4231	2336
1730	18,966	17,452	4403	2401
1731	18,877	20,832	4169	2539
1732	18,605	17,532	3983	2474
1733	17,825	17,456	4132	2414
1734	19,835	15,122	4133	2654
1735	18,862	16,196	3876	2577
1736	18,877	18,900	3990	2681
Totals	168,199	160,239	37,015	22,242

And it is certainly no impoſſible point, to give the births in the city of London the ſame ſuperiority over the burials, as the procreative power in this laſt city cannot be ſuppoſed, by any Engliſhman, to be inferior to that of Paris.

PROBLEM VII.

To find how many perſons, more than remain at preſent, would now probably have ſubſiſted in Britain, if the annual births and burials in London, from 1688 *to* 1750, *both years incluſive, had been kept upon an equality.*

SOLUTION.

This will be no leſs than the foregoing whole number of 500,000, who have before appeared to have been drawn from the country, and waſted in London; all which might not only have been preſerved at preſent to the nation, or an equivalent amount continued by procreation, but might have been increaſed, by this time, to a much larger multitude; probably, at leaſt, to 600,000. This is juſtly to be concluded from the common courſe of other adults, ſubſiſting in the country, eſpecially as theſe were the flower of both ſexes, and almoſt all capable of raiſing children. And here let it be conſidered, what a valuable acquiſition this number of all ages, and ſexes, would have been to the preſent ſtrength, and riches of this kingdom. A race of healthy and robuſt people. Admit, for the preſent, that they had only maintained themſelves by their own labour, and let the annual amount of their expences be eſtimated at ten pound for each head, upon a medium, which is a moderate computation during this term; then the whole ex-

pence of theſe people would have amounted, by this time, to about ſix millions annually; almoſt all which would have been paid to the landed gentlemen of England, in addition to their preſent rents. For it muſt all have been paid by this body of people, for their own proviſions, and to the manufacturers of Engliſh produces for their cloathing and other conſumptions; which manufacturers muſt again have laid out the ſums they received with the farmers, to buy proviſions; and all this, without increaſing the prices of proviſions, but by increaſing the quantity raiſed, and thereby rather diminiſhing the prices. And here let it be juſtly apprehended by country gentlemen, that the ſource, from whence they are to expect improvement of their fortunes, is not from an increaſe of money flowing into the nation; for though that may, in ſome reſpects, operate in their favour, yet, as it muſt flow into the kingdom through other channels than theirs, ſuch new perſons will raiſe the method of living upon them;—and the prices of all labour, manufactures, and other articles, will be greatly exaggerated; whereby they will ſcarcely be able to ſupport their uſual rank.—But the true ſource, from whence their eſtates are to be improved, is to increaſe the conſumption of their own produces, and to diminiſh the price of labour. That is, to increaſe the number of laborious people amongſt them, who have mouths to eat, and bodies to be covered, and at the ſame time have hands alſo to cultivate the lands of theſe gentlemen. Under this ſituation, they may enter with ſpirit upon the improvement of their worſt grounds, and not only raiſe, at a moderate expence, to themſelves, more produces, but happily find alſo their vent increaſed. This would ſenſibly render their purſes weightier, and fill the country with new people, and new improvements.

If the value of laborious active adults be thus juſtly conſidered, the miſchiefs of a continual drain of them from the country, to be waſted in London, without renewing themſelves, will begin to be viewed with due concern. The loſs within a term ſo ſhort, within the memory of thouſands living, at preſent, of no leſs than ſix hundred thouſand people, who might now in themſelves, and their children, have ſubſiſted in this nation, will at length be viewed with horror and amazement; a loſs wholly owing to the continual deſtruction of infants and adults in this ſlaughter-houſe of London.

PROBLEM.

To determine the amount of the annual drain made upon the provinces of this kingdom, for furniſhing recruits to London, ſuppoſing the number of people in this city to have continued, for ſome years paſt, upon a level.

SOLUTION.

This is evidently the difference between the annual burials and births; for ſuppoſing, in a ſimilar inſtance, a pond of water to be continually drained from every part, and to be ſupplied by a ſpring, naturally ariſing within itſelf. Now, if the amount of the continual drain be greater than that of the continual ſupply, and

and this pond be kept to its original level, by continual additional recruits of water, it is evident that the annual amount of ſuch recruits will be the difference between the annual amount of the drain, and of the ſupply.

But the annual amount of the drain upon London by burials, hath been, upon a medium, for the laſt five years, 25,352 perſons. And the amount of its ſupply, from its own ſpring of births within itſelf, hath been, upon a medium, for the ſame time, 14,496 annually. Therefore, the amount of the recruit, which it hath drawn from the country, during each year, for theſe five years paſt, hath been no leſs than 10,856, upon a medium; which ſeems to be the rate of its preſent progreſs. And whether ſuch an annual deſtruction of the moſt active and uſeful ſubjects of the kingdom, is to be ſuffered to continue, and to rob the provinces of their beſt hands, muſt now be ſubmitted to the legiſlative wiſdom.

It may only be added, that it appears by the firſt table annexed, that the total amount of the burials, excluſive of the plague, for the laſt hundred and fifty years, hath been	2,631,137
To which, add what have died of the plague, during that time	188,571
Total of burials in London during this term—	2,819,708
Deduct from this the total amount of the chriſtnings during the ſame time	1,806,769
Difference	1,012,939

This ſum of upwards of one million of people actually appears upon record, to have been waſted in London, during this term, more than it has raiſed of its own growth, and ſtill many more have undoubtedly died therein unrecorded, beyond the births; which ought to be added to this account.

This would be the caſe, ſuppoſing London had gained no increaſe of inhabitants ſince the year 1600; but, inſtead of keeping the ſame amount, it hath continually drawn to itſelf increaſing multitudes, and hath now actually in its own poſſeſſion 400,000 inhabitants more than at the beginning of this term; which, together with their produce by procreation, it proceeds forwards, deſtroying with ſtill greater havock than formerly; even at no leſſer a rate than of 10,856 annually; ſo that if this be not interrupted, in the next hundred and fifty years, it will abſolutely deſtroy, inſtead of one million, above one million and half of people; and this without begging any aſſiſtance from the plague.

In this place, perhaps, may be required the ſolution of the following

PROBLEM.

To find the preſent tendency of the progreſs of London; or, in other words, whether the people of this city proceed increaſing, diminiſhing, or nearly upon a level.

SOLU-

Solution.

To ſtate what ſuggeſts itſelf at this inſtant, in favour of each ſide of the queſtion, —And, firſt, to begin with the opinion which prevails, that London increaſes:—Under this head are to be urged,—the growing progreſs of luxury in London; the larger number of expenſive families, with more attendants and ſervants reſident here, than formerly; the augmentation of the national debt, which attaches many to this city; and the increaſing number of houſes in London, of which a ſmaller proportion than ever are now vacant.—It is certain, all theſe circumſtances imply an increaſing number of adults in this metropolis; and ſuch is the ſtate of its progreſs, if no ſuperior cauſes operate at the ſame time to the contrary.

On the other hand it is certain that the quantity of commercial buſineſs tranſacted in London, for ſeveral years paſt, particularly in the importation of the great articles of wine and tobacco, and the iſſue of theſe from hence to other parts of the kingdom, hath much decreaſed; the out-ports having gradually augmented, during this time, their dealings in theſe and other commercial branches; and go on at a great increaſing rate, to furniſh ſupplies of many commodities to various parts of the kingdom, which were formerly drawn almoſt wholly from London: this muſt operate, therefore, in preventing the uſual demand made by London, for great numbers of adults, who were neceſſarily employed in theſe branches:—Again, the improvement of the roads near this metropolis, and the increaſing conveniencies of conveyance to all the villages around it, prevent that ſtagnation of people in London, which was formerly; enabling great numbers, who have buſineſs to tranſact in London, to come there for this purpoſe, during a few hours only of the day, and to retire into the country in the evening; which is become a general practice.—Add to which, the improvement of the roads from London to every part of the kingdom:—Which hath alſo operated towards diminiſhing the medium number of inhabitants conſtantly reſident in this city.—It will here probably be ſaid, that this improvement of the roads may as well contribute to bring more perſons to London, as to carry them from thence to the country: but the caſe is apprehended to be very different;—for the great body of people, who come to London, are neceſſarily drawn thither by commercial buſineſs; by the courts of law; attendance upon parliament, and applications for preferment:—Whatever be the ſtate of the roads, theſe will all come to London.—Wherefore the improvement of the roads does not greatly act towards bringing more perſons to London; but it acts towards enabling theſe perſons, at Chriſtmas, and at all other ſeaſons, when they can gain even one week's intermiſſion from buſineſs, to retire for that time into the country; whereas they were formerly pent up in London, during the whole winter.—Many families alſo, who were formerly hurried from the country to town, at the end of autumn, to avoid the badneſs of the roads, are now able to continue many months longer in the country; being ſecure of convenient paſſage to town at any ſeaſon: this therefore muſt greatly leſſen the conſtant number of inhabitants in London, computed at a medium. At the ſame time, theſe gentry, and their tradeſmen alſo, continually retain their houſes in London; which accounts for ſo many of them being conſtantly tenanted. Beſides this, a practice hath lately prevailed,

vailed of working, in the country, manufactures for ſale in London, which formerly employed great numbers of journeymen in this city: this is viſible in the article of ſhoes; in which there are fewer, by many hundreds, retained at work, than were twenty years ago in this metropolis; and this method will probably be followed in many other branches of conſumption.—Eſpecially as the expence of carriage from the country to London, by the improvement of the roads, becomes eaſy.—Theſe conſiderations are therefore to be urged, in ſupport of the opinion, that the number of adults, conſtantly reſident in London, rather diminiſhes.—However, it will be difficult from talking at large upon any, or all of theſe articles, on both ſides of the queſtion, to ſtrike the balance;—It muſt therefore be referred to the bills of mortality.

In entering upon this reference, it may ſafely be premiſed, that the rate of mortality in London, of late years, hath gone on continually increaſing, both in reſpect to adults and infants; which is particularly to be charged to the abominable, notorious conſumption of ſpirituous liquors. Wherefore, if the annual amount of the burials, for theſe twenty years paſt, had been even greater than it was formerly, this might juſtly be allotted to the ſame number of people as before, and to their greater deſtruction. But if the amount of the burials for twenty years paſt, has been gradually declining; and the amount of the chriſtnings, for the ſame time, hath been alſo in a courſe of declenſion, ſtill more ſwift, it is then preſumed the diſpute is determined; for if a greater mortality hath ſubſiſted among the common people, of all ages, and yet a leſſer number have annually died, for ſeveral years under it, it is evident that the ſum total, out of which they have died, muſt have been diminiſhed.

But that ſuch a decreaſe hath actually happened, both in the burials and chriſtnings, will be demonſtrated by the following table.

Years.	Total burials.	Total chriſtnings.	Annual medium of burials.	Annual medium of chriſtnings.
Both years inclusive. 1726 to 1730	142,358	87,890	28,472	17,578
1731 to 1735	127,453	87,586	25,491	17,517
1736 to 1740	137,472	80,723	27,494	16,145
1741 to 1745	126,754	72,097	25,351	14,419
1746 to 1750	126,763	72,480	25,353	14,496

Whereby

Whereby it is evident, that in the courſe of twenty years paſt, the aggregate amount of the burials for five years hath ſunk from 142,358 to 126,763; and the aggregate amount of the chriſtnings, during the ſame term, from 87,890 to 72,480; which, it is apprehended, ſufficiently teſtifies, that the total amount of the medium number of people conſtantly reſident in London, for the laſt twenty five years, hath proceeded forwards continually decreaſing.

However, though the whole medium number of perſons continually ſubſiſting together in London be diminiſhed, yet it is much to be ſuſpected, from the continual decreaſe of the chriſtnings of late years, that this diminution lies ſolely upon the infants under ten years old; and not upon the number of perſons above ten years old ſubſiſting in this city.—To bring this alſo to the teſt of calculation, let the amounts of the burials of children under ten years old, and alſo of the burials above that age, for the twenty laſt years, be ſeparately exhibited in the following table.

Years.	Totals of burials under ten years old.	Totals of burials ten years old, and upwards.
Both years inclusive. 1731 to 1735	66974	60479
1736 to 1740	68399	69073
1741 to 1745	57848	68906
1746 to 1750	56721	70042

It thus appears from this table, that the number of perſons of ten years old and upwards, continually ſubſiſting in London, upon a medium, proceeds rather increaſing; and that it hath proceeded in the courſe of the laſt fifteen years in the increaſing proportion of 60479 to 70042, whilſt the number of perſons under ten years old, hath ſunk, during this time, in the proportion of 66974 to 56721, which is the reverſe; and in a greater decreaſing proportion.———Therefore, though the numbers, who are ten years old and upwards, have increaſed, the numbers under that age have ſtill more been diminiſhed: whence the total number of perſons in London of all ages is rather decreaſed; the diminution lying wholly upon that part, which is under ten years old; and proceeding from two melancholy cauſes, a leſs number of annual births, and a greater proportion of what are born dying in their firſt infancy.———The numbers which ſurvive being chiefly

the children of perſons of ſubſtance, inſtead of thoſe of the common people.——— And this muſt ſtill aggravate the drain upon the country: for if both the number of children born in London is leſs than formerly, and a leſs portion of theſe, in reſpect to their whole number, paſſes beyond ten years old, it is evident that the annual ſupply which this city furniſhes to itſelf of its own growth, continually decreaſes.———But the whole number of perſons of ten years old and upwards ſubſiſting in London, proceeds rather increaſing; therefore if London furniſhes leſs towards this ſupply than formerly, the country muſt furniſh more; and conſequently, the drain upon the provinces of this nation goes on continually increaſing.

The preſent diminution of the chriſtnings in London is indeed very ſhocking and alarming; their amount for the laſt ten years being ſunk to as low an ebb, as they were even ſixty years ago; for the amount of the chriſtnings for the ten years, from 1681 to 1690, both incluſive, aroſe to 144,390, and went on rapidly increaſing, whilſt the burials for the ſame time amounted to 223,626; whereas the chriſtnings for the laſt ten years, ending at Chriſtmas 1750, amounted to no more than 144,577, which exceeds the amount of the chriſtnings for the former term, ſixty years before it, only by the ſmall number of one hundred and eighty ſeven; whilſt the burials aroſe for the ſame term to 253,517, which exceeds the amount of the burials in the former term, by no leſs than twenty nine thouſand eight hundred and ninety one, falling ſhort only by one hundred and nine of the full ſum of thirty thouſand:———This is not oratorical aggravation, but undeniable fact, glaring upon the face of the bills of mortality.

The foregoing calculations are reſpectfully ſubmitted, with an honeſt intention, to the public. And the foundations upon which they proceed have been conſtantly laid open, perhaps with too much prolixity, that every gentleman may readily convince himſelf of their rectitude, or miſtake. It is to be hoped, that the procuring, and digeſting into proper tables, ſo many particular articles of information upon this curious and important ſubject, will be no unacceptable preſent to thoſe into whoſe hands this treatiſe ſhall enter.—All care has been taken to avoid errors in theſe tables, which the very ſhort time allotted to this work would permit. Other gentlemen, with more leiſure, and ſuperior abilities, having theſe materials furniſhed to their hands, and the riſk of advancing the firſt calculations adventured upon, will quickly proceed much beyond theſe haſty eſſays, and eaſily confirm the concluſions in them, or diſcover their errors. Eſpecially if it could be hoped, that the Royal Society might at length be awakened after its very long paſt repoſe.

But, before theſe calculations be cloſed, it may be proper to obviate one objection, which I recollect hath been briefly ſpoken to already, but may require a more diſtinct anſwer.—It may perhaps be alledged, that great bodies of perſons, of the growth of London, have gone to our American colonies, and have furniſhed ſeveral *ultra-marine* demands, which muſt otherwiſe have fallen upon the provinces of this realm; and therefore, that this city hath ſaved a drain, which would otherwiſe have been made upon the country by this article.—To which I anſwer, admitting this to be ſo, which is however in part diſputable, that in recompence hereof, London hath received a continual acceſſion of foreigners, particularly of French refugees, to a large amount, which may juſtly be ſuppoſed to have

balanced the egreſſion of its own natives. It hath therefore conſtantly received an equivalent for theſe ſupplies, which it may be ſuggeſted to have furniſhed to our American colonies.

And if London had not ſubſiſted, though the provinces, in ſuch caſe, muſt have furniſhed theſe foreign demands, yet they would alſo have received to themſelves the foreign recruits; all which, as the caſe has ſtood, have been wholly poſſeſſed by London.

Laſtly, If the total amount be demanded of the whole body of people ſubſiſting together in London upon a medium, for the five laſt years, it may thus briefly be approached, to ſufficient exactneſs. The number which hath died of twenty years old and upwards, upon a medium of theſe years, hath been 13244 annually; of which it may be ſuppoſed, that one out of ſixty die in the courſe of a year: therefore, the conſtant amount of theſe adults ſubſiſting together in London is 60 × 13244, that is, 794,640.———Again, the number who have died between ten and twenty years old, upon a medium of the ſame term, have been 762 annually, which may be ſuppoſed to be the one hundredth part of the number of ſuch perſons generally ſurviving together, therefore 76200 is the total amount within this diviſion; and the number which have annually died in the ſame term, between five and ten years old, appears to have been 851 upon a medium; which may have been about one fiftieth part of their total.

Therefore, the number ſurviving together at one time in this diviſion, hath been about 42,550 perſons. But, as to the number under five years old, ſurviving together at any one time, it is thought proper to omit inſerting any eſtimate of it in this place.

The total of which three antecedent articles alone, is 913,390 perſons. And if the number which this city contained under twenty years old, was equal to that above that age, according to the general courſe ſubſiſting in country villages, and which would be the caſe here, if its births annually exceeded its burials, and the ſame care was taken of infants as is in the country, the number of its inhabitants would be above one million and half of perſons.———But, as it ſtands at preſent, it is the greateſt monſter of the ſort which hath ever appeared upon the face of the globe.

But to proceed. The gradual diminution of the annual births for the laſt twenty-ſix years,———and a greater proportion than formerly of thoſe, who are born of poor parents, annually dying, plainly diſcover ſome new enfeebling cauſe powerfully attacking the common people, from whom the great bulk of the chriſtnings is conſtantly derived.———And what is really this cauſe, is impoſſible to be doubted, under the preſent ſhocking conſumption of ſpirituous liquors.———Aſk the phyſician, and he will inſtantly declare, that the certain conſequence to adults of drinking theſe burning potions is to be enervated, and rendered leſs fit for bodily labour, and procreation of children.———Let it now be ſeen by the bills of mortality how this actually has reſulted in fact.

It appears by theſe bills, that the amount of the births in London went on annually increaſing to the year 1724; in which year they amounted to upwards of 19000: but, ſince then, have continually ſunk to the preſent time; and now ſcarcely ariſe to 14500 annually.—Nor have actually for ten years paſt amounted to this laſt ſum, upon a medium. Whereby it appears, that this diminution of the

the births ſet out from the ſame time that the conſumption of theſe liquors by the common people became enormous; and that as this conſumption hath been conſtantly increaſing ſince that time, the amount of the births hath likewiſe been continually diminiſhing. But let this diminution, and the number of infants loſt thereby within this city, be ſtrictly computed. Now the amount of the chriſtnings in the year 1724, was 19370; and had proceeded in a gradual courſe of increaſe up to that number.—Admit then, that they would have ſtood only to this amount from that time to the preſent, without advancing, beyond this level, though that was their evident tendency: then for the twenty-ſix years paſt, from 1725 to 1750, both years incluſive, the amount of the births would have been 26×19370, that is, 503,620. But the actual amount of the births for theſe years hath been no more than 419,635. The difference between which numbers is 83985, falling ſhort, by only the ſmall number of fifteen, of fourſcore and four thouſand infants; —which, at a very moderate computation, have been loſt, during this ſhort term, within this capital only, by the drinking of ſpirituous liquors.—Beſides what have been loſt in all other parts of the kingdom, wherein this conſumption hath been prevalent.

Can it be neceſſary to add to this ſhocking loſs, by prevention of births, the ſickly ſtate of ſuch infants as are born, who, with difficulty paſs through the firſt ſtages of life, and live very few of them to years of manhood.—What actually arrive to it, being alſo a weakly unhealthy race, unfit for the great uſeful ſervices of ſociety, labour, and agriculture.

Aſk the maſters of every trade, and every manufacture, whether they feel no miſchiefs in their trades, from the conſumption of theſe liquors? They will tell you, with horror, the ſtupefaction they cauſe in their workmen, and continual diſability to perform their labour.

Enquire from the phyſicians of the ſeveral hoſpitals in this city, whether any increaſe of patients, and of what ſort, are daily brought under their care? They will all declare, increaſing multitudes of dropſical and conſumptive people, ariſing from the effects of ſpirituous liquors.

And if any conviction was farther wanted, it would be eaſy to draw it from all other ſcenes of inferior life, in ſupport of the neceſſity of totally ſuppreſſing the conſumption of theſe liquors by the common people; which ought only to be ſold at the ſame ſhops where arſenic and laudanum are allowed to be vended.

Having hitherto proceeded in pointing out evils, it may perhaps be expected, that ſome remedies alſo ſhould be propoſed, towards preventing the annual waſte of infants and adults in this metropolis; and to encourage matrimony.—In this view I have added the following propoſals.—The firſt of which, I am not inſenſible, will appear to many perſons extremely chimerical.

The unhealthineſs of the air of London, though not greater than formerly, has been mentioned before, as one operating cauſe of the annual deſtruction of many people. This, indeed, is the leaſt powerful weapon, in the hands of death; yet, to obviate its force, as the preſervation and health of the people in every inſtance is of great importance, it is propoſed, that the cleanſing of this city ſhould be put under one uniform public management, and all the filth be carried into lighters, and conveyed by the Thames to proper diſtances in the country; where it would

be of great benefit to the lands, inſtead of being lodged, as at preſent, on the outſides of this city; a nauſeous, noxious ſpectacle.—It is alſo further propoſed upon this head, that open ſtreets nearly parallel to each other, at proper diſtances, be cut from the river ſide through the town, and continued in ſtrait roads or walks for ſeveral miles diſtant, directly into the country. By which meaſures, the air of London would be free from many of the poiſonous particles loading it at preſent; and a new circulation of pure air introduced. Opportunities alſo would hereby be given to the inhabitants of this city, to extend themſelves further into the country, and to breathe a freſher air than they generally can at preſent, in a walk of the ſame length:—And however romantic this may ſeem at firſt view, whoſoever has obſerved the vaſt multitudes of people poured forth by this city into the fields around it, on ſummer evenings; and conſidered the great refreſhment and ſupport of their health, which they conſtantly derive from theſe promenades, will perhaps think this propoſal merits regard: the execution of it is far inferior to the public works, which old Rome could boaſt of the ſame ſort: her grand Appian, Flaminian, and twenty other roads, cut in ſtrait lines for many miles together into the country; and her magnificent aqueducts;—all built at the public expence for public convenience.

2°. To prevent the grand annual deſtruction of the infants of poor married women in this city, and the deſtruction and ſuppreſſion of the infants of ſingle women, it is propoſed, that ſeveral foundling-hoſpitals be eſtabliſhed in different parts of this town, for the receiving all children, which ſhall be offered, without exception; to be conducted under one uniform public management;—and to be ſupported by an annual tax upon all perſons in London, of both ſexes above twenty-one years old, who have never been married;—at proper rates ſuitable to their reſpective ranks and qualities. A tax, which applied to ſo compaſſionate a public ſervice, would not be regretted by thoſe on whom it was raiſed; who would rightly conſider the benefits attending it, and the annual ſaving of thouſands of infants from being deſtroyed by various methods.

This tax might be collected in the ſame manner, and according to the ſame proportion as the poll-taxes were, ſoon after the revolution. And one hundred thouſand pounds be immediately raiſed upon the credit of this fund, as ſoon as it ſhall be eſtabliſhed, in order to carry ſo valuable and compaſſionate a public deſign immediately into execution;—the means of conducting it in the beſt method, being happily furniſhed from the experience already obtained by the prudent and judicious management of that ſmall contribution, which hath been made for a few years paſt, to a charity of the ſame ſort begun in this city.

3°. The luxury of great families, in their preſent general uſe of unmarried ſervants, conſiderably obſtructs the annual produce of children:—Thus, ſuppoſe a faſhionable family in London, to conſiſt of half a dozen perſons, and upwards;—and of theſe, perhaps at moſt, only the maſter and miſtreſs married; the reſt, all ſervants marriageable, and unmarried:—It is here evident, that the luxury of the maſter and miſtreſs detains many adults of both ſexes from manufacture and agriculture, merely for grandeur and their own perſonal attendance; and reſtrains them from marrying, during their continuance in this ſervice.—Is not this a treſpaſs upon the national growth, and a miſapplication of the labour and induſtry of many individuals? And though it may be proper, in a wealthy community, to indulge

dulge ſuch exceſſes, where they run not to great enormity, yet ſurely the perſons indulged in them, and who publicly declare thereby, their income to be ſuperfluous, cannot decently oppoſe the making a ſuitable recompence to the public for their reſpective treſpaſſes in this article.

4°. The retailers of commodities, not being employed in manufactures themſelves, nor in public labour, but ſubſiſting by the advantages they take of the induſtry of one part, and the appetites of the other part of the ſociety preying upon both, and being too numerous in many branches: it is therefore propoſed, that all preſent retailers ſhall take licences from the public for vending the produce of the induſtry of others.—This extended throughout the kingdom, would furniſh a very conſiderable public revenue, and might be laid in aid of any diminution of the preſent duty upon ſpirituous liquors:—this tax would be welcome and chearfully paid, if the following regulation was annexed to it; which is, that hawkers and pedlars be entirely ſuppreſſed: a ſet of unmeriting people, who carry luxury into all corners; and ſollicit and enflame the pride of every farmer's wife and daughter in the kingdom. It is further propoſed under this head, that all unmarried perſons be prohibited from ſetting up anew, in any retail buſineſs; ſuch perſons not meriting the indulgence of this liberty from the public.—Under this regulation many perſons, who would otherwiſe continue ſingle, would enter into matrimony; whereby the annual produce of children would be promoted, and the riſing national ſtrength and wealth greatly increaſed.

If the clergy of the realm would zealouſly unite in warning their reſpective flocks of the fatal miſchiefs flowing upon the nation, from the uſe of theſe ſpirituous liquors by the common people;--the ruin of all decency, ſhame, morality, and principle, it would animate all perſons in their ſeveral ſtations, to exert themſelves to ſuppreſs this evil, now ravaging like one continual peſtilence throughout the kingdom. And this is to be hoped the rather, as upon other occaſions they have made pathetic exhortations, with great effect, upon the dreaded approach of leſs formidable, though public evils; ſuch as diſtempers amongſt the cattle, and earthquakes;—ſome of which have actually happened, and others only happened to be expected.--But this is a diſtemper amongſt the people, which hath raged for many years paſt, and actually now rages with increaſing fury.—Threatning not only a ſhock, but a total overthrow of all induſtry amongſt us, and mortality.

But in this ſituation, whatever lukewarmneſs may appear in ſome, the zeal of others of this body is highly to be applauded. And it muſt give ſatisfaction in this juncture to every lover of his country to know, that due remedies to theſe evils are now the ſubject of the conſideration of the legiſlature; and that every laudable meaſure which can be propoſed, every ſalutary ſcheme which can be offered from any hand, for reforming theſe miſchiefs, will be ſure to obtain full countenance, and ſupport, under the upright, diſintereſted and public-ſpirited miniſtry of Mr. PELHAM.

POSTSCRIPT.

THE time neceſſary to the working of the ſheet, antecedent to this, at the preſs, allowing me a ſhort leiſure, I ſhall allot it to the clearing of ſome articles in the foregoing work, upon which, it is poſſible, doubts may be ſuggeſted.

It

It may, perhaps, be imagined by ſome perſons, that the accounts of the chriſtnings and burials, in the bills of mortality, are not to be depended on; and therefore, that inferences drawn from them may be erroneous. I ſhall therefore beg leave to advance the following

PROPOSITION;

To demonſtrate that the reſpective annual amounts in the bills of mortality of London of the chriſtnings and burials of perſons in communion with the church of England, are the total amounts of all ſuch perſons; or, that the ſmall additions to each, including alſo the births and burials of diſſenters, are proportional to theſe amounts; and therefore, that any inferences drawn from theſe bills, in regard to the total numbers born and deceaſed, cannot be exaggerated, but may be defective.

DEMONSTRATION.

It is not to be doubted, but the numbers exhibited in theſe bills, to have been chriſtned and buried, have been actually born, and deceaſed in London.—But the doubt is, what omiſſions have been annually made of each ſort. Now it cannot be ſuppoſed, that there have been many ſuch of the church of England; if it be conſidered, that the performance of Chriſtian baptiſm and burial is yet very rarely omitted to perſons of this church, either born, or deceaſed. This would be to ſuppoſe the evil complained of, to have really ſpread farther than hath been repreſented, and to have totally obliterated all the remains of decency among the inferior claſs of people.—It is therefore to be preſumed, that very few of this church, who are born or buried in London, are omitted to be inſerted in the bills of mortality. And if there be any ſuch actually omitted, the omiſſion may be juſtly ſuppoſed to be equal on both ſides.—But beſides this, it is certain that there are ſeveral who annually die in London, and are carried from thence to diſtant places to be interred, who are not inſerted in the London burials. Therefore, if the exact account of the births and deaths of perſons in London, eſteemed in communion with the church of England, was inſerted in theſe bills, it is to be ſuppoſed, though there might be the addition of a few units, yet that in theſe added on both ſides, the births would be ſtill exceeded by the deaths. Therefore, the preſent proportion between both inſerted in the annual bills of mortality, would not be thereby altered. And as to the diſſenters, whoſe chriſtnings and burials are not inſerted, theſe are alſo to be ſuppoſed to have happened in the ſame proportion.—Therefore, if the annual totals of the burials and chriſtnings in London be augmented, beyond what they ſtand in the preſent bills, to their full amount, as their proportions to each other continue the ſame, their differences will neceſſarily become greater; and therefore, the miſchiefs exhibited in the foregoing work will ſtill be greater than they have been repreſented. Q. E. D.

It was intended, in addition to the foregoing propoſals, to have alſo ſubmitted one for ſuppreſſing the enormous conſumption of ſpirituous liquors, without giving any encouragement to ſmuggling, and providing at the ſame time a full compenſation to the public revenue; but I have choſen, for ſome reaſons, to withdraw from the preſs, and reſerve at preſent, the papers upon this ſubject; particularly, being firſt deſirous of obſerving, what acceptance this previous part ſhall appear to merit from the public.

15th March, 1750.

Diſeaſes and caſualties annis	1728	1729	1730	1731	1732	Totals	Medium.	In every thouſand.
Abortive and ſtill-born	588	552	634	673	637	3084	617	23,3
Aged — —	2768	2681	2071	1675	1781	10976	2195	82,6
Ague —	44	27	16	11	10	108	21	0,8
Apoplexy and ſuddenly --	174	182	238	237	237	1068	214	8,0
Aſthma and tiſſick	612	657	403	469	573	2714	543	20,5
Bedridden —	14	8	9	2	3	36	7	0,25
Bleeding —	3	3	3	6	5	20	4	0,15
Bloody flux —	23	21	19	17	13	93	19	0,7
Burſten and rupture	12	26	13	8	22	81	16	0,6
Cancer —	49	55	71	75	50	300	60	2,2
Canker —	16	20	10	8	14	68	13,6	0,5
Chicken and ſwine pox	1	1	0	0	0	2	0,4	0,15
Childbed —	216	244	266	251	219	1196	239,2	9,0
Cold — —	0	2	0	1	1	4	0,8	0,03
Colick, gripes, and twiſting of the guts	527	537	447	352	325	2188	438	16,5
Conſumption —	3491	3544	3728	3425	3719	17907	3581	134,8
Convulſion —	7517	8359	8023	7986	7428	39313	7863	295,8
Cough and hooping-cough —	26	35	152	33	65	311	62	2,4
Diabetes —	3	2	3	3	5	16	3	0,1
Dropſy and tympany	1143	1060	943	1050	951	5147	1030	38,8
Evil — —	35	36	30	47	19	167	33	1,22
Carried forward	17262	18052	17079	16329	16077	84799	16960	638,4

Diſeaſes

Diſeaſes and caſualties annis	1728	1729	1730	1731	1732	Totals.	Medium.	In every thouſand.
Brought forw.	17262	18052	17079	16329	16077	84799	16960	638,4
Falling ſickn.	0	0	1	2	0	3	0,6	0,01
Fever, malignant, ſcarlet and ſpotted fever, and purples	4822	5235	4011	3225	2939	20232	4046	152,2
Fiſtula —	10	10	17	23	17	77	15	0,55
Flux —	14	17	28	25	32	116	23	0,86
French pox	113	105	108	98	90	514	103	4,0
Gout —	39	43	45	66	38	231	46	1,73
Gravel, ſtone and ſtrangury —	51	42	49	41	52	235	47	1,73
Grief —	13	19	17	14	14	77	16	0,6
Head-ach, concuſſion of the brain	0 1	7	1	2	0	11	2	0,07
Headmold-ſhot, horſe-ſhoehead, and water in the head	141	107	104	64	81	497	100	4,0
Jaundies —	132	119	122	106	117	596	119	4,5
Impoſthume	28	27	33	29	31	148	30	1,0
Inflammation	4	4	7	12	19	46	9	0,35
Itch — —	3	5	0	0	2	10	2	0,07
Leproſy —	8	0	7	2	2	19	4	0,15
Lethargy —	13	5	11	4	13	46	9	0,35
Livergrown —	10	11	3	5	9	38	7	0,25
Lunatick —	26	41	29	21	25	142	29	1,0
Meaſles —	82	41	311	102	30	566	113	4,5
Miſcarriage	1	6	7	6	3	23	4,4	0,15
Mortification	238	227	232	189	149	1035	207	8,0
Carried forw.	23011	24123	22222	20365	19740	109461	21892	824,47

Diſeaſes and caſualties annis	1728	1729	1730	1731	1732	Totals.	Medium.	In every thouſand.
Brought forward	23011	24123	22222	20365	19740	109461	21892	824,47
Palſy	28	38	29	38	30	163	33	1,22
Pleuriſy	48	77	44	50	55	274	55	2,0
Quinſy	11	14	12	8	11	56	11	0,5
Raſh	2	5	8	6	2	23	4	0,15
Rheumatiſm	25	17	30	24	29	126	25	1,0
lameneſs			1					
Rickets	103	102	85	54	74	418	84	3,1
Riſing of the lights	41	36	27	37	34	175	35	1,21
St. Anthony's fire	6	4	3	2	2	17	3	0,1
Scald-head	5	0	1	0	2	8	2	0,07
Scurvy	3	2	3	3	0	11	2	0,07
Small pox	2105	2849	1914	2640	1197	10705	2141	80,57
Sores and ulcers	36	36	35	32	45	184	37	1,21
Spleen and vapours	3	4	3	4	6	20	4	0,15
Stoppage in the ſtomach	147	258	229	193	197	1024	205	7,73
Surfeit	8	4	5	1	4	22	4	0,15
Swelling	1	2	2	1	1	7	2	0,07
Teeth	1676	1629	1585	1242	1361	7493	1498	56,0
Thruſh	84	54	51	48	65	302	60	2,0
Vomiting and looſeneſs	39	39	49	38	26	192	39	1,5
overflowing of the gall			1					
Worms	31	24	15	27	11	108	22	0,83
Caſualties	397	405	407	449	466	2124	424	15,9
Totals	27810	29722	26761	25262	23358	132913	26582	1000

Diſeaſes and caſualties annis	1733	1734	1735	1736	1737	Totals.	Medium.	In every thouſand.
Abortive and ſtill-born	657	661	590	592	641	3141	628	23,5
Aged	2207	1459	1595	1918	1984	9163	1833	68,2
Ague	3	6	6	1	3	19	4	0,15
Apoplexy and ſuddenly	227	183	196	208	243	1057	211	8,0
Aſthma and tiſſick	896	466	477	582	620	3041	608	22,5
Bedridden	10	5	10	13	12	50	10	0,4
Bleeding	3	8	3	5	2	21	4	0,15
Bloody flux	10	13	13	7	7	50	10	0,4
Burſten and rupture	24	21	19	15	15	94	19	0,7
Cancer	48	48	58	54	51	259	52	2,0
Canker	17	12	11	10	7	57	11	0,4
Chicken and ſwine pox	1	0	0	0	0	1	0,2	0,01
Childbed	292	271	192	202	284	1241	248	9,2
Colick, gripes, and twiſting of the guts	332	351	317	362	338	1700	340	12,5
Conſumption	4601	4139	4064	4554	4441	21799	4360	162,5
Convulſion	9336	8295	7572	7924	7811	40938	8188	305,0
Cough and hooping cough	97	139	81	130	160	607	121	4,5
Diabetes	0	2	0	3	0	5	1	0,03
Dropſy and tympany	1134	1001	1051	1145	1038	5369	1074	40,0
Evil	28	30	26	33	35	152	30,6	1,1
Falling ſickneſs	2	1	0	0	0	3	0,6	0,01
Carried forward	19925	17111	16281	17758	17692	88767	17753,4	661,25

Diſeaſes

Diſeaſes and caſualties annis	1733	1734	1735	1736	1737	Totals.	Medium.	In every thouſand.
Brought forward —	19925	17111	16281	17758	17692	88767	17753,4	661,25
Fever, malignant, ſcarlet and ſpotted fever, and purples —	3831	3116	2544	3361	4580	17432	3487	130,0
Fiſtula —	22	14	8	16	16	76	15	0,54
Flux — —	12	24	17	24	19	106	21	0,8
French pox —	125	105	102	111	159	602	120	4,5
Gout — —	54	44	38	47	55	238	48	1,8
Gravel, ſtone and ſtrangury —	70	56	38	47	66	277	55	2,0
Grief — —	13	12	14	10	10	59	12	0,5
Head-ach —	0	0	1	0	0	1	0,2	0,01
Headmold-ſhot, horſe-ſhoe head, and water in the head	71	116	143	117	153	600	120	4,5
Jaundies —	158	126	154	142	158	738	148	5,5
Impoſthume —	28	36	16	24	33	137	27	1,0
Imflammation	62	31	22	25	56	196	39	1,5
Itch —	4	2	1	1	0	8	1,6	0,05
Leproſy —	2	6	9	6	5	28	5,6	0,2
Lethargy —	10	9	8	9	7	43	8,6	0,3
Livergrown —	3	8	10	13	10	34	7	0,25
Lunatick —	19	22	29	30	34	134	26,8	1,0
Meaſles —	605	20	10	169	127	931	186,2	7,0
Miſcarriage —	7	2	4	2	1	16	3,2	0,1
Mortification —	169	193	167	232	209	970	194	7,2
Carried forward	25190	21053	19616	22144	23390	111393	22278,6	830,0

Diſeaſes and caſualties annis	1733	1734	1735	1736	1737	Totals.	Medium.	In every thouſand.
Brought forw.	25190	21053	19616	22144	23390	111393	22278,6	830
Palſy —	36	37	39	43	35	190	38	1,5
Pleuriſy —	63	58	55	51	71	298	60	2,0
Quinſy —	10	31	19	14	31	105	21	0,8
Raſh — —	1	3	1	2	5	12	2	0,07
Rheumatiſm —	18	21	12	19	19	89	18	0,62
Rickets —	83	82	107	70	80	422	84	3,1
Riſing of the lights —	26	18	21	24	8	97	19	0,7
St. Anthony's fire — —	4	4	0	0	1	9	2	0,07
Sciatica — —	0	2	0	0	0	2	0,4	0,01
Scald-head —	0	0	2	0	0	2	0,4	0,01
Scurvy — —	2	3	2	0	2	9	2	0,07
Small pox —	1370	2688	1594	3014	2084	10750	2150	80,0
Sores and ulcers —	34	34	34	23	27	152	30	1,1
Sore throat —	0	0	0	2	0	2	0,4	0,01
Spleen and vapours —	4	5	0	0	2	11	2	0,07
Stoppage in the ſtomach —	188	138	162	173	173	834	167	6,3
Surfeit — —	4	2	3	2	5	16	3	0,1
Swelling —	1	4	1	2	2	10	2	0,07
Teeth — —	1623	1316	1342	1447	1423	7151	1431	53,3
Thruſh — —	87	90	55	71	69	372	75	2,8
Vomiting and looſeneſs	26	20	19	15	11	91	18,2	0,7
Worms —	4	10	9	10	12	45	9	0,3
Caſualties —	459	443	445	455	373	2175	435	16,3
Totals —	29233	26062	23538	27581	27823	134237	26848	1000

Diſeaſes

Diſeaſes and caſualties annis	1738	1739	1740	1741	1742	Totals.	Medium.	In every thouſand.
Abortive and ſtill-born	608	602	554	548	530	2842	568	20,0
Aged — —	1841	1770	2592	2512	2131	10846	2170	77,0
Ague —	1	3	6	3	8	21	4	0,1
Apoplexy and ſuddenly --	201	194	228	230	235	1088	218	8,0
Aſthma and tiſſick	656	638	1153	646	585	3678	735	26,0
Bedridden —	5	8	23	17	8	61	12	0,4
Bleeding —	3	3	8	5	0	19	4	0,1
Bloody flux —	5	9	6	20	19	59	12	0,4
Burſten and rupture	25	20	28	16	19	108	22	0,8
Cancer —	54	50	56	62	40	262	52	2,0
Canker —	8	8	6	5	9	36	7	0,2
Childbed —	261	260	227	256	203	1207	241	8,0
Cold — —	0	0	0	0	2	2	0,4	0,02
Colick, gripes, and twiſting of the guts —	295	280	296	258	109	1238	248	9,0
Conſumption —	4326	4429	4919	4981	4716	23371	4674	165,0
Convulſion —	7524	7371	8479	8250	6820	38444	7689	271,0
Cough and hooping-cough —	69	72	280	109	122	652	130	5,0
Diabetes —	0	1	1	3	1	6	1	0,05
Dropſy and tympany	973	1009	1225	1060	1113	5380	1076	38,0
Evil — —	38	32	50	31	24	175	35	1,0
Falling ſickneſs —	0	0	1	1	1	3	0,6	0,03
Carried forward —	16893	16759	20138	19013	16695	89498	17899	632,1

Diſeaſes and caſualties annis	1738	1739	1740	1741	1742	Totals.	Medium.	In every thouſand.
Brought forward —	16893	16759	20138	19013	16695	89498	17899	632,1
Fever, malignant, ſcarlet and ſpotted fever, and purples —	3890	3334	4003	7528	5108	23863	4773	168,0
Fiſtula —	17	9	8	16	17	67	13	0,5
Flux — —	11	10	16	31	27	95	19	0,65
French pox —	117	116	162	128	104	627	126	4,0
Gout — —	66	48	60	46	54	274	55	2,0
Gravel, ſtone and ſtrangury —	74	47	43	53	41	258	51	2,0
Grief — —	10	10	12	10	12	54	11	0,4
Head-ach —	0	0	1	1	0	2	0,4	0,02
Headmold-ſhot, horſe-ſhoe head, and water in the head	175	155	165	129	118	742	148	5,0
Jaundies —	130	121	108	161	155	675	135	5,0
Impoſthume —	13	22	28	25	24	112	23	0,8
Inflammation	52	39	35	33	51	210	42	1,5
Itch —	6	4	1	5	0	16	3,2	0,15
Leproſy —	4	4	4	9	5	26	5	0,15
Lethargy —	7	5	8	6	10	36	7	0,25
Livergrown —	6	10	7	0	3	26	5	0,15
Lunatick —	39	34	90	71	80	314	63	2,5
Meaſles —	216	326	46	42	981	1611	322	11,0
Miſcarriage —	1	3	5	5	3	17	3,4	0,15
Mortification —	222	258	318	282	271	1351	270	10,0
Carried forward	21949	21314	25258	27594	23759	119874	23974	846,32

Diſeaſes

Diſeaſes and caſualties annis	1738	1739	1740	1741	1742	Totals.	Medium.	In every thouſand.
Brought forw.	21949	21314	25258	27594	23759	119874	23974	846,32
Palſy —	30	37	43	48	53	211	42	1,5
Piles —	0	0	0	0	1	1	0,2	0,01
Pleuriſy —	51	53	70	44	52	270	54	2,0
Quinſy —	23	19	18	13	21	94	19	0,65
Raſh — —	3	4	3	6	0	16	3	0,15
Rheumatiſm —	21	23	38	26	24	132	27	1,0
Rickets —	73	80	81	50	47	331	66	2,5
Riſing of the lights —	6	11	12	13	6	48	10	0,4
St. Anthony's fire — —	2	6	4	5	1	18	3,6	0,15
Scald-head —	2	1	2	2	5	12	2,2	0,1
Scurvy — —	0	0	2	0	2	4	0,8	0,04
Small pox— white ives	1590	1690 4	2725	1977	1429	9415	1883	66,0
Sores and ulcers —	19	37	30	19	19	124	25	0,9
Sore throat —	0	2	0	3	1	6	1,2	0,06
Spleen and vapours —	0	1	1	0	0	2	0,4	0,02
Stoppage in the ſtomach	188	206	185	197	117	893	178	6,0
Surfeit — —	2	6	5	8	4	25	5	0,15
Swelling —	1	2	8	3	4	18	3,6	0,15
Teeth — —	1376	1372	1708	1501	1358	7315	1463	52,0
Thruſh — —	94	104	136	158	128	620	124	4,0
Vomiting and looſeneſs	12	5	7	20	12	56	12	0,4
Worms —	16	10	13	16	14	69	14	0,5
Caſualties —	367	445	462	466	426	2166	433	15,0
Totals —	25825	25432	30811	32169	27483	141720	28344	1000

Diſeaſes and caſualties annis	1743	1744	1745	1746	1747	Totals.	Medium.	In every thouſand.
Abortive and ſtill-born	601	530	512	541	554	2738	547	22,5
Aged	2429	1573	1843	2424	2010	10279	2056	85,0
Ague	5	6	6	15	8	40	8	0,3
Apoplexy and ſuddenly	237	205	211	253	194	1100	220	9,0
Aſthma and tiſſick	611	471	533	553	416	2584	517	21,0
Bedridden	5	3	7	5	2	22	4	0,15
Bleeding	2	4	2	4	3	15	3	0,1
Bloody flux	7	2	15	21	6	51	10	0,5
Burſten and rupture	21	25	17	17	18	98	20	1,0
Cancer	61	46	46	50	47	250	50	2,5
Canker	8	4	1	3	4	20	4	0,15
Childbed	176	184	197	188	207	952	191	8,0
Cold	9	0	0	0	2	11	2	0,08
Colick, gripes, and twiſting of the guts	136	86	135	119	160	636	127	6,0
Conſumption	4353	3865	4015	4887	4560	21680	4336	180,0
Convulſion	6761	5715	5728	6952	6783	31939	6388	264,0
Cough and hooping-cough	92	46	135	95	151	519	104	4,0
Diabetes	1	1	1	0	3	6	1,2	0,05
Dropſy and tympany	1044	1000	1096	1198	1133	5471	1094	45,0
Evil	21	16	23	20	17	97	19,4	0,9
Falling ſickneſs	0	0	0	0	2	2	0,4	0,02
Carried forward	16580	13782	14523	17345	16280	78510	15702	650,25

Diſeaſes

Diſeaſes and caſualties annis	1743	1744	1745	1746	1747	Totals.	Medium.	In every thouſand.
Brought forward —	16580	13782	14523	17345	16280	78510	15702	650,25
Fever, malignant, ſcarlet and ſpotted fever, and purples —	3837	2670	2690	4167	4779	18143	3629	150,0
Fiſtula —	10	14	12	14	13	63	12	0,45
Flux — —	23	10	34	40	28	135	27	1,5
French pox —	64	54	76	100	69	363	73	3,0
Gout — —	54	46	55	60	52	267	53	2,55
Gravel, ſtone and ſtrangury —	34	29	36	24	31	154	31	1,5
Grief — —	3	10	11	5	6	35	7	0,25
Headmold-ſhot, horſe-ſhoe head, and water in the head	24	144	154	148	150	720	144	6,0
Jaundies —	134	110	128	130	139	641	128	5,0
Impoſthume —	29	31	22	19	12	113	23	1,0
Inflammation	60	63	62	88	53	326	65	2,5
Itch — —	5	1	4	6	6	22	4	0,15
Leproſy —	4	1	3	5	6	19	4	0,15
Lethargy —	7	8	5	4	3	27	6	0,25
Livergrown —	0	3	1	2	1	7	1	0,05
Lunatick —	75	64	75	90	53	357	72	3,0
Meaſles —	17	5	14	250	81	367	73	3,0
Miſcarriage —	3	3	2	3	6	17	3	0,15
Mortification —	206	226	209	251	227	1119	224	9,0
Carried forward —	21269	17274	18116	22751	21995	101405	20281	839,75

Diſeaſes and caſualties annis	1743	1744	1745	1746	1747	Totals.	Medium.	In every thouſand.
Brought forward	21269	17274	18116	22751	21995	101405	20281	839,75
Palſy	40	48	41	61	52	242	48	2,0
Piles	0	0	1	0	0	1	0,2	0,01
Pleuriſy	51	35	59	43	31	219	44	2,0
Quinſy	29	18	13	17	24	101	20	1,0
Raſh	4	4	6	3	8	25	5	0,2
Rheumatiſm	15	10	13	22	10	70	14	0,6
Rickets	27	21	40	39	36	163	32,6	1,24
Riſing of the lights	5	4	4	5	4	22	4,4	0,15
St. Anthony's fire	4	1	1	1	4	11	2	0,08
Scald-head	1	6	4	2	1	14	3	0,12
Scurvy	0	1	0	3	5	9	2	0,08
Sciatica	0	0	1	0	0	1	0,2	0,01
Small pox	2029	1633	1206	3236	1380	9484	1897	78,0
Sores and ulcers	14	18	21	28	28	109	22	1,0
Sore throat	0	3	1	1	6	11	2	0,08
Spleen and vapours	0	0	1	2	0	3	0,6	0,03
Stoppage in the ſtomach	83	65	112	102	81	443	89	4,0
Surfeit	1	3	5	5	5	19	4	0,15
Swelling	4	2	7	3	3	19	4	0,15
Teeth	1121	969	1048	1309	1283	5730	1146	47,5
Thruſh	89	93	152	121	144	599	120	5,0
Vomiting and looſeneſs	0	2	2	7	11	22	4	0,15
Worms	10	1	13	12	8	44	9	0,35
Caſualties	404	395	429	384	375	1987	397	16,8
Totals	25200	20606	21296	28157	25494	120753	24151	1000

Diſeaſes

Diſeaſes and caſualties annis	1748	1749	1750	1751	1752	Totals.	Medium.	In every thouſand.
Abortive and ſtill-born	481	611	581	572	529	2774	555	24,0
Aged — —	2127	1983	1896	1688	1263	8957	1791	78,0
Ague —	9	15	11	7	2	44	9	0,4
Apoplexy and ſuddenly --	222	239	227	208	178	1074	215	9,0
Aſthma and tiſſick	599	410	468	427	289	2193	438	20,0
Bedridden —	2	2	2	2	7	15	3	0,2
Bleeding —	5	8	3	7	3	26	5	0,2
Bloody flux —	10	7	8	3	3	31	6	0,2
Burſten and rupture	14	14	8	9	10	55	11	0,5
Cancer —	40	35	46	46	53	220	44	2,0
Canker —	6	6	4	4	6	26	5	0,2
Childbed —	197	187	228	172	156	940	188	8,0
Colick, gripes, and twiſting of the guts —	111	148	145	114	123	641	128	6,0
Conſumption —	4487	4623	4543	4182	3558	21393	4279	187,0
Convulſion —	5948	6128	5837	5594	5431	28938	5788	252,0
Cough and hooping-cough —	150	82	55	275	188	750	150	7,0
Diabetes —	2	1	1	0	0	4	1	0,04
Dropſy and tympany	1013	1039	1054	1004	682	4792	958	42,0
Evil — —	9	16	14	14	21	74	15	0,7
Carried forward —	15432	15554	15131	14328	12502	72947	14589	637,44

Diſeaſes

Diſeaſes and caſualties annis	1748	1749	1750	1751	1752	Totals.	Medium.	In every thouſand.
Brought forw.	15432	15554	15131	14328	12502	72947	14589	637,44
Fever, malignant, ſcarlet and ſpotted fever, and purples	3981	4458	4294	3219	2070	18022	3605	157,0
Fiſtula —	5	5	8	8	17	43	9	0,4
Flux —	47	38	24	21	10	140	28	1,0
French pox	73	73	73	75	54	348	70	3,0
Gout —	47	48	59	38	40	232	46	2,0
Gravel, ſtone and ſtrangury	32	22	30	28	28	140	28	1,0
Grief —	8	7	8	5	4	32	6	0,2
Head-ach —	1	0	0	0	0	1	0,2	0,01
Headmold-ſhot, horſe-ſhoehead, and water in the head	93	116	107	115	85	516	103	4,0
Jaundies —	164	147	186	121	115	733	147	6,0
Impoſthume	20	18	17	13	17	85	17	1,0
Inflammation	34	40	41	38	33	186	37	1,5
Itch — —	5	1	5	2	0	13	2,6	0,1
Leproſy —	7	2	5	3	3	20	4	0,2
Lethargy —	6	9	11	10	8	44	9	0,4
Livergrown --	1	2	1	0	2	6	1,2	0,06
Lunatick —	59	62	66	76	69	332	66	3,0
Meaſles —	10	106	321	21	111	569	114	5,0
Miſcarriage	7	3	3	4	5	22	4	0,2
Mortification	231	201	259	225	199	1115	223	10,0
Carried forw.	20263	20912	20649	18350	15372	95546	19109	833,51

Diſeaſes and caſualties annis	1748	1749	1750	1751	1752	Totals.	Medium.	In every thouſand.
Brought forw.	20263	20912	20649	18350	15372	95546	19109	833,51
Palſy — —	80	86	105	75	80	426	86	4,0
Pleuriſy —	76	36	34	26	23	195	39	1,5
Quinſy —	18	13	16	10	8	65	13	0,5
Raſh — —	6	6	4	6	2	24	5	0,2
Rheumatiſm —	7	20	21	20	6	74	15	0,7
Rickets —	15	25	21	23	11	95	19	1,0
Riſing of the lights —	0	5	1	5	4	15	3	0,2
St. Anthony's fire — —	0	4	3	4	4	15	3	0,2
Scald-head —	2	5	1	1	3	12	2,4	0,1
Scurvy — —	5	5	4	7	5	26	5	0,2
Small pox —	1789	2625	1229	998	3538	10179	2036	89,0
Sores and ulcers —	18	13	22	27	15	95	19	1,0
Sore throat —	5	3	7	3	3	21	4	0,2
Spleen and vapours —	1	0	1	0	0	2	0,4	0,0
Stoppage in the ſtomach	38	32	10	9	10	99	20	1,0
Surfeit — —	3	3	0	0	1	7	1,4	0,07
Swelling —	1	1	3	4	5	14	2,8	0,1
Teeth — —	1064	1147	1109	1053	968	5341	1068	46,0
Thruſh — —	94	152	111	95	99	551	110	5,0
Vomiting and looſeneſs	11	6	8	8	5	38	8	0,3
Worms —	2	9	5	10	7	33	6	0,2
Caſualties —	371	408	363	294	316	1752	350	15,0
Totals —	23869	25516	23727	21028	20485	114625	22925	1000

Diſeaſes and caſualties annis	1753	1754	1755	1756	1757	Totals.	Medium.	In every thouſand.
Abortive and ſtill-born	570	578	565	588	569	2870	574	27,0
Aged — —	1466	1946	1662	1512	1545	8131	1626	77,0
Ague —	4	4	5	6	4	23	5	0,2
Apoplexy and ſuddenly --	238	240	208	260	205	1151	230	11,0
Aſthma and tiſſick —	305	398	359	313	401	1776	355	16,0
Bedridden —	2	2	7	6	7	24	5	0,2
Bleeding —	5	11	1	5	5	27	5	0,2
Bloody flux —	5	4	6	7	6	28	6	0,3
Burſten and rupture —	14	6	10	8	12	50	10	0,5
Cancer —	52	48	46	42	58	246	49	2,0
Canker —	6	3	9	2	10	30	6	0,3
Chicken and ſwine pox	0	2	1	0	1	4	1	0,06
Childbed —	169	213	208	180	175	945	189	9,0
Cold — —	0	0	0	1	1	2	0,4	0,02
Choaked with fat	0	0	0	1	0	1	0,2	0,01
Colick, gripes, and twiſting of the guts —	128	115	81	68	64	456	91	4,0
Conſumption —	3915	4241	4322	4459	3973	20910	4182	197,0
Convulſion —	5977	6115	5741	5718	5211	28762	5752	271,0
Cough and hooping-cough —	65	336	93	199	239	932	186	9,0
Diabetes —	0	1	1	0	0	2	0,4	0,02
Dropſy and tympany	794	910	921	944	864	4433	887	41,0
Evil — —	11	8	14	17	14	64	13	0,8
Carried forward	13726	15181	14260	14336	13364	70867	14173	666,61

Diſeaſes and caſualties annis	1753	1754	1755	1756	1757	Totals.	Medium.	In every thouſand.
Brought forw.	13726	15181	14260	14336	13364	70867	14173	666,61
Falling ſickneſs	0	1	0	0	0	1	0,2	0,01
Fever, malignant, ſcarlet and ſpotted fever, and purples —	2292	2964	3042	2579	2564	13441	2688	126,0
Fiſtula —	4	10	14	6	11	45	9	0,4
Flux — —	5	18	8	9	6	46	9	0,4
French pox —	55	73	68	68	53	317	63	3,0
Gout — —	49	74	79	60	58	320	64	3,0
Gravel, ſtone and ſtrangury —	32	30	24	26	21	133	27	1,0
Grief — —	7	4	6	5	6	28	6	0,3
Green ſickneſs	0	0	1	0	0	1	0,2	0,01
Head-ach —	0	1	1	2	1	5	1	0,05
Headmold-ſhot, horſe-ſhoe head, and water in the head	64	57	56	43	42	262	52	2,5
Jaundies —	90	91	113	112	98	504	101	5,0
Impoſthume —	12	14	11	12	13	62	12	0,6
Inflammation	64	60	57	86	76	343	69	3,0
Itch — —	3	1	0	2	3	9	2	0,1
Leproſy —	2	3	0	3	1	9	2	0,1
Lethargy —	9	9	6	4	7	35	7	0,3
Livergrown —	2	1	2	4	2	11	2	0,1
Lunatick —	86	86	103	79	77	431	86	4,0
Meaſles —	253	12	423	156	24	868	174	8,0
Miſcarriage —	4	5	2	0	6	17	3,4	0,1
Mortification —	201	218	190	196	222	1027	205,4	10,0
Carried forward	16960	18913	18466	17788	16655	88782	17756,2	834,58

Diſeaſes and caſualties annis	1753	1754	1755	1756	1757	Totals.	Medium.	In every thouſand.
Brought forward —	16960	18913	18466	17788	16655	88782	17756,2	834,58
Palſy — —	60	68	58	51	55	292	58	2,5
Pleuriſy —	14	22	12	18	13	79	16	1,0
Quinſy —	11	10	14	14	14	63	13	0,7
Raſh — —	0	0	6	2	1	9	2	0,1
Rheumatiſm —	6	22	9	10	8	55	11	0,5
Rickets —	7	13	6	6	16	48	10	0,5
Riſing of the lights —	1	2	2	6	2	13	3	0,1
St. Anthony's fire —	2	3	5	6	3	19	4	0,2
Scald-head —	2	3	1	0	1	7	1,4	0,1
Scurvy —	5	5	2	2	3	17	3	0,1
Sciatica —	1	0	0	0	1	2	0,4	0,02
Small pox —	774	2359	1988	1608	3296	10025	2005	95,0
Sores and ulcers —	14	17	15	12	16	74	15	1,0
Sore throat —	7	4	4	8	22	45	9	0,4
Stoppage in the ſtomach —	14	20	14	19	16	83	17	1,0
Surfeit —	3	2	4	1	2	12	2	0,1
Swelling —	3	1	4	7	5	20	4	0,2
Teeth —	961	841	813	887	766	4268	853	41,0
Thruſh —	83	77	81	84	78	403	81	4,0
Vomiting and looſeneſs —	6	6	11	5	11	39	8	0,4
Worms —	11	10	11	9	11	52	10	0,5
Caſualties —	331	298	391	329	318	1667	333	16,0
Totals —	19276	22696	21917	20872	21313	106074	21215	1000

Diſeaſes and caſualties annis	From 1728 to 1732, both incl.	From 1733 to 1737, both incl.	From 1738 to 1742, both incl.	From 1743 to 1747, both incl.	From 1748 to 1752, both incl.	From 1753 to 1757, both incl	Totals.	Medium.	In every thouſand.
Abortive and ſtill born—	3084	3141	2842	2738	2774	2870	17449	2908	23,0
Aged ——	10976	9163	10846	10279	8957	8131	58352	9725	78,0
Ague ——	108	19	21	40	44	23	255	43	0,3
Apoplexy and ſuddenly --	1068	1057	1088	1100	1074	1151	6538	1090	9,0
Aſthma and tiſſick	2714	3041	3678	2584	2193	1776	15986	2664	21,0
Bedridden	36	50	61	22	15	24	208	35	0,3
Bleeding —	20	21	19	15	26	27	128	21	0 2
Bloody flux	93	50	59	51	31	28	312	52	0,4
Burſten and rupture	81	94	108	98	55	50	486	81	0,7
Cancer ——	300	259	262	250	220	246	1537	256	2,0
Canker —	68	57	36	20	26	30	237	40	0,3
Chicken and ſwine-pox—	2	1	0	0	0	4	7	1,2	0 01
Childbed—	1196	1241	1207	952	940	945	6481	1080	8,0
Cold ——	4	0	2	11	0	2	19	3	0,02
Choaked with fat	0	0	0	0	0	1	1	0,2	0,002
Colick, gripes, andtwiſtingof the guts —	2188	1700	1238	636	641	456	6859	1143	9,0
Conſumpt.	17907	21799	23371	21680	21393	20910	127060	21177	170 0
Convulſion	39313	40938	38444	31939	28938	28762	208334	34722	277,0
Cough & hooping-cough—	311	607	652	519	750	932	3771	628,6	5,0
Car. forw.	79469	83238	83934	72934	68077	66368	454020	75670	604,232

Diſeaſes and caſualties	From 1728 to 1732, both incl.	From 1733 to 1737, both incl.	From 1738 to 1742, both incl.	From 1743 to 1747, both incl.	From 1748 to 1752, both incl.	From 1753 to 1757, both incl.	Totals.	Medium.	In every thouſand.
Brought forward	79469	83238	83934	72934	68077	66368	454020	75670	604,232
Diabetes	16	5	6	6	4	2	39	6,5	0,06
Dropſy and tympany	5147	5369	5380	5471	4792	4433	30592	5099	41,0
Evil	167	152	175	97	74	64	729	121,5	1,0
Falling-ſickneſs	3	3	3	2	0	1	12	2	0,01
Fever, malignant, ſcarlet, and ſpotted, and purples	20232	17432	23863	18143	18022	13441	111133	18522	148,0
Fiſtula	77	76	67	63	43	45	371	62	0,5
Flux	116	106	95	135	140	46	638	106,2	1,0
French pox	514	602	627	363	348	317	2771	462	3,0
Gout	231	238	274	267	232	320	1562	260,3	2,0
Gravel, ſtone and ſtrangury	235	277	258	154	140	133	1197	199,5	1,0
Grief	77	59	54	35	32	28	285	47,5	0,4
Green-ſickn.	0	0	0	0	0	1	1	0,2	0,002
Head-ach	11	1	2	0	1	5	20	3,3	0,03
Headmold-ſhot, horſe-ſhoehead, and water in the head	497	600	742	720	516	262	3337	556	4,0
Jaundies	596	738	675	641	733	504	3887	648	5,0
Impoſthume	148	137	112	113	85	62	657	109	1,0
Inflammation	46	196	210	326	186	343	1307	218	2,0
Itch	10	8	16	22	13	9	78	13	0,1
Leproſy	19	28	26	19	20	9	121	20	0,2
Carried forw.	107611	109265	116519	99511	93458	86393	612757	102126	814,734

Diſeaſes

Diſeaſes and caſualties annis	From 1728 to 1732, both incl.	From 1733 to 1737, both incl.	From 1738 to 1742, both incl.	From 1743 to 1747, both incl.	From 1748 to 1752, both incl.	From 1753 to 1757, both incl.	Totals.	Medium.	In every thouſand.
Brought forward	107611	109265	116519	99511	93458	86393	612757	102126	814,534
Lethargy	46	43	36	27	44	35	231	38	0,3
Livergrown	38	34	26	7	6	11	122	20	0,2
Lunatick	142	134	314	357	332	431	1710	285	3,0
Meaſles	566	931	1611	367	569	868	4912	819	7,0
Miſcarriage	23	16	17	17	22	17	112	19	0,2
Mortification	1035	970	1351	1119	1115	1027	6617	1103	9,0
Palſy	163	190	211	242	426	292	1524	254	2,0
Piles	0	0	1	1	0	0	2	0,3	0,006
Pleuriſy	274	298	270	219	195	79	1335	222	2,0
Quinſy	56	105	94	101	65	63	484	81	0,6
Raſh	23	12	16	25	24	9	109	18	0,1
Rheumatiſm	126	89	132	70	74	55	546	91	0,8
Rickets	418	422	331	163	95	48	1477	246	2,0
Riſing of the lights	175	97	48	22	15	13	370	62	0,5
St. Anthony's fire	17	9	18	11	15	19	89	15	0,1
Scald-head	8	2	12	14	12	7	55	9	0,1
Sciatica	0	2	0	1	0	2	5	0,7	0,01
Scurvy	11	9	4	9	26	17	76	13	0,1
Small pox	10705	10750	9415	9484	10179	10025	60558	10093	80,0
Car. forw.	121437	123378	130426	111767	106672	99411	693091	115515	922,55

Diſeaſes

Diſeaſes and caſualties	From 1728 to 1732, both incl.	From 1733 to 1737, both incl.	From 1738 to 1742, both incl.	From 1743 to 1747, both incl.	From 1748 to 1752, both incl.	From 1753 to 1757, both incl.	Totals.	Medium.	In every thouſand.
Brought forw.	121437	123378	130426	111767	106672	99411	693091	115515	922,55
Sores and ulcers	184	152	124	109	95	74	738	123	1,0
Sore throat	0	2	6	11	21	45	85	14	0,1
Spleen and vapours	20	11	2	3	2	0	38	6	0,05
Stoppage in the ſtomach	1024	834	893	443	99	83	3376	563	5,0
Surfeit —	22	16	25	19	7	12	101	17	0,1
Swelling —	7	10	18	19	14	20	88	15	0,1
Teeth —	7493	7151	7315	5730	5341	4268	37298	6216	50,0
Thruſh —	302	372	620	599	551	403	2847	475	4,0
Vomiting and looſeneſs	192	91	56	22	38	39	438	73	0,6
Worms —	108	45	69	44	33	52	351	59	0,5
Caſualties	2124	2175	2166	1987	1752	1667	11871	1978	16,0
Totals —	132913	134237	141720	120753	114625	106074	750322	125054	1000

Ages

Ages of the perſons dying annis	1728	1729	1730	1731	1732	Totals.	Medium.	In every thouſand.
Under two years of age —	9851	10735	10368	9907	9502	50363	10073	378
tween two and ive —	2407	2516	2448	2096	1517	10984	2192	83
and ten — —	1038	1056	1092	932	716	4834	967	37
nd twenty —	950	999	901	806	611	4267	853	32
and thirty	2254	2371	2048	1916	1627	10216	2043	76
nd forty —	2490	2784	2471	2351	2175	12271	2452	93
fifty —	2624	2698	2373	2261	2121	12077	2415	91
ſixty —	2123	2338	1713	1839	1741	9754	1951	73
eventy —	1863	1938	1577	1500	1581	8459	1692	64
eighty	1290	1375	1001	913	974	5553	1111	41
ninety	785	769	622	628	660	3464	693	24
up- —	135	143	147	113	133	671	134	8
—	27810	29722	26761	25262	23358	132913	26583	1000

Ages of the perſons dying annis	1733	1734	1735	1736	1737	Totals.	Medium.	In every thouſand.
Under two years of age —	11738	10752	9672	10580	10054	52796	10559	393
Between two and five — —	2409	2830	1963	2706	2613	12521	2504	93
Five and ten — —	957	1228	755	993	1008	4941	988	37
Ten and twenty —	754	829	691	816	885	3975	795	29
Twenty and thirty	1857	1718	1605	2139	2241	9560	1912	72
Thirty and forty —	2564	2212	2158	2445	2652	12031	2406	89
Forty and fifty —	2685	2154	2138	2357	2578	11912	2383	89
Carried forward —	22964	21723	18982	22036	22031	107736	21547	802

Diſeaſes and caſualties	From 1728 to 1732, both incl.	From 1733 to 1737, both incl.	From 1738 to 1742, both incl.	From 1743 to 1747, both incl.	From 1748 to 1752, both incl.	From 1753 to 1757, both incl.	Totals.	Medium.	In every thouſand.
Brought forw.	121437	123378	130426	111767	106672	99411	693091	115515	922,55
Sores and ulcers	184	152	124	109	95	74	738	123	1,0
Sore throat	0	2	6	11	21	45	85	14	0,1
Spleen and vapours	20	11	2	3	2	0	38	6	0,05
Stoppage in the ſtomach	1024	834	893	443	99	83	3376	563	5,0
Surfeit —	22	16	25	19	7	12	101	17	0,1
Swelling —	7	10	18	19	14	20	88	15	0,1
Teeth —	7493	7151	7315	5730	5341	4268	37298	6216	50,0
Thruſh —	302	372	620	599	551	403	2847	475	4,0
Vomiting and looſeneſs	192	91	56	22	38	39	438	73	0,6
Worms —	108	45	69	44	33	52	351	59	0,5
Caſualties	2124	2175	2166	1987	1752	1667	11871	1978	16,0
Totals —	132913	134237	141720	120753	114625	106074	750322	125054	1000

Ages

Ages of the perſons dying annis	1728	1729	1730	1731	1732	Totals.	Medium.	In every thouſand.
Under two years of age	9851	10735	10368	9907	9502	50363	10073	378
Between two and five	2407	2516	2448	2096	1517	10984	2192	83
Five and ten	1038	1056	1092	932	716	4834	967	37
Ten and twenty	950	999	901	806	611	4267	853	32
Twenty and thirty	2254	2371	2048	1916	1627	10216	2043	76
Thirty and forty	2490	2784	2471	2351	2175	12271	2452	93
Forty and fifty	2624	2698	2373	2261	2121	12077	2415	91
Fifty and ſixty	2123	2338	1713	1839	1741	9754	1951	73
Sixty and ſeventy	1863	1938	1577	1500	1581	8459	1692	64
Seventy and eighty	1290	1375	1001	913	974	5553	1111	41
Eighty and ninety	785	769	622	628	660	3464	693	24
Ninety and upwards	135	143	147	113	133	671	134	8
Totals	27810	29722	26761	25262	23358	132913	26583	1000

Ages of the perſons dying annis	1733	1734	1735	1736	1737	Totals.	Medium.	In every thouſand.
Under two years of age	11738	10752	9672	10580	10054	52796	10559	393
Between two and five	2409	2830	1963	2706	2613	12521	2504	93
Five and ten	957	1228	755	993	1008	4941	988	37
Ten and twenty	754	829	691	816	885	3975	795	29
Twenty and thirty	1857	1718	1605	2139	2241	9560	1912	72
Thirty and forty	2564	2212	2158	2445	2652	12031	2406	89
Forty and fifty	2685	2154	2138	2357	2578	11912	2383	89
Carried forward	22964	21723	18982	22036	22031	107736	21547	802

Ages of the perſons dying annis	1733	1734	1735	1736	1737	Totals.	Medium.	In every thouſand.
Brought forward —	22964	21723	18982	22036	22031	107736	21547	802
Fifty and ſixty —	2196	1668	1684	2121	2270	9939	1988	74
Sixty and ſeventy —	1871	1324	1339	1666	1650	7850	1570	59
Seventy and eighty	1188	793	872	1114	1164	5131	1026	38
Eighty and ninety—	804	484	565	557	576	2986	597	22
Ninety and upwards — —	210	70	96	87	132	595	119	5
Totals —— ——	29233	26062	23538	27581	27823	134237	26847	1000

Ages of the perſons dying annis	1738	1739	1740	1741	1742	Totals.	Medium.	In every thouſand.
Under two years of age — —	9600	9687	10765	10456	9030	49538	9908	349
Between two and five —— —	2366	2302	2862	2368	2642	12540	2508	89
Five and ten — —	784	844	1235	1072	1035	4970	994	35
Ten and twenty —	783	875	947	1048	893	4546	909	32
Twenty and thirty	2072	1866	2205	2816	2203	11162	2232	78
Thirty and forty —	2439	2218	2783	3476	2813	13729	2746	97
Forty and fifty —	2363	2378	2866	3731	2959	14297	2859	101
Fifty and ſixty ——	2106	2039	2585	2851	2333	11914	2383	84
Sixty and ſeventy—	1551	1421	1977	1933	1634	8516	1703	60
Seventy and eighty	1121	1166	1716	1540	1250	6793	1359	48
Eighty and ninety—	529	547	758	734	582	3150	630	23
Ninety and upwards — —	111	89	112	144	109	565	113	4
Totals — —	25825	25432	30811	32169	27483	141720	28344	1000

Ages

Ages of the perſons dying annis	1743	1744	1745	1746	1747	Totals.	Medium.	In every thouſand.
Under two years of age	8621	7394	7689	9503	8741	41948	8390	347
Between two and five	1955	1657	1631	2611	2085	9939	1988	82
Five and ten	947	679	672	1089	905	4292	858	36
Ten and twenty	813	663	626	895	790	3787	757	31
Twenty and thirty	1935	1744	1695	2356	2190	9920	1984	82
Thirty and forty	2342	2019	1940	2728	2649	11678	2336	97
Forty and fifty	2611	2123	2332	2876	2717	12659	2532	105
Fifty and ſixty	2004	1637	1741	2243	2079	9704	1941	80
Sixty and ſeventy	1729	1307	1382	1699	1544	7661	1532	64
Seventy and eighty	1507	920	1064	1444	1199	6134	1227	50
Eighty and ninety	629	387	437	625	520	2598	519	22
Ninety and upwards	107	76	87	88	75	433	86	4
Totals	25200	20606	21296	28157	25494	120753	24150	1000

Ages of the perſons dying annis	1748	1749	1750	1751	1752	Totals.	Medium.	In every thouſand.
Under two years of age	7637	8504	8024	7483	8239	39887	7977	347
Between two and five	1798	2028	1533	1485	2225	9069	1814	80
Five and ten	760	794	709	575	814	3652	730	31
Ten and twenty	661	719	746	588	660	3374	675	30
Twenty and thirty	2142	2291	2031	1694	1566	9724	1945	85
Thirty and forty	2491	2753	2542	2207	1823	11816	2363	103
Forty and fifty	2700	2855	2708	2234	1633	12130	2426	106
Carried forward	18189	19944	18293	16266	16960	89652	17930	782

Ages

Ages of the perſons dying annis	1748	1749	1750	1751	1752	Totals.	Medium.	In every thouſand.
Brought forward —	18189	19944	18293	16266	16960	89652	17930	782
Fifty and ſixty —	2160	2113	2107	1815	1348	9543	1909	83
Sixty and ſeventy —	1704	1691	1728	1490	1079	7692	1538	67
Seventy and eighty	1187	1155	1038	925	738	5043	1009	44
Eighty and ninety —	558	533	475	461	316	2343	469	20
Ninety and upwards —	71	80	86	71	44	352	70	4
Totals —	23869	25516	23727	21028	20485	114625	22925	1000

Ages of the perſons dying annis	1753	1754	1755	1756	1757	Totals.	Medium.	In every thouſand.
Under two years of age —	7892	8115	7803	7466	7095	38371	7674	361
Between two and five — —	1403	1904	2001	1973	2411	9692	1939	92
Five and ten — —	418	640	612	605	948	3223	645	30
Ten and twenty —	478	628	577	572	687	2942	588	28
Twenty and thirty	1338	1685	1651	1523	1695	7892	1578	74
Thirty and forty —	1861	2141	2087	1982	1906	9977	1995	94
Forty and fifty —	1775	2179	2234	2069	1906	10163	2033	96
Fifty and ſixty —	1568	1944	1918	1788	1710	8928	1786	84
Sixty and ſeventy —	1186	1642	1433	1412	1418	7091	1418	67
Seventy and eighty	864	1143	1018	976	1024	5025	1005	47
Eighty and ninety —	435	586	504	451	431	2407	481	23
Ninety and upwards — —	58	89	79	55	82	363	73	4
Totals —	19276	22696	21917	20872	21313	106074	21215	1000

Ages

Ages of the persons dying	From 1728 to 1732, both incl.	From 1733 to 1737, both incl.	From 1738 to 1742, both incl.	From 1743 to 1747, both incl.	From 1748 to 1752, both incl.	From 1753 to 1757, both incl.	Totals.	Medium.	In every thousand.
Under two years of age	50363	52796	49538	41948	39887	38371	272903	45484	363
Between two and five	10984	12521	12540	9939	9069	9692	64745	10791	87
Five and ten	4834	4941	4970	4292	3652	3223	25912	4319	34
Ten and twenty —	4267	3975	4546	3787	3374	2942	22891	3815	31
Twenty and thirty —	10216	9560	11162	9920	9724	7892	58474	9746	77
Thirty and forty —	12271	12031	13729	11678	11816	9977	71502	11917	96
Forty and fifty —	12077	11912	14297	12659	12130	10163	73238	12206	97
Fifty and sixty —	9754	9939	11914	9704	9543	8928	59782	9964	80
Sixty and seventy —	8459	7850	8516	7661	7692	7091	47269	7878	63
Seventy and eighty —	5553	5131	6793	6134	5043	5025	33679	5613	45
Eighty and ninety —	3464	2986	3150	2598	2343	2497	16948	2825	23
Ninety and upwards	671	595	565	433	352	363	2979	496	4
Totals —	132913	134237	141720	120753	114625	106074	750322	125054	1000

AN ACCOUNT of perſons buried in the laſt thirty years, who lived to the age of one hundred and upwards.

Ages of the perſons	From 1728 to 1732, both incl.	From 1733 to 1737, both incl.	From 1738 to 1742, both incl.	From 1743 to 1747, both incl.	From 1748 to 1752, both incl.	From 1753 to 1757, both incl.	Totals.
One hund. years of age —	6	7	13	14	5	4	49
One hundred and one —	6	4	4	3	10	7	34
One hundred and two —	9	2	17	3	6	2	39
One hundred and three --	7	5	5	8	6	1	32
One hundred and four —	4	2	5	4	3	0	18
One hundred and five —	4	5	4	7	6	2	28
One hundred and ſix —	2	8	2	3	3	0	18
One hundred and ſeven	1	0	3	1	1	1	7
One hundred and eight	2	1	1	0	1	0	5
One hundred and nine —	0	0	0	0	1	1	2
One hundred and ten —	1	0	2	0	0	0	3
One hundred and eleven	0	0	1	1	0	0	2
One hundred and twelve	0	1	0	0	1	0	2
One hundred and ſixteen	0	2	0	0	0	0	2
One hund. and thirty eight	0	0	1	0	0	0	1
Totals — —	42	37	58	44	43	18	242

From

From the preceding accounts it appears, that in every thouſand perſons, who have been buried within the ſpace of thirty years laſt paſt, computing at a medium,

Years of age:

637 have lived to be — 2
550 — — — — 5
516 — — — 10
485 — — — — 20
408 — — — 30
312 — — — 40
215 — — — 50
135 — — — 60
72 — — — 70
27 — — — 80
4 — — — 90

And, that in every 3,100 perſons, one has lived to be one hundred years of age, or upwards.

A TABLE of the *Probabilities* of *Life*, deduced from the above bills for thirty years laſt paſt, by J. P. F. R. S. compared with that deduced from the ſaid bills for the firſt ten years of the ſaid thirty, by the late John Smart, Gent.

N. B. The laſt columns in each table, are the decrements of life, or numbers ſuppoſed to die off yearly.

TABLE by J. P.

Ages.	Numb. of perſons.	Decrements.	
Born	1000	0	
1	750	250	
2	637	113	
		—	363
3	597	40	
4	570	27	
5	550	20	
		—	87
			450

TABLE by J. S.

Ages.	Numb. of perſons.	Decrements.	
Born	1000	0	
1	710	290	
2	614	96	
		—	386
3	564	50	
4	539	25	
5	526	13	
		—	88
			474

TABLE

TABLE by J. P. continued.

Ages.	Numb. of persons.	Decrements.	
6	540	10	450
7	531	9	
8	525	6	
9	520	5	
10	516	4	
		—	34
11	512	4	
12	509	3	
13	506	3	
14	504	2	
15	502	2	
16	500	2	
17	497	3	
18	494	3	
19	490	4	
20	485	5	
		—	31
21	478	7	
22	471	7	
23	464	7	
24	456	8	
25	448	8	
26	440	8	
27	432	8	
28	424	8	
29	416	8	
30	408	8	
		—	77
			592

TABLE by J. S. continued.

Ages.	Numb. of persons.	Decrements.	
6	516	10	474
7	508	8	
8	501	7	
9	495	6	
10	490	5	
		—	36
11	486	4	
12	482	4	
13	479	3	
14	477	2	
15	475	2	
16	473	2	
17	471	2	
18	468	3	
19	464	4	
20	459	5	
		—	31
21	453	6	
22	447	6	
23	440	7	
24	433	7	
25	426	7	
26	418	8	
27	410	8	
28	402	8	
29	394	8	
30	385	9	
		—	74
			615

TABLE

TABLE by J. P. continued.

Ages.	Numb. of persons.	Decrements.	
			592
31 —	399 —	9	
32 —	390 —	9	
33 —	381 —	9	
34 —	372 —	9	
35 —	362 —	10	
36 —	352 —	10	
37 —	342 —	10	
38 —	332 —	10	
39 —	322 —	10	
40 —	312 —	10	
		—	96
41 —	302 —	10	
42 —	292 —	10	
43 —	282 —	10	
44 —	272 —	10	
45 —	262 —	10	
46 —	252 —	10	
47 —	242 —	10	
48 —	233 —	9	
49 —	224 —	9	
50 —	215 —	9	
		—	97
51 —	206 —	9	
52 —	197 —	9	
53 —	189 —	8	
54 —	181 —	8	
55 —	173 —	8	
56 —	165 —	8	
		—	
		50	
			785

TABLE by J. S. continued.

Ages.	Numb. of persons.	Decrements.	
			615
31 —	376 —	9	
32 —	367 —	9	
33 —	358 —	9	
34 —	349 —	9	
35 —	340 —	9	
36 —	331 —	9	
37 —	322 —	9	
38 —	313 —	9	
39 —	304 —	9	
40 —	294 —	10	
		—	91
41 —	284 —	10	
42 —	274 —	10	
43 —	264 —	10	
44 —	255 —	9	
45 —	246 —	9	
46 —	237 —	9	
47 —	228 —	9	
48 —	220 —	8	
49 —	212 —	8	
50 —	204 —	8	
		—	90
51 —	196 —	8	
52 —	188 —	8	
53 —	180 —	8	
54 —	172 —	8	
55 —	165 —	7	
56 —	158 —	7	
		—	
		46	
			796